

Advertisement of Highway Bid Letting

Electronic Bids for the following construction projects will be received by the South Dakota Department of Transportation (SDDOT) via the South Dakota Electronic Bid System (SDEBS) until 10 A.M. Central time, on May 02, 2019, at which time the SDDOT will open bids. All bids will be checked for qualifications with results posted on the SDDOT website.

ITEM NO.	PROJECT NUMBER	COUNTY	LENGTH MILES	TYPE OF WORK	DESCRIPTION OF LOCATION
1.	P 6042(00) (PCN 001E)	Davison SWPPP = 16.30 AC	1.090	Grading, Precast Box Culvert, and Asphalt Concrete Surfacing	County Road from 12 miles west of Ethan, west 1 mile on 265th Street

This is a mock letting for the Construction Management class at SDSU being instructed by Gary Johnson with A-G-E Corporation. All contracting parties are invited and encouraged to participate in an effort to make this a realistic experience for the students.

Subcontractors and Suppliers should submit their mock quotes to Gary by fax (605-223-2767), phone (605-223-2732), or email (agecorp@dakota2k.net). Contractors will be allowed to participate as Prime Bidders in the mock letting and should submit mock bids through the South Dakota Electronic Bidding System (SDEBS). Bid results will be posted on the bid letting website Thursday, May 2, 2019.

Thank you to all contractors, subcontractors, and suppliers for your help and support.

* Indicates combination bids

SWPPP = Storm Water Pollution Prevention Plan

ITEMS INVOLVED ARE AS FOLLOWS

This letting has been moved to 5/3/19.

1. P 6042(00)
Work Type 1

Area Engineer: Jay Peppel, PO Box 1206, Mitchell, SD, 57301-7206

Phone: 605/995-8120

DBE Goal: NONE

Contract Id: 4055

See Special Provisions for Completion Requirements

1	Maintenance of Traffic Diversion(s)	LS	1.000
2	Mobilization	LS	1.000
3	Clearing	LS	1.000
4	Remove Sediment	CuYd	5.000
5	Salvage Riprap	CuYd	37.000
6	Unclassified Excavation	CuYd	67,889.000
7	Muck Excavation	CuYd	500.000
8	Undercutting	CuYd	12,586.000
9	Water for Embankment	MGal	683.000
10	Water for Granular Material	MGal	124.000
11	Placing Topsoil	CuYd	7,651.000
12	Incidental Work, Grading	LS	1.000
13	Base Course	Ton	10,327.000
14	PG 64-22 Asphalt Binder	Ton	180.000
15	Class E Asphalt Concrete	Ton	2,831.000
16	Compaction Sample	Each	3.000
17	MC-70 Asphalt for Prime	Ton	23.400
18	SS-1h or CSS-1h Asphalt for Tack	Ton	4.000
19	Blotting Sand for Prime	Ton	75.000
20	Structure Excavation, Box Culvert	CuYd	43.000
21	Box Culvert Undercut	CuYd	184.000
22	18" RCP Safety End, Furnish	Each	4.000
23	18" RCP Safety End, Install	Each	4.000
24	24" RCP Safety End, Furnish	Each	2.000
25	24" RCP Safety End, Install	Each	2.000
26	18" CMP 16 Gauge, Furnish	Ft	138.000
27	18" CMP, Install	Ft	138.000
28	24" CMP 16 Gauge, Furnish	Ft	156.000
29	24" CMP, Install	Ft	156.000
30	18" CMP Safety End, Furnish	Each	6.000
31	18" CMP Safety End, Install	Each	6.000
32	24" CMP Safety End, Furnish	Each	6.000
33	24" CMP Safety End, Install	Each	6.000
34	10'x10' Precast Concrete Box Culvert, Furnish	Ft	102.000
35	10'x10' Precast Concrete Box Culvert, Install	Ft	102.000
36	10'x10' Precast Concrete Box Culvert End Section, Furnish	Each	2.000
37	10'x10' Precast Concrete Box Culvert End Section, Install	Each	2.000
38	Type II Field Laboratory	Each	1.000
39	Type 2 Right-of-Way Fence	Ft	12,090.000
40	Type 1 Temporary Fence	Ft	5,255.000
41	2 Post Panel	Each	61.000
42	3 Post Panel	Each	23.000
43	Pavement Marking Paint, 4" White	Ft	10,400.000
44	Pavement Marking Paint, 4" Yellow	Ft	5,160.000
45	Traffic Control Signs	SqFt	1,342.000
46	Traffic Control, Miscellaneous	LS	1.000
47	Class B Riprap	Ton	4,156.000
48	Type B Permanent Seed Mixture	Lb	315.000
49	Mulching	Ton	38.000
50	Fiber Mulching	Lb	400.000
51	Type 1 Erosion Control Blanket	SqYd	1,000.000
52	Type 3 Erosion Control Blanket	SqYd	1,600.000
53	Erosion Bale	Each	30.000

54	12" Diameter Erosion Control Wattle	Ft	2,100.000
55	Remove and Reset Erosion Control Wattle	Ft	500.000
56	Shaping for Erosion Control Blanket	Ft	872.000
57	High Flow Silt Fence	Ft	5,100.000
58	Mucking Silt Fence	CuYd	350.000
59	Repair Silt Fence	Ft	1,275.000
60	Temporary Diversion Channel for Fish Passage	Each	1.000
61	Type B Drainage Fabric	SqYd	3,398.000

Instructions

PROPOSALS, PLANS AND SPECIFICATIONS: Plans, Proposals, and Standard Specifications are available on the SDDOT Bid Letting website.

MINIMUM WAGE RATES: Minimum wage rates for 1 have been predetermined by the Department of Transportation, and are set forth in the advertised specification.

BID PREPARATION: Bids shall be completed in their entirety utilizing the SDEBS.

Please refer to the SDDOT bid letting webpage for the SDEBS user manual and further information on how to bid.

NONDISCRIMINATION ASSURANCE: The Department of Transportation in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C. 2000d to 2000d-4 and Title 49, Code of Federal Regulations, Department of Transportation, Subtitle A, Office of the Secretary, Part 21, Nondiscrimination in Federally-assisted programs of the Department of Transportation issued pursuant to such Act, hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, religion, national origin, sex, age or disability in consideration for an award.

EXECUTION OF CONTRACT: In accordance with Section 7.15 of the Standard Specifications, Current Edition, all Contractors prior to execution of any contract, must file with the Department a Certificate of Liability Insurance.

Foreign Corporations, prior to execution of any contract, must file their Articles of Incorporation in accordance with the Foreign Corporation Laws of South Dakota, Chapter 47-8 of the 1967 South Dakota Compiled Laws as amended.

GENERALLY: A list of plan and proposal holders for each project is available on our website for each project in the letting. The plan holders list is updated immediately when a contractor or supplier logs into the project as indicated above.

Prior to plant operation, either a construction permit or an operating permit must be obtained from the Department of Environmental & Natural Resources, Minerals & Mining Program, Foss Building, Pierre, SD 57501. (Phone [605] 773-4201) Allow thirty (30) days for processing.

Operation of contractor furnished material sources shall be in accordance with SDCL 45-6 governing the extraction of construction aggregate. To obtain licensing and bonding requirements contact: Minerals and Mining Program, South Dakota Department of Environmental and Natural Resources, Foss Building, Pierre, South Dakota 57501. (Phone [605] 773-4201)

Hydrostatic Testing and Excavation Dewatering shall be in accordance with the NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES), GENERAL PERMIT NUMBER SDG-100000. For further information contact the South Dakota Department of Environmental and Natural Resources, Foss Building, Pierre, South Dakota 57501 (Phone [605] 773-3351).

The Department of Transportation reserves the right to reject any or all bids.

STATE OF SOUTH DAKOTA, DEPARTMENT OF TRANSPORTATION

BY: Darin Bergquist
SECRETARY OF TRANSPORTATION