

Planning & Engineering Office of Project Development

700 E Broadway Avenue Pierre, South Dakota 57501-2586 O: 605.773.3275 | F: 605.773.2614 dot.sd.gov

December 6, 2024

ADDENDUM NO. 2

RE: Item #1, December 11, 2024 Letting - NH-CR 0014(185)229, PCN 026Z, Hughes County -Urban Grading, Curb & Gutter, Sidewalk, Signals, Storm Sewer, Lighting, Asphalt Concrete Surfacing, PCC Surfacing

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made a part of your proposal for the referenced project.

SPECIAL PROVISIONS: NO CHANGE

SDEBS BID PROPOSAL:

The electronic bid proposal for this contract has been revised to include the changes associated with this addendum. Bidders must log in to the SDEBS to retrieve and incorporate these changes into their bid.

Bid Items were added:

Bid Item 450E8029 "42" RCP to CMP Transition, Furnish" Bid Item 450E8030 "42" Pipe Transition, Install"

Quantities for Bid Items were changed:

Bid Item 450E0192 "42" RCP Class 2, Furnish" changed from 2,064 to 2,090 Ft Bid Item 450E0200 "42" RCP, Install" changed from 2,064 to 2,090 Ft Bid Item 450E4798 "42" CMP 14 Gauge, Furnish" changed from 302 to 214 Ft Bid Item 450E4800 "42" CMP, Install" changed from 302 to 214 Ft Bid Item 450E5030 "42" CMP Elbow, Furnish" changed from 2 to 4 Each Bid Item 450E5031 "42" CMP Elbow, Install" changed from 2 to 4 Each Bid Item 634E0640 "Temporary Pavement Marking" changed from 28,858 to 26,283 Ft

PLANS: Please destroy sheets A1, B2, B21, B61, B62, B63, C2 and C11 and replace with the enclosed sheets, dated 12/5/24 & 12/6/24.

Sheets A2 & B2: Bid Items were added:

Bid Item 450E8029 "42" RCP to CMP Transition, Furnish" Bid Item 450E8030 "42" Pipe Transition, Install"

Quantities for Bid Items were changed:

Bid Item 450E0192 "42" RCP Class 2, Furnish" changed from 2,064 to 2,090 Ft
Bid Item 450E0200 "42" RCP, Install" changed from 2,064 to 2,090 Ft
Bid Item 450E4798 "42" CMP 14 Gauge, Furnish" changed from 302 to 214 Ft

Bid Item 450E4800 "42" CMP, Install" changed from 302 to 214 Ft Bid Item 450E5030 "42" CMP Elbow, Furnish" changed from 2 to 4 Each Bid Item 450E5031 "42" CMP Elbow, Install" changed from 2 to 4 Each

Sheets A2 & C2:Quantities for Bid Items were changed:Bid Item 634E0640 "Temporary Pavement Marking" changed from
28,858 to 26,283 Ft

- Sheet B21: PIPE TABLE was revised.
- <u>Sheet B61</u>: Stationing was revised. Pipe install callouts and associated quantities for pipes at Stations 935+05 through Station 936+20 were revised. Pipe quantity for pipe callouts at Station 932+73 and Station 936+20 were revised.
- **Sheet B62**: Concrete collar note was revised to show pipe transition. Elbows were added to drawing.
- **<u>Sheet B63</u>**: End Station Callout Note for 60" RCP was revised.
- **Sheet C11:** TABLE OF TEMPOARY PAVEMENT MARKING was revised and note was added.

Sincerely,

Sam Weisgram Engineering Supervisor

SW/cj

CC: Jason Humphrey, Pierre Region Engineer Dean VanDeWiele, Pierre Area Engineer

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

Section B - Grading

| BID ITEM NUMBER | Ітем | QUANTITY | UNIT |
|--------------------|--|----------|------|
| 009E0010 | Mobilization | Lump Sum | LS |
| 009E3220 | Reestablish Right-of-Way and Property Corner | 152 | Each |
| 009E3230 | Grade Staking | 2.902 | Mile |
| 009E3250 | Miscellaneous Staking | 1.392 | Mile |
| 009E3301 | Engineer Directed Surveying/Staking | 80.0 | Hour |
| 009E4300 | Construction Schedule, Category | Lump Sum | LS |
| 009E4330 | Project Management, Category III | Lump Sum | LS |
| 100E0020 | Clear and Grub Tree | 70 | Each |
| 100E0100 | Clearing | Lump Sum | LS |
| 110E0300 | Remove Concrete Curb and/or Gutter | 15,215 | Ft |
| 110E0400 | Remove Drop Inlet | 39 | Each |
| 110E1100 | Remove Concrete Pavement | 1,433.0 | SqYd |
| 110E1130 | Remove Concrete Driveway Pavement | 2,711.3 | SqYd |
| 110E1140 | Remove Concrete Sidewalk | 9,383.3 | SqYd |
| 110E5720 | Salvage Drop Inlet Frame and Grate Assembly | 5 | Each |
| 120E0010 | Unclassified Excavation | 41,396 | CuYd |
| 120E6000 | Water for Dust Contro | 50.0 | MGa |
| 120E6100 | Water for Embankment | 14.5 | MGa |
| 250E0020 | Incidental Work, Grading | Lump Sum | LS |
| 260E6010 | Granular Material | 2,241.0 | Ton |
| 270E0022 | Salvage Asphalt Mix Materia | 11,612.1 | Ton |
| 270E0112 | Salvage Granular Materia | 21,353,1 | Ton |
| 380E2564 | 4" Barrier Type Colored Median PCC Pavement | 344.6 | SqYd |
| 380E3540 | 8" PCC Approach Pavement | 3,736.7 | SqYd |
| 380E4050 | 8" PCC Fillet Section | 1,542.0 | SqYd |
| 450E0122 | 18" RCP Class 2, Furnish | 4,214 | Ft |
| 450E0130 | 18" RCP, Install | 4,214 | Ft |
| 450E0142 | 24" RCP Class 2, Furnish | 2,028 | Ft |
| 450E0150 | 24" RCP, Install | 2,028 | Ft |
| 450E0162 | 30" RCP Class 2, Furnish | 542 | Ft |
| 450E0170 | 30" RCP, Install | 542 | Ft |
| 450E0182 | 36" RCP Class 2, Furnish | 826 | Ft |
| 450E0190 | 36" RCP, Instal | 826 | Ft |
| 450E0192 | 42" RCP Class 2, Furnish | 2,090 | Ft |
| 450E0200 | 42" RCP, Instal | 2,090 | Ft |
| 450E0212 | 54" RCP Class 2, Furnish | 162 | Ft |
| 450E0220 | 54" RCP, Install | 162 | Ft |
| 450E0222 | 60" RCP Class 2, Furnish | 64 | Ft |
| 450E0230 | 60" RCP, Install | 64 | Ft |
| 450E2044 | 60" RCP Flared End, Furnish | 1 | Each |
| 450E2045 | 60" RCP Flared End, Install | 1 | Each |
| 450E3062 | 54" RCP Arch Class 2, Furnish | 398 | Ft |
| 450E3070 | 54" RCP Arch, Install | 398 | Ft |

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|---|----------|------|
| 450E4798 | 42" CMP 14 Gauge, Furnish | 214 | Ft |
| 450E4800 | 42" CMP, Install | 214 | Ft |
| 450E5030 | 42" CMP Elbow, Furnish | 4 | Each |
| 450E5031 | 42" CMP Elbow, Install | 4 | Each |
| 450E8029 | 42" RCP to CMP Transition, Furnish | 2 | Each |
| 450E8030 | 42" Pipe Transition, Instal | 2 | Each |
| 451E0518 | 8" PVC Pipe | 28 | Ft |
| 451E3118 | 18" Pipe Cap | 1 | Each |
| 462E0100 | Class M6 Concrete | 334.1 | CuYd |
| 480E0100 | Reinforcing Steel | 63,179 | Lb |
| 600E0300 | Type III Field Laboratory | 1 | Each |
| 650E0060 | Type B66 Concrete Curb and Gutter | 13,563 | Ft |
| 650E0080 | Type B68 Concrete Curb and Gutter | 1,843 | Ft |
| 650E4660 | Type P6 Concrete Gutter | 1,272 | Ft |
| 650E4680 | Type P8 Concrete Gutter | 70 | Ft |
| 650E6280 | 8" Concrete Valley Gutter | 333.5 | SqYd |
| 651E0040 | 4" Concrete Sidewalk | 24,073 | SqFt |
| 651E0060 | 6" Concrete Sidewalk | 84,113 | SqFt |
| 651E0560 | 6" Colored Concrete Sidewalk | 29,250 | SqFt |
| 651E5000 | Sidewalk Drain | 23.0 | Ft |
| 651E7000 | Type 1 Detectable Warnings | 1,737 | SqFt |
| 670E1200 | Type B Frame and Grate | 84 | Each |
| 670E5340 | 4' x 11' Precast Concrete Type S Drop Inlet Lid | 3 | Each |
| 670E5400 | Precast Drop Inlet Collar | 84 | Each |
| 671E4048 | 48" Manhole Riser Section | 41.3 | Ft |
| 671E6009 | Type A9 Manhole Frame and Lid | 33 | Each |
| 900E0010 | Refurbish Single Mailbox | 7 | Each |
| 900E1150 | Right of Way Marker | 6 | Each |
| 900E5145 | Bollard | 2 | Each |
| 998E0100 | Railroad Protective Insurance | Lump Sum | LS |

A1 to A3 A4 to A7

Ş

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|---|----------|------|
| 633E6005 | Pavement Marking Masking, 5" | 885 | Ft |
| 633E6035 | Pavement Marking Masking, Combination Arrow | 4 | Each |
| 634E0010 | Flagging | 1,000.0 | Hour |
| 634E0110 | Traffic Control Signs | 1,178.7 | SqFt |
| 634E0120 | Traffic Control, Miscellaneous | Lump Sum | LS |
| 634E0135 | Traffic Control Supervisor | Lump Sum | LS |
| 634E0275 | Type 3 Barricade | 58 | Each |
| 634E0330 | Temporary Raised Pavement Markers | 21,589 | Ft |
| 634E0420 | Type C Advance Warning Arrow Board | 2 | Each |
| 634E0640 | Temporary Pavement Marking | 26,283 | Ft |
| 634E0700 | Traffic Control Movable Concrete Barrier | 17 | Each |
| 634E1002 | Detour and Restriction Signing | 1,492,5 | SqFt |
| 634E1020 | Temporary Business Signing | 98.4 | SqFt |
| 634E1215 | Contractor Furnished Portable Changeable Message Sign | 3 | Each |
| 634E2000 | Longitudinal Pedestrian Barricade | 348 | Ft |
| 634E2015 | Temporary Pedestrian Access Route | Lump Sum | LS |
| 634E2020 | Temporary Curb Ramp | 5 | Each |
| 634E2025 | Longitudinal Pedestrian Barrier | 1,705 | Ft |



| STATE OF | PROJECT | SHEET | TOTAL SHEETS |
|-----------------|--|--|-----------------|
| SOUTH DAKOTA | NH-CR 0014(185)229 | A1 | A7 |
| | REV 07 REV 08 REV 12 REV 12 REV 12 | 5-31-24 0 7-09-24 0 3-27-24 0 1-22-24 0 2-03-24 0 2-06-24 0 |)E)E)E |

INDEX OF SHEETS

Estimate of Quantities for Sections B, C, D, F, L, M and S

Environmental Commitments

Section C - Traffic Control

SECTION B ESTIMATE OF QUANTITIES

| BID TEM | ITEM | QUANTITY | UNIT |
|----------|--|----------|------|
| 009E0010 | Mobilization | Lump Sum | LS |
| 009E3220 | Reestablish Right of Way and Property Corner | 152 | Each |
| 009E3230 | Grade Staking | 2.902 | Mile |
| 009E3250 | Miscellaneous Staking | 1,392 | Mile |
| 009E3301 | Engineer Directed Surveying/Staking | 80.0 | Hour |
| 009E4300 | Construction Schedule, Category | Lump Sum | LS |
| 009E4330 | Project Management, Category III | Lump Sum | LS |
| 100E0020 | Clear and Grub Tree | 70 | Each |
| 100E0100 | Clearing | Lump Sum | LS |
| 110E0300 | Remove Concrete Curb and/or Gutter | 15,215 | Ft |
| 110E0400 | Remove Drop Inlet | 39 | Each |
| 110E1100 | Remove Concrete Pavement | 1,433.0 | SqYd |
| 110E1130 | Remove Concrete Driveway Pavement | 2,711.3 | SqYd |
| 110E1140 | Remove Concrete Sidewalk | 9,383.3 | SqYd |
| 110E5720 | Salvage Drop Inlet Frame and Grate Assembly | 5 | Each |
| 120E0010 | Unclassified Excavation | 41,396 | CuYd |
| 120E6000 | Water for Dust Contro | 50.0 | MGa |
| 120E6100 | Water for Embankment | 14,5 | MGa |
| 250E0020 | Incidental Work, Grading | Lump Sum | LS |
| 260E6010 | Granular Material | 2,241.0 | Ton |
| 270E0022 | Salvage Asphalt Mix Material | 11,612.1 | Ton |
| 270E0112 | Salvage Granular Material | 21,353.1 | Ton |
| 380E2564 | 4" Barrier Type Colored Median PCC Pavement | 344.6 | SqYd |
| 380E3540 | 8" PCC Approach Pavement | 3,736.7 | SqYd |
| 380E4050 | 8" PCC Fillet Section | 1,542.0 | SqYd |
| 450E0122 | 18" RCP Class 2, Furnish | 4,214 | Ft |
| 450E0130 | 18" RCP, Install | 4,214 | Ft |
| 450E0142 | 24" RCP Class 2, Furnish | 2,028 | Ft |
| 450E0150 | 24" RCP, Instal | 2,028 | Ft |
| 450E0162 | 30" RCP Class 2, Furnish | 542 | Ft |
| 450E0170 | 30" RCP, Install | 542 | Ft |
| 450E0182 | 36" RCP Class 2, Furnish | 826 | Ft |
| 450E0190 | 36" RCP, Install | 826 | Ft |
| 450E0192 | 42" RCP Class 2, Furnish | 2,090 | Ft |
| 450E0200 | 42" RCP, Install | 2,090 | Ft |
| 450E0212 | 54" RCP Class 2, Furnish | 162 | Ft |
| 450E0220 | 54" RCP, Instal | 162 | Ft |
| 450E0222 | 60" RCP Class 2, Furnish | 64 | Ft |
| 450E0230 | 60" RCP, Install | 64 | Ft |
| 450E2044 | 60" RCP Flared End, Furnish | 1 | Each |
| 450E2045 | 60" RCP Flared End, Install | 1 | Each |
| 450E3062 | 54" RCP Arch Class 2, Furnish | 398 | Ft |
| 450E3070 | 54" RCP Arch, Instal | 398 | Ft |

| BID ITEM | ITEM | QUANTITY | UNIT |
|----------|---|----------|------|
| 450E4798 | 42" CMP 14 Gauge, Furnish | 214 | Ft |
| 450E4800 | 42" CMP, Install | 214 | Ft |
| 450E5030 | 42" CMP Elbow, Furnish | 4 | Each |
| 450E5031 | 42" CMP Elbow, Install | 4 | Each |
| 450E8029 | 42" RCP to CMP Transition, Furnish | 2 | Each |
| 450E8030 | 42" Pipe Transition, Instal | 2 | Each |
| 451E0518 | 8" PVC Pipe | 28 | Ft |
| 451E3118 | 18" Pipe Cap | 1 | Each |
| 462E0100 | Class M6 Concrete | 334.1 | CuYd |
| 480E0100 | Reinforcing Steel | 63,179 | Lb |
| 600E0300 | Type III Field Laboratory | 1 | Each |
| 650E0060 | Type B66 Concrete Curb and Gutter | 13,563 | Ft |
| 650E0080 | Type B68 Concrete Curb and Gutter | 1,843 | Ft |
| 650E4660 | Type P6 Concrete Gutter | 1,272 | Ft |
| 650E4680 | Type P8 Concrete Gutter | 70 | Ft |
| 650E6280 | 8" Concrete Valley Gutter | 333.5 | SqYd |
| 651E0040 | 4" Concrete Sidewalk | 24,073 | SqFt |
| 651E0060 | 6" Concrete Sidewalk | 84,113 | SqFt |
| 651E0560 | 6" Colored Concrete Sidewalk | 29,250 | SqFt |
| 651E5000 | Sidewalk Drain | 23.0 | Ft |
| 651E7000 | Type 1 Detectable Warnings | 1,737 | SqFt |
| 670E1200 | Type B Frame and Grate | 84 | Each |
| 670E5340 | 4' x 11' Precast Concrete Type S Drop Inlet Lid | 3 | Each |
| 670E5400 | Precast Drop Inlet Collar | 84 | Each |
| 671E4048 | 48" Manhole Riser Section | 41.3 | Ft |
| 671E6009 | Type A9 Manhole Frame and Lid | 33 | Each |
| 900E0010 | Refurbish Single Mailbox | 7 | Each |
| 900E1150 | Right of Way Marker | 6 | Each |
| 900E5145 | Bollard | 2 | Each |
| 998E0100 | Railroad Protective Insurance | Lump Sum | LS |

GRADING OPERATIONS

Water for Embankment is estimated at the rate of 10 gallons of water per cubic yard of Embankment minus Waste.

The estimated cubic yards of excavation and/or embankment required to construct outlet ditches, ditch blocks, and approaches are included in the earthwork balance notes on the profile sheets.

Special ditch grades and other sections of the roadway different than the typical section(s) will be constructed to the limits shown on the cross sections. If significant changes to the cross sections are necessary during construction, the Engineer will contact the Designer for the proposed change.

Generally, all shallow inlet and outlet ditches as noted on the plan sheets will be cut with a 10-foot wide bottom with 5:1 backslopes. However, the Engineer may direct the Contractor to adjust the ditch width for proper alignment with the drainage structure.

A copy of the subsurface investigation for this project is available for review at the Pierre Region and Pierre Area offices.

Table for Water for Embankment

Station to Mainline 10+00 29+93 61+50

Subtotal Mainlin **Elizabeth Street** 698+07 Тс Subtotal Mainlin

Water at 10




| STA | STATE OF | PROJECT | SHEET | TOTAL SHEETS |
|-----------------|----------|--------------------|-------|-----------------|
| SOUTH DAKOTA | | NH-CR 0014(185)229 | B2 | B151 |


REV 4-16-24 GE REV 7-9-24 GE REV 08-27-24 GE REV 11-22-24 GE REV 12-05-24 GE

| Water for Embankment | |
|------------------------|------------|
| | Embankment |
| Station | (CuYd) |
| 29+93 | 181 |
| 61+50 | 178 |
| 80+45 | 1,076 |
| Total Mainline | 1,435 |
| ne Water at 10gal/cy | 14.4 |
| 701+50 | 14 |
| otal Elizabeth Street | 14 |
| ne Water at 10gal/cy | 0.1 |
| Total Project | 1,449 |
|) gal/cy Total Project | 14.5 |
| | |


| | | Reinforced Concrete | | | | | | | C | MP | RCP to CMP | PVC | | | |
|--------------------------|--------------|---------------------|------|-------|----------|------|------|------|------|-------------|------------|----------|-------|------------|-----|
| | | | | | Circular | | | | Arch | Flared Ends | Pipe Cap | Circular | Elbow | Transition | PVC |
| | | 18" | 24" | 30" | 36" | 42" | 54" | 60" | 54" | 60" | 18" | 42" | 42" | 42" | 8" |
| | | Cl. 2 | Cl.2 | Cl. 2 | | Cl.2 | Cl.2 | Cl.2 | Cl.2 | | | | 10° | | - |
| Station | Offset (L/R) | Ft | Ft | Ft | Ft | Ft | Ft | Ft | Ft | Each | Each | Ft | Each | Each | Ft |
| 54+13-29.17' L to 54+13- | -29.17' R | 58 | | | | | | | | | | | | | |
| 55+63-29.17' R to 54+13 | -29.17' R | 148 | | | | | | | | | | | | | |
| 55+65-29.29' R to 55+63 | -29.17' L | 58 | | | | | | | | | | | | | |
| 57+38-29.17' R to 55+63 | -29.17' R | 172 | | | | | | | | | | | | | |
| 57+38-29.17' L to 57+38- | -29.17' R | 58 | | | | | | | | | | | | | |
| 61+03-5.50' R to 61+03-2 | 28.17' R | | 20 | | | | | | | | | | | | |
| 61+03-28.17' L to 61+03- | -5.50' R | | 30 | | | | | | | | | | | | |
| 61+03-28.17' R to 714+2 | 4-10.42' R | | 70 | | | | | | | | | | | | |
| 62+02-5.50' R to 61+03-5 | 5.50' R | | 100 | | | | | | | | | | | | |
| 62+01-28.17' R to 62+02 | -5.50' R | 22 | | | | | | | | | | | | | |
| 62+98-5.50' R to 62+02+ | 5.50' R | | 98 | | | | | | | | | | | | |
| 62+98-28.17' R to 62+98 | | 22 | | | | | | | | | | | | | |
| 63+52-5.50' R to 62+98-5 | | | 54 | | | | | | | | | | | | |
| 956+58-18.10' R to 63+5 | | 52 | ~ | | | | | | | | | | | | |
| 64+78-5.50' R to 63+52-5 | | | 126 | | | | | | | | | | | | |
| 64+78-29.17' R to 64+78 | | 24 | 120 | | | | | | | | | | | | |
| 66+30-5.50' R to 64+78-5 | | 24 | 152 | | | | | | | | | | | | |
| 66+28-28.17' R to 66+30 | | 24 | 152 | | | | | | | | | | | | |
| 67+60-5.30' R to 66+30-5 | | 24 | 132 | | | | | | | | | | | | |
| 67+78-28.17' R to 67+60 | | | 28 | | | | | | | | | | | | |
| 69+28-28.17' R to 67+78 | | | | | | | | | | | | | | | |
| 70+78-29.17' R to 69+28 | | | 150 | | | | | | | | | | | | |
| | | 440 | 150 | | | | | | | | | | | | |
| 71+88-29.17' R to 70+78 | | 110 | | | | | | | | | | | | | |
| 71+88-29.17' L to 71+88- | | 58 | | | | | | | | | | | | | |
| 73+93-28.67' R to 71+88 | | 206 | | | | | | | | | | | | | |
| 73+93-28.67' L to 73+93- | | 58 | | | | | | | | | | | | | |
| 74+98-29.17' R to 73+93 | | 106 | | | | | | | | | | | | | |
| 75+18-29.17' L to 74+98- | | 60 | | | | | | | | | | | | | |
| 75+88-29.17' R to 74+98 | | 90 | | | | | | | | | | | | | |
| 77+83-31.50' R to 75+88 | | 196 | | | | | | | | | | | | | |
| 77+85-4.20' R to 77+84-3 | | 26 | | | | | | | | | | | | | |
| 77+85-3.83' L to 77+85-4 | | 8 | | | | | | | | | | | | | |
| 77+87-29.17' L to 77+85- | -3.83' L | 26 | | | | | | | | | | | | | |
| Wynoka Street | | | | | | | | | | | | | | | |
| 926+41-14.43' R to 927+ | | | | | | 86 | | | | | | | | | |
| 927+32-7.41' R to 929+8 | 5-9.42' R | | | | | 248 | | | | | | | | | |
| 929+82-17.70' R to 929+ | | 6 | | | | | | | | | | | | | |
| 929+85-9.42' R to 930+2 | | | | | | 34 | | | | | | | | | |
| 930+23-11.68' R to 932+ | 73-9.02' R | | | | | 250 | | | | | | | | | |
| 932+73.9.02' R to 933+53 | 3-7.96' R | | | | | 80 | | | | | | | | | |
| 933+53-7.96' R to 935+0 | 6-5.82' R | | | | | 20 | | | | | | 164 | 2 | 1 | |
| 935+06-5.82' R to 935+5 | 9-82.21' L | | | | | 100 | | | | | | | | | |
| 935+59-82.21' L to 936+2 | 20-82.39' L | | | | | 6 | | | | | | 50 | 2 | 1 | |
| 936+20-82.39' L to 938+3 | 35-83.47' L | | | | | 210 | | | | | | | | | |
| 938+35-83.47' L to 936+0 | 02-83.96' L | | | | | | | 64 | | 1 | | | | | |
| | Totals: | 1588 | 1110 | 0 | 0 | 1034 | 0 | 64 | 0 | 1 | 0 | 214 | 4 | 2 | 0 |
| | Grand Total: | | 2028 | 542 | 826 | 2090 | 162 | 64 | 398 | 1 | 1 | 214 | 4 | 2 | 28 |

| | STATE OF | PROJECT | SHEET | TOTAL SHEETS |
|------|-----------------|--|--------|-----------------|
| | SOUTH DAKOTA | NH-CR 0014(185)229 | B21 | B151 |
| | | REV 08-12 | -24 GE | |
| | | REV 08-27 | -24 GE | |
| | | REV 12-05 | -24 GE | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | AMIIIIIIIII | | |
| | IIIIIII PRO | FESSIONING | | |
| 3 | 110 87.8 | EG NO SALL | | |
| | ALL A | | | |
| E | | | | |
| | the | AMILTON | | |
| 1111 | d' sh | TR. DI | | |
| | 11111 10 | TH DANS | | |
| | 111/11 | 106/200000000000000000000000000000000000 | | |
| | | | | |
| | | | | |
| | | | | |





| <u> </u> | STATE OF | PROJECT | SHEET | TOTAL SHEETS |
|----------|--------------------|------------------------|---------|-----------------|
| | SOUTH DAKOTA | NH-CR 0014(185)229 | B62 | B151 |
| | Plotting Date: | 12/5/2024 REV 12-05 | -24 GCE | |
| | | | | 5 2 |
| | | | | |
| | | | | |
| | | | | 1560 |
| | | | | |
| | | | | |
| | | | | 1555 |
| | NINH PBC | FESSION | | |
| | IIII. 6 K | G. No Anti | | 1550 |
| | 32.18 | | | 1550 |
| | | 13586 | | |
| | EF. | TNATO | | 1545 |
| | = 7: 23 | | | |
| | | | | |
| | 110 | 19 . ALONG WIL | | 1540 |
| | 111, 10 | | | |
| | 11/11/12 | -06 Cymmin | | |
| | | | | 1535 |
| | | | | |
| | | | | |
| | | | | 1530 |
| | | | | |
| | | | | 4505 |
| | | | | 1525 |
| | | | | |
| | | | | 1520 |
| | | | | 1520 |
| | | | | |
| | | | | 1515 |
| | | | | 1010 |
| | | | | |
| | | | | 1510 |
| | | | | |
| | | | | |
| | | | | 1505 |
| | | | | |
| | | | | |
| | | | | 1500 |
| | | | | |
| | | | | |
| | | | | 1495 |
| | | | | |
| | | | | 1490 |
| | | | | 1490 |
| | | | | |
| | 40"F | 2P 0.6260% | | 1485 |
| | 42 04 | . ~ 0.0∠00% | | 1400 |
| | | | | |
| | | | | 1480 |
| | | | | |
| | | | | |
| | | | | 1475 |
| | | | | |
| | | | | |
| 1 | | | | 1470 +00 |



| | | DDO IEOT | | TOTAL |
|--------------|-----------------------------|---|-----------------------------------|-------------------------|
| | STATE OF SOUTH DAKOTA | PROJECT NH-CR 0014(185)229 | SHEET B63 | TOTAL SHEETS B151 |
| | | | REV 11-1 REV 12-0 REV 08-20 | |
| 1 | | | REV 08-26 REV 12-05 | 5-24 GCE 5-24 GCE |
| | | | | |
| | | | | |
| \mathbf{A} | | | | |
| Ŷ | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | OFESSION ANTIN | | |
| | WIIIIII | QFESSIO | | |
| | IIII P | REG NO TO | | |
| ŝ | E E | | | |
| | | 13586 | | |
| | All | HAMILTON TTE | | |
| - | | | | |
| | 1111 | TH DAYO | | |
| | 11111 | 2/06/04/10/11/11/11 | | |
| | | Manna and a second s | | |
| | | | | |
| | | | | |
| | | | | |
| | | | - | |
| | | | ┝ | C |
| | | | | |

SECTION C ESTIMATE OF QUANTITIES*

| BID ITEM | ITEM | QUANTITY | UNIT |
|----------|---|----------|------|
| 633E6005 | Pavement Marking Masking, 5" | 885 | Ft |
| 633E6035 | Pavement Marking Masking, Combination Arrow | 4 | Each |
| 634E0010 | Flagging | 1,000.0 | Hour |
| 634E0110 | Traffic Control Signs | 1,178.7 | SqFt |
| 634E0120 | Traffic Control, Miscellaneous | Lump Sum | LS |
| 634E0135 | Traffic Control Supervisor | Lump Sum | LS |
| 634E0275 | Type 3 Barricade | 58 | Each |
| 634E0330 | Temporary Raised Pavement Markers | 21,589 | Ft |
| 634E0420 | Type C Advance Warning Arrow Board | 2 | Each |
| 634E0640 | Temporary Pavement Marking | 26,283 | Ft |
| 634E0700 | Traffic Control Movable Concrete Barrier | 17 | Each |
| 634E1002 | Detour and Restriction Signing | 1,492.5 | SqFt |
| 634E1020 | Temporary Business Signing | 98.4 | SqFt |
| 634E1215 | Contractor Furnished Portable Changeable Message Sign | 3 | Each |
| 634E2000 | Longitudinal Pedestrian Barricade | 348 | Ft |
| 634E2015 | Temporary Pedestrian Access Route | Lump Sum | LS |
| 634E2020 | Temporary Curb Ramp | 5 | Each |
| 634E2025 | Longitudinal Pedestrian Barrier | 1,705 | Ft |

*Some quantities are based on the maximum number of TC phases that can be implemented simultaneously. See "Mainline Phases" notes below.

SEQUENCE OF OPERATIONS

Contractor requests to deviate from the sequence of operations will be submitted in writing to the Engineer for review. Approval of an alternate sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work. An alternate sequence will be submitted for review a minimum of one week prior to potential implementation.

Work on this project will consist of pavement removal, grading, storm sewer, utility relocation, traffic signal removal and installation, ADA improvements, PCC installation, asphalt concrete resurfacing, and permanent pavement marking.

The Contractor will be required to maintain all detour routes throughout the length and duration of the project to the satisfaction of the Engineer. Locations for repair will be determined by the Engineer. See Section F for quantities.

Details in the traffic control plans are based on the following sequence of operations for construction of the project. The sequencing is based on anticipated areas of construction. Mainline Phases 1 & 2 can be worked on concurrently, and the side-street phases (Wynoka St. and Elizabeth St.) can be worked on in conjunction with any mainline phase. Additional concurrent work will be allowed if resources are proven available, concurrent work is supported by the construction schedule, and the work is ultimately approved by the Engineer. The work will be divided into the following phases:

MAINLINE PHASE 1A/1B/1C/1D/1E

Phase 1 will consist of work on the Sioux Ave./South Pierre St. intersection as well as mainline S Pierre St./Pleasant Dr. Work on Sioux Ave will be in the westbound lane from approximately Sta. 900+91.25 to Sta. 901+91.70. Work on S Pierre St. will be from approximately Sta. 10+00 to Sta. 32+70. Work on Pleasant Dr. will be from approximately Sta. 906+00 to Sta. 910+55.

- During Phase 1A, the Contractor will set up two-way traffic in the westbound lanes of Sioux Ave. to complete all work on the south side of the S Pierre St./Sioux Ave. intersection. Work from approximately Sta. 10+37 to 12+66 will be allowed on S Pierre St. as a full road closure. This work will continue into Phases 1B and 1C. The two-way traffic will be set up for continuous flow in both directions, with no turning movements allowed. S Pierre St. south of the intersection will be given two-way functionality. Phase 1A will consist of work from approximately Sta. 9+50 to Sta. 10+00 (S Pierre St. alignment).
 - During phases 1A-1C, S Pierre St. will be open to southbound traffic from Pleasant Dr. in order to access the Federal Building and Walgreens. A U-turn will be implemented just north of the work zone in order to return traffic to Pleasant Dr., and a temporary access will be set up from the alley north of the Federal Building to provide access to the parking lot. Direct access to the Federal Building from S Pierre St. will be closed.
 - Traffic intending to access S Pierre St. south of the intersection will be detoured to Highland Ave. and Central Ave., with access then provided off Dakota Ave. This portion of S Pierre St. will be reconfigured as a two-way road for the duration of Phases 1A-1C, with a U-turn at the north end to return traffic back to Dakota Ave. See sheets C16, C32, and C44 for detailing.
- During Phase 1B, the Contractor will set up continuous two-way traffic in the eastbound lanes of Sioux Ave. No turning movements from Sioux Ave. will be allowed, as in Phase 1A. Phase 1B will consist of work from approximately Sta. 10+00 to Sta. 12+66.
- During Phase 1C, the Contractor will set up two-way traffic in the outermost lanes of Sioux Ave. to accommodate resurfacing work in the middle of the intersection. The two-way functionality of S Pierre St. will be removed, and access re-opened from Sioux Ave., following completion of Phase 1C work. No turning movements from Sioux Ave. will be allowed, as in Phase 1A.
- During Phase 1D, the U-turn at the Federal Building/Walgreens will be flipped and placed facing south at roughly Sta. 12+66. S Pierre St. will be closed in its entirety from Sta. 12+66 to Pleasant Dr. Two-way traffic will be implemented in the existing westbound lanes of Pleasant. The gravel access through the alley to the Federal Building will be maintained, and access to Walgreens and the alley will be closed off. Work will extend past the limits of S Pierre St. onto Pleasant Dr. Phase 1D will consist of work from approximately Sta. 12+66 to Sta. 18+00 on S Pierre St., and from Sta. 906+00 to 910+55 on Pleasant Dr.
- During Phase 1E, Pleasant Dr. will be closed off at the west intersection with S Pierre St. Two-way traffic will be implemented in the eastbound lanes, with ingress/egress allowed only onto S Pierre St. south of Pleasant Dr. and onto Pleasant Dr. east of the work zone. The U-turn will be moved to roughly Sta. 18+10 facing north to return traffic to Capitol Ave. Phase 1E will consist of work from approximately Sta. 12+50 to Sta. 18+80 on S Pierre St., and from Sta. 906+00 to 910+55 on Pleasant Dr.

Phase 1 will consist of removal and installation of storm sewer reinforced concrete pipe/inlets, removal and installation of manholes, installation of junction boxes, traffic signal replacement, pedestrian push buttons, grading, curb and gutter, sidewalk, city utility work, PCC and asphalt resurfacing, and permanent pavement markings. Work will also include tying new storm sewer into the existing storm sewer system in all directions to maintain drainage on the project at all times.

Revised 12/0

The Contractor will take the following additional considerations into account during Phase 1 operations:

- sheets C33-C36.

MAINLINE PHASE 2A/2B/2C/2D

Phase 2 will consist of sequential full-width closures on Euclid Ave. between Pleasant Dr. and Wynoka St. from approximately Sta. 18+80 to Sta. 32+70. These closures are allowed to take place concurrently with Phases 1A-1C. Phase 2 closures will only be worked south to north. Egress onto at least one of the side streets within Phase 2 work limits (Capitol Ave, Prospect Ave, Broadway Ave) will be maintained at all times. If the Contractor elects to close any side street/Euclid intersection at half-intersection width, traffic control will be set up in accordance with Standard Plate 634.25. Block closure phases are as follows:

Phase 2 will consist of removal and installation of storm sewer reinforced concrete pipe/inlets, removal and installation of manholes, installation of junction boxes, grading, curb and gutter, sidewalk, city utility work, asphalt concrete resurfacing, and permanent pavement markings. Work will also include tying new storm sewer into the existing storm sewer system in all directions to maintain drainage on the project at all times.

The Contractor will take the following additional considerations into account during Phase 2 operations:

MAINLINE PHASE 3A/3B/3C

Phase 3 will consist of work from approximately Sta. 32+70 to Sta. 61+50 on Euclid Ave. Phase 3A will consist of a block closure from approximately Sta. 32+70 to Sta. 47+00. Phases 3B/3C will consist of two-way traffic from approximately Sta. 47+00 to 61+50, with Phase 3B being the southbound lane closures and Phase 3C being the northbound lane closures. 3A can be worked on concurrently with 3B and 3C.

Utility adjustments on the south side of the Euclid/4th St intersection will require a full road closure of Euclid. This closure will be implemented at a time during Phase 3B or 3C where it is suitable to work on the existing utilities south of the intersection. Traffic control will be set up to allow stop-controlled traffic on 4th St., and full access to Euclid north of the intersection. This closure will be limited to 3 weeks, and will not take place during school season. See sheet C23 for detailing.

| /06/2024 JDC | |
|--------------|--|
| | |

| STATE OF | PROJECT | SHEET | TOTAL SHEETS | |
|-----------------|--------------------|-------|-----------------|--|
| SOUTH DAKOTA | NH-CR 0014(185)229 | C2 | C46 | |

1. OVERWIDTH DETOUR – During Phases 1A-1C, overwidth traffic on Sioux Ave. will be diverted north around the Oahe Dam as detailed on

2. Work on Phase 1D will not begin until work on Phase 1C is completed. 3. Phase 1E can be worked on concurrently with Phases 1A-1C. If the Contractor elects to do this. Phase 1D will take place after 1E, and existing road width will be utilized to allow egress onto Pleasant Dr. west of the work zone. Phase 2A will not be worked on if 1E is closed.

> • Phase 2A – Approx. Sta 18+80 to Sta. 22+11 • Phase 2B – Approx. Sta. 22+11 to Sta. 26+18 • Phase 2C – Approx. Sta. 26+18 to Sta. 30+47 • Phase 2D – Approx. Sta. 30+47 to Sta. 32+70

1. Phase 2A will not be worked on concurrently with Phase 1E. 2. Only 2 sub-phases (i.e. 2A and 2B) will be worked on at a time. All surfacing on the first closure will be completed prior to beginning another phase (i.e. 2A is surfaced before 2C is closed to traffic). 3. A detour as detailed on sheet C38 will be established during all fullwidth closures to divert thru traffic to Garfield Ave.

TABLE OF TR

| | CES* Revised 12/06/2024 JDC STATE OF SOUTH DAKOTA NH-CR 0014(1) | | | | | PROJECT | SHEET | ٦ S | | |
|---------------|--|--|--|---|--|--|-------|--------------------|-----|--|
| CONTROL DEVIC | <u>CES*</u> | | | | Revised 12/ | Revised 12/06/2024 JDC | | NH-CR 0014(185)229 | C11 | |
| | | FOR TRAFFIC CC | ONTROL DELINEATION A | ND MARKING (TOTAL <u>APPLIC</u> | ATION ESTIMATES) | | | | | |
| PHASE | TEMPORARY RAISED PAVEMENT MARKER (4" YELLOW UNLESS OTHERWISE SPECIFIED) | BALLASTABLE JERSEY BARRIER (EDGELINE) | TUBULAR MARKER (CENTERLINE) (N.A.B.I.) | TRAFFIC CONTROL DRUM (EDGELINE/TAPERS) (N.A.B.I.) | TRAFFIC CONTROL MOVABLE CONCRETE BARRIER | TRAFFIC CONTRO CANDLESTICK (DELINEATOR (N.A.B.I.) | | (DELINEATOR | | |
| | (ft) | (ft) | (each) | (each) | (each) | (eac | h) | (each) | | |
| 1A | 1971 (yellow) 290 (white) | - | 44 | 98 | 17 | 8 | | 37 | | |
| 1B | 985 | - | 44 | 98 | 12 | 8 | | 37 | | |
| 1C | 842 | - | 37 | 65 | 4 | 14 | | 37 | | |
| 1D | 692 | 455 | 15 | 20 | - | 9 | | - | | |
| 1E | 1005 | 315 | 22 | 17 | - | 9 | | | | |
| 2A/2B/2C/2D | - | - | - | - | - | 20 | | - | | |
| 3A | 2846 | - | - | - | - | 31 | | - | | |
| 3B | 2534 | 1410 | 51 | 12 | - | 17 | | - | | |
| 3C | 2396 | 1410 | 51 | 12 | - | 18 | | - | | |
| 3 UTIL RELOC | 468 | - | 15 | 10 | - | 16 | | - | | |
| 4A | 3638 | 1705 | 79 | 45 | - | 14 | | - | | |
| 4B | 3922 | 1705 | 79 | 45 | - | 24 | | - | | |
| TOTALS: | 21589 | 7000 | 437 | 422 | 33 | 188 | 3 | 37 | 1 | |

TABLE OF TEMPORARY PAVEMENT MARKING**

**If the Contractor wishes to restore traffic to a hard surface prior to permanent pavement marking being placed down, temporary marking in the form of raised pavement markers (tabs), tape, or paint will be applied.

Temporary marking paint will only be applied to existing permanent surfacing, temporary surfacing, or any combination of the two. Temporary marking paint will not be applied to new permanent surfacing.

If the Contractor places a temporary surface over the winter months as defined in the Special Provision for "Winter Months Hard Surfacing Requirement", all markings placed on the temporary surface will be temporary marking paint only.

| | FOR PERMANENT PAVEMENT MARKING | | | | |
|----------------|---|---|--|--|--|
| PHASE | TEMPORARY PAVEMENT MARKING (4" WHITE) | TEMPORARY PAVEMENT MARKING (4" YELLOW) | | | |
| | (ft) | (ft) | | | |
| 1A/1B/1C/1D/1E | 1262 | 2631 | | | |
| 2A/2B/2C/2D | 2607 | 3462 | | | |
| 3A | 1942 | 2813 | | | |
| 3B/3C | 688 | 2835 | | | |
| 4A/4B | 1891 | 5023 | | | |
| ELIZABETH ST. | 201 | 928 | | | |
| TOTALS: | 8591 | 17692 | | | |
| | 26283 | | | | |

*S. Pierre St. configuration quantities included in Phase 1A, 1B, and 1C entries.