

March 12, 2024

ADDENDUM NO. 1

RE: Item #9, March 20, 2024 Letting - NH 0037(164)24, PCN 06PN, Bon Homme, Hutchinson County - Cold Milling, Asphalt Concrete Resurfacing, Pipe Work

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made a part of your proposal for the referenced project.

SPECIAL PROVISIONS: NO CHANGE

SDEBS BID PROPOSAL: *The electronic bid proposal for this contract has been revised to include the changes associated with this addendum. Bidders must log in to the SDEBS to retrieve and incorporate these changes into their bid.*

Bid Items were added:

Bid Item 720E1010 "PVC Coated Bank and Channel Protection Gabion"

Bid Items were removed:

Bid Item 720E1015 "Bank and Channel Protection Gabion"

PLANS: Please destroy sheet 2 and replace with the enclosed sheets, dated 3/12/24.

Sheet 2: **Bid Items were added:**

Bid Item 720E1010 "PVC Coated Bank and Channel Protection Gabion"

Bid Items were removed:

Bid Item 720E1015 "Bank and Channel Protection Gabion"

Sincerely,

Sam Weisgram
Engineering Supervisor

SW/cj

CC: Travis Dressen, Mitchell Region Engineer
Greg Rothschadl, Yankton Area Engineer

ESTIMATE OF QUANTITIES

STATE OF SOUTH DAKOTA	PROJECT NH 0037(164)24	SHEET 2	TOTAL SHEETS 63
-----------------------------	----------------------------------	-------------------	------------------------------

Rev. 03/12/24 GAW

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E0135	Remove Delineator	47	Each
110E0500	Remove Pipe Culvert	68	Ft
110E0510	Remove Pipe End Section	2	Each
110E0595	Remove Cattle Pass End Section	2	Each
110E0600	Remove Fence	174	Ft
110E0730	Remove Beam Guardrail	350.0	Ft
110E0800	Remove W Beam Guardrail End Terminal	8	Each
110E1010	Remove Asphalt Concrete Pavement	1,827.0	SqYd
110E7500	Remove Pipe for Reset	90	Ft
110E7510	Remove Pipe End Section for Reset	16	Each
120E0010	Unclassified Excavation	1,229	CuYd
120E0100	Unclassified Excavation, Digouts	595	CuYd
120E0600	Contractor Furnished Borrow Excavation	1,332	CuYd
260E1010	Base Course	2,624.0	Ton
* 260E6000	Granular Material, Furnish	7,682.0	Ton
* 270E0200	Blend, Haul, and Stockpile Granular Material	15,364.0	Ton
320E0005	PG 58-34 Asphalt Binder	1,443.1	Ton
320E1200	Asphalt Concrete Composite	346.0	Ton
320E1203	Class Q3R Hot Mixed Asphalt Concrete	28,163.0	Ton
320E1800	Asphalt Concrete Blade Laid	1,786.0	Ton
320E4000	Hydrated Lime	296.6	Ton
320E7008	Grind 8" Rumble Strip or Stripe in Asphalt Concrete	23.9	Mile
320E7040	Grind 6" Transverse Rumble Strip in Asphalt Concrete	408.0	Ft
330E0100	SS-1h or CSS-1h Asphalt for Tack	136.1	Ton
330E0210	SS-1h or CSS-1h Asphalt for Flush Seal	2.4	Ton
332E0010	Cold Milling Asphalt Concrete	247,461	SqYd
421E0100	Pipe Culvert Undercut	26	CuYd
450E0182	36" RCP Class 2, Furnish	74	Ft
450E0190	36" RCP, Install	74	Ft
450E2028	36" RCP Flared End, Furnish	2	Each
450E2029	36" RCP Flared End, Install	2	Each
450E3052	48" RCP Arch Class 2, Furnish	62	Ft
450E3060	48" RCP Arch, Install	62	Ft
450E4520	48" RCP Arch Flared End, Furnish	2	Each
450E4521	48" RCP Arch Flared End, Install	2	Each
450E8300	Culvert Joint Cleaning	308.0	Ft
450E8305	Repair Culvert Joint	308.0	Ft
450E8310	Chemical Grout Void Fill	22.0	Gal
* 450E8900	Cleanout Pipe Culvert	1	Each
450E9000	Reset Pipe	90	Ft
450E9001	Reset Pipe End Section	16	Each
464E0100	Controlled Density Fill	14.0	CuYd

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
600E0300	Type III Field Laboratory	1	Each
620E0020	Type 2 Right-of-Way Fence	142	Ft
620E1020	2 Post Panel	4	Each
620E1030	3 Post Panel	2	Each
630E0500	Type 1 MGS	750.0	Ft
630E1501	Type 1 Retrofit Guardrail Transition	8	Each
630E2017	MGS MASH Flared End Terminal	8	Each
632E2220	Guardrail Delineator	36	Each
632E2510	Type 2 Object Marker Back to Back	74	Each
633E1200	High Build Waterborne Pavement Marking Paint, White	542	Gal
633E1205	High Build Waterborne Pavement Marking Paint, Yellow	204	Gal
634E0010	Flagging	670.0	Hour
634E0020	Pilot Car	310.0	Hour
634E0110	Traffic Control Signs	1,023.6	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0275	Type 3 Barricade	2	Each
634E0630	Temporary Pavement Marking	35.7	Mile
720E1010	PVC Coated Bank and Channel Protection Gabion	74.0	CuYd
730E0204	Type C Permanent Seed Mixture	45	Lb
732E0100	Mulching	5.0	Ton
734E0102	Type 2 Erosion Control Blanket	1,783	SqYd
734E0103	Type 3 Erosion Control Blanket	1,800	SqYd
734E0510	Shaping for Erosion Control Blanket	1,105	Ft
831E0110	Type B Drainage Fabric	206	SqYd
900E0010	Refurbish Single Mailbox	6	Each
900E1980	Storage Unit	1	Each

* - Denotes Non-Participating

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications and Special Provisions as included in the Proposal.