

October 26, 2023

**ADDENDUM NO. 1**

**RE: Item #5, November 1, 2023 Letting - NH 0012(281)233, PCN 06PV, Edmunds County - Cold Milling, Asphalt Concrete Resurfacing, Pipe Work (End Sections)**

**TO WHOM IT MAY CONCERN:**

The following addenda to the plans shall be inserted and made a part of your proposal for the referenced project.

**SPECIAL PROVISIONS:** NO CHANGE

**SDEBS BID PROPOSAL:** *The electronic bid proposal for this contract has been revised to include the changes associated with this addendum. Bidders must log in to the SDEBS to retrieve and incorporate these changes into their bid.*

**Bid Items were added:**  
Bid Item 634E0630 "Temporary Pavement Marking"

**PLANS:** Please destroy sheet 2 and replace with the enclosed sheet, dated 10/19/23.

**Sheet 2:** Bid Item 634E0630 "Temporary Pavement Marking" was added.

Sincerely,

Sam Weisgram  
Engineering Supervisor

SW/cj

CC: Mark Peterson, Aberdeen Region Engineer  
Bruce Schroeder, Aberdeen Area Engineer

# ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	NH 0012(281)233	2	51

Revised: 10/19/2023 PB

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E0510	Remove Pipe End Section	20	Each
110E1010	Remove Asphalt Concrete Pavement	1,119.0	SqYd
110E1690	Remove Sediment	1.0	CuYd
110E1700	Remove Silt Fence	200	Ft
110E7500	Remove Pipe for Reset	178	Ft
110E7510	Remove Pipe End Section for Reset	21	Each
120E0100	Unclassified Excavation, Digouts	746	CuYd
250E0020	Incidental Work, Grading	Lump Sum	LS
260E1010	Base Course	2,696.5	Ton
320E0005	PG 58-34 Asphalt Binder	1,963.9	Ton
320E1200	Asphalt Concrete Composite	373.9	Ton
320E1203	CLASS Q3R HOT MIXED ASPHALT CONCRETE	38,492.9	Ton
320E1800	Asphalt Concrete Blade Laid	2,237.3	Ton
320E4000	Hydrated Lime	406.5	Ton
320E7012	Grind 12" Rumble Strip or Stripe in Asphalt Concrete	29.0	Mile
320E7028	Grind Centerline Rumble Stripe in Asphalt Concrete	12.4	Mile
320E7030	Grind Sinusoidal Centerline Rumble Stripe in Asphalt Concrete	2.1	Mile
330E0100	SS-1h or CSS-1h Asphalt for Tack	193.1	Ton
330E0210	SS-1h or CSS-1h Asphalt for Flush Seal	68.2	Ton
330E2000	Sand for Flush Seal	841.9	Ton
332E0010	Cold Milling Asphalt Concrete	320,635	SqYd
450E2008	18" RCP Flared End, Furnish	12	Each
450E2009	18" RCP Flared End, Install	12	Each
450E2016	24" RCP Flared End, Furnish	6	Each
450E2017	24" RCP Flared End, Install	6	Each
450E2204	30" RCP Sloped End, Furnish	2	Each
450E2205	30" RCP Sloped End, Install	2	Each
* 450E8900	Cleanout Pipe Culvert	5	Each
450E9000	Reset Pipe	178	Ft
450E9001	Reset Pipe End Section	21	Each
600E0300	Type III Field Laboratory	1	Each
633E0030	Cold Applied Plastic Pavement Marking, 24"	166	Ft
633E0040	Cold Applied Plastic Pavement Marking, Arrow	6	Each
633E0046	Cold Applied Plastic Pavement Marking, Lane Reduction Arrow	5	Each
633E1200	High Build Waterborne Pavement Marking Paint, White	700	Gal
633E1205	High Build Waterborne Pavement Marking Paint, Yellow	270	Gal
633E5015	Grooving for Cold Applied Plastic Pavement Marking, 24"	166	Ft
633E5025	Grooving for Cold Applied Plastic Pavement Marking, Arrow	6	Each
633E5031	Grooving for Cold Applied Plastic Pavement Marking, Lane Reduction Arrow	5	Each
634E0010	Flagging	820.0	Hour
634E0020	Pilot Car	275.0	Hour
634E0110	Traffic Control Signs	679.2	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0630	Temporary Pavement Marking	60.0	Mile
734E0010	Erosion Control	Lump Sum	LS
734E0154	12" Diameter Erosion Control Wattle	200	Ft
734E0604	High Flow Silt Fence	200	Ft
734E0610	Mucking Silt Fence	15	CuYd
900E0010	Refurbish Single Mailbox	8	Each
900E1980	Storage Unit	1	Each

## SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

\* - Denotes Non-Participating