

Planning & Engineering Office of Project Development

700 E Broadway Avenue Pierre, South Dakota 57501-2586 O: 605.773.3268 | F: 605.773.2614 dot.sd.gov

February 25, 2022

ADDENDUM NO. 1

RE: Item #6, March 2, 2022 Letting - NH-P 0043(34), PCN 0884, Fall River, Oglala Lakota County - Rout & Seal

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made a part of your proposal for the referenced project.

SPECIAL PROVISIONS: NO CHANGE

SDEBS BID PROPOSAL: NO CHANGE

- **PLANS:** Please destroy sheets 1, 3, 6, and 7 and replace with the enclosed sheets, dated 2/24/22. Sheet 7a was added.
 - **Sheet 1**: The title was changed from SD Highway 79 to SD Highway 71.
 - **Sheet 3:** TRAFFIC CONTROL notes were revised to allow mobile work operation.
 - **Sheets 6, 7, & 7a**: Standard Plate 634.06 was added and Standard Plate placement was adjusted.

Sincerely,

Sam Weisgram Engineering Supervisor

SW/cj

CC: Todd Seaman, Rapid City Region Engineer Rich Zacher, Custer Area Engineer



	STATE OF	PROJECT	SHEET	TOTAL SHEETS		
	SOUTH DAKOTA	NH-P 0043(34)	1	7		
<u>[</u>	Plotting Date: 02/24/2022 Revised Date: 2/24/21 jpr					
4)		INDEX OF SHEE	TS			
-,	Sheets 1: Title Sheet					
Sheet 2-4: Estimate of Quantities & Plan Notes						
Sheet 5: Crack Sealing Details						
	Sheets 6-7: Standard Plates					
ΓIES						

ile - ...\2022\0884_Title.dgn

ROADWAY CLEANING

The Contractor will be responsible for removing the router tailings from the roadway surface, including shoulders, intersecting roads, median crossovers, sidewalks, etc. as directed by the Engineer.

A Pickup Broom will be required to remove the router tailings from the project as per Sec. 360.3.B.1..

CRACK SEALING

All guantities are based on a factor of 0.4 lbs. of sealant per 1 foot of existing crack. Actual quantities used may vary depending upon the location and width of the existing crack. Rates may vary as directed by the Engineer.

The Typical Reservoir Section will be 3/4 inch wide x 3/4 inch deep.

The use of a squeegee will not be allowed on this project except for locations where the sealant begins to run out of the routed crack due to the grade or superelevation of the road and at locations where cracks are less than 6" apart. The squeegee will be used to push the sealant material back into the crack and remove as much sealant as possible from the roadway surface at these locations.

All other requirements stated in Section 350 of the Specifications will apply.

At locations with multiple cracks less than 6" apart, route only the widest crack. Routing will not be required to seal the remaining cracks. Trace these remaining cracks with sealant and use a squeegee to level and fill.

TABLE OF CRACK SEAL QUANTITIES

Highway	MRM to		MRM		Length (Miles)	Asphalt Concrete Crack Sealing (Lb)
US18	62.25+	0.000	87.52+	0.265	25.522	1,383
SD71	0+	0.000	17+	0.568	16.962	1,648
			Total		42.484	3,031

SEQUENCE OF OPERATIONS

The Contractor will submit a sequence of operations for approval two weeks prior to the preconstruction meeting. If changes to the sequence of operations are proposed during the project, these must be submitted for review a minimum of one week prior to potential implementation. Approval for changes to the sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work.

TRAFFIC CONTROL

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices, including delineation, will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost will be replaced by the Contractor at no cost to the State.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation.

All construction operations will be conducted in the general direction of traffic movement.

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Traffic will be maintained on the driving lanes. Use of the shoulder as a driving lane will not be permitted. Any damage to the shoulder due to rerouted traffic or Contractor's equipment will be repaired at no expense to the Department.

Lane closures will be removed prior to nightfall.

A mobile work operation will be allowed provided the crack sealing can be completed by a continuously moving work operation. A mobile work operation will require approval by the Engineer.

TRAFFIC CONTROL SIGNS

FLAGGING

Operations will be conducted so that the traveling public will not have to wait longer than 15 minutes at the flagger station.

Included in the Estimate of Quantities are WAIT FOLLOW PILOT CAR signs for use on low volume intersecting roads as determined by the Engineer. WAIT FOLLOW PILOT CAR signs will not block the view of the stop sign.



It is required that the flaggers and pilot car operators be able to communicate with one another. If an emergency vehicle needs to pass through the project, the Contractor will be required to expedite traffic movement. All costs associated with this will be incidental to the contract unit price per hour for "Flagging".

	STATE OF	PROJECT	SHEET	TOTAL SHEETS			
	DAKOTA	NH-P 0043(34)	3	7			
Revised 2/24/21 ipr							

Traffic control signs have been included in a table for each route. Payment will only be for those signs used on each route.



			S D			
The leng fit field c	th of A may be adj onditions.	usted to				1
be used control in required The buff so that ti placed b curve to distance of stopp	at intersecting road ntersecting road tra- er space should be he two-way traffic to efore a horizontal of provide adequates for the flagger and ed vehicles.	ds to fffic as extended aper is or vertical sight l queue				1
Channel	izing devices and f	laggers will		r		
area.	END BOAD WORK G20-2					
Channel along the area whe escorting	izing devices are n e centerline adjace en pilot cars are uti g traffic through the	ot required nt to work lized for work				
The cha or 42" co	nnelizing devices wones.	vill be drum:	6			
Flashing may be advance	warning lights and used to call attentic warning signs.	l/or flags on to the				01
For tack when fla FRESH in advar	and/or flush seal o ggers are not being OIL sign (W21-2) v ice of the liquid asp	perations, g used, the vill be displa halt areas.	ayed			⊥
The RO WORK s duration	AD WORK AHEAD signs may be omitte operations (1 hour	and the ENed for short or less).	ID R	ROAD	[]	/
with sho roadway to road u direction	rt work zones on st s where the flagge users approaching s, a single flagger	raight r is visible from both may be use	d.		/	[].
- -	Channelizing Dev	vice				
<u>60 - 65</u>	1000 Flagger	50				
55	750	50				
45	500	25				
35 - 40	350	25				
0 - 30	200	25	-			
Work	(Feet)	(Feet)				as b
Speed Prior to	Advance Warning Signs	Channelizir Devices	ng			Wari in op
<u> </u>		Spacing o				









STATE OF	PROJECT	SHEET	TOTAL
SOUTH DAKOTA	NH-P 0043(34)	7a	7
Plotting Date: Revised Date:	02/24/2022 2/24/21 jpr		