

Advertisement of Highway Bid Letting

Electronic Bids for the following construction projects will be received by the South Dakota Department of Transportation (SDDOT) via the South Dakota Electronic Bid System (SDEBS) until 10 A.M. Central time, on August 19, 2026, at which time the SDDOT will open bids. All bids will be checked for qualifications with results posted on the SDDOT website.

ITEM NO.	PROJECT NUMBER	COUNTY	LENGTH MILES	TYPE OF WORK	DESCRIPTION OF LOCATION
* 1.	BRO-B 8055(37) (PCN 09ML)	Roberts SWPPP = 0.71 AC	0.200	Structure (3-11'x7' CIP RCBC) & Approach Grading	Structure 0.5 N & 0.7 E of Claire City on 105 St over Little Minnesota Rv, SN 55-068-050
* 2.	BRF-B 6202(07) (PCN 09M7)	Roberts SWPPP = 0.79 AC	0.200	Structure (2-12x6 CIP RCBC) & Approach Grading	Structure 3 E & 6.5 S of Claire City on 112 St over Little Minnesota Ck, SN 55-091-120
3.	BRO-B 8025(17) (PCN 09LX)	Faulk SWPPP = 0.06 AC	---	Structure Removal (72' Pony Truss)	Structure 9.7 N & 2 W of Zell on 370 Ave over the South Fork of Snake Ck, SN 25-390-143
4.	PH 8037(02) (PCN 04L5)	Jerauld	---	Signing & Delineation	Various County, City, & Township Roads in Jerauld Co

* Indicates combination bids

<> Indicates Optional Combination Bids

SWPPP = Storm Water Pollution Prevention Plan

ITEMS INVOLVED ARE AS FOLLOWS

1.	BRO-B 8055(37)	Area Engineer: Matt Brey, 5000 9th Avenue SE, Watertown, SD, 57201			Phone: 605/882-5166
	Work Type 9	DBE Goal: NONE	Contract Id: 9895	See Special Provisions for Completion Requirements	
	1 Mobilization		LS		1.000
	2 Incentive/Disincentive Pay		Day		0.000
	3 Grade Staking		Mile		0.066
	4 Miscellaneous Staking		Mile		0.066
	5 Slope Staking		Mile		0.066
	6 Structure Staking		Each		1.000
	7 Engineer Directed Surveying/Staking		Hour		20.000
	8 Construction Schedule, Category II		LS		1.000
	9 Remove Pipe Culvert		Ft		40.000
	10 Remove Fence		Ft		369.000
	11 Remove Sediment		CuYd		1.000
	12 Remove Erosion Control Wattle		Ft		100.000
	13 Remove Silt Fence		Ft		250.000
	14 Unclassified Excavation		CuYd		1,439.000
	15 Contractor Furnished Borrow Excavation		CuYd		60.000
	16 Placing Topsoil		CuYd		254.000
	17 Incidental Work, Structure		LS		1.000
	18 Structure Excavation, Box Culvert		CuYd		120.000
	19 Box Culvert Undercut		CuYd		324.000
	20 18" CMP 12 Gauge, Furnish		Ft		56.000
	21 18" CMP, Install		Ft		56.000
	22 18" CMP Flared End, Furnish		Each		2.000
	23 18" CMP Flared End, Install		Each		2.000
	24 Class A45 Concrete, Box Culvert		CuYd		233.100
	25 Reinforcing Steel		Lb		30,985.000
	26 Type 2 Right-of-Way Fence		Ft		355.000
	27 Type 1 Temporary Fence		Ft		447.000
	28 3 Post Panel		Each		2.000
	29 Type 2 Object Marker		Each		4.000
	30 Traffic Control Signs		SqFt		109.000
	31 Traffic Control, Miscellaneous		LS		1.000
	32 Type 3 Barricade		Each		8.000
	33 Class B Riprap		Ton		127.400
	34 Erosion Control		LS		1.000
	35 12" Diameter Erosion Control Wattle		Ft		240.000
	36 Remove and Reset Erosion Control Wattle		Ft		60.000
	37 High Flow Silt Fence		Ft		250.000
	38 Mucking Silt Fence		CuYd		18.000
	39 Repair Silt Fence		Ft		63.000
	40 Type B Drainage Fabric		SqYd		99.000
2.	BRF-B 6202(07)	Area Engineer: Matt Brey, 5000 9th Avenue SE, Watertown, SD, 57201			Phone: 605/882-5166
	Work Type 9	DBE Goal: NONE	Contract Id: 9948	See Special Provisions for Completion Requirements	
	1 Mobilization		LS		1.000
	2 Incentive/Disincentive Pay		Day		0.000
	3 Grade Staking		Mile		0.089
	4 Miscellaneous Staking		Mile		0.089
	5 Slope Staking		Mile		0.089
	6 Structure Staking		Each		1.000
	7 Engineer Directed Surveying/Staking		Hour		20.000
	8 Construction Schedule, Category II		LS		1.000
	9 Remove Fence		Ft		499.000
	10 Remove Erosion Control Wattle		Ft		240.000
	11 Unclassified Excavation		CuYd		738.000

12	Contractor Furnished Borrow Excavation	CuYd	920.000
13	Placing Topsoil	CuYd	300.000
14	Incidental Work, Structure	LS	1.000
15	Structure Excavation, Box Culvert	CuYd	84.000
16	Box Culvert Undercut	CuYd	243.000
17	Class A45 Concrete, Box Culvert	CuYd	162.500
18	Reinforcing Steel	Lb	23,960.000
19	Type 2 Right-of-Way Fence	Ft	479.000
20	Type 1 Temporary Fence	Ft	499.000
21	2 Post Panel	Each	10.000
22	Type 2 Object Marker Back to Back	Each	4.000
23	Traffic Control Signs	SqFt	163.500
24	Traffic Control, Miscellaneous	LS	1.000
25	Type 3 Barricade	Each	9.000
26	Class B Riprap	Ton	51.800
27	Erosion Control	LS	1.000
28	12" Diameter Erosion Control Wattle	Ft	340.000
29	Remove and Reset Erosion Control Wattle	Ft	80.000
30	Type B Drainage Fabric	SqYd	69.000
31	Reinforcement Fabric (MSE)	SqYd	347.000

3. BRO-B 8025(17) Area Engineer: Lane Goldsmith, West Highway 12, Aberdeen, SD, 57402-1767 Phone: 605/626-7885

**Work Type 7 or Work Type 8 or
Work Type 9 or Work Type 13**

DBE Goal: NONE

Contract Id: 10168

See Special Provisions for Completion Requirements

1	Mobilization	LS	1.000
2	Construction Schedule, Category I	LS	1.000
3	Remove Delineator	Each	8.000
4	Remove Erosion Control Wattle	Ft	340.000
5	Unclassified Excavation	CuYd	146.000
6	Placing Topsoil	CuYd	33.000
7	Incidental Work, Structure	LS	1.000
8	2.0"x2.0" Perforated Tube Post	Ft	48.000
9	Flat Aluminum Sign, Nonremovable Copy Super/Very High Intensity	SqFt	63.000
10	Type 3 Double Sided Barricade	Ft	12.000
11	Type 3 Single Sided Barricade	Ft	48.000
12	Traffic Control Signs	SqFt	109.000
13	Traffic Control, Miscellaneous	LS	1.000
14	Type 3 Barricade	Each	8.000
15	Erosion Control	LS	1.000
16	12" Diameter Erosion Control Wattle	Ft	340.000
17	Remove and Reset Erosion Control Wattle	Ft	80.000
18	Floating Silt Curtain	Ft	80.000

4. PH 8037(02) Area Engineer: Jay Peppel, PO Box 1206, Mitchell, SD, 57301-7206 Phone: 605/995-8120

Work Type 11

DBE Goal: NONE

Contract Id: 10121

See Special Provisions for Completion Requirements

1	Mobilization	LS	1.000
2	As-Built Survey	LS	1.000
3	Construction Schedule, Category I	LS	1.000
4	Remove Traffic Sign	Each	2,289.000
5	Salvage Traffic Sign	Each	69.000
6	Remove Sign for Reset	Each	4.000
7	2.0"x2.0" Perforated Tube Post	Each	2,617.000
8	2.5"x2.5" Perforated Tube Post	Each	2.000
9	No Passing Zone Reference Post	Each	109.000
10	4"x4" White Delineator Back to Back with 1.12 Lb/Ft Post	Each	1,091.000
11	4" Tubular White Delineator with 1.12 Lb/Ft Post	Each	40.000
12	4" Tubular White Delineator Reflector	Each	575.000
13	Guardrail Delineator	Each	16.000

14	Type 2 Object Marker Back to Back	Each	872.000
15	Type 3 Flexible Object Marker	Each	64.000
16	Type 4 Object Marker	Each	66.000
17	Flat Aluminum Sign, Nonremovable Copy High Intensity	SqFt	7,727.400
18	Flat Aluminum Sign, Nonremovable Copy Super/Very High Intensity	SqFt	9,491.100
19	Reset Sign	Each	4.000
20	Traffic Control, Miscellaneous	LS	1.000

Instructions

PROPOSALS, PLANS AND SPECIFICATIONS: Plans, Proposals, and Standard Specifications are available on the SDDOT Bid Letting website.

MINIMUM WAGE RATES: Minimum wage rates for 1 through 4 have been predetermined by the U.S. Department of Labor and the Department of Transportation, and the Contractor shall pay at least the highest wage set forth in the advertised specification for each job classification, according to the county(ies) in which the work is actually performed. Contractors are required to meet the provisions of the Fair Labor Standards Act of 1938, as amended. Federal-aid projects are subject to the Work Hours Act of 1962, Public Law 87-581 and implementing regulations.

BID PREPARATION: Bids shall be completed in their entirety utilizing the SDEBS. Bidders submitting a bid on Item 1 must also submit a bid on Item 2. Award of these combinations (Items 1 & 2) will be to the same bidder based on the total combined two projects.

Please refer to the SDDOT bid letting webpage for the SDEBS user manual and further information on how to bid.

NONDISCRIMINATION ASSURANCE: The South Dakota Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights Act of 1964 (78 Stat. 252, 42 U.S.C. §§ 2000d to 2000d-4) and the Regulations, hereby notifies all bidders that it will affirmatively ensure that any contract entered into pursuant to this advertisement, disadvantaged business enterprises will be afforded full and fair opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

EXECUTION OF CONTRACT: In accordance with Section 7.14 of the Standard Specifications, Current Edition, all Contractors prior to execution of any contract, must file with the Department a Certificate of Liability Insurance.

Foreign Corporations, prior to execution of any contract, must file their Articles of Incorporation in accordance with the Foreign Corporation Laws of South Dakota, Chapter 47-8 of the 1967 South Dakota Compiled Laws as amended.

GENERALLY: A list of plan and proposal holders for each project is available on our website for each project in the letting. The plan holders list is updated immediately when a contractor or supplier logs into the project as indicated above.

Prior to plant operation, either a construction permit or an operating permit must be obtained from the Department of Agricultural & Natural Resources, Minerals & Mining Program, Foss Building, Pierre, SD 57501. (Phone [605] 773-4201) Allow thirty (30) days for processing.

Operation of contractor furnished material sources shall be in accordance with SDCL 45-6 governing the extraction of construction aggregate. To obtain licensing and bonding requirements contact: Minerals and Mining Program, South Dakota Department of Agricultural and Natural Resources, Foss Building, Pierre, South Dakota 57501. (Phone [605] 773-4201)

Hydrostatic Testing and Excavation Dewatering shall be in accordance with the NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES), GENERAL PERMIT NUMBER SDG-100000. For further information contact the South Dakota Department of Agricultural and Natural Resources, Foss Building, Pierre, South Dakota 57501 (Phone [605] 773-3351).

The Department of Transportation reserves the right to reject any or all bids.

STATE OF SOUTH DAKOTA, DEPARTMENT OF TRANSPORTATION

BY: Joel Jundt
SECRETARY OF TRANSPORTATION