DEPARTMENT OF TRANSPORTATION

Planning & Engineering
Office of Project Development
700 E Broadway Avenue
Pierre, South Dakota 57501-2586
O: 605.773.3275 | F: 605.773.2614
dot.sd.gov

October 30, 2026

ADDENDUM NO. 1

RE: Item #4, November 4, 2026 Letting - BRO-B 8063(21), PCN 09MF, Turner County - Structure (164' Continuous Concrete) & Approach Grading

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made a part of your proposal for the referenced project.

SPECIAL PROVISIONS: Please remove the Index of Special Provisions and replace with the attached Index of Special Provisions revised 10/27/26.

Please add the "Special Provision for Aggregates for Granular Base and Surfacing", dated 10/26/26 before the "Special Provision for Acknowledgment and Certification Regarding Article 3, Section 12 of the South Dakota constitution", dated 8/24/23.

SDEBS BID PROPOSAL: NO CHANGE

PLANS: NO CHANGE

Sincerely,

Sam Weisgram
Engineering Supervisor

SW/gp

CC: Travis Dressen, Mitchell Region Engineer
Harry Johnston, Sioux Falls Area Engineer

REV 10/27/26

INDEX OF SPECIAL PROVISIONS

PROJECT NUMBER(S): BRO-B 8063(21) PCN: 09MF

TYPE OF WORK: STRUCTURE (164' CONTINUOUS CONCRETE) & APPROACH GRADING

COUNTY: TURNER

The following clauses have been prepared subsequent to the Standard Specifications for Roads and Bridges and refer only to the above described improvement, for which the following Proposal is made.

The Contractor's attention is directed to the need for securing from the Department of Environment & Natural Resources, Foss Building, Pierre, South Dakota, permission to remove water from public sources (lakes, rivers, streams, etc.). The Contractor should make his request as early as possible after receiving his contract, and insofar as possible at least 30 days prior to the date that the water is to be used.

Sara Garbe is the official in charge of the Sioux Falls Career Center for Turner County.

THE FOLLOWING ITEMS ARE INCLUDED IN THIS PROPOSAL FORM:

Special Provision Regarding Section 404 of the Clean Water Act, dated 6/9/26.

Fact Sheet #23.

Special Provision for Construction Practices in Streams Inhabited by the Topeka Shiner, dated 8/29/18.

Special Provision for Contractor Staking, dated 9/28/26.

Special Provision for Aggregates for Granular Bases and Surfacing, dated 10/26/26.
Special Provision for Acknowledgment and Certification Regarding Article 3, Section 12 of the South Dakota Constitution, dated 8/24/23.
Fuel Adjustment Affidavit, DOT form 208 dated 11/25.
Standard Title VI Assurance, dated 3/1/16
Special Provision for Equal Employment Opportunity Requirements for Highway Construction Contracts, dated 10/7/26.
Special Provision for Contract Provisions for Federal-Aid Construction Contracts, Form FHWA 1273 (Rev. June 25, 2026), dated 10/7/26.
Contract Provisions for Federal-Aid Construction Contracts, Form FHWA 1273 (Rev. 6/25/26).
Special Provision Regarding Minimum Wage on Federal-Aid Projects, dated 10/24/19.
Wage and Hour Division US Department of Labor Washington DC. - US Dept. of Labor Decision Number SD20260001, dated 1/30/26.

Special Provision Regarding Stormwater Discharges to Waters of the State, dated 11/5/25.
General Permit Authorizing Stormwater Discharges Associated with Construction Activities, dated 11/1/23.
https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/StormWaterConstruction.aspx

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
AGGREGATES FOR GRANULAR BASES AND SURFACING

OCTOBER 26, 2026

Section 882 – Delete Table 2 and replace it with the following:

Table 2 – Other Properties

Property	Subbase	Gravel Cushion	Base Course	Limestone Ledge Rock Base Course	Limestone Ledge Rock Gravel Cushion	Gravel Surfacing	Pit Run	Granular Bridge End Backfill
Liquid Limit (max)		25	25	25	25			25
Plasticity Index (max) *1	0-6	0-6	0-6	0-3	0-3	4-12		0-6
LA Abrasion Loss (max)	50	40	40	40	40	40		40
Crushed Particles (min) +#4 Sieve	30% 1-CF	30% 1-CF	30% 1-CF	30% 1-CF	30% 1-CF	30% 1-CF		30% 1-CF
Foot Notes		*2	*1, *2				*3	

*1 The fraction passing the #200 sieve will not be greater than 2/3 of the fraction passing the #40 sieve. In no case will the upper limit specified for the #200 sieve be exceeded.

*2 Requirements apply to ledge rock other than limestone ledge rock.

*3 Acceptance of pit run will be by visual inspection. The Engineer may require a sieve analysis to verify the material meets the specified gradation. Independent Assurance will not be required.

* * * * *