



Planning & Engineering
Office of Project Development
700 E Broadway Avenue
Pierre, South Dakota 57501-2586
O: 605.773.3275 | F: 605.773.2614
dot.sd.gov

October 6, 2026

ADDENDUM NO. 4

RE: Item #8, October 7, 2026 Letting - IM 0292(100)55, PCN 09TY, Lincoln County - Construct Median & Ramp Crossovers

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made a part of your proposal for the referenced project.

SPECIAL PROVISIONS: NO CHANGE

SDEBS BID PROPOSAL: *The electronic bid proposal for this contract has been revised to include the changes associated with this addendum. Bidders must log in to the SDEBS to retrieve and incorporate these changes into their bid.*

Bid Items were added:

Bid Item 009E3250 "Miscellaneous Staking"

PLANS: Please destroy sheets A1, F2 & F6 and replace with the enclosed sheets, dated 10/6/26. Sheet F7A was added.

Sheets A1 & F2: Bid Item 009E3250 "Miscellaneous Staking" was added.

Sheet F6: TABLE OF CONSTRUCTION STAKING was revised.

Sheet F7A: CONTROL DATEA Sheet was added.

Sincerely,

Sam Weisgram
Engineering Supervisor

SW/gp

CC: Travis Dressen, Mitchell Region Engineer
Greg Rothschadl, Yankton Area Engineer

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	IM 0292(100)55	A1	A3

Section C – Traffic Control

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
633E1220	High Build Waterborne Pavement Marking Paint, 4" White	500	Ft
633E1222	High Build Waterborne Pavement Marking Paint, 4" Yellow	2,500	Ft
634E0010	Flagging	160.0	Hour
634E0110	Traffic Control Signs	840.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0275	Type 3 Barricade	10	Each
634E0330	Temporary Raised Pavement Markers	7,680	Ft
634E0420	Type C Advance Warning Arrow Board	4	Each
634E1215	Contractor Furnished Portable Changeable Message Sign	2	Each
634E1255	Contractor Furnished Vehicle Speed Feedback Sign	2	Each

Section D - Erosion and Sediment Control

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
110E1700	Remove Silt Fence	500	Ft
230E0100	Remove and Replace Topsoil	Lump Sum	LS
730E0100	Cover Crop Seeding	4.0	Bu
730E0202	Type B Permanent Seed Mixture	97	Lb
731E0200	Fertilizing	2.70	Ton
732E0100	Mulching	10.8	Ton
734E0602	Low Flow Silt Fence	500	Ft
734E0610	Mucking Silt Fence	35	CuYd
734E0620	Repair Silt Fence	125	Ft

Section F – Surfacing

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
009E3230	Grade Staking	1.592	Mile
009E3250	Miscellaneous Staking	0.796	Mile
009E3301	Engineer Directed Surveying/Staking	40.0	Hour
009E4200	Construction Schedule, Category II	Lump Sum	LS
110E7020	Remove Interim Crossover Closure for Reset	280	Ft
120E0010	Unclassified Excavation	4,606	CuYd
120E6200	Water for Granular Material	324.4	MGal
120E9000	Pit Run	16,359.0	Ton
260E1010	Base Course	10,678.0	Ton
320E1200	Asphalt Concrete Composite	7,094.0	Ton
332E0010	Cold Milling Asphalt Concrete	3,419	SqYd
450E4749	15" CMP 16 Gauge, Furnish	1,000	Ft
450E4750	15" CMP, Install	1,000	Ft
450E5005	15" CMP Elbow, Furnish	8	Each
450E5006	15" CMP Elbow, Install	8	Each
450E5100	CMP Tee, Furnish	2	Each
450E5101	CMP Tee, Install	2	Each
450E5402	15" CMP Safety End, Furnish	6	Each
450E5403	15" CMP Safety End, Install	6	Each
450E6119	15" Slotted CMP 16 Gauge, Furnish	900	Ft
450E6120	15" Slotted CMP, Install	900	Ft
462E0100	Class M6 Concrete	78.9	CuYd
464E0100	Controlled Density Fill	66.6	CuYd
600E0200	Type II Field Laboratory	1	Each
629E9010	Interim Crossover Closure	1,350	Ft
629E9060	Reset Interim Crossover Closure	280	Ft
831E0210	Non-woven Separator Fabric	13,817	SqYd

Revised: 10-06-2026 BAH

INDEX OF SHEETS

A1 Estimate of Quantities for Sections C, D and F
A2 to A3 Environmental Commitments

1:200
Plot Scale -

Plotted From -
TRPR18388A

SECTION F – ESTIMATE OF QUANTITIES

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
009E3230	Grade Staking	1.592	Mile
009E3250	Miscellaneous Staking	0.796	Mile
009E3301	Engineer Directed Surveying/Staking	40.0	Hour
009E4200	Construction Schedule, Category II	Lump Sum	LS
110E7020	Remove Interim Crossover Closure for Reset	280	Ft
120E0010	Unclassified Excavation	4,606	CuYd
120E6200	Water for Granular Material	324.4	MGal
120E9000	Pit Run	16,359.0	Ton
260E1010	Base Course	10,678.0	Ton
320E1200	Asphalt Concrete Composite	7,094.0	Ton
332E0010	Cold Milling Asphalt Concrete	3,419	SqYd
450E4749	15" CMP 16 Gauge, Furnish	1,000	Ft
450E4750	15" CMP, Install	1,000	Ft
450E5005	15" CMP Elbow, Furnish	8	Each
450E5006	15" CMP Elbow, Install	8	Each
450E5100	CMP Tee, Furnish	2	Each
450E5101	CMP Tee, Install	2	Each
450E5402	15" CMP Safety End, Furnish	6	Each
450E5403	15" CMP Safety End, Install	6	Each
450E6119	15" Slotted CMP 16 Gauge, Furnish	900	Ft
450E6120	15" Slotted CMP, Install	900	Ft
462E0100	Class M6 Concrete	78.9	CuYd
464E0100	Controlled Density Fill	66.6	CuYd
600E0200	Type II Field Laboratory	1	Each
629E9010	Interim Crossover Closure	1,350	Ft
629E9060	Reset Interim Crossover Closure	280	Ft
831E0210	Non-woven Separator Fabric	13,817	SqYd

CONTROL OF ACCESS

If a Contractor's operations would require access to the interstate ROW in any locations not currently designated as public access, prior approval must be obtained from the Department. All requests will be reviewed based on safety and construction sequencing. A Contractor will not assume that all requests will be granted.

Anytime Contractor operations have ceased for the day, any entrances approved in a control of access area will be closed by the Contractor.

The request for access will be provided in writing to the Engineer two weeks in advance of any proposed break in control of access.

SURFACING THICKNESS DIMENSIONS

Plans quantity will be applied though the thickness may vary from that shown on the plans.

At those locations where material must be placed to achieve a required elevation, plans quantity may be varied to achieve the required elevation.

UTILITIES

The Contractor will contact the involved utility companies through South Dakota One Call (1-800-781-7474) prior to starting work. It will be the responsibility of the Contractor to coordinate work with the utility owners to avoid damage to existing facilities. If utilities are identified near the improvement area through the SD One Call Process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25, the Contractor will contact the Engineer to determine modifications that will be necessary to avoid utility impacts.

Listed below are the Utility Contacts for the project that were gathered by running a South Dakota 811 Informational Ticket on September 11th, 2025. Please provide these to the Contractor and include the list after the Standard Utility Note in the plans.

Jeff Hove
Alliance Communications Cooperative, Inc.
1400 E Aspen Blvd
Brandon, SD 57005
O: (605) 582-6311
C: (605) 941-7035
E: JeffH@Alliance.Coop

Brian Matson
Finley Engineering Co. Inc., (AT&T Consultant)
1981 Engebretson Street
Slayton MN 56172
O: 507-777-2000
D: 507-777-2256
F: 507-777-2200
C: 507-920-7319
E: b.matson@finleyusa.com

Gabreil Perez
Network Technical Specialist (Sioux Falls Onsite Local Locator)
3000 W 10TH ST
SIOUX FALLS, SD 57104
C: 786-650-4336
E: gp8061@att.com

Lawrence Escobin
SDN COMMUNICATIONS, INC.
2900 W 10TH ST
SIOUX FALLS, SD 57104-2543
O: (605) 978-1094: *Goes straight to C if not In-Office.*
C: (605) 310-7238
E: Lawrence.Escobin@SDNCommunications.com

John Stearns
South Lincoln Rural Water System, Inc.
28647 472nd Ave
Beresford, SD 57004
O: (605) 777-9905
E: John.Stearns@SLRWS.com

John Euchner
Southeastern Electric Cooperative, Inc.
47077 276th St
Lennox, SD 57039
O: (800) 333-2859
P: (605) 310-2684
E: JohnE@Southeastern.coop

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	IM 0292(100)55	F	2/32

Plotting Date: 10/06/2026

Revised: 10-06-2026 BAH

Southeastern Electric Cooperative, Inc. Onsite Contact
Line Superintendent
Duane Pulse
C:605-421-9769
E: duane@southeastern.coop

Jordan Huber
Bluepeak
5100 S Broadband Rd
Sioux Falls, SD 57108
O: (605) 498-4922
P: (605) 366-1360
E: Jordan.Huber@MyBluepeak.com

TYPE II FIELD LABORATORY

The lab will be equipped with an internet connection such as DSL, cable modem, or other approved service. The internet connection will be provided with a multi-port wireless router. The internet connection will be a minimum speed of 5 Mbps unless limited by job location and approved by the DOT. Prior to installing the wireless router, the Contractor will submit the wireless router's technical data to the Area Office to check for compatibility with the state's computer equipment. The internet connection is intended for state personnel usage only. The Contractor's personnel are prohibited from using the internet connection unless pre-approved by the Project Engineer. These items will be incidental to the contract unit price per each for "Type II Field Laboratory".

ASPHALT CONCRETE COMPOSITE

Asphalt Concrete Composite will include MC-70 Asphalt for Prime placed at the rate of 0.30 gallons per square yard. The Asphalt for Prime will be applied to the Base Course for the full width of the bottom layer of Asphalt Concrete Composite plus one foot additional on the outside shoulder.

Asphalt for tack SS-1h or CSS-1h will be applied prior to each lift of Asphalt Concrete Composite. Asphalt for tack will be applied at a rate of 0.09 gallons per square yard on existing pavement or milled asphalt concrete surfaces and at a rate of 0.06 gallons per square yard on primed base course or new asphalt concrete pavement. The Asphalt for tack will be applied for the full width of the bottom layer of Asphalt Concrete Composite plus one-half foot additional on the outside shoulder. Flush seal is covered in Section 324 of the Specifications.

Asphalt for flush seal and sand for flush seal will be required.

File -
...prj\inc09TY\Notes\SectionF.dgn

Plot Scale - 1:200

Plotted From - TRPR18388A

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	IM 0292(100)55	F	6/32

Plotting Date: 10/06/2026

Revised: 10-06-2026 - BAH

TABLE OF CONSTRUCTION STAKING
(See Special Provision for Contractor Staking)

Roadway and Description	Begin Station	End Station	Number of Lanes	Grade Staking					Misc. Staking
				Length (Ft)	Length (Mile)	Lane Factor	*Sets of Stakes	**Grade Staking Quantity (Mile)	Miscellaneous Staking Quantity (Mile)
I-29 Mainline - Stationing									
Median Crossover - North of Exit 47, MRM 48.00+0.00	101+00.00	111+51.50	2	1,051.50	0.199	1	2	0.398	0.199
Median Crossover - North of Exit 50, MRM 51.00+0.80	201+00.00	211+51.50	2	1,051.50	0.199	1	2	0.398	0.199
Median Crossover - South of Exit 56, MRM 55.00+0.40	301+00.00	311+51.50	2	1,051.50	0.199	1	2	0.398	0.199
Median Crossover - North of Exit 56, MRM 57.00+0.30	401+00.00	411+51.50	2	1,051.50	0.199	1	2	0.398	0.199
							Totals:	1.592	0.796

* 2 = Blue Top Grading Stakes and Paving Hub Stakes (AC Pavement)
** Grade Staking Quantity = (Length) x (Lane Factor) x (Sets of Stakes)

Plotted From - TRPR18388A Plot Scale - 1:200 File - ...\\proj\\inc09TY\\Notes\\SectionF.dgn

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	IM 0292(100)55	F	7A/32

Plotting Date: 10/06/2026

Revised: 10-06-2026 BAH

CONTROL DATA – (PCN 09TY -proposed project)

HORIZONTAL AND VERTICAL CONTROL POINTS						
POINT	STATION	OFFSET	DESCRIPTION	NORTHING	EASTING	ELEVATION
CP1	---	---	POINT IS THROUGH A 5" LOGO CAP	294208.855	2913375.158	1449.79
CP2	---	---	POINT IS THROUGH A 5" LOGO CAP	342182.291	2911305.175	1327.2
CP3	---	---	POINT IS THROUGH A 5" LOGO CAP	346492.3815	2911075.369	1331.815
CP4	412+22.84	147.1196	POINT IS THROUGH A 5" LOGO CAP	314779.8549	2912257.557	1401.12
CP5	---	---	POINT IS THROUGH A 5" LOGO CAP	320082.6734	2912330.81	1450.86
CP6	513+29.79	152.8701	POINT IS THROUGH A 5" LOGO CAP	363432.5833	2910004.55	1302.15

The coordinates shown on this sheet are based on the South Dakota State Plane Coordinate System. North Zone (NAD 83/2011); SF = 0.999839492. The elevations shown on this sheet are based on NAVD 88.