

Plot Scale - 1:200

Plotted From - TRSF12140

File - U:\proj\proj067\DT\Title.dgn

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION
PLANS FOR PROPOSED

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P 0127(09)214	1	130



Plotting Date: 03/04/2025

INDEX OF SECTIONS

Section A:	Estimate of Quantities and Environmental Commitments
Section B:	Grading Plans
Section C:	Traffic Control Plans
Section D:	Erosion and Sediment Control Plans
Section E:	Structure Plans
Section F:	Surfacing Plans
Section X:	Cross Sections
Section Z:	Pipe Sections

PROJECT P 0127(09)214
SD HIGHWAY 127
ROBERTS COUNTY
REPLACE STRUCTURES (BRIDGE & RCBC),
APPROACH GRADING & ROW PLANS

PCN 067D



DESIGN DESIGNATION

AADT (2023)	838
AADT (2048)	1835
DHV	122
D	50%
DHV T%	8.7%
AADT T%	14.8%
V	70 mph

STORM WATER PERMIT

Major Receiving	
Body of Water:	Little Minnesota River
Area Disturbed:	3.4 Acres
Total Project Area:	4.5 Acres
Approx. Begin Lat,Long:	45.6733,-97.0186

BEGIN P 0127(09)214
BEGIN GRADING
Station 0+92.91
located 565.48 feet South and
307.07 feet East of the Northwest
corner of Section 26 -
Township 126 North- Range 51 West
of the 5th P.M.
MRM 214.90

END P 0127(09)214
END GRADING
Station 100+65.00
located 1321.89 feet South and
3.62 feet East of the Northwest
corner of Section 14 -
Township 126 North - Range 51 West
of the 5th P.M.

END EXCEPTION
BEGIN GRADING
Station 90+68.40
MRM 216.66

Gross Length	9972.09 Feet	1.8887 Miles
Length of Exceptions	8445.18 Feet	1.5995 Miles
Net Length	1526.91 Feet	0.2892 Miles

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P 0127(09)214	A1	A5

Plotting Date: 09/23/2025
Revised Date: 09/23/2025 MDJ

Section B – Grading

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
009E3220	Reestablish Right-of-Way and Property Corner	37	Each
009E3225	Reestablish Public Land Survey System Corner	4	Each
009E3230	Grade Staking	0.245	Mile
009E3250	Miscellaneous Staking	0.245	Mile
009E3280	Slope Staking	0.245	Mile
009E3290	Structure Staking	2	Each
009E3301	Engineer Directed Surveying/Staking	40.0	Hour
009E4200	Construction Schedule, Category II	Lump Sum	LS
100E0100	Clearing	Lump Sum	LS
110E0730	Remove Beam Guardrail	764.0	Ft
110E1010	Remove Asphalt Concrete Pavement	5,353.0	SqYd
120E0010	Unclassified Excavation	20,007	CuYd
120E0600	Contractor Furnished Borrow Excavation	9,790	CuYd
120E1000	Muck Excavation	2,334	CuYd
120E2000	Undercutting	6,441	CuYd
120E6100	Water for Embankment	253.0	MGal
250E0020	Incidental Work, Grading	Lump Sum	LS
450E0122	18" RCP Class 2, Furnish	52	Ft
450E0130	18" RCP, Install	52	Ft
450E2008	18" RCP Flared End, Furnish	1	Each
450E2009	18" RCP Flared End, Install	1	Each
450E4769	24" CMP 16 Gauge, Furnish	132	Ft
450E4770	24" CMP, Install	132	Ft
450E5410	24" CMP Safety End, Furnish	4	Each
450E5411	24" CMP Safety End, Install	4	Each
462E0100	Class M6 Concrete	3.6	CuYd
480E0100	Reinforcing Steel	525	Lb
600E0300	Type III Field Laboratory	1	Each
630E0500	Type 1 MGS	325.0	Ft
630E1500	Type 1 Guardrail Transition	4	Each
630E2017	MGS MASH Flared End Terminal	4	Each
670E0200	Type A Frame and Grate	2	Each
670E5400	Precast Drop Inlet Collar	2	Each

Section C - Traffic Control

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
110E7150	Remove Sign for Reset	2	Each
632E2220	Guardrail Delineator	18	Each
632E2510	Type 2 Object Marker Back to Back	4	Each
632E3500	Reset Sign	2	Each
633E1200	High Build Waterborne Pavement Marking Paint, White	20	Gal
633E1205	High Build Waterborne Pavement Marking Paint, Yellow	7	Gal
634E0010	Flagging	50.0	Hour
634E0110	Traffic Control Signs	198.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0275	Type 3 Barricade	24	Each
634E1002	Detour and Restriction Signing	832.8	SqFt

Section D - Erosion and Sediment Control

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
110E1690	Remove Sediment	1.9	CuYd
110E1693	Remove Erosion Control Wattle	150	Ft
110E1695	Remove Sediment Filter Bag	48	Ft
110E1700	Remove Silt Fence	633	Ft
230E0010	Placing Topsoil	882	CuYd
730E0100	Cover Crop Seeding	1.5	Bu
730E0212	Type G Permanent Seed Mixture	43	Lb
731E0200	Fertilizing	1.20	Ton
732E0100	Mulching	3.3	Ton
734E0044	Soil Stabilizer	1.0	Acre
734E0103	Type 3 Erosion Control Blanket	540	SqYd
734E0154	12" Diameter Erosion Control Wattle	600	Ft
734E0165	Remove and Reset Erosion Control Wattle	150	Ft
734E0180	Sediment Filter Bag	48	Ft
734E0325	Surface Roughening	1.5	Acre
734E0510	Shaping for Erosion Control Blanket	304	Ft
734E0602	Low Flow Silt Fence	2,096	Ft
734E0604	High Flow Silt Fence	436	Ft
734E0610	Mucking Silt Fence	176	CuYd
734E0620	Repair Silt Fence	633	Ft
734E0845	Sediment Control at Inlet with Frame and Grate	2	Each
900E1320	Construction Entrance	2	Each

Section E – Structure
Structure No. 55-101-181

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
250E0030	Incidental Work, Structure	Lump Sum	LS
420E0200	Structure Excavation, Box Culvert	177	CuYd
421E0200	Box Culvert Undercut	510	CuYd
460E0120	Class A45 Concrete, Box Culvert	424.6	CuYd
480E0100	Reinforcing Steel	63,188	Lb
700E0210	Class B Riprap	837.5	Ton
831E0110	Type B Drainage Fabric	919	SqYd

A1 and A2 Estimate of Quantities for Sections B, C, D, E & F
A2 to A5 Environmental Commitments

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 10-1-25 Version, Required Provisions, and Special Provisions as included in the Proposal. The Standard Specifications for Roads and Bridges are available for download and viewing at <https://dot.sd.gov/doing-business/contractors/standard-specifications>.

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

Structure No. 55-100-164

ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P 0127(09)214	A2	A5

Plotting Date: 03/13/2025
Revised Date: 03/13/2025 MDJ

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E3310	Bridge Elevation Survey	Lump Sum	LS
009E5000	Concrete Penetrating Sealer	1,044.0	SqYd
120E7000	Select Granular Backfill	22.4	Ton
250E0030	Incidental Work, Structure	Lump Sum	LS
410E2600	Membrane Sealant Expansion Joint	75.8	Ft
420E0100	Structure Excavation, Bridge	1,514	CuYd
430E0200	Bridge End Embankment	252	CuYd
430E0300	Granular Bridge End Backfill	68.5	CuYd
430E0510	Approach Slab Underdrain Excavation	7.5	CuYd
430E0700	Precast Concrete Headwall for Drain	4	Each
460E0030	Class A45 Concrete, Bridge Deck	475.2	CuYd
460E0050	Class A45 Concrete, Bridge	543.4	CuYd
460E0150	Concrete Approach Slab for Bridge	159.8	SqYd
460E0160	Concrete Approach Sleeper Slab for Bridge	37.9	SqYd
480E0100	Reinforcing Steel	51,867	Lb
480E0200	Epoxy Coated Reinforcing Steel	9,124	Lb
480E0300	Stainless Reinforcing Steel	156,602	Lb
510E0100	Extract Pile	5	Each
510E0300	Preboring Pile	100	Ft
510E3361	HP 10x42 Steel Test Pile, Furnish and Drive	200	Ft
510E3365	HP 10x42 Steel Bearing Pile, Furnish and Drive	760	Ft
510E3521	HP 14x73 Steel Test Pile, Furnish and Drive	375	Ft
510E3525	HP 14x73 Steel Bearing Pile, Furnish and Drive	8,050	Ft
680E0040	4" Underdrain Pipe	147	Ft
680E2500	Porous Backfill	14.1	Ton
700E0210	Class B Riprap	1,978.0	Ton
700E1100	Overburden Excavation for Riprap	4,054	CuYd
831E0110	Type B Drainage Fabric	2,341	SqYd
831E1030	Perforated Geocell	640	SqFt

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: [<https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf >](https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf)

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT A: AQUATIC RESOURCES

COMMITMENT A1: WETLANDS

All efforts to avoid and minimize wetland impacts from the project have resulted in approximately 0.38 acres of wetlands (includes temporary and permanent) becoming impacted. Refer to Section B – Grading Plans/plans for location and boundaries of the impacted wetlands.

Table of Impacted Wetlands

Wetland No.	Station	Perm. Impact Left (Acres)	Perm. Impact Right (Acres)	Temp. Impact Left (Acres)	Temp. Impact Right (Acres)	Total Impact (Acres)
1	3+90 to 4+30	0.00	0.00	0.02	0.00	0.02
2	93+80 to 96+50	0.00	0.00	0.30	0.06	0.36

Action Taken/Required:

Temporary impacts identified in the Table of Impacted Wetlands will not be mitigated as original contours and elevations will be re-established as designated in Section B – Grading Plans. Prior to initiating temporary work in wetlands, the Contractor will submit a plan to the Project Engineer in accordance with Section 7.21 D of the Specifications.

COMMITMENT A2: STREAMS

All efforts to avoid and minimize stream impacts from the project have resulted in approximately 0.18 acres of stream (includes temporary and permanent) becoming impacted. Refer to Section B – Grading Plans/plans for location and boundaries of the impacted streams.

Table of Impacted Streams

Stream Name	Station	Perm. Impact Left (Acres)	Perm. Impact Right (Acres)	Temp. Impact Left (Acres)	Temp. Impact Right (Acres)	Total Impact (Acres)
Little Minnesota Tributary	3+80 to 4+00	0.00	0.00	0.03	0.03	0.06
Little Minnesota	95+20 to 95+50	0.00	0.00	0.07	0.05	0.12

Action Taken/Required:

It has been determined that project impacts do not require mitigation. Temporary impacts identified in the Table of Impacted Streams will not be mitigated as the finished ground under the bridge will be shaped to match the upstream channel and flood plain and the existing low water channel will be maintained as near as practical to the existing location as designated in Section B – Grading Plans.

The contractor will complete excavation after temporary diversion is in place, if required, with minimal standing water to create the profile of slope protection specified in plans. Once the instream work is completed, the removed material will be placed on top of the riprap to match the natural ground, proposed groundline, or specified shape and elevations shown in plans. When overburden extends into the streambed it will form the channel bottom and profile as specified in plans. The finished ground under the bridge will be shaped to match the upstream and downstream channel and flood plain. See Overburden Excavation for Riprap note within structure sheets.

The Contractor will notify the Project Engineer if additional easement is needed to complete work adjacent to any stream. The Project Engineer will obtain an appropriate course of action from the Environmental Office before proceeding with construction activities that affect any streams beyond the work limits and easements shown in the plans.

Section F – Surfacing

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E3320	Checker	Lump Sum	LS
120E6200	Water for Granular Material	54.9	MGal
260E1010	Base Course	4,548.8	Ton
320E1200	Asphalt Concrete Composite	1,858.2	Ton
320E7012	Grind 12" Rumble Strip or Stripe in Asphalt Concrete	0.5	Mile

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P 0127(09)214	A3	A5

Plotting Date: 03/13/2025
Revised Date: 03/11/2025 MDJ

COMMITMENT B: FEDERALLY THREATENED, ENDANGERED, AND PROTECTED SPECIES

COMMITMENT B2: WHOOPING CRANE

The Whooping Crane is a spring and fall migratory bird in South Dakota that is about 5 feet tall and typically stops on wetlands, rivers, and agricultural lands along their migration route. An adult Whooping Crane is white with a red crown and a long, dark, pointed bill. Immature Whooping Cranes are cinnamon brown. While in flight, their long necks are kept straight and their long dark legs trail behind. Adult Whooping Cranes' black wing tips are visible during flight.

Action Taken/Required:

Harassment or other measures to cause the Whooping Crane to leave the site is a violation of the Endangered Species Act. If a Whooping Crane is sighted roosting in the vicinity of the project, borrow pits, or staging areas associated with the project, cease construction activities in the affected area until the Whooping Crane departs and immediately contact the Project Engineer. The Project Engineer will contact the Environmental Office so that the sighting can be reported to USFWS.

COMMITMENT B4: BALD EAGLE

Bald eagles are known to occur in this area.

Action Taken/Required:

If a nest is observed within one mile of the project site, notify the Project Engineer immediately so that he/she can consult with the Environmental Office for an appropriate course of action.

COMMITMENT B6: MIGRATORY BIRDS WORK RESTRICTION

Migratory birds are known to use the project area for nesting, which primarily occurs from April 1st to July 15th.

Action Taken/Required:

The Contractor is responsible for contracting the services of a qualified biologist for conducting preconstruction migratory bird surveys in suitable areas that have not been mowed or cleared prior to April 1st to determine if there are current nests and to determine offsetting measures to compensate for impacts to migratory birds. A survey will be conducted annually for each year of construction. Contractor will coordinate the survey findings with the Project Engineer. If any nests are found, appropriate minimization measures will need to be developed in cooperation with the Environmental Office.

Construction activities should not occur in the locations listed in the table below during the migratory bird work restriction without prior approval from the SDDOT Environmental Office to avoid conflicts with nesting migratory birds.

Station	Migratory Bird Restriction
3+20 to 4+19 L/R & 94+57 to 96+97 L/R	Clear/mow (barn swallow nests) prior to April 1, 2026

COMMITMENT C: WATER SOURCE

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species (AIS) positive waters within South Dakota without prior approval from the SDDOT Environmental Office. To prevent and control the introduction and spread of invasive species into the project vicinity, all equipment will be power washed with hot water (≥140 °F) and completely dried for a minimum of 7 days prior to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the possession and transport of AIS; therefore, all attached dirt, mud, debris and vegetation must be removed and all compartments and tanks capable of holding standing water must be drained. This includes, but is not limited to, all equipment, pumps, lines, hoses and holding tanks.

Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Agriculture and Natural Resources (DANR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of water sources impacted by Aquatic Invasive Species in South Dakota can be accessed at:
< <https://sdleastwanted.sd.gov/maps/default.aspx> >

< [South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species: https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04](https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04) >

COMMITMENT D: WATER QUALITY STANDARDS

COMMITMENT D1: SURFACE WATER QUALITY

The Little Missouri River is classified as a warm water semi-permanent fishery with a total suspended solids standard of less than 90 mg/L 30-day average, less than 158 mg/L daily maximum.

This project may be in the vicinity of multiple streams and wetlands. These waters are considered waters of the state and are protected under Administrative Rules of South Dakota (ARSD) Chapter 74:51. Special construction measures may have to be taken to ensure that this water body is not impacted.

Action Taken/Required:

The Contractor is advised that the South Dakota Surface Water Quality Standards, administered by the South Dakota Department of Agriculture and Natural Resources (DANR), apply to this project. Special construction measures will be taken to ensure the above standard(s) of the surface waters are maintained and protected.

COMMITMENT D2: SURFACE WATER DISCHARGE

The DANR General Permit for Temporary Discharge is required for temporary dewatering and discharges to waters of the state. The effluent limit for total suspended solids will be 90 mg/L 30-day average. The effluent limit applies to discharges to all waters of the state except discharges to waters classified as cold water permanent fish life propagation waters according to the ARSD 74:51:01:45. For discharges to waters of the state classified as cold water permanent fish life propagation waters, the effluent limit for total suspended solids will be 53 mg/L daily maximum.

The permittee has the option of completing effluent testing or implementing a pollution prevention plan for compliance with this permit. If the permittee develops a pollution prevention plan instead of total suspended solids sampling, the plan must be developed and implemented prior to discontinuing total suspended solids sampling. Refer to Section 4.0 of the permit. If any pollutants are suspected of being discharged, a sample must be taken for those parameters listed in Section 3.4 of the permit.

Refer to Commitment D1: Surface Water Quality for stream classification.

Action Taken/Required:

If construction dewatering is required and this project is not required to be covered under a General Permit for Stormwater Discharges Associated with Construction Activities, the Contractor will obtain the General Permit for Temporary Discharge Activities from the DANR Surface Water Program, 605-773-3351.

<https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR_TemporaryDischargeNOI2018Fillable.pdf>

If construction dewatering is required and this project is currently covered under a General Permit for Stormwater Discharges Associated with Construction Activities, the contractor will need to submit the dewatering information to the SDDANR using the following form:

<https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR_AddTemplInfoFillable.pdf>

The Contractor will provide a copy of the approved permit or the submitted dewatering information to the Project Engineer prior to proceeding with any dewatering activities. The approved permit or submitted dewatering information must be kept on-site and as part of the project records.

Effluent monitoring, as a result of dewatering activities, will be summarized for each month and recorded on a separate Discharge Monitoring Report (DMR) and submitted to DANR monthly. Additional information can be found at:

<<https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/swdpermitting/Ereporting.aspx>>

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P 0127(09)214	A4	A5

Plotting Date: 03/04/2025

COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

Construction activities constitute 1 acre or more of earth disturbance and/or work in a waterway.

Action Taken/Required:

The EPA 2017 Construction General Permit is required for this project. The SDDOT is the owner of this permit and will submit the NOI to EPA 15 days prior to project start in order to obtain coverage. Work can begin after authorization is received from the EPA. This permit provides coverage for construction and dewatering activities for this project.

The Contractor must adhere to the “Special Provision Regarding Storm Water Discharge to Waters of the United States within Indian Reservations”.

Storm Water Pollution Prevention Plan

The Storm Water Pollution Prevention Plan (SWPPP) will be developed prior to the submittal of the NOI and will be implemented for all construction activities for compliance with the permit. The SWPPP must be kept on-site and updated as site conditions change. Erosion control measures and best management practices will be implemented in accordance with the SWPPP.

The DOT 298 Form will be used for site inspections and to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents and retained for a minimum of three years.

The inspection will include disturbed areas of the construction site that have not been finally stabilized, areas used for storage materials, structural control measures, and locations where vehicles enter or exit the site. These areas will be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the SWPPP will be observed to ensure that they are operating correctly, and sediment is not tracked off the site.

Information on storm water permits and SWPPPs are available on the following websites:

SDDOT: < <https://dot.sd.gov/doing-business/environmental/stormwater> >

DANR:<<https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/default.aspx> >

EPA: < <https://www.epa.gov/npdes> >

COMMITMENT F: SEASONAL WORK RESTRICTION

The State of South Dakota Game, Fish, and Parks has designated a warm water fishery associated with this project.

Action Taken/Required:

Construction or demolition activities should not take place during the Seasonal Work Restriction listed in the below table to avoid conflicts with spawning fish. If flows during this time are nonexistent or extremely low, the seasonal use restriction may not be applicable. The Contractor will not conduct in-stream work during the Seasonal Work Restriction without prior approval from the SDDOT Environmental Office.

Stream Name	Stream Classification	Seasonal Work Restriction
Little Minnesota River	Warm Water	April 1 to June 30

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, “No Dumping Allowed”.

2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P 0127(09)214	A5	A5

Plotting Date: 03/04/2025

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historic Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 150 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

COMMITMENT J: CONSTRUCTION PRACTICES FOR TEMPORARY WORKS IN WATERWAYS OF THE U.S.

The Contractor is advised that special construction measures must be taken to ensure that the waterways of the U.S. are not impacted.

Action Taken/Required:

Excavation will not occur below the ordinary high-water elevation in waterways outside of caissons, cribs, cofferdams, steel piling, or sheeting. The natural streambed will not be disturbed unless specified by the plans and under the observation of the Project Engineer. Refer to the Table of U.S. Waterways to Protect for ordinary high-water elevations. Any structure work over or within the waterway will be constructed according to Section 7.21 C of the Specifications.

All dredged or excavated materials will be placed at a site above the ordinary high-water elevation in a confined area (not classified as a wetland) that is a minimum of 50 feet away from concentrated flows of storm water, drainage courses, and inlets to prevent return of such material to the waterway.

The construction of temporary work platforms, crossings, or berms below the ordinary high-water elevation will be allowed if all material placed below the ordinary high-water elevation consists of Class B or larger riprap.

All temporary caissons, cribs, cofferdams, steel piling, sheeting, work platforms, crossings, and berms will be removed with minimal disturbance to the streambed. Proper construction practices will be used to minimize increases in suspended solids and turbidity in the waterway.

Bridge berms, wing dams, traffic diversions, channel reconstruction, stream diversions, grading, etc. will be constructed in close conformity with the plans to ensure that the hydraulic capacity of the waterway is not changed.

Temporary waterway crossings required for the Contractor's construction operations will be constructed with an adequate drainage structure size and minimum fill height to reduce the potential for upstream flooding. The Contractor will be responsible for sizing the temporary drainage structure for these crossings.

All temporary works in waterways of the US are required to be covered in the Corp of Engineers 404 Permit. At the time of the preconstruction meeting, the Contractor will submit documentation for all temporary works for the purpose of complying with the 404 Permit requirements in accordance with Section 423.3 A of the Specifications.

Table of U.S. Waterways to Protect

Station	Waterway	Ordinary High-Water Elevation
3+89	Tributary to Little Minnesota River	1150.2
95+83	Little Minnesota River	1137.7

Stream channel excavation within "Waters of the US" is subject to USACE regulatory jurisdiction. Stream channel excavation cannot exceed the permitted quantities and/or surface area. The 404 Permit is included in the Special Provisions.

The Contractor will take all precautions necessary to prevent any incidental discharges associated with the excavation and hauling of material from the stream channel. This pertains to any excavation operations such as, foundation, pier, or abutment excavation, channel cleanout, excavation for riprap protection, and removal of any temporary fill associated with construction activities.

COMMITMENT N: SECTION 404 PERMIT

The SDDOT has obtained a Section 404 Permit from the USACE for the permanent actions associated with this project.

Action Taken/Required:

The Contractor will comply with all requirements contained in the Section 404 Permit.

The Contractor will also be responsible for obtaining a Section 404 Permit for any dredge, excavation, or fill activities associated with material sources, storage areas, waste sites, and Contractor work sites outside the plan work limits that affect wetlands, floodplains, or waters of the United States.