

STATE OF SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED

PROJECT IM 0296(33)168 INTERSTATE 29 NBL HAMLIN COUNTY

PRESTRESSED GIRDER REPAIR & CONCRETE METALIZING PCN 07D4

R 52 W

TOTAL SHEETS PROJECT STATE OF SOUTH IM 0296(33)168 DAKOTA

Plotting Date: 02/12/2024

INDEX OF SHEETS

Sheet 1 **Title Sheet**

Sheet 2-3 Estimate of Quantites &

Environmental Commitments

Sheet 4-6 **Traffic Control**

Sheet 7-14 Structure 29-272-012 Plans



KRANZBURG POP. 163

Exit 164

Project Location Str. No. 29-272-012 I-29 NBL MRM 168.59

May 1, 2024

DESIGN DESIGNATION AADT (2021) AADT (2041) DHV

3975 5970 747 50% 8.2% 18.0% 80 M.P.H. DHV T% AADT T%

STORM WATER PERMIT NONE REQUIRED

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF	PROJECT	SHEET	TOTAL SHEETS	
SOUTH DAKOTA	IM 0296(33)168	2	14	

GENERAL QUANTITIES

	OLIVERAL GOARTITIES									
BID ITEM NUMBER	ITEM	QUANTITY	UNIT							
009E0010	Mobilization	Lump Sum	LS							
634E0010	Flagging	10.0	Hour							
634E0110	334E0110 Traffic Control Signs		SqFt							
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS							
634E0275	Type 3 Barricade	4	Each							
634E0420	Type C Advance Warning Arrow Board	1	Each							
634E0560	4E0560 Remove Pavement Marking, 4" or Equivalent		Ft							
634E0600	4" Temporary Pavement Marking Tape Type I	1,920	Ft							

STRUCTURE NUMBER 29-272-012

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
460E0174	Concrete Patching Material, Miscellaneous	3.5	CuFt
460E0300	Breakout Structural Concrete	0.2	CuYd
900E7080	Concrete Metalizing	2,048	SqFt

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf>

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT B: FEDERALLY THREATENED, ENDANGERED, AND PROTECTED SPECIES

COMMITMENT B2: WHOOPING CRANE

The Whooping Crane is a spring and fall migratory bird in South Dakota that is about 5 feet tall and typically stops on wetlands, rivers, and agricultural lands along their migration route. An adult Whooping Crane is white with a red crown and a long, dark, pointed bill. Immature Whooping Cranes are cinnamon brown. While in flight, their long necks are kept straight and their long dark legs trail behind. Adult Whooping Cranes' black wing tips are visible during flight.

Action Taken/Required:

Harassment or other measures to cause the Whooping Crane to leave the site is a violation of the Endangered Species Act. If a Whooping Crane is sighted roosting in the vicinity of the project, borrow pits, or staging areas associated with the project, cease construction activities in the affected area until the Whooping Crane departs and immediately contact the Project Engineer. The Project Engineer will contact the Environmental Office so that the sighting can be reported to USFWS.

COMMITMENT C: WATER SOURCE

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species (AIS) positive waters within South Dakota without prior approval from the SDDOT Environmental Office. To prevent and control the introduction and spread of invasive species into the project vicinity, all equipment will be power washed with hot water (≥140 °F) and completely dried for a minimum of 7 days prior to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the possession and transport of AIS; therefore, all attached dirt, mud, debris and vegetation must be removed and all compartments and tanks capable of holding standing water must be drained. This includes, but is not limited to, all equipment, pumps, lines, hoses and holding tanks.

The Contractor will not withdraw water directly from streams of the James, Big Sioux, and Vermillion watersheds without prior approval from the SDDOT Environmental Office.

Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Agriculture and Natural Resources (DANR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of water sources impacted by Aquatic Invasive Species in South Dakota can be accessed at:

< https://sdleastwanted.sd.gov/maps/default.aspx>

< South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species: https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04 >

COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

- 1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, "No Dumping Allowed".
- 2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

STATE	F PROJECT	SHEET	SHEETS
SOUTI DAKOT		3	14

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historic Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 100 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

SEQUENCE OF OPERATIONS

The following Sequence of Operations will be adhered to.

- 1. Install Traffic Control Signing.
- 2. Complete Prestressed Girder Repair and Metalizing on Prestressed Girders.
 - for phase 1.
- 3. Switch traffic and complete Prestressed Girder Repair and Metalizing on Prestressed Girders for phase 2.
- 4. Cleanup project site and remove Traffic Control Signing.

Contractor requests to deviate from the sequence of operations will be submitted in writing to the Engineer for review. Approval of an alternate sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work. An alternate sequence will be submitted for review a minimum of one week prior to potential implementation.

GENERAL TRAFFIC CONTROL

One lane of traffic on I-29 northbound will be always maintained. A 16' minimum lane width will be always maintained.

Road Work Ahead signs will be placed on the private road beneath the bridge during the Metalizing on Prestressed Girders. All signing on the private road beneath the bridge will be kept within the I-29 corridor ROW.

If the Metalizing on Prestressed Girders would decrease the vertical clearance by more than 4 feet above the private road beneath the bridge, Road Closed Ahead signs along with a Road Closed signs mounted to a Type 3 Barricade will be placed on the private road. The private road beneath the bridge will only be closed when work is actively being pursued and will be reopened during non-working hours.

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices, including delineation, will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost will be replaced by the Contractor at no cost to the State.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation.

All temporary speed limit signs will have a minimum mounting height of 5 feet in rural locations, even when mounted on portable supports.

All construction operations will be conducted in the general direction of traffic movement.

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Fixed location signing placed more than 4 calendar days prior to the start of construction will be covered or laid down until the time of construction. The covers must be approved by the Engineer prior to installation. The cost of materials, labor, and equipment necessary to complete this work will be incidental to other contract items. No separate payment will be made.

All fixed location signs, sign posts, and breakaway bases will be removed within 7 calendar days following project completion.

Traffic will be maintained on the driving lanes. Use of the shoulder as a driving lane will not be permitted. Any damage to the shoulder due to rerouted traffic or Contractor's equipment will be repaired at no expense to the Department.

A Type 3 Barricade will be installed at the end of a lane closure taper as detailed in these plans. Additional Type 3 Barricades will be installed facing traffic within the closed lane at a spacing of $\frac{1}{4}$ mile.

Construction vehicles will exit or enter the construction work zone at locations identified by the Engineer. At no time will construction vehicles utilize the maintenance crossovers or the Interstate median to exit or enter Interstate traffic.

If inappropriate or conflicting pavement markings exist, the markings will be removed and replaced with applicable temporary pavement markings when the work duration is more than 3 days. When the work duration is less than 3 days, the channelizing devices in the area where the pavement markings conflict will be placed at one-half of the normal channelizing device spacing. Pavement marking removals will be incidental to the contract unit price per foot for "Remove Pavement Marking, 4" or equivalent". The additional channelizing devices will be incidental to the contract lump sum price for "Traffic Control, Miscellaneous".

STATE OF	PROJECT	SHEET	TOTAL SHEETS	
SOUTH DAKOTA	IM 0296(33)168	4	14	

Rev. 2-29-24 SLS

LANE CLOSURES

Interstate lane closures will be removed when work will not be occurring for a period of 3 or more calendar days. Activities that do not involve workers being present, such as curing time for concrete, constitute work. Lane closures will not be set up on a Friday if no work will be occurring on Saturday or Sunday. In these cases, the lane closure will be installed on Monday.

WORK ZONE SPEED REDUCTION

The Department is required to obtain a speed reduction resolution prior to the installation of any SPEED LIMIT (R2-1) signs shown on standard plate 634.63. To provide adequate time for the resolution to be enacted, the Contractor will inform the Engineer a minimum of 3 weeks prior to the scheduled installation of any work zone speed reduction signs on the project. The information provided by the Contractor will include the anticipated date of sign installation, the newly reduced speed limit, the location of the work zone, and the anticipated completion date of work requiring the speed reduction.

TEMPORARY PAVEMENT MARKING TAPE, TYPE I

Temporary Pavement Marking Tape Type I will be required for lane tapers as shown on standard plate 634.63. Temporary raised pavement markers may be used in place of Temporary Pavement Marking Tape Type I.

Temporary tape or pavement markers will be removed upon completion of the project.

ITEMIZED LIST FOR TRAFFIC CONTROL SIGNS

CONVENTIONAL ROAD EXPRESSWAY / INTERSTA					TE				
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT	NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT
R2-1	SPEED LIMIT 45		24" x 30"	5.0		2	36" x 48"	12.0	24.0
R2-1	SPEED LIMIT 65		30" x 36"	7.5		3	36" x 48"	12.0	36.0
R2-1	SPEED LIMIT 80		36" x 48"	12.0		1	48" x 60"	20.0	20.0
R2-6aP	FINES DOUBLE (plaque)		24" x 18"	3.0		1	36" x 24"	6.0	6.0
R11-2	ROAD CLOSED	2	48" x 30"	10.0	20.0		48" x 30"	10.0	
W3-5	SPEED REDUCTION AHEAD (45 MPH)		48" x 48"	16.0		1	48" x 48"	16.0	16.0
W3-5	SPEED REDUCTION AHEAD (65 MPH)		48" x 48"	16.0		2	48" x 48"	16.0	32.0
W4-2	LEFT or RIGHT LANE ENDS (symbol)		48" x 48"	16.0		2	48" x 48"	16.0	32.0
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0	2	48" x 48"	16.0	32.0
W20-3	ROAD CLOSED AHEAD	2	48" x 48"	16.0	32.0		48" x 48"	16.0	
W20-5	LEFT or RIGHT LANE CLOSED AHEAD		48" x 48"	16.0		2	48" x 48"	16.0	32.0
W20-7	FLAGGER (symbol)		48" x 48"	16.0		1	48" x 48"	16.0	16.0
G20-2	END ROAD WORK		36" x 18"	4.5		1	48" x 24"	8.0	8.0
	CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT 84.0			SSWAY / INTE		254.0			

Spacing of

Advance Warning

Signs

(Feet)

(A) (B) (C)

Posted

Speed

Prior to

Work


(M.P.H.

0 - 30 200 35 - 40 350 45 - 50 500 55 750 60 - 65 1000 (A) (B) (C) 70 - 80 1000 1500 2640		SEE DE on Shee	
**Speed appropriate for location.			
Reflectorized Drum			
■ Channelizing Device			
ROAD WORK AHEAD sign is only required in advance of the first lane closure.			<u> </u>
High speed is defined as having a posted speed limit greater than 45 mph.	9		No.
		m N	EED MIT
		6 R	** 2-1
		M N	^
			T LANE OSED SEAD SO
		Olu	\\\ \mathcal{L}_{\
			** 55 55
		ROAD WORK AHEAD A	September 22, 2021
	SD	WORK ZONE SPEED REDUCTION	PLATE NUMBER
Published Date: 2024	D O	FOR INTERSTATE AND HIGH SPEED MULTI-LANE HIGHWAYS	634.63 Sheet / of 2
	T		

 STATE OF SOUTH DAKOTA
 PROJECT
 SHEET
 TOTAL SHEETS


 1M 0296(33)168
 5
 14


Plotting Date: 02/12/2024




STATE OF	PROJECT	SHEET	TOTAL	
SOUTH DAKOTA	IM 0296(33)168	6	SHEETS 14	

Plotting Date: 02/12/2024







ESTIMATE OF STRUCTURE QUANTITIES

ITEM NO.	DESCRIPTION	QUANTITY	UNIT
460E0174	Concrete Patching Material, Miscellaneous	3.5	CuFt
460E0300	Breakout Structural Concrete	0.2	CuYd
900E7080	Concrete Metalizing	2048	SqFt

SPECIFICATIONS

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications and Special Provisions as included in the Proposal.

DETAILS AND DIMENSIONS OF EXISTING BRIDGE

- 1. All details and dimensions of the existing bridge, contained in these plans, are based on the original construction plans. It is the Contractor's responsibility to inspect and verify the actual field conditions and any necessary as-built dimensions affecting the satisfactory completion of the work required for this project.
- 2. The stationing shown in the original construction plans is reversed from the current project. As such, labels for the begin and end of bridge as well as the substructure units are reversed.

SCOPE OF BRIDGE WORK & SEQUENCE OF OPERATIONS

All work on this structure will be accomplished with the traffic control shown elsewhere in the plans. Alternate sequence of operations may be submitted by the Contractor for approval by the Engineer a minimum of two weeks prior to the preconstruction meeting.

- 1. Breakout and repair concrete on prestressed girders at designated locations for first phase of construction.
- 2. Perform concrete metalizing on prestressed girders for first phase of construction.
- 3. Switch traffic and repeat steps 1 and 2 for the second phase of construction.

CONCRETE BREAKOUT

 Deteriorated areas on the prestressed girders will be broken out and repaired according to the plans. Breakout limits will remove delaminated concrete and expose at least a half the diameter of the reinforcing steel. The removal area will have vertical edges where practical, feathered edges will not be allowed. The removal limits will be as approved by the Engineer.

- 2. Use chipping hammers not heavier than 15-pound class for concrete removal around rebar. Care will be taken not to damage the reinforcing steel and prestressing strands in the prestressed girders during concrete breakout. Any reinforcing steel or prestressing strands that are damaged during concrete breakout will be replaced or repaired (as approved by the Engineer) by the Contractor at no cost to the Department. All broken out concrete will be disposed of in accordance with the Environmental Commitments.
- 3. The deteriorated areas shown in the plans are an approximation and are based on a delamination survey obtained in April 2022. The actual repair areas will be determined in the field and as approved by the Engineer.
- 4. After removing all loose concrete to the defined limits, the areas will be sandblasted and blown clean with clean, dry, oil-free compressed air at 90 psi. Remove rust on exposed reinforcing steel by scraping, wire brushing, or sand blasting as approved by the Engineer.
- 5. All broken out concrete and discarded reinforcing steel will become the property of the Contractor and will be disposed of at a site obtained by the Contractor and approved by the Engineer. An appropriate site will be as described in the Environmental Commitments.
- 6. During concrete removal operations, no concrete will be allowed to fall into Strayhorse Creek.
- 7. The contract unit price per cubic yard for Breakout Structural Concrete will include breaking out concrete, cleaning, straightening reinforcing steel, and disposal of all broken out material.

VERTICAL SPALL REPAIR

- Concrete used in vertical patching applications on the prestressed girders where forms are not practical will consist of one of the following products, or equal as approved by the Office of Bridge Design.
 - a. Recrete 20 MinDayton Superior1125 Byers RoadMiamisburg, OH 45342Phone: (800) 745-3700

Web site: www.daytonsuperior.com

b. Sika Repair 223
 Stan Houston Equipment Company, Inc
 Sioux Falls, SD 57104
 Phone: (605) 336-3727
 Web site: www.stanhouston.com

c. Meadow Crete GPS W.R. Meadows, Inc P.O. Box 338 Hampshire, IL 60140-2100 Phone: (800) 342-5976

Web site: www.wrmeadows.com

- STATE OF
 PROJECT
 SHEET NO. SHEETS
 TOTAL NO. SHEETS

 S.D.
 IM 0296(33)168
 8
 14
- 2. The concrete patch material will be applied and cured as recommended by the manufacturer and as approved by the Engineer.
- 3. The cost of furnishing and placing vertical patching material including all labor, equipment, tools, and any incidentals necessary to complete the work will be paid for at the contract unit price per cubic foot for Concrete Patching Material, Miscellaneous.

CONCRETE METALIZING

The Concrete Metalizing will be installed in accordance with the Special Provision for Concrete Metalizing.

(NORTHBOUND LANES)
ESTIMATE OF STRUCTURE QUANTITIES AND NOTES

FOR 183' - 0" PRESTRESSED CONCRETE GIRDER BRIDGE

STR. NO. 29-272-012

MARCH 2024



DESIGNED BY CK. DES. BY DRAFTED BY THUS BRIDGE ENGINEER

DESIGNED BY CK. DES. BY THUS BRIDGE ENGINEER

