

 STATE OF SOUTH DAKOTA
 PROJECT
 SHEET
 TOTAL SHEETS

 PT 0908(105)349
 A1
 A5

Plotting Date:

08/21/2024

08-12-2024-JRF

Section B - Grading

| Section B - Grading | | | |
|---------------------|---|----------|------|
| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
| 009E0010 | Mobilization | Lump Sum | LS |
| 009E3220 | Reestablish Right-of-Way and Property Corner | 92 | Each |
| 009E3230 | Grade Staking | 4.958 | Mile |
| 009E3245 | Final Cross Section Survey | 2.663 | Mile |
| 009E3250 | Miscellaneous Staking | 2.663 | Mile |
| 009E3280 | Slope Staking | 2.266 | Mile |
| 009E3290 | Structure Staking | 3 | Each |
| 009E3301 | Engineer Directed Surveying/Staking | 10.0 | Hour |
| 009E4200 | Construction Schedule, Category II | Lump Sum | LS |
| 100E0100 | Clearing | Lump Sum | LS |
| 110E0600 | Remove Fence | 11,606 | Ft |
| 110E0707 | Remove High Tension 4 Cable Guardrail | 840 | Ft |
| 110E0730 | Remove Beam Guardrail | 466.0 | Ft |
| 110E1010 | Remove Asphalt Concrete Pavement | 16,261.8 | SqYd |
| 110E1100 | Remove Concrete Pavement | 32,690.3 | SqYd |
| 110E6016 | Remove High Tension 4 Cable Guardrail Anchor Assembly for Reset | 4 | Each |
| 110E6250 | Remove Beam Guardrail Trailing End Terminal for Reset | 2 | Each |
| 120E0010 | Unclassified Excavation | 86,136 | CuYd |
| 120E0600 | Contractor Furnished Borrow | 72,011 | CuYd |
| 120E1000 | Muck Excavation | 12,074 | CuYd |
| 120E2000 | Undercutting | 36,927 | CuYd |
| 120E6100 | Water for Embankment | 1,375.3 | MGal |
| 250E0020 | Incidental Work, Grading | Lump Sum | LS |
| 421E0100 | Pipe Culvert Undercut | 85 | CuYd |
| 450E0122 | 18" RCP Class 2, Furnish | 520 | Ft |
| 450E0130 | 18" RCP, Install | 520 | Ft |
| 450E0142 | 24" RCP Class 2, Furnish | 298 | Ft |
| 450E0150 | 24" RCP, Install | 298 | Ft |
| 450E0182 | 36" RCP Class 2, Furnish | 184 | Ft |
| 450E0190 | 36" RCP, Install | 184 | Ft |
| 450E0192 | 42" RCP Class 2, Furnish | 76 | Ft |
| 450E0200 | 42" RCP, Install | 76 | Ft |
| 450E0416 | 24" RCP Bend, Furnish | 4 | Each |
| 450E0417 | 24" RCP Bend, Install | 4 | Each |
| 450E2028 | 36" RCP Flared End, Furnish | 2 | Each |
| 450E2029 | 36" RCP Flared End, Install | 2 | Each |
| 450E2032 | 42" RCP Flared End, Furnish | 2 | Each |
| 450E2033 | 42" RCP Flared End, Install | 2 | Each |
| 450E2200 | 24" RCP Sloped End, Furnish | 4 | Each |
| 450E2201 | 24" RCP Sloped End, Install | 4 | Each |
| 450E2304 | 18" RCP Safety End, Furnish | 5 | Each |
| 450E2307 | 18" RCP Safety End, Install | 5 | Each |

Section B – Grading (Continued)

| BID ITEM | ID ITEM | | | |
|----------|--|----------|------|--|
| NUMBER | ITEM | QUANTITY | UNIT | |
| 450E5243 | 66" CMP Flared End, Furnish | 2 | Each | |
| 450E5244 | 66" CMP Flared End, Install | 2 | Each | |
| 450E5314 | 30" CMP Sloped End, Furnish | 2 | Each | |
| 450E5315 | 30" CMP Sloped End, Install | 2 | Each | |
| 450E7630 | 30" Steel Pipe, Furnish | 72 | Ft | |
| 450E7666 | 66" Steel Pipe, Furnish | 134 | Ft | |
| 451E5130 | Bore and Jack 30" Pipe | 72 | Ft | |
| 451E5166 | Bore and Jack 66" Pipe | 134 | Ft | |
| 462E0100 | Class M6 Concrete | 9.4 | CuYd | |
| 480E0100 | Reinforcing Steel | 888 | Lb | |
| 600E0200 | Type II Field Laboratory | 1 | Each | |
| 620E0020 | Type 2 Right-of-Way Fence | 11,606 | Ft | |
| 620E0510 | Type 1 Temporary Fence | 10,904 | Ft | |
| 620E0515 | Type 1A Temporary Fence | 702 | Ft | |
| 620E1020 | 2 Post Panel | 12 | Each | |
| 620E1030 | 3 Post Panel | 28 | Each | |
| 629E0110 | High Tension 4 Cable Guardrail | 840 | Ft | |
| 629E0290 | High Tension Cable Guardrail Anchor Assembly | 4 | Each | |
| 629E0295 | Reset High Tension Cable Guardrail Anchor Assembly | 4 | Each | |
| 630E0110 | Straight Double Class A Thrie Beam Guardrail with Wood Posts | 175.0 | Ft | |
| 630E0500 | Type 1 MGS | 150.0 | Ft | |
| 630E1500 | Type 1 Guardrail Transition | 2 | Each | |
| 630E2001 | Asymmetrical W Beam to Thrie Beam Guardrail Transition | 4 | Each | |
| 630E2017 | MGS MASH Flared End Terminal | 2 | Each | |
| 630E2018 | MGS MASH Tangent End Terminal | 4 | Each | |
| 630E2055 | Thrie Beam Guardrail Trailing End Terminal | 2 | Each | |
| 630E5210 | Reset Beam Guardrail Trailing End Terminal | 2 | Each | |
| 670E4205 | Type M Frame and Grate Assembly | 5 | Each | |
| 720E1010 | PVC Coated Bank and Channel Protection Gabion | 23.0 | CuYd | |
| 831E0110 | Type B Drainage Fabric | 66 | SqYd | |

Section C - Traffic Control

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|---|----------|------|
| 634E0010 | Flagging | 60.0 | Hour |
| 634E0110 | Traffic Control Signs | 1,657.7 | SqFt |
| 634E0120 | Traffic Control, Miscellaneous | Lump Sum | LS |
| 634E0275 | Type 3 Barricade | 25 | Each |
| 634E0380 | Tubular Marker | 200 | Each |
| 634E0390 | Replace Tubular Marker | 20 | Each |
| 634E0420 | Type C Advance Warning Arrow Board | 4 | Each |
| 634E0630 | Temporary Pavement Marking | 14.5 | Mile |
| 634E1002 | Detour and Restriction Signing | 1,325.4 | SqFt |
| 634E1215 | Contractor Furnished Portable Changeable Message Sign | 4 | Each |
| 634E1260 | Truck/Trailer Mounted Attenuator | 2 | Each |

INDEX OF SHEETS

A1 to A2 Estimate of Quantities for Sections B, C, D, E, F,

M, and S

A3 to A5 Environmental Commitments

Section D - Erosion and Sediment Control

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|--|----------|------|
| 110E1690 | Remove Sediment | 7.6 | CuYd |
| 110E1695 | Remove Sediment Filter Bag | 160 | Ft |
| 110E1700 | Remove Silt Fence | 1,659 | Ft |
| 230E0010 | Placing Topsoil | 13,239 | CuYd |
| 730E0100 | Cover Crop Seeding | 20.0 | Bu |
| 730E0208 | Type E Permanent Seed Mixture | 120 | Lb |
| 730E0212 | Type G Permanent Seed Mixture | 488 | Lb |
| 731E0200 | Fertilizing | 12.41 | Ton |
| 732E0100 | Mulching | 49.5 | Ton |
| 734E0132 | Type 2 Turf Reinforcement Mat | 356.0 | SqYd |
| 734E0154 | 12" Diameter Erosion Control Wattle | 2,750 | Ft |
| 734E0165 | Remove and Reset Erosion Control Wattle | 698 | Ft |
| 734E0180 | Sediment Filter Bag | 160 | Ft |
| 734E0325 | Surface Roughening | 7.6 | Acre |
| 734E0602 | Low Flow Silt Fence | 5,705 | Ft |
| 734E0604 | High Flow Silt Fence | 886 | Ft |
| 734E0610 | Mucking Silt Fence | 460 | CuYd |
| 734E0620 | Repair Silt Fence | 1,659 | Ft |
| 734E0845 | Sediment Control at Inlet with Frame and Grate | 5 | Each |
| 900E1320 | Construction Entrance | 2 | Each |

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

| STATE OF | PROJECT | SHEET | TOTAL SHEETS |
|-----------------|------------------|-------|-----------------|
| SOUTH DAKOTA | PT 0908(105)349 | ΛΩ. | |
| DAKOTA | 1 1 0000(100)010 | AZ | A5 |

Section E – Structure

Structure Numbers 44-052-140 & 44-065-126

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT | |
|--------------------|---|----------|------|--|
| 420E0200 | Structure Excavation, Box Culvert | 112 | CuYd | |
| 421E0200 | Box Culvert Undercut | 437 | CuYd | |
| 560E0156 | 11'x5' Precast Concrete Box Culvert, Furnish | 44.0 | Ft | |
| 560E0157 | 11'x5' Precast Concrete Box Culvert, Install | 44.0 | Ft | |
| 560E1156 | 11'x5' Precast Concrete Box Culvert End Section, Furnish | 2 | Each | |
| 560E1157 | 11'x5' Precast Concrete Box Culvert End Section, Install | 2 | Each | |
| 560E2090 | 2-9'x4' Precast Concrete Box Culvert, Furnish | 170.0 | Ft | |
| 560E2091 | 2-9'x4' Precast Concrete Box Culvert, Install | 170.0 | Ft | |
| 560E3090 | 2-9'x4' Precast Concrete Box Culvert End Section, Furnish | 2 | Each | |
| 560E3091 | 2-9'x4' Precast Concrete Box Culvert End Section, Install | 2 | Each | |
| 700E0210 | Class B Riprap | 95.8 | Ton | |
| 831E0110 | Type B Drainage Fabric | 122 | SqYd | |
| 831E0300 | Reinforcement Fabric (MSE) | 496 | SqYd | |
| | | | | |

Structure Number 44-054-126 Alternate A

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|-----------------------------------|----------|------|
| 420E0200 | Structure Excavation, Box Culvert | 76 | CuYd |
| 421E0200 | Box Culvert Undercut | 312 | CuYd |
| 460E0120 | Class A45 Concrete, Box Culvert | 214.1 | CuYd |
| 460E0380 | Install Dowel in Concrete | 22 | Each |
| 480E0100 | Reinforcing Steel | 35,234 | Lb |
| 700E0210 | Class B Riprap | 24.0 | Ton |
| 831E0110 | Type B Drainage Fabric | 35 | SqYd |
| 831E0300 | Reinforcement Fabric (MSE) | 437 | SqYd |

Structure Number 44-054-126 Alternate B

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|---|----------|------|
| 420E0200 | Structure Excavation, Box Culvert | 64 | CuYd |
| 421E0200 | Box Culvert Undercut | 291 | CuYd |
| 560E0116 | 9'x8' Precast Concrete Box Culvert, Furnish | 216.0 | Ft |
| 560E0117 | 9'x8' Precast Concrete Box Culvert, Install | 216.0 | Ft |
| 560E1116 | 9'x8' Precast Concrete Box Culvert End Section, Furnish | 2 | Each |
| 560E1117 | 9'x8' Precast Concrete Box Culvert End Section, Install | 2 | Each |
| 700E0210 | Class B Riprap | 25.7 | Ton |
| 831E0110 | Type B Drainage Fabric | 37 | SqYd |
| 831E0300 | Reinforcement Fabric (MSE) | 406 | SqYd |

Section F - Surfacing

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|--|----------|------|
| 009E3320 | Checker | Lump Sum | LS |
| 110E7020 | Remove Interim Crossover Closure for Reset | 224 | Ft |
| 120E6200 | Water for Granular Material | 316.3 | MGal |
| 120E9000 | Pit Run | 4,685.7 | Ton |
| 260E1010 | Base Course | 3,456.0 | Ton |
| 260E2010 | Gravel Cushion | 18,254.2 | Ton |
| 320E1200 | Asphalt Concrete Composite | 1,508.4 | Ton |
| 380E0050 | 8" Nonreinforced PCC Pavement | 4,476.1 | SqYd |
| 380E0100 | 10.5" Nonreinforced PCC Pavement | 4,559.8 | SqYd |
| 380E0550 | 10.5"Continuously Reinforced PCC Pavement | 28,484.0 | SqYd |
| 380E0800 | PCC Shoulder Pavement | 12,430.9 | SqYd |
| 380E6000 | Dowel Bar | 4,683 | Each |
| 380E6110 | Insert Steel Bar in PCC Pavement | 192 | Each |
| 450E4749 | 15" CMP 16 Gauge, Furnish | 204 | Ft |
| 450E4750 | 15" CMP, Install | 204 | Ft |
| 450E5005 | 15" CMP Elbow, Furnish | 2 | Each |
| 450E5006 | 15" CMP Elbow, Install | 2 | Each |
| 450E5402 | 15" CMP Safety End, Furnish | 1 | Each |
| 450E5403 | 15" CMP Safety End, Install | 1 | Each |
| 450E6119 | 15" Slotted CMP 16 Gauge, Furnish | 260 | Ft |
| 450E6120 | 15" Slotted CMP, Install | 260 | Ft |
| 451E3115 | 15" Pipe Cap | 1 | Each |
| 462E0100 | Class M6 Concrete | 25.7 | CuYd |
| 464E0100 | Controlled Density Fill | 9.6 | CuYd |
| 629E9010 | Interim Crossover Closure | 368 | Ft |
| 629E9060 | Reset Interim Crossover Closure | 224 | Ft |
| 831E0210 | Non-woven Separator Fabric | 5,010 | SqYd |

Section M – Pavement Markings

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|--|----------|------|
| 633E3000 | Durable Pavement Marking, 4" White | 14,571 | Ft |
| 633E3005 | Durable Pavement Marking, 4" Yellow | 11,256 | Ft |
| 633E3020 | Durable Pavement Marking, 12" White | 600 | Ft |
| 633E5100 | Grooving for Durable Pavement Marking, 4" | 25,827 | Ft |
| 633E5110 | Grooving for Durable Pavement Marking, 12" | 600 | Ft |

Section S - Permanent Signing

| BID ITEM NUMBER | ITEM | QUANTITY | UNIT |
|--------------------|--|----------|------|
| 110E0130 | Remove Traffic Sign | 1 | Each |
| 110E0135 | Remove Delineator | 83 | Each |
| 110E7150 | Remove Sign for Reset | 2 | Each |
| 632E1340 | 2.5"x2.5" Perforated Tube Post | 36.8 | Ft |
| 632E2000 | 4"x4" Amber Delineator with 1.12 Lb/Ft Post | 20 | Each |
| 632E2004 | 4"x8" Amber Delineator with 1.12 Lb/Ft Post | 5 | Each |
| 632E2020 | 4"x4" White Delineator with 1.12 Lb/Ft Post | 20 | Each |
| 632E2024 | 4"x8" White Delineator with 1.12 Lb/Ft Post | 28 | Each |
| 632E2220 | Guardrail Delineator | 24 | Each |
| 632E2510 | Type 2 Object Marker Back to Back | 14 | Each |
| 632E2520 | Type 2 Object Marker | 8 | Each |
| 632E3203 | Flat Aluminum Sign, Nonremovable Copy High Intensity | 23.5 | SqFt |
| 632E3500 | Reset Sign | 2 | Each |

| STATE OF | PROJECT | SHEET | TOTAL SHEETS |
|-----------------|-----------------|-------|-----------------|
| SOUTH DAKOTA | PT 0908(105)349 | A3 | A5 |

ing Date:

08/21/202

ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT A: AQUATIC RESOURCES

COMMITMENT A1: WETLANDS

All efforts to avoid and minimize wetland impacts from the project have resulted in approximately 2.72 acre(s) of wetlands (includes temporary and permanent) becoming impacted. Refer to Section B – Grading Plans for location and boundaries of the impacted wetlands.

Table of Impacted Wetlands

| Wetland No. | Station | Perm. Impact Left (Acres) | Perm. Impact Right (Acres) | Temp. Impact Left (Acres) | Temp. Impact Right (Acres) | Total Impact (Acres) |
|----------------|------------------------|------------------------------------|-------------------------------------|------------------------------------|-------------------------------------|----------------------------|
| WL 1 | 35+00 | 0.00 | 0.004 | 0.00 | 0.00 | 0.004 |
| WL 2 | 610+00 to 616+00 | 0.00 | 0.036 | 0.00 | 0.278 | 0.314 |
| WL3 | 700+00 to 703+00 | 0.00 | 0.017 | 0.00 | 0.00 | 0.017 |
| WL 5a | 1+00 to 2+00 | 0.00 | 0.00 | 0.00 | 0.027 | 0.027 |

| Wetland No. | Station | Perm. Impact Left (Acres) | Perm. Impact Right (Acres) | Temp. Impact Left (Acres) | Temp. Impact Right (Acres) | Total Impact (Acres) |
|----------------|------------------------|------------------------------------|-------------------------------------|------------------------------------|-------------------------------------|----------------------------|
| WL 5b | 1+00 to 2+00 | 0.003 | 0.00 | 0.00 | 0.00 | 0.003 |
| WL6a | 477+00 to 485+00 | 0.155 | 0.00 | 0.00 | 0.00 | 0.155 |
| WL 6b | 809+00 to 817+97 | 0.00 | 0.427 | 0.00 | 0.00 | 0.427 |
| WL 6c | 500+00 to 505+00 | 0.148 | 0.00 | 0.00 | 0.00 | 0.148 |
| WL 7 | 492+00 to 599+00 | 0.00 | 0.168 | 0.00 | 0.449 | 0.617 |
| WL 8 | 711+00 to 718+10 | 0.167 | 0.00 | 0.089 | 0.00 | 0.256 |
| WL9a | 707+00 to 711+00 | 0.086 | 0.00 | 0.00 | 0.00 | 0.086 |
| WL 9b | 707+00 to 711+00 | 0.00 | 0.119 | 0.00 | 0.00 | 0.119 |
| WL 11a | 560+00 to 572+00 | 0.273 | 0.00 | 0.00 | 0.00 | 0.273 |
| WL11b | 553+00 to 555+00 | 0.00 | 0.054 | 0.00 | 0.00 | 0.054 |
| WL 12a | 562+00 to 570+00 | 0.00 | 0.166 | 0.00 | 0.00 | 0.166 |
| WL 13a | 554+00 | 0.00 | 0.047 | 0.00 | 0.012 | 0.059 |

Action Taken/Required:

SDDOT will acquire 2.66 credits in the Lower James GSA from the Ducks Unlimited Sanborn County Mitigation Bank to mitigate permanent impacts. SDDOT will acquire 2.30 credits in the Vermillion GSA from the SDDOT's Vermillion Site 1 Mitigation Bank Site to mitigate permanent impacts.

Temporary impacts identified in the Table of Impacted Wetlands will not be mitigated as original contours and elevations will be re-established as designated in Section B – Grading Plans. Prior to initiating temporary work in wetlands, the Contractor will submit a plan to the Project Engineer in accordance with Section 7.21 D of the Specifications.

The Contractor will notify the Project Engineer if additional easement is needed to complete work adjacent to any wetland. The Project Engineer will obtain an appropriate course of action from the Environmental Office before proceeding with construction activities that affect any wetlands beyond the work limits and easements shown in the plans.

COMMITMENT B: FEDERALLY THREATENED, ENDANGERED, AND PROTECTED SPECIES

COMMITMENT B2: WHOOPING CRANE

The Whooping Crane is a spring and fall migratory bird in South Dakota that is about 5 feet tall and typically stops on wetlands, rivers, and agricultural lands along their migration route. An adult Whooping Crane is white with a red crown and a long, dark, pointed bill. Immature Whooping Cranes are cinnamon brown. While in flight, their long necks are kept straight and their long dark legs trail behind. Adult Whooping Cranes' black wing tips are visible during flight.

Action Taken/Required:

Harassment or other measures to cause the Whooping Crane to leave the site is a violation of the Endangered Species Act. If a Whooping Crane is sighted roosting in the vicinity of the project, borrow pits, or staging areas associated with the project, cease construction activities in the affected area until the Whooping Crane departs and immediately contact the Project Engineer. The Project Engineer will contact the Environmental Office so that the sighting can be reported to USFWS.

 STATE OF SOUTH DAKOTA
 PROJECT
 SHEET
 TOTAL SHEETS

 PT 0908(105)349
 A4
 A5

Plotting Date:

08/21/2024

COMMITMENT C: WATER SOURCE

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species (AIS) positive waters within South Dakota without prior approval from the SDDOT Environmental Office. To prevent and control the introduction and spread of invasive species into the project vicinity, all equipment will be power washed with hot water (≥140 °F) and completely dried for a minimum of 7 days prior to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the possession and transport of AIS; therefore, all attached dirt, mud, debris and vegetation must be removed and all compartments and tanks capable of holding standing water must be drained. This includes, but is not limited to, all equipment, pumps, lines, hoses and holding tanks.

The Contractor will not withdraw water directly from streams of the James, Big Sioux, and Vermillion watersheds without prior approval from the SDDOT Environmental Office.

Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Agriculture and Natural Resources (DANR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of water sources impacted by Aquatic Invasive Species in South Dakota can be accessed at: https://sdleastwanted.sd.gov/maps/default.aspx

South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species: https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04

COMMITMENT D: WATER QUALITY STANDARDS

COMMITMENT D1: SURFACE WATER QUALITY

The project work is near Gross Lake. Gross Lake is classified as a warm water, marginal fishery with a total suspended solids standard of less than 150 mg/L 30-day average, less than 263 mg/L daily maximum.

Gross Lake is classified as fish and wildlife propagation, recreation, irrigation, and stock watering waters. Because of these beneficial uses, special construction measures may have to be taken to ensure that this water body is not impacted.

This project may be in the vicinity of multiple streams and wetlands. These waters are considered waters of the state and are protected under Administrative Rules of South Dakota (ARSD) Chapter 74:51. Special construction measures may have to be taken to ensure that this water body is not impacted.

Action Taken/Required:

The Contractor is advised that the South Dakota Surface Water Quality Standards, administered by the South Dakota Department of Agriculture and Natural Resources (DANR), apply to this project. Special construction measures will be taken to ensure the above standard(s) of the surface waters are maintained and protected.

COMMITMENT D2: SURFACE WATER DISCHARGE

The DANR General Permit for Temporary Discharge is required for temporary dewatering and discharges to waters of the state. The effluent limit for total suspended solids will be 90 mg/L 30-day average. The effluent limit applies to discharges to all waters of the state except discharges to waters classified as cold water permanent fish life propagation waters according to the ARSD 74:51:01:45. For discharges to waters of the state classified as cold water permanent fish life propagation waters, the effluent limit for total suspended solids will be 53 mg/L daily maximum.

The permittee has the option of completing effluent testing or implementing a pollution prevention plan for compliance with this permit. If the permittee develops a pollution prevention plan instead of total suspended solids sampling, the plan must be developed and implemented prior to discontinuing total suspended solids sampling. Refer to Section 4.0 of the permit. If any pollutants are suspected of being discharged, a sample must be taken for those parameters listed in Section 3.4 of the permit.

Refer to Commitment D1: Surface Water Quality for stream classification. https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf

Action Taken/Required:

If construction dewatering is required and this project is currently covered under a General Permit for Stormwater Discharges Associated with Construction Activities, the contractor will need to submit the dewatering information to the SDDANR using the following form:

https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR_AddTempInfoFillable.pdf

The Contractor will provide a copy of the approved permit or the submitted dewatering information to the Project Engineer prior to proceeding with any dewatering activities. The approved permit or submitted dewatering information must be kept on-site and as part of the project records.

Effluent monitoring, as a result of dewatering activities, will be summarized for each month and recorded on a separate Discharge Monitoring Report (DMR) and submitted to DANR monthly. Additional information can be found at: https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/swdpermitting/Ereporting.aspx

COMMITMENT E: STORM WATER

Construction activities constitute 1 acre or more of earth disturbance and/or work in a waterway.

Action Taken/Required:

The DANR General Permit for Stormwater Discharges Associated with Construction Activities is required for construction activity disturbing one or more acres of earth and work in a waterway. The SDDOT is the owner of this permit and will submit the NOI to DANR 15 days prior to project start in order to obtain coverage under the General Permit. Work can begin once the DANR letter of approval is received.

The Contractor must adhere to the "Special Provision Regarding Storm Water Discharges to Waters of the State."

The Contractor will complete the DANR Contractor Certification Form prior to the pre-construction meeting. The form certifies under penalty of law that the Contractor understands and will comply with the terms and conditions of the permit for this project. Work may not begin on this project until this form is signed and submitted to DANR.

The form can be found at:

https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR CGPAppendixCCA2018Fillable.pdf

The Contractor is advised that permit coverage may also be required for offsite activities, such as borrow and staging areas, which are the responsibility of the Contractor.

Storm Water Pollution Prevention Plan

The Storm Water Pollution Prevention Plan (SWPPP) will be developed prior to the submittal of the NOI and will be implemented for all construction activities for compliance with the permit. The SWPPP must be kept on-site and updated as site conditions change. Erosion control measures and best management practices will be implemented in accordance with the SWPPP.

The DOT 298 Form will be used for site inspections and to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents and retained for a minimum of three years.

The inspection will include disturbed areas of the construction site that have not been finally stabilized, areas used for storage materials, structural control measures, and locations where vehicles enter or exit the site. These areas will be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the SWPPP will be observed to ensure that they are operating correctly, and sediment is not tracked off the site.

Information on storm water permits and SWPPPs are available on the following websites:

SDDOT: https://dot.sd.gov/doing-business/environmental/stormwater

DANR: https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/default.aspx

EPA: https://www.epa.gov/npdes

| STATE OF | PROJECT | SHEET | TOTAL SHEETS |
|-----------------|-----------------|-------|-----------------|
| SOUTH DAKOTA | PT 0908(105)349 | A5 | A5 |

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

- Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, "No Dumping Allowed".
- Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historic Preservation Office (SHPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow 30 Days from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 150 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites. and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

COMMITMENT M: SECTION 4(f)/6(f) RESOURCES

COMMITMENT M1: SECTION 4(f) PROPERTY

A Section 4(f) Evaluation concluded there are no feasible and prudent alternatives to avoiding Section 4(f) property located within the project.

| Station | Section 4(f) Property |
|------------------|----------------------------------|
| 600+00 to 624+00 | Welker Waterfowl Production Area |
| 700+00 to 718+00 | Gross Lake Game Production Area |

Action Taken/Required:

The following measures are required to minimize harm to the above Section

Welker Waterfowl Production Area (Station 600+00 to 624+00): The occupancy of Welker Waterfowl Production Area will be temporary, the scope of the work is minor, there are no anticipated permanent adverse physical impacts, and the land disturbed will be fully restore and returned to the condition which existed prior to the project.

Gross Lake Game Production Area (Station 700+00 to 718+00): The occupancy of Gross Lake Game Production Area will be temporary, the scope of the work is minor, there are no anticipated permanent adverse physical impacts, and the land disturbed will be fully restore and returned to the condition which existed prior to the project.

The Contractor is not permitted to stage equipment or materials within [name of park(s)]. The Contractor will notify the Project Engineer if additional easement is needed to complete the work adjacent to any Section 4(f) property. The Project Engineer will obtain an appropriate course of action from the Environmental Office before proceeding with construction activities that affect any Section 4(f) property.

COMMITMENT N: SECTION 404 PERMIT

The SDDOT has obtained a Section 404 Permit from the USACE for the permanent actions associated with this project.

Action Taken/Required:

The Contractor will comply with all requirements contained in the Section 404

The Contractor will also be responsible for obtaining a Section 404 Permit for any dredge, excavation, or fill activities associated with material sources, storage areas, waste sites, and Contractor work sites outside the plan work limits that affect wetlands, floodplains, or waters of the United States.