

Plot Scale - 1:9750

Plotted From - trpr25289

File - ... \Trip09AC\09AC_Title.dgn

PT 0183(28)2 PCN 09AC
 Str. No. 62-235-518
 Over Keya Paha River
 Length: 122.7' = 0.023 Mile
 US 183 MRM 2.23

T O C O L U M B I A

320 AVE

WEWELA

318 AVE

319 AVE

26

35

36

19

31

T 95 N

JCT. NEB. 12
7.4

R 76 W

R 75 W

S 1° 3' E

S 89° 55' W

183

SECTION C ESTIMATE OF QUANTITIES

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
009E3200	Construction Staking	Lump Sum	LS
009E4100	Construction Schedule, Category I	Lump Sum	LS
634E0010	Flagging	40.0	Hour
634E0110	Traffic Control Signs	266.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0275	Type 3 Barricade	2	Each
634E0310	Temporary Flexible Vertical Markers (Tabs)	2,200	Ft
634E0560	Remove Pavement Marking, 4" or Equivalent	3,344	Ft
634E0600	4" Temporary Pavement Marking Tape Type I	1,144	Ft

SEQUENCE OF OPERATIONS

The Contractor will submit a sequence of operations for approval two weeks prior to the preconstruction meeting. If changes to the sequence of operations are proposed during the project, these must be submitted for review a minimum of one week prior to potential implementation. Approval for changes to the sequence of operations will only be allowed when the proposed changes meet with the Department’s intent for traffic control and sequencing of the work.

Traffic will be maintained through the project at ALL times.

GENERAL TRAFFIC CONTROL

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices, including delineation, will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost will be replaced by the Contractor at no cost to the State.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Fixed location signing placed more than 4 calendar days prior to the start of construction will be covered or laid down until the time of construction. The covers must be approved by the Engineer prior to installation. The cost of materials, labor, and equipment necessary to complete this work will be incidental to other contract items. No separate payment will be made.

All fixed location signs, sign posts, and breakaway bases will be removed within 7 calendar days following pavement marking.

All haul trucks will be equipped with an additional flashing amber light that is visible from the backside of the haul truck. The costs for the flashing amber lights will be incidental to the various related contract items.

Traffic will be maintained on the driving lanes. Use of the shoulder as a driving lane will not be permitted. Any damage to the shoulder due to rerouted traffic or Contractor’s equipment will be repaired at no expense to the Department.

FLAGGING

Operations will be conducted so that the traveling public will not have to wait longer than 15 minutes at the flagger station.

If an emergency vehicle needs to pass through the project, the Contractor will be required to expedite traffic movement. All costs associated with this will be incidental to the contract unit price per hour for “Flagging”.

TEMPORARY PAVEMENT MARKING

In the absence of a signed lane closure or pilot car operation, FLAGGER (W20-7) symbol signs and flaggers, or a shadow vehicle with rotating yellow lights or strobe lights will be positioned on the shoulder in advance of workers for both directions of traffic during the installation and removal of the temporary flexible vertical markers (tabs). The traffic control device used will be moved intermittently to provide proper warning of the work operation. A ROAD WORK AHEAD (W20-1) sign, a WORKER (W21-1) symbol sign or a BE PREPARED TO STOP (W3-4) sign will be mounted on the rear of the shadow vehicle. The method of traffic control used by the Contractor for this work must be approved by the Engineer.

TEMPORARY PAVEMENT MARKING TAPE, TYPE I

Temporary pavement marking for stop lines will consist of 4” Temporary Pavement Marking Tape Type I. Placement of each 24” white stop line will be accomplished by placing six pieces of 4” x 12’ tape adjacent to one another. Each workspace requires two stop lines which is an equivalent of approximately 144’ of 4” tape (1 workspace at 144’ = 144’). Temporary pavement marking on centerline will consist of temporary flexible vertical markers (tabs) or temporary raised pavement markers and will be used as depicted on standard plate 634.25 when the stop condition must remain in place during nighttime hours, 9:00 pm to 6:00 am (Estimate 1 workspace remaining during nighttime hours x 2,200’ per workspace = 2,200’). Temporary tape will be removed upon completion of the project.

ITEMIZED LIST FOR TRAFFIC CONTROL SIGNS

SIGN CODE	SIGN DESCRIPTION	CONVENTIONAL ROAD			
		NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT
R1-1	STOP	2	30"	5.2	10.4
W1-4	REVERSE CURVE (L or R)	2	48" x 48"	16.0	32.0
W3-1	STOP AHEAD (symbol)	2	48" x 48"	16.0	32.0
W3-4	BE PREPARED TO STOP	2	48" x 48"	16.0	32.0
W13-1P	ADVISORY SPEED (plaque)	2	30" x 30"	6.3	12.6
W16-2P	1000 FEET (supplemental distance plaque)	2	30" x 24"	5.0	10.0
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0
W20-4	ONE LANE ROAD AHEAD	2	48" x 48"	16.0	32.0
W20-7	FLAGGER (symbol)	2	48" x 48"	16.0	32.0
W21-5	SHOULDER WORK	2	48" x 48"	16.0	32.0
G20-2	END ROAD WORK	2	36" x 18"	4.5	9.0
		CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT			
		266.0			


The signs illustrated are not required if the work space is behind a barrier, more than 2 feet behind the curb, or 15 feet or more from the edge of any roadway.

The signs illustrated will be used where there are distracting situations; such as: vehicles parked on shoulder, vehicles accessing the work site via the highway, and equipment traveling on or crossing the roadway to perform work operations.


The ROAD WORK AHEAD sign may be replaced with other appropriate signs, such as the SHOULDER WORK sign. The SHOULDER WORK sign may be used for work adjacent to the shoulder.

* If the work space is on a divided highway, an advance warning sign should also be placed on the left side of the directional roadway.

For short term, short duration, or mobile operations, all signs and channelizing devices may be eliminated if a vehicle with an activated flashing or revolving yellow light is used.



Posted Speed Prior to Work (M.P.H.)	Spacing of Advance Warning Signs (Feet) (A)
0 - 30	200
35 - 40	350
45 - 50	500
55	750
60 - 80	1000



January 22, 2021


S
D
D
O
T

WORK BEYOND THE SHOULDER

PLATE NUMBER
634.01


Sheet 1 of 1

Published Date: 2027



Posted Speed Prior to Work (M.P.H.)	Spacing of Advance Warning Signs (Feet) (A)	Taper Length (Feet) (L)	Spacing of Channelizing Devices (Feet) (G)
0 - 30	200	180	25
35 - 40	350	320	25
45	500	600	25
50	500	600	50
55	750	660	50
60 - 65	1000	780	50

Channelizing Device



The channelizing devices will be drums or 42" cones if traffic control must remain overnight.

For short duration operations (1 hour or less) all channelizing devices may be eliminated if a vehicle with an activated flashing or revolving yellow light is used.

Worker signs (W21-1 or W21-1a) may be used instead of SHOULDER WORK signs.

A SHOULDER WORK sign should be placed on the left side of a divided or one-way roadway only if the left shoulder is affected.

The SHOULDER WORK sign on an intersecting roadway is not required if drivers emerging from that roadway will encounter another advance warning sign before they reach a work activity area.

WORK SPACE



January 22, 2021

S
D
D
O
T

WORK ON SHOULDERS

PLATE NUMBER
634.03

Sheet 1 of 1

Published Date: 2027

STATE OF SOUTH DAKOTA

PROJECT

PT 0183(28)2

Plotting Date: 05/29/2026

Revised 5/29/26

SML

SHEET

C4

TOTAL SHEETS

C6

Posted Speed Prior to Work (M.P.H.)	Spacing of Advance Warning Signs (Feet) (A)	Spacing of Channelizing Devices (Feet) (G)
0 - 30	200	25
35 - 40	350	25
45	500	25
50	500	50
55	750	50
60 - 65	1000	50

Flagger

Channelizing Device

For low-volume traffic situations with short work zones on straight roadways where the flagger is visible to road users approaching from both directions, a single flagger may be used.

The ROAD WORK AHEAD and the END ROAD WORK signs may be omitted for short duration operations (1 hour or less).

For tack and/or flush seal operations, when flaggers are not being used, the FRESH OIL sign (W21-2) will be displayed in advance of the liquid asphalt areas.

Flashing warning lights and/or flags may be used to call attention to the advance warning signs.

The channelizing devices will be drums or 42" cones.

Channelizing devices are not required along the centerline adjacent to work area when pilot cars are utilized for escorting traffic through the work area.

Channelizing devices and flaggers will be used at intersecting roads to control intersecting road traffic as required.

The buffer space should be extended so that the two-way traffic taper is placed before a horizontal or vertical curve to provide adequate sight distance for the flagger and queue of stopped vehicles.

The length of A may be adjusted to fit field conditions.

Warning sign sequence in opposite direction same as below.

January 22, 2021

PLATE NUMBER 634.23

Sheet 1 of 1

Published Date: 2027

SDOT

LANE CLOSURE WITH FLAGGER PROVIDED

Posted Speed Prior to Work (M.P.H.)	Spacing of Advance Warning Signs (Feet) (A)	Taper Length (Feet) (L)	Spacing of Channelizing Devices (Feet) (G)
0 - 30	200	180	25
35 - 40	350	320	25
45	500	600	25
50	500	600	50
55	750	660	50
60 - 65	1000	780	50

24" White Temporary Pavement Marking

4" Yellow Temporary Pavement Marking

Channelizing Device

** Need and safe speed to be determined at the site by the Engineer.

Type 3 Barricade

Diagram of lane closure using stop signs. It shows a two-lane road with a single-lane work zone. Signs include 'ROAD WORK AHEAD' (W20-1), 'ONE LANE ROAD AHEAD' (W20-4), 'STOP' (R1-1), and 'END ROAD WORK' (G20-2). Dimensions include 20' for the work zone, 100' (Max.) for the buffer space, and 'A' for the taper length. A 'One Lane Two-way Traffic Taper' is indicated.

January 22, 2021

PLATE NUMBER 634.25

Sheet 1 of 1

Published Date: 2027

SDOT

LANE CLOSURE USING STOP SIGNS


File - ...Section C09AC- TCStd Plts.dgn

Plot Scale - 1:200


Plotted From - tpr25299

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	PT 0183(28)2	C6	C6


Plotting Date: 05/29/2026 Revised 5/29/26 SML




RURAL DISTRICT



RURAL DISTRICT WITH
SUPPLEMENTAL PLATE



URBAN DISTRICT




RURAL DISTRICT
3 DAY MAXIMUM
(Not applicable to regulatory signs)


* If the bottom of supplemental plate is mounted lower than 7 feet above a pedestrian walkway, the supplemental plate should not project more than 4" into the pedestrian facility.

January 22, 2021

Published Date: 2027	S D D O T	CRASHWORTHY SIGN SUPPORTS (Typical Construction Signing)	PLATE NUMBER 634.85
			Sheet 1 of 1



PLAN VIEW
(Examples of stub height clearance checks)



ELEVATION VIEW

GENERAL NOTES:

The top of anchor posts and slip bases WILL NOT extend above a 60" chord line within a 120" diameter circle around the post with ends 4" above the ground.

At locations where there is curb and gutter adjacent to the breakaway sign support, the stub height will be a maximum of 4" above the ground line at the localized area adjacent to the breakaway support stub.

The 4" stub height clearance is not necessary for U-channel lap splices where the support is designed to yield (bend) at the base.

January 22, 2021

Published Date: 2027	S D D O T	BREAKAWAY SUPPORT STUB CLEARANCE	PLATE NUMBER 634.99
			Sheet 1 of 1

File - ...Section C09AC- TCStd Plts.dgn