

	STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	SOUTH DAKOTA	PH 0020(242)	1	12
_				

Plotting Date: 04/25/2024

INDEX OF SHEETS

Sheet 1 Sheet 2-3 Sheet 4 Sheets 5-6 Sheets 7 Sheets 8-9 Sheets 10-12

General Layout W/ Index
Estimate of Quantities & Plan Notes
Table of Quantities, Centerline Rumble Stripes
Centerline Rumble Stripe (Special Detail)
Pavement Marking Layout
Fixed Location Signing Layouts
Standard Plates

BROOKINGS & KINGSBURY US81 MRM 107.73+0.00 TO

MRM 107.1310.00 TO 112.00+0.281 MRM 114.00+0.888 TO 115.91+0.00 MRM 116.14+0.00 TO 116.64+0.00

HUTCHINSON & MCCOOK US81 MRM 35.00+0.272 TO

49.00+0.290



ESTIMATE OF QUANTITIES

PH 0020(242) - PCN 09FL

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
380E6302	Reseal PCC Pavement Joint - Hot Pour	105,595	Ft
380E6548	Grind Sinusoidal Centerline Rumble Stripe in PCC Pavement	20.0	Mile
633E3000	Durable Pavement Marking, 4" White	211,190	Ft
633E3005	Durable Pavement Marking, 4" Yellow	44,724	Ft
634E0010	Flagging	200.0	Hour
634E0020	Pilot Car	100.0	Hour
634E0110	Traffic Control Signs	253.8	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0630	Temporary Pavement Marking	20.2	Mile

ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: <https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf >

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT C: WATER SOURCE

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species (AIS) positive waters within South Dakota without prior approval from the SDDOT Environmental Office. To prevent and control the introduction and spread of invasive species into the project vicinity, all equipment will be power washed with hot water (≥140 °F) and completely dried for a minimum of 7 days prior to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the possession and transport of AIS; therefore, all attached dirt, mud, debris and vegetation must be removed and all compartments and tanks capable of holding standing water must be drained. This includes, but is not limited to, all equipment, pumps, lines, hoses and holding tanks.

The Contractor will not withdraw water directly from streams of the James, Big Sioux, and Vermillion watersheds without prior approval from the SDDOT Environmental Office.

COMMITMENT C: WATER SOURCE (CONTINUED)

Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Agriculture and Natural Resources (DANR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of water sources impacted by Aquatic Invasive Species in South Dakota can be accessed at:

< https://sdleastwanted.sd.gov/maps/default.aspx>

< South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species: https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04 >

COMMITMENT B2: WHOOPING CRANE

The Whooping Crane is a spring and fall migratory bird in South Dakota that is about 5 feet tall and typically stops on wetlands, rivers, and agricultural lands along their migration route. An adult Whooping Crane is white with a red crown and a long, dark, pointed bill. Immature Whooping Cranes are cinnamon brown. While in flight, their long necks are kept straight and their long dark legs trail behind. Adult Whooping Cranes' black wing tips are visible during flight.

Action Taken/Required:

Harassment or other measures to cause the Whooping Crane to leave the site is a violation of the Endangered Species Act. If a Whooping Crane is sighted roosting in the vicinity of the project, borrow pits, or staging areas associated with the project, cease construction activities in the affected area until the Whooping Crane departs and immediately contact the Project Engineer. The Project Engineer will contact the Environmental Office so that the sighting can be reported to USFWS.

COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

COMMITMENT H: WASTE DISPOSAL SITE (CONTINUED)

1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, "No Dumping Allowed".

2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

6-1.13. and ARSD 74:27:10:06. 1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historic Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another gualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow 30 **Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

STATE OF	PROJECT	SHEET	TOTAL	
SOUTH DAKOTA	PH 0020(242)	2	12	

REV. 5-30-2024, JP

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58. SDCL 34A-

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law. SDCL 34A-6-

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES (CONTINUED)

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 100 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

SEQUENCE OF OPERATIONS

Contractor requests to deviate from the sequence of operations will be submitted in writing to the Engineer for review. Approval of an alternate sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work. An alternate sequence will be submitted for review a minimum of one week prior to potential implementation.

SCOPE OF WORK

The project consists of centerline rumble strips.

Centerline rumble strip locations will also have Epoxy Pavement Marking Paint, Yellow applied.

SCOPE OF WORK

- 1. Install traffic control for 3-mile closure.
- 2. Grind sinusoidal centerline rumble stripes.
- 3. Repeat 3-mile process until project completion.
- 4. Place temporary pavement markings before the end of the day.
- 5. Sawcut and seal centerline longitudinal joint.
- 6. Install permanent pavement marking paint.

CENTERLINE RUMBLE STRIPS IN PCC

INSTALLATION

Rumble Strips will be constructed according to Standard Plate 380.56.

Rumble strips will be completed prior to the application of the permanent pavement marking.

Sinusoidal centerline rumble stripes will be installed in rural areas with posted speeds greater than 60 mph. The Engineer will provide the exact start and stop locations.

ROADWAY CLEANING

The Contractor will be required to remove loose material from the driving surface and asphalt shoulders of the roadway. Loose material may be broomed to the edge of the shoulders. It will be the Contractor's responsibility to ensure the loose material does not enter any vegetated areas or waterways.

The cost for this work will be incidental to the contract unit price per mile for "Grind Sinusoidal Centerline Rumble Stripe in PCC Pavement".

RESEAL PCC PAVEMENT CENTERLINE LONGITUDINAL JOINT

Existing longitudinal joints will be cleaned and resealed with Hot Poured Elastic Joint Sealer on all sections of highway except the asphalt overlay on US81 south of the junction of US81 and US14.

Joints will not be sealed unless they are thoroughly clean and dry. Cleaning will be accomplished by sand blasting and other tools as necessary. Sand blasting of both sides the vessel will be accomplished simultaneously with a mechanical device approved by the Engineer. Just prior to sealing, each joint will be blown out using a jet compressed air to remove all traces of dust.

Final joint width is to be kept as narrow as possible and may only be widened to provide a clean surface. Each joint will not be widened more than 1/8 inch if sawing is utilized to prepare the joint for sealant. If sawing is used this may require two passes with the saw, one pass for each side of the joint.

In certain areas to be sealed with a Hot Pour Elastic Joint Sealer the joint may be wider than the original construction. Any additional cost to perform this work will be at no additional cost to the State. The Contractor will be responsible to verify joint widths prior to establishing the contract unit price.

It is not essential that all of the sealant be removed. Remaining sealant adhering to the sides may remain in place if the Engineer determines that it is not detrimental to the joint.

Cost for cleaning and resealing longitudinal joints with Hot Pour Elastic Joint Sealer will be included in the contract unit price per foot for Reseal PCC Pavement Joint – Hot Pour.

Joint sealing will conform to Section 380.3 P.

MARKINGS WITHIN SINUSOIDAL CENTERLINE RUMBLE STRIPES

The sinusoidal centerline rumble stripes are recessed below the pavement surface, so pavement marking grooving will not be required at these locations.

Sinusoidal rumble stripes will receive an asphalt surface treatment to seal the centerline joint and minimize the depth of water held on centerline.

Retroreflectivity readings will not be taken for pavement markings within the sinusoidal rumble stripe. Restriping of pavement markings to meet the specified application rate requirements and to provide a quality retroreflective line will be at the expense of the Contractor with no additional cost to the Department. Sections to be restriped will be determined by the Engineer.

PAVEMENT MARKING PAINT

The resealing of the longitudinal centerline joint will be done prior to the placement of the permanent pavement markings.

Application of the centerline permanent pavement markings will be completed withing 14 calendar days of the placement of the center line rumble stripes.

COORDINATION BETWEEN CONTRACTORS

A separate contract for Project NH 0081(112)95 – PCN 06P9 will be to another Contractor Mill, Full Depth Reclamation, AC Surfacing, Pipe Work, Modify Intersection on US81 adjacent to this project (PCN pcn# for this set of plans). The Mill, Full Depth Reclamation, AC Surfacing, Pipe Work, Modify Intersection for PCN 06P9 will begin at MRM 95.21+0.208 and end at MRM 107.00+0.719.

The Contractor will schedule work so as not to interfere with or hinder the progress of the work performed by the other Contractor on PCN 06P9. Conflicting traffic control devices may need to be temporarily adjusted or removed as directed by the Engineer and at no additional cost to the contract.

FLAGGING

Operations will be conducted so that the traveling public will not have to wait longer than 15 minutes at the flagger station.

Additional flagger warning signs and flagger hours have been included in the Estimate of Quantities for use on intersecting roads. These flaggers will be used as directed by the Engineer and will be used primarily during daytime hours. Also included in the Estimate of Quantities are WAIT FOLLOW PILOT CAR signs for use on low volume intersecting roads as determined by the Engineer. WAIT FOLLOW PILOT CAR signs will not block the view of the stop sign.



It is required that the flaggers and pilot car operators be able to communicate with one another. If an emergency vehicle needs to pass through the project, the Contractor will be required to expedite traffic movement. All costs associated with this will be incidental to the contract unit price per hour for "Flagging".

TEMPORARY PAVEMENT MARKING

Temporary flexible vertical markers (tabs) will be installed on one side of the centerline rumble for the temporary pavement marking. No passing zones will be marked in accordance with Specifications. DO NOT PASS (R4-1) and PASS WITH CARE (R4-2) signs will also be used in addition to the temporary flexible vertical markers (tabs) placed per Specifications to mark no passing zones.

The total length of no passing zone on this project is estimated to be 4.5 miles.

It is estimated that 2 required.

In the absence of a signed lane closure or pilot car operation, FLAGGER (W20-7) symbol signs and flaggers, or a shadow vehicle with rotating yellow lights or strobe lights will be positioned on the shoulder in advance of workers for both directions of traffic during the installation and removal of the temporary flexible vertical markers (tabs). The traffic control device used will be moved intermittently to provide proper warning of the work operation. A ROAD WORK AHEAD (W20-1) sign, a WORKER (W21-1) symbol sign or a BE PREPARED TO STOP (W3-4) sign will be mounted on the rear of the shadow vehicle. The method of traffic control used by the Contractor for this work must be approved by the Engineer.

Covers on the tabs will be sufficiently secured to prevent traffic from dislodging the cover and when removed, the covers will be properly disposed of. The Contractor will remove and properly dispose of the tabs after permanent pavement marking is applied. Method of removal will be nondestructive to the road surface and will be accomplished within one week of completion of the permanent pavement marking.

STATE OF	PROJECT	SHEET	TOTAL
SOUTH DAKOTA	PH 0020(242)	3	12

REV. 5-20-2024, JP

It is estimated that 22 DO NOT PASS and 19 PASS WITH CARE signs will be

UNDIVIDED ROADWAY





PAVEMENT MARKING

Typical pavement marking as shown on this sheet will be applied throughout the entire length of undivided roadway.

Traffic Control will be incidental to the cost of application. The striper and advance or trailing warning vehicle will be equipped with flashing amber lights and advance warning arrow board.

Application rates will be as follows:

Four Lane Roadway	Two Lane Roadway
(Rates for one line)	(Rates for one line)
Solid Yellow Centerline	Dashed Yellow Centerline
Rate = 27.8 Gals./Pass-Mile	Rate = 7.6 Gals./Pass-Mile
Dashed White Laneline	Solid Yellow Centerline
Rate = 7.6 Gals./Pass-Mile	Rate = 27.8 Gals./Pass-Mile
Solid White Edgeline	Solid White Edgeline
(Not applicable in curb and gutter)	Rate = 27.8 Gals./Pass-Mile
Rate = 27.8 Gals./Pass-Mile	

4" Yellow Skip Centerline (when not adjacent to a 4" Yellow No Passing Zone) will be placed consistently to the south or east side of centerline.

ESTIMATED QUANTITIES (BASED ON ONE APPLICATION)								
DURABLE 4" 8" 12" 24" SOLID AREA								
WHITE	211190'	-	-	-	-			
YELLOW	44724'	-	-	-	-			

Included in the above quantities are:							
Additional White (1 A	pplica	ation)	Additional Yellow (1 Application)				
Description		Gallons	Description	Gallons			
4" Lines	-	-	Transitions - ·	· -			
8" Lines	-	-	4" Skip Lines	· -			
12" Gore Lines	-	-	8" Lines ·	· -			
Crosswalks -	-	-	12" Lines	· -			
24" Stop Lines	-	-	24" Hatches	· -			
24" Hatches	-	-	Solid Areas				
Solid Areas			Additional Yellow: -				
Arrows							
Left Arrows	-	-	Additional Quantities				
Right Arrows	-	-	Rates of Coverage:	<u>SqFt/Gal</u>			
Straight Arrows	-	-	4", 8" & 12" Lines -	50			
Combo Arrows	-	-	24" Lines & Hatches -	30			
Lane Drop Arrows	-	-	Arrows, Messages				
<u>Messages</u>			and Solid Areas -	20			
STOP	-	-					
STOP AHEAD	-	-	All pavement marking dime	nsions			
R X R w/ Stop Lines	-	-	- are based on 12' driving lanes.				
SCHOOL X-ING	-	-					
Additional V	Vhite [.]	-					

ESTIMATED QUANTITIES (BASED ON ONE APPLICATION)								
DURABLE	Project No. 1	Project No. 2	Project No. 2 Project No. 3					
	GALLONS	GALLONS	GALLONS	GALLONS				
WHITE	1113	-	-	1113				
YELLOW	248	-	-	248				

						STATE OF	-	PROJECT		SHEET	TOTAL SHEETS
						DAKOTA		PH 0020(2	242)	4	12
	REV. 5-30-2024, JP										24, JP
ESTIMATE OF QUANTITIES (For Information Only)											
					Bid	Item	380	DE6548	380E6302	633E1	005
Route No.	County	Route	Begin	End	Length		Grind Sinusoidal Centerline Rumble Stripe in PCC Pavement		Rescal PCC Pavement Joint - Hot Pour Ft. (Net)	Dural Pavem Mark Pain Yello Ft.	ble ent ing t, ww
1	HUTCHINSON & MCCOOK	US81	715 ft. north of 278th St.	SD42	74,260'	14.0	74,260'	14.1	74,260'	22,90	9'
2	BROOKINGS & KINGSBURY	US81	220th St.	8015 ft. north of 217th St.	23,788'	4.5	23,788'	4.5	23,788'	12,43	57'
3	& KINGSBURY	US81	560 ft. north of 213th St.	1,140 ft. north of 212th St.	8,777'	1.7	7,547'	1.4	7,547'	9,37	8'
				Total		20.2		20.0	105,595'	44,72	4'

Locations that Centerline Rumble Stripes will not be installed (For Information Only)								
Route No.	Hwy.	Beginning Location	End Location	County	Location Comments	Length		
4	US81	1130 ft. North of 212th St.	651 ft. South of 211th St.	Kingsbury and Brookings	An existing asphalt patch is at this location has centerline rumble stripes.	1230'		

ITEMIZED LIST FOR TRAFFIC CONTROL SIGNS

		CONVENTIONAL ROAD			
SIGN CODE	SIGN DESCRIPTION	NUM BER	SIGN SIZE	SQFT PER SIGN	SQFT
W3-4	BE PREPARED TO STOP	1	48" x 48"	16.0	16.0
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0
W20-4	ONE LANE ROAD AHEAD	2	48" x 48"	16.0	32.0
W20-7	FLAGGER (symbol)	4	48" x 48"	16.0	64.0
W21-1	WORKERS (symbol)	1	48" x 48"	16.0	16.0
G20-1	'ROAD WORK NEXT 2 MILES	1	36" x 18"	4.5	4.5
G20-1	'ROAD WORK NEXT 3 MILES	3	36" x 18"	4.5	13.5
G20-1	'ROAD WORK NEXT 5 MILES	2	36" x 18"	4.5	9.0
G20-1	'ROAD WORK NEXT 6 MILES	1	36" x 18"	4.5	4.5
SPECIAL	WAIT FOLLOW PILOT CAR	1	30" x 18"	3.8	3.8
G20-1	ROAD WORK NEXT 7 MILES	1	36" x 18"	4.5	4.5
G20-1	ROAD WORK NEXT 8 MILES	2	36" x 18"	4.5	9.0
G20-1	ROAD WORK NEXT 9 MILES	1	36" x 18"	4.5	4.5
G20-1	ROAD WORK NEXT 11 MILES	1	36" x 18"	4.5	4.5
G20-2	END ROAD WORK	6	36" x 18"	4.5	27.0
G20-1	ROAD WORK NEXT 13 MILES	1	36" x 18"	4.5	4.5
G20-1	ROAD WORK NEXT 14 MILES	1	36" x 18"	4.5	4.5
		CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT 253.			253.8

CENTERLINE RUMBLE STRIPE (SPECIAL DETAIL)



(SPECIAL DETAIL)



Pavement Marking on PCC Centerline Rumble Stripes





All Fixed Location signs will remain inplace until permanent pavement marking is complete.

Signs will be placed 200' to 300' from intersections. Exact location to be determined by the Engineer.

Construction signs cannot obscure existing signs and must be installed a minimum of 200' from existing sign.

Construction signs will not be installed on the same post as an existing highway sign or light pole.

- 200' FROM INTERSECTIONS

STATE OF SOUTH DAKOTA PROJECT PH 0020(242) Plotting Date: 04/25/2024

ROAD WORK NEXT 8 MILES

4

TOTAL SHEETS

12

SHEET

8







	Arrow Board
 Vehicle hazard warning signals will not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights. When an arrow board is used, it will be used in the caution mode. Marching Diamonds are acceptable. Arrow boards will, as a minimum, be Type B, with a size of 60" x 30". All costs associated with the traffic control for mobile operation including signs, arrow boards and equipment will be incidental to the contract lump sum price for "Traffic Control, Miscellaneous". 	Truck Mounted Attenuator (optional) WET PAINT * PASS WITH CARE Shadow Vehicle
 Messages on signs will vary depending on the operation being conducted. Vehicle-mounted signs will be mounted in a manner such that they are not obscured by equipment or supplies. Sign legends on vehicle-mounted signs will be covered or turned from view when work is not in progress. Shadow and Work vehicles will display high-intensity rotating, flashing, oscillating, or strobe lights, flags, signs, or arrow boards. 	Work Vehicle

fit field c	onulions.				I 1
The lend	onditions	usted to			*
required The buff so that the placed be curve to distance of stoppe	er space should be he two-way traffic t efore a horizontal provide adequate for the flagger and ed vehicles.	e extended aper is or vertical sight I queue			
Channel be used control in	izing devices and f at intersecting road ntersecting road tra	laggers will ds to affic as		J	
	END END MORK]			
Channel along the area whe escorting area.	izing devices are n e centerline adjace en pilot cars are ut g traffic through the 	not required ant to work ilized for e work			
The cha or 42" co	nnelizing devices v ones.	vill be drum	S		
Flashing may be advance	warning lights and used to call attention warning signs.	d/or flags on to the			
For tack when fla FRESH in advar	and/or flush seal c ggers are not bein OIL sign (W21-2) v ice of the liquid asp	operations, g used, the vill be displ ohalt areas.	ayed		
The RO WORK s duration	AD WORK AHEAD signs may be omitto operations (1 hour	and the El ed for short or less).	ND RO		// ,
For low- with sho roadway to road u direction	volume traffic situa rt work zones on si s where the flagge users approaching s, a single flagger	tions traight r is visible from both may be use	ed.		
-	Channelizing De	vice			
60 - 65	1000 Flagger	50			
50 55	500 750	50 50	_		
35 - 40 45	500	25 25			
0 - 30	200	25			
(M.P.H.)	(Feet) (A)	(Feel) (G)			as De
VVORK					an ha
Prior to Work	Signs	Devices	ng		in op



