

STATE OF SOUTH DAKOTABIDDING PURPOSES ONLY DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED

PROJECT P TAPU(38) CITY OF SIOUX FALLS - 26TH STREET SHARED USE PATH MINNEHAHA COUNTY

GRADING AND SURFACING PCN 09FV

ATE OF OUTH AKOTA	PROJECT	SHEET	TOTAL
	P TAPU(38)	1	70

FILE: A.1-TITLE PLOTTING DATE: 7/10/2024 REV DATE: INITIAL:

INDEX OF SECTIONS

Sheet 1: Title Sheet and Overview Map

Sheet 2: Estimate of Quantities

Sheets 3-5: Environmental Commitments

Sheets 6-20: General Notes and Tables

Sheet 21: Control Data

Sheet 22: Horizontal Alignment Table

Sheet 23: Typical Sections

Sheet 24: Legend

Sheets 25-33: Plan and Profile Sheets
Sheets 34-35: Pavement Removals
Sheets 36-38: Detailed Ramp Layouts

Sheets 39-40: Traffic Control

Sheets 41-42: Erosion and Sediment Control

Sheets 43-44: Pipe Sections
Sheets 45-60: Cross Sections
Sheets 61-70: Standard Plates




City of Sioux Falls PUBLIC WORKS - DIVISION OF ENGINEERING 231 N. DAKOTA AVENUE SIOUX FALLS, SD 57117 (605) 367-8601

Approved

City Engineer

Major Receiving Body of Water: Big Sioux River Area Disturbed: 2.26 ACRES Total Project Area: 2.97 ACRES Approx. Begin 43.5293, -96.6614



Gross Length 5200.00 Feet 0.98 Miles
Length of Exceptions 0.00 Feet 0.00 Miles
Net Length 5200.00 Feet 0.98 Miles

SOctober 16, 2024

FOR BIDDING PURPOSES ONLY SOUTH DAKOTA

PROJECT SHEET P TAPU(38) 2

Plotting Date: 8/12/2024

Estimate of Quantities

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
100E0020	Clear and Grub Tree	6	Each
100E0100	Clearing	Lump Sum	LS
110E0300	Remove Concrete Curb and/or Gutter	35	Ft
110E1010	Remove Asphalt Concrete Pavement	15.5	SqYd
110E1100	Remove Concrete Pavement	9.1	SqYd
110E1140	Remove Concrete Sidewalk	308.1	SqYd
110E1600	Remove Riprap	10.0	SqYd
110E1700	Remove Silt Fence	623	Ft
110E7510	Remove Pipe End Section for Reset	4	Each
120E0010	Unclassified Excavation	3,046	CuYd
120E0600	Contractor Furnished Borrow	150	CuYd
120E6200	Water for Granular Material	23.5	MGal
120E6300	Water for Vegetation	574.5	MGal
230E0010	Placing Topsoil	1,510	CuYd
250E0020	Incidental Work, Grading	Lump Sum	LS
260E2010	Gravel Cushion	1,949.1	Ton
260E6010	Granular Material	79.2	Ton
320E1200	Asphalt Concrete Composite	4.5	Ton
380E4010	6" PCC Fillet Section	9.1	SqYd
421E0100	Pipe Culvert Undercut	40	CuYd
450E3062	54" RCP Arch Class 2, Furnish	64	Ft
450E3070	54" RCP Arch, Install	64	Ft
450E9001	Reset Pipe End Section	4	Each
451E7510	Verify Utilities	1	Each
464E0100	Controlled Density Fill	12.9	CuYd
632E4000	Type 3 Double Sided Barricade	2.0	Ft
634E0010	Flagging	20.0	Hour
634E0110	Traffic Control Signs	216.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0420	Type C Advance Warning Arrow Board	1	Each
634E1002	Detour and Restriction Signing	100.0	SqFt
634E2000	Longitudinal Pedestrian Barricade	48	Ft
650E0059	Modified Type B66 Concrete Curb and Gutter	40	Ft
651E0040	4" Concrete Sidewalk	1,269	SqFt
651E0060	6" Concrete Sidewalk	34,124	SqFt
651E0560	6" Colored Concrete Sidewalk	1,417	SqFt
651E7000	Type 1 Detectable Warnings	72	SqFt
700E0210	Class B Riprap	143.7	Ton
730E0206	Type D Permanent Seed Mixture	380	Lb
730E0212	Type G Permanent Seed Mixture	18	Lb
731E0100	Fertilizing	2,676	Lb
732E0200	Fiber Mulching	2.9	Ton

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
733E0100	Sodding	3,555	SqYd
734E0602	Low Flow Silt Fence	2,591	Ft
734E0610	Mucking Silt Fence	173	CuYd
734E0620	Repair Silt Fence	623	Ft
734E0847	Sediment Control at Type S Reinforced Concrete Drop Inlet	96	Ft
734E5010	Sweeping	20	Hour
831E0110	Type B Drainage Fabric	103	SqYd
900E1310	Concrete Washout Facility	2	Each
900E1320	Construction Entrance	2	Each

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.



ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Action Taken/Required:

Environmental Office.

Action Taken/Required:

water extraction activities.

not impacted.

Section 7.21 D of the Specifications.

COMMITMENT C: WATER SOURCE

equipment, pumps, lines, hoses and holding tanks.

Invasive Species in South Dakota can be accessed at:

< https://sdleastwanted.sd.gov/maps/default.aspx >

COMMITMENT D: WATER QUALITY STANDARDS

COMMITMENT D1: SURFACE WATER QUALITY

The City of Sioux Falls has previously acquired 1.8 Functional Units required

for this project per the USACE Section 404 Permit to mitigate permanent

Temporary impacts identified in the Table of Impacted Wetlands will not be

mitigated as original contours and elevations will be re-established as

designated the plans. Prior to initiating temporary work in wetlands, the

Contractor will submit a plan to the Project Engineer in accordance with

The Contractor will not withdraw water with equipment previously used outside

the State of South Dakota or previously used in aquatic invasive species (AIS)

positive waters within South Dakota without prior approval from the SDDOT

Environmental Office. To prevent and control the introduction and spread of

invasive species into the project vicinity, all equipment will be power washed

with hot water (≥140 °F) and completely dried for a minimum of 7 days prior

to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the

possession and transport of AIS; therefore, all attached dirt, mud, debris and

vegetation must be removed and all compartments and tanks capable of

holding standing water must be drained. This includes, but is not limited to, all

The Contractor will not withdraw water directly from streams of the James, Big

Sioux, and Vermillion watersheds without prior approval from the SDDOT

The Contractor will obtain the necessary permits from the regulatory agencies

such as the South Dakota Department of Agriculture and Natural Resources

(DANR) and the United States Army Corps of Engineers (USACE) prior to

Additional information and mapping of water sources impacted by Aquatic

This project may be in the vicinity of multiple streams and wetlands. These waters are considered waters of the state and are protected under Administrative Rules of South Dakota (ARSD) Chapter 74:51. Special construction measures may have to be taken to ensure that this water body is

< South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species:

https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04 >

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf">https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT A: AQUATIC RESOURCES

COMMITMENT A1: WETLANDS

All efforts to avoid and minimize wetland impacts from the project have resulted in approximately 0.171 acre of wetlands (includes temporary and permanent) becoming impacted. Refer to the plans for location and boundaries of the impacted wetlands.

Table of Impacted Wetlands

Wetland No.	Station	Perm. Impact Left (Acres)	Perm. Impact Right (Acres)	Temp. Impact Left (Acres)	Temp. Impact Right (Acres)	Total Impact (Acres)
1	17+00 to 20+00	0.104	0.00	0.00	0.00	0.104
2	45+50 to 47+50	0.023	0.00	0.00	0.00	0.023
2	51+00 to 52+50	0.044	0.00	0.00	0.00	0.044

FOR BIDDING PURPOSES ONLY BOAKOTA

SHEET STATE OF P TAPU(38) 3

70

Plotting Date: 7/10/2024

Action Taken/Required:

The Contractor is advised that the South Dakota Surface Water Quality Standards, administered by the South Dakota Department of Agriculture and Natural Resources (DANR), apply to this project. Special construction measures will be taken to ensure the above standard(s) of the surface waters

COMMITMENT D2: SURFACE WATER DISCHARGE

The DANR General Permit for Temporary Discharge is required for temporary dewatering and discharges to waters of the state. The effluent limit for total suspended solids will be 90 mg/L 30-day average. The effluent limit applies to

The permittee has the option of completing effluent testing or implementing a

https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR AddTe

Effluent monitoring, as a result of dewatering activities, will be summarized for each month and recorded on a separate Discharge Monitoring Report (DMR) and submitted to DANR monthly. Additional information can be found at:

are maintained and protected.

discharges to all waters of the state except discharges to waters classified as cold water permanent fish life propagation waters according to the ARSD 74:51:01:45. For discharges to waters of the state classified as cold water permanent fish life propagation waters, the effluent limit for total suspended solids will be 53 mg/L daily maximum.

pollution prevention plan for compliance with this permit. If the permittee develops a pollution prevention plan instead of total suspended solids sampling, the plan must be developed and implemented prior to discontinuing total suspended solids sampling. Refer to Section 4.0 of the permit. If any pollutants are suspected of being discharged, a sample must be taken for those parameters listed in Section 3.4 of the permit.

Refer to Commitment D1: Surface Water Quality for stream classification.

Action Taken/Required:

If construction dewatering is required and this project is currently covered under a General Permit for Stormwater Discharges Associated with Construction Activities, the contractor will need to submit the dewatering information to the SDDANR using the following form:

mpInfoFillable.pdf >

The Contractor will provide a copy of the approved permit or the submitted dewatering information to the Project Engineer prior to proceeding with any dewatering activities. The approved permit or submitted dewatering information must be kept on-site and as part of the project records.

https://danr.sd.gov/Office@ffffage/SurfaceWaterQuality/swdpermitting/Ereporting.aspx >

7/1/1/1/8/21/2024 HILLIAM

COMMITMENT E: STORM WATER

Construction activities constitute 1 acre or more of earth disturbance and/or work in a waterway.

Action Taken/Required:

The DANR General Permit for Stormwater Discharges Associated with Construction Activities is required for construction activity disturbing one or more acres of earth and work in a waterway. The SDDOT is the owner of this permit and will submit the NOI to DANR 15 days prior to project start in order to obtain coverage under the General Permit. Work can begin once the DANR letter of approval is received.

The Contractor must adhere to the "Special Provision Regarding Storm Water Discharges to Waters of the State."

The Contractor will complete the DANR Contractor Certification Form prior to the pre-construction meeting. The form certifies under penalty of law that the Contractor understands and will comply with the terms and conditions of the permit for this project. Work may not begin on this project until this form is signed and submitted to DANR.

The form can be found at:

https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR_CGPA ppendixCCA2018Fillable.pdf >

The Contractor is advised that permit coverage may also be required for offsite activities, such as borrow and staging areas, which are the responsibility of the Contractor.

Storm Water Pollution Prevention Plan

The Storm Water Pollution Prevention Plan (SWPPP) will be developed prior to the submittal of the NOI and will be implemented for all construction activities for compliance with the permit. The SWPPP must be kept on-site and updated as site conditions change. Erosion control measures and best management practices will be implemented in accordance with the SWPPP.

The DOT 298 Form will be used for site inspections and to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents and retained for a minimum of three years.

The inspection will include disturbed areas of the construction site that have not been finally stabilized, areas used for storage materials, structural control measures, and locations where vehicles enter or exit the site. These areas will be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the SWPPP will be observed to ensure that they are operating correctly, and sediment is not tracked off the site.

Information on storm water permits and SWPPPs are available on the following websites:

SDDOT: < https://dot.sd.gov/doing-business/environmental/stormwater >

DANR:<https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/default.aspx>

EPA: < https://www.epa.gov/npdes >

FOR BIDDING PURPOSES ONLY BOAKOTA

STATE OF SOUTH DAKOTA

PROJECT
P TAPU(38)

SHEET TOTAL SHEETS

4 70

Plotting Date: 7/10/2024

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

- 1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, "No Dumping Allowed".
- 2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

Minimul Control of the Control of th

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historic Preservation Office (SHPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 150 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

COMMITMENT N: SECTION 404 PERMIT

The SDDOT has obtained a Section 404 Permit from the USACE for the permanent actions associated with this project.

Action Taken/Required:

The Contractor will comply with all requirements contained in the Section 404 Permit.

The Contractor will also be responsible for obtaining a Section 404 Permit for any dredge, excavation, or fill activities associated with material sources, storage areas, waste sites, and Contractor work sites outside the plan work limits that affect wetlands, floodplains, or waters of the United States.

		SIAI
FOR BIDDING PURPOSES ONL	\/	SOI
FOR RIDDING PURPOSES ONL	ıΥ	DAK

STATE OF SOUTH DAKOTA

PROJECT SHEET P TAPU(38) 5

70

Plotting Date: 7/10/2024



GRADING OPERATIONS

Water for Embankment is estimated at the rate of 10 gallons of water per cubic yard of Embankment minus Waste. The estimated quantity of Water for Embankment is 12 MGal. No separate payment will be made for the Water for Embankment and all costs associated will be incidental to the contract unit price per cubic yard of "Unclassified Excavation".

NOISE PERMIT

A noise permit will not be approved on this project as it has deemed night work to be a disturbance to the surrounding neighborhood. No work between 10:30 PM and 6:00 AM will be allowed.

COORDINATION MEETINGS

The Contractor will conduct coordination meetings with the subcontractors, utilities, the Engineer, and the public. These meetings will be held weekly at a location on or near the project. The Contractor will determine the time and location and as approved by the Engineer.

Landowners, business owners, and the general public will be invited to the first half of the meeting. The Contractor will give a brief summary of the project schedule and will answer any questions. The public will then be dismissed and the Contractor can discuss construction coordination and other issues as needed.

All costs to conduct the coordination meetings will be incidental to the project.

PORTABLE TOILET FACILITES

The Contractor will be responsible for providing portable toilet facilities for the project at no cost to the DOT.

FOR BIDDING PURPOSES ONLY BOAKOTA

The Contractor will be aware that the existing utilities shown in the plans were surveyed prior to the design of this project and might have been relocated or replaced by a new utility facility prior to construction of this project, might be relocated or replaced by a new utility facility during the construction of this project, or might not require adjustment and may remain in its current location. The Contractor will contact each utility owner and confirm the status of all existing and new utility facilities. The utility contact information is provided below.

UTILITIES

The Contractor will be responsible for notifying South Dakota One Call 1-800-781-7474 to have utilities field located.

The following utility companies are known to have facilities on the project:

oux Falls Water Reclamation - Sanitary
nad Hochstein
500 N Sycamore Ave
oux Falls, SD 57117
05) 941-1163
unicipal Light & Power
erry Jongeling
000 North Minnesota
oux Falls, SD 57104
05) 373-6979
idAmerican Energy Company, Inc.
200 S Blauvelt Avenue
oux Falls, SD 57105
tn: Ryan Hendriks
ell: (605) 373-6061
ON Communications
ddress: 2900 W 10 th Street
oux Falls, SD 57104
tn: Matt Burton
ffice: (605) 978-1050
CEL Energy
00 West Russell St
oux Falls, SD 57104
tn: Chad Peterson
ffice: (612) 330-7825
, ,

VERIFY UTILITY

This work consists of excavating material to verify the depth of an existing utility line, (Private or Public), to avoid possible conflicts, when directed by the Engineer. Payment for this item will be at the contract unit price per each.

STATE OF

Plotting Date: 9/4/2024

SHEET

6

Rev 09/04/2024 KAO

70

P TAPU(38)

The Contractor will verify the depths of the following utilities:

Sta 39+69, 22' R – Sioux Valley Energy

After verification, the Contractor will coordinate information with the Engineer and Sioux Valley Energy. Primary cable will require 30" of ground cover and any adjustments to the cable will be coordinated with Sioux Valley Energy by the Contractor.



PRIVATE SPRINKLER SYSTEM

Private sprinkler systems are located within the construction limits. The City will notify all property owners about the expected construction and the procedures for preparing their systems for construction. When found, the Contractor will notify the Engineer and take reasonable measures to minimize any damage to the system. It will be the responsibility of the City to pay the property owner's sprinkler contractor directly for repairs. The Contractor will be responsible for any damaged due to the Contractor's negligence.

The Contractor will notify the Engineer when the sprinkler system can be restored and the City will coordinate with the property owner and sprinkler contractor. The system should be restored before seed or sod placement and the Contractor will make reasonable accommodations to allow for the homeowner's sprinkler contractor to make final repairs and adjustments.

PROTECTION OF EXISTING WATER MAIN, SANITARY SEWER, AND STORM SEWER SYSTEMS

For the protection of existing public underground utilities and the surrounding work area, consideration will be given to isolating portions of the existing water distribution system within the construction limits while maintaining fire protection. During underground utility installation such as, but not limited to, sanitary sewer, water main, storm sewer, sump pump drain, etc., in the proximity of existing water main and/or water services, the existing water main distribution will be isolated within the work area. Upon receiving notice from the Contractor 24 hours in advance of any work, City staff will operate designated water valves, where appropriate, to isolate the work area as much as reasonably possible. The Contractor will become aware of the location and status (open/closed) of any designated isolation valve(s). Sioux Falls Water Maintenance staff will be notified immediately in the event of a water service emergency or interruption. It will be permissible for the Contractor to operate the designated valve(s) in the event of a water main or water service failure within the construction area. The Contractor is required to have a valve operating key on site in the event of such a failure. Sioux Falls Water Maintenance (367-8810) will be notified immediately after the shutdown. City crews will operate the valves after repairs have been made and inspections have been completed.

Existing sanitary sewer lines and manholes within the construction limits will be protected at all times during construction. The upstream ends of existing sanitary sewer lines downstream from new sanitary sewer construction will be plugged at locations to be approved by the Engineer. Water, stone, dirt, gravel, asphalt, concrete or any other debris will not be allowed to enter the City's sanitary sewer system during flushing operations or at any other time. Construction taking place in the vicinity of any existing City sanitary sewer lines or manholes will not cause any inflow of surface water, ground water, water from damaged water lines, or debris to enter the City's sanitary sewer system. The Contractor will be responsible for any damages or costs incurred to the City's sanitary sewer system, Water Reclamation Division, and/or private property, and any actions imposed by SDDANR due to spills, overflows, inflows, lift station surcharges, City Water discharge, sanitary sewer discharges to surface waters, sanitary sewer backups into homes, etc.

Existing storm sewer inlets and pipes within the construction limits will be protected from the entrance of stone, dirt, gravel, asphalt, concrete or any other debris during construction. The SWPPP must be followed at all times.

REMOVAL OF EXISTING CONCRETE PAVEMENT

Existing asphalt concrete and/or existing asphalt concrete patch work that was placed above the existing concrete pavement is included in the quantity for "Remove Concrete Pavement". The Contractor will dispose of the concrete pavement and asphalt concrete at a site approved by the Engineer.

TABLE OF UNCLASSIFIED EXCAVATION

TABLE OF EARTHWORK		
West of Veterans Parkway (1+42 to 37+60)	(CuYd)	
Excavation	864	
Embankment (30% SF)	993	
Waste	-129	
SalvageTopsoil	897	
East of Veterans Parkway (39+23 to 53+84)	(CuYd)	
Excavation	672	
Embankment (30% SF)	156	
Waste	516	
SalvageTopsoil	613	
Totals	(CuYd)	
Excavation*	1536	
Embankment (30% SF)**	1149	
Waste**	387	
SalvageTopsoil*	1510	
*Included in Unclassified Excavation Quantity		
**Quantity for reference only		

PROCEDURES FOR DETERMINING UNCLASSIFIED EXCAVATION QUANTITY

Plans quantity will be the basis of payment for the Unclassified Excavation quantity and will be used for final payment and the plans quantity of Topsoil and salvaged surfacing items listed in the Table of Unclassified Excavation will not be adjusted according to field measurements.

CONTRACTOR FURNISHED BORROW EXCAVATION

The Contractor will provide a suitable site for Contractor furnished borrow excavation material. The Contractor is responsible for obtaining all required permits and clearances for the borrow site. The borrow material will be approved by the Engineer. The quantity for "Contractor Furnished Borrow Excavation" will be based on field measurements.

"Contractor Furnished Borrow" has been included in the plans due to the time and construction constraints required with the coordination of the separate City of Sioux Falls utility project (PS 240) within the project limits. Any use of "Contractor Furnished Borrow" will be approved of by the Engineer.

Restoration of the Contractor furnished borrow excavation site will be the responsibility of the Contractor.

FOR BIDDING PURPOSES ONL

	STATE OF	PROJECT	SHEET	TOTAL SHEETS
NL	Y SOUTH DAKOTA	P TAPU(38)	7	70

Plotting Date: 7/10/2024

INCIDENTAL WORK, GRADING

TABLE OF INCIDENTAL WORK, GRADING				
East of Veteran	s			
Station to	Station	Offset	Description	
33+11	33+15	R	Remove 10" PVC Pipe	
52+50	53+25	L	Ditch Grading	

DITCH GRADING

Ditch grading will be completed where shown in the table. Existing ditches will be regraded with the installation of the shared use path and the extension on the existing storm sewer culverts. Contractor will regrade the ditch so that flow is maintained in the same direction as it was prior to the construction of the project.

All costs associated with regrading the ditch will be incidental to the bid item "Incidental Work, Grading".



PIPE CULVERT UNDERCUT

Pipe culvert undercut may be required for this project. The Engineer will determine which pipe will be undercut in accordance with Section 421 of the Specifications.

If pipe culvert undercut is required, the table below contains the rate for one-foot depth of pipe culvert undercut per foot of pipe length. When calculating pipe culvert undercut, the length of pipe ends should be included in the overall pipe length.

The table includes undercut for 36 inch and larger pipe culverts. The depth of undercut is an estimate and the actual depth necessary will be determined during construction. Pipes listed may or may not require undercutting and pipes not listed may require undercutting. The Engineer will determine which pipe will be undercut in accordance with Section 421 of the Specifications.

TABLE OF PIPE CULVERT UNDERCUT AND GRANULAR MATERIAL				
Station	Undercut	Pipe Culvert	Granular	
Station	Depth	Undercut	Material	
East of Veterans	(Ft)	(CuYd)	(Ton)	
52+71.08 - 27.10' L to 52+90.55 - 13.20' L	1	10	19.8	
52+73.16 - 37.49' L to 52+92.73 - 23.59' L	1	10	19.8	
52+75.46 - 47.42' L to 52+94.85 - 33.30' L	1	10	19.8	
52+78.46 - 57.13' L to 52+97.53 - 42.48' L	1	10	19.8	
Т	otal Project	40	79.2	

Granular material may be required for backfilling the pipe culvert undercut areas where site conditions warrant. Granular material will conform to the gradation requirements in Section 421.2.A of the Specifications and will be paid for at the contract unit price per ton for "Granular Material".

The quantity will be adjusted or eliminated by construction change order, depending on field conditions.

The table below contains the rate for one-foot depth of pipe culvert undercut per foot of pipe length and should be used as an aid in determining the actual amount of undercut to be performed during construction. The table is derived from the drawing below and conforms to the Specifications. When calculating pipe culvert undercut, the length of pipe ends should be included in the overall pipe length.




FOR BIDDING PURPOSES ONLY

STATE OF	PROJECT	SHEET TOT	
Y SOUTH DAKOTA	P TAPU(38)	8	70

Plotting Date: 7/10/2024

Storm sewer and approach pipes do not require undercutting unless specified otherwise in these plans.

Pipe Diameter	Round Pipe Undercut Rate for 1' Depth	Arch Pipe Undercut Rate for 1' Depth
(In)	(CuYd/Ft)	(CuYd/Ft)
24	0.2407	0.2577
30	0.2623	0.2847
36	0.2840	0.3110
42	0.3056	0.3337
48	0.3272	0.3596
54	0.3488	0.3827
60	0.3704	0.4105
66	0.3920	
72	0.4136	0.4630
78	0.4352	
84	0.4568	0.5123
90	0.4784	



CONCRETE PIPE CONNECTIONS

Pipe connections to existing pipes, manholes, junction boxes, and drop inlets will be done by breaking a hole into the existing structure and inserting the pipe. A concrete collar will then be poured around the pipe in the area of the connection.

When it is not possible to use a normal pipe joint (male-female ends), connections to existing pipe will be made by placing a 2' wide by 6" thick M6 concrete collar around the outside of the connection. The concrete collar will be reinforced with 6x6 W2.9 x W2.9 wire mesh.

All costs for constructing the concrete collars including materials and labor will be incidental to the contract unit price per foot for the corresponding pipe contract item.

CONTROLLED DENSITY FILL FOR PIPE

Controlled density fill will be in conformance with Section 464 of the Specifications.

The controlled density fill will be placed between the pipes from the base of pipe elevation to the haunch of the pipes and extend to the end of the end section.

TABLE OF CONTROLLED DENSITY FILL FOR PIPE							
Station	Quantity						
East of Veterans	(CuYd)						
52+71.08 - 27.10' L to 52+90.55 - 13.20' L	4.3						
52+73.16 - 37.49' L to 52+92.73 - 23.59' L	4.3						
52+75.46 - 47.42' L to 52+94.85 - 33.30' L	4.3						
Total	12.9						

STORM SEWER

Reinforced concrete pipe may be bell and spigot. The pipe sections will be adjoined such that the ends are fully entered and the inner surfaces are reasonably flush and even.

Lift holes are prohibited for pipe or culverts. The Contractor will be responsible for developing and utilizing procedures and equipment for handling and installing storm drainage pipe or culvert without penetrations through the wall. The Contractor is allowed to utilize lifting devices which are incorporated or cast into the pipe or culvert upon shop drawing approval by the Engineer.

All culvert joints will be tied. Tie bolts will be incidental to the bid item "54" RCP Arch. Install".

Watertight joints are required for reinforced concrete pipe, drop inlets, manholes, and junction boxes where storm sewers run parallel to and within 10 feet horizontally from existing or proposed water mains.

Watertight joints are required where reinforced concrete pipes, drop inlets, manholes, or junction boxes cross water mains and are separated a distance of 18 inches or less, above or below, the water main.

If watertight joints are required, then the watertight joints will extend for a distance of 10 feet beyond the water main. This measurement will be from the sealed concrete joint to the outer most surface of the water main.

Reinforced concrete pipe will be provided with gasketed joints. Gasketed RCP will comply with ASTM C443. All costs associated with providing gasketed joints will be incidental to the "54" RCP Arch Class 2, Furnish" bid item.

STORM SEWER (cont.)

Watertight joint seals will conform to the following requirements:

- Reinforced Concrete Pipe (Circular): Gasketed pipe will conform to the requirements of ASTM C443 and the gasket will be in conformance with Section 990 of the Specifications. Non-gasketed concrete pipe will be sealed with a mastic joint seal conforming to the requirements of ASTM C990 and encased with a minimum 2-foot wide by 6-inch thick M6 concrete collar reinforced with 6x6 W2.9 x W2.9 wire mesh.
- 2. Reinforced Concrete Pipe (Arch): Gasketed pipe will conform to the requirements of ASTM C443 and the gasket will be in conformance with Section 990 of the Specifications. Non-gasketed concrete pipe joints will be sealed with a hydrophilic flexible water stop seal and wrapped with a 1-foot wide strip of fabric above the cradle. The fabric will conform to the requirements of Section 831 of the Specifications for Type A Drainage Fabric. The hydrophilic flexible water stop will be from the list below.
- 3. <u>Drop Inlets, Manholes, and Junction Boxes</u>: Joints will be sealed with one of the following methods:
 - A. A flexible strip seal placed in the joints conforming to the requirements of ASTM C990 and the perimeter encased with a minimum 2-foot wide by 6-inch thick M6 concrete collar reinforced with 6x6 W2.9 x W2.9 wire mesh.
 - B. A hydrophilic flexible water stop seal placed in the joints and a 1-foot wide strip of fabric wrapped around the perimeter of the pipe. The fabric will conform to the requirements of Section 831 of the Specifications for Type A Drainage Fabric. The hydrophilic flexible water stop will be from the list below.
 - A self-adhesive external joint seal wrap. The seal wrap will be from the list below.

Approved List of Self-adhesive Joint Wrap

<u>Product</u>	<u>Manufacturer</u>
Mar Mac Seal Wrap	Mar Mac Construction Products McBee, SC 843-335-5909 www.marmac.com
ConWrap CS-212	Concrete Sealants, Inc. Tipp City, OH

800-332-7325

http://www.conseal.com

Approved List of Hydrophilic Flexible Water Stop Seal:

Waterstop RX	Cetco
·	Hoffman Estates, IL
	800-527-9948
	www.cetco.com

Product

Conseal CS-231

Concrete Sealants, Inc. Tipp City, OH

800-332-7325

http://www.conseal.com

Manufacturer

Gaskets and seals (mastic, waterstop, and seal wraps) will be installed in accordance with the Manufacturer's recommendations.

The cost for furnishing and installing all gaskets, mastic joint seal, water stop seal, seal wrap, concrete collars, and for plugging the lift holes will be incidental to the contract unit price per foot for the corresponding pipe contract item.

TABLE OF REINFORCED CONCRETE PIPE									
		Flared End							
		54" Arch							
	54" Arch	Remove and							
	CI 2	Reset							
Station Offset (L/R)	(Ft)	(EA)							
East of Veterans									
52+71.08 - 27.10' L to 52+90.55 - 13.20' L	16	1							
52+73.16 - 37.49' L to 52+92.73 - 23.59' L	16	1							
52+75.46 - 47.42' L to 52+94.85 - 33.30' L	16	1							
52+78.46 - 57.13' L to 52+97.53 - 42.48' L	16	1							
Total Project	64	4							

FOR BIDDING PURPOSES ONLY

STATE OF	PROJECT	SHEET	TOTAL SHEETS
Y SOUTH DAKOTA	P TAPU(38)	9	70

Plotting Date: 7/10/2024

COLORED CONCRETE FOR SIDEWALK

The colored concrete will have the integral color Solomon Brick Red #417 or an equal approved by the Engineer.

ColorFlo Liquid Color Color #417 Red Solomon Colors, Inc. www.solomoncolors.com

Brick Red requires a rate of 12.50 pounds of Solomon ColorFlo #417 Red per cubic yard of concrete. The colored concrete must be cured according to the manufacturer's recommendations with two coats of a non-yellowing acrylic curing and sealing compound. The curing and sealing compound will meet ASTM C309. The curing and sealing product will be DECRA-SEAL or an equal approved by the Engineer.

DECRA-SEAL W.R. Meadows, Inc. 1-800-342-5976 www.wrmeadows.com

White pigmented cure will not be used. The Contractor will protect the colored concrete to ensure white pigmented curing compound will not come in contact with the colored concrete. All costs for furnishing, handling, applying the curing and sealing compound, and liquid integral color, including the materials, equipment, labor, and incidentals necessary will be incidental to the contract unit price for "6" Colored Concrete Sidewalk".


MODIFIED TYPE B66 CONCRETE CURB AND GUTTER

The concrete curb and gutter will be installed as shown in detail 650.01 – Standard Curb and Gutter

CONCRETE SIDEWALK

The concrete sidewalk will be constructed in accordance with Section 651. Due to the extra depth required, the granular cushion material required, as per the typical sections, will be paid for separately at the contract unit price per ton for Gravel Cushion. The gravel cushion will meet the requirements of Section 882. Compaction will be to the satisfaction of the Engineer.

All joints will be sawed in accordance with Section 380.3 P of the Specifications. Max spacing on transverse joints will be 10'. No centerline longitudinal joint will be required.



TYPE 1 DETECTABLE WARNINGS

Detectable warnings will be in compliance with the Americans with Disabilities Act regulations.

The detectable warnings will be installed according to the manufacturer's installation instructions.

A concrete thickness equal to the adjacent concrete sidewalk thickness and 2 inches of granular cushion material will be placed below the Type 1 Detectable Warnings. When concrete is placed below the detectable warnings then the concrete thickness will be transitioned at the rate of 1" per foot to match the adjacent concrete sidewalk thickness.

The detectable warnings will be a brick red color for application in concrete curb ramps. Cast iron plates may be a natural patina (weathered steel).

Type 1 Detectable Warning Panels will be one of the following products:

Type 1 Detectable Warnings

Manufacturer Product **Detectable Warning Plate** Neenah Foundry Company Cast Iron Plate Neenah, WI 800-558-5075 http://www.neenahfoundry.com/ Detectable Warning Plate

Cast Iron Plate

Deeter Foundry Lincoln, NE 800-234-7466 http://www.deeter.com/

Detectable Warning Plate Cast Iron Plate(No Coating)

East Jordan Iron Works, Inc. 301 Spring Street East Jordan, MI 49727 800-626-4653 http://www.ejiw.com

Iron Dome Cast Iron Detectable Warning Tile

ADA Solutions, Inc. 323 Andover St., Suite 3 Wilmingtion, MA 01887 800-372-0519 https://adatile.com

TufTile (wet-set) Cast Iron Replaceable Tile TufTile 1200 Flex Court Lake Zurich, IL 60047 888-960-8897 http://www.tuftile.com/ FOR BIDDING PURPOSES ONLY DAKOTA

STATE OF

PROJECT SHEET P TAPU(38) 10 70

Plotting Date: 7/10/2024

		TABL	E OF REM C	VALS			
		Curb and Gutter	Asphalt Pavement	Concrete Pavement*	Concrete Sidew alk	Saw Asphalt**	Saw Concrete**
Station to	Station	(Ft)	(SqYd)	(SqYd)	(SqYd)	(Ft)	(Ft)
West of Veteran	s Pkwy						
1+42	6+56				287.7		26
13+19	23+79		2.7	4.4		16	8
24+00	37+41		3.1	4.7	13.6	18	13
East of Veterans	Pkwy						
39+05	53+84	30	6.7			45	20
Silverthorne Ave)						
200+50	202+31				1.8		4
Fi	eld Determined	5	3.0		5.0		
	Total	35	15.5	9.1	308.1	79	71
**Incidental to ass	ociated pavement	bid item.					
*Removal of Conc	rete Fillet, paid for	as "Remov	e Concrete	Pavement".			

**12 gallons per ton was used to calculate the quantity.

TABLE OF SURFACING											
		Asp Area	halt* 4" Depth*	4" Sidew alk	6" Sidew alk	6" Colored Sidew alk	6" Fillet	Modified B66 Curb and Gutter	Gravel Cushion*	Water for Granular Material**	Detectable Warning Type 1
Station to	Station	(SqYd)	(Ton)	(SqFt)	(SqFt)	(SqFt)	(SqYd)	(Ft)	(Ton)	(MGal)	(SqFt)
West of Veter	ans Pkwy										
1+42	6+56				4125	1417			234.2	2.8	
16+00	24+00	3	0.8		6445		4.4		313.7	3.8	16
24+00	37+75	3	0.9	93	10845		4.7		530.4	6.4	16
East of Vetera	ans Pkwy										
39+05	53+97	7	1.9	504	12629			30	631.2	7.6	32
Silverthorne A	Ave										
200+50	202+31			622	80				39.6	0.5	8
Field	Determined	3	0.9	50				10	200.0	2.4	
	Total	15	4.5	1269	34124	1417	9.1	40	1949.1	23.5	72



SEQUENCE OF OPERATIONS

The Contractor will submit a sequence of operations for approval two weeks prior to the preconstruction meeting. If changes to the sequence of operations are proposed during the project, these must be submitted for review a minimum of one week prior to potential implementation. Approval for changes to the sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work.

COORDINATION BETWEEN CONTRACTORS

A separate utility project (PS 240) will be constructed along Veterans Parkway in 2025. The project consists of sanitary sewer installation on the east side of Veterans Parkway. The construction limits for this project begin at approximately Station 39+25 and end at Station 45+00. See plan and profile sheets for location.

The Contractor will schedule work so as not to interfere with or hinder the progress of the work performed by the other Contractor. The Contractor will not install the proposed shared use path or conduct any grading activities within the outlined stationing limits until the utility work has been completed with the separate utility project. Conflicting traffic control devices may need to be temporarily adjusted or removed as directed by the Engineer and at no additional cost to the contract.

All costs for coordination between the projects will be incidental to the project cost

GENERAL TRAFFIC CONTROL

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices, including delineation, will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost will be replaced by the Contractor at no cost to the State.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation.

Portable sign supports will not be located on sidewalks, bicycle facilities, or other areas designated for pedestrian or bicycle traffic.

All construction operations will be conducted in the general direction of traffic movement.

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Fixed location signing placed more than 4 calendar days prior to the start of construction will be covered or laid down until the time of construction. The covers must be approved by the Engineer prior to installation. The cost of materials, labor, and equipment necessary to complete this work will be incidental to other contract items. No separate payment will be made.

All fixed location signs, sign posts, and breakaway bases will be removed within 7 calendar days following pavement marking.

FOR BIDDING PURPOSES ONLY DAKOTA

STATE OF SOUTH DAKOTA

Plotting Date: 7/10/2024

26th STREET LANE CLOSURE

The south most eastbound lane on 26th Street will be allowed to be closed once as shown in the plans. The 26th Street lane closure will be allowed to be closed for no more than fourteen (14) calendar days.


All costs associated with the lane closure will be included in the appropriate bid items.

TEMPORARY PEDESTRIAN ACCESS ROUTE

A Temporary Pedestrian Access Route (TPAR) will be provided when crosswalks, sidewalks, or other pedestrian facilities are blocked, closed, or relocated. A TPAR may consist of a combination of existing and/or temporary pedestrian facilities. The TPAR will be kept free of any obstructions and hazards, such as holes, debris, mud, snow, construction equipment, traffic control signing, stored materials, etc.

The Contractor will notify the Engineer at least 72 hours prior to start of any construction operation that will necessitate a change in pedestrian access. Pedestrian traffic signal displays controlling a crosswalk that is closed will be covered or removed.

PEDESTRIAN CHANNELIZING DEVICE DETAILS



Longitudinal Pedestrian Barrier

Longitudinal Pedestrian Barricade


- 1. Barricade rail supports may not extend into the pedestrian walkway more than 4 inches from the face of the barricade.
- 2. The top edge of the bottom portion will be a minimum of 8 inches above the walkway.
- 3. Devices will not block water drainage from the walkway. A gap height or opening from the walkway surface up to a maximum of 2 inches in height is allowed for drainage purposes.
- 4. The top edge of the longitudinal pedestrian barricade is to be used as a guiderail to provide visual and tactile guidance to pedestrians along a designated route. The top surface should have a minimum width of 0.5 inches to allow the hand to feel the surface. The surface should be smooth and free of any sharp or abrasive elements to allow safe hand trailing.
- 5. Longitudinal pedestrian barrier used to provide positive protection from traffic to pedestrians should be crashworthy.

CHANNELIZING DEVICES

In transition and taper sections, channelizing devices will be reflectorized drums. In tangent sections, 42" tall grabber cones may be used instead of reflectorized drums. Payment for channelizing devices will be incidental to the lump sum bid price for "Traffic Control, Miscellaneous".

STANDARD SPACING FOR SIGNS, TAPERS, AND CHANNELIZING DEVICES

Posted Speed Prior to Work (M.P.H.)	Spacing of Advance Warning Signs (Feet) (A) (B) (C) (D)	Taper Length (Feet) (L)	Spacing of Channelizing Devices (Feet) (G)
0 – 30	200	180	25
35 – 40	350	320	25
45 – 50	500	600	50
55	500	660	50
	(A) (B) (C) (D)		
60 - 65	500 1000 1300 1600	780	50
75	500 1000 1300 1600	1125	50



PROJECT STATE OF SOUTH DAKOTA SHEET P TAPU(38) 12 70

FILE: TRAFFIC CONTROL PLOTTING DATE: 7/10/2024

REV DATE: INITIAL:

I	т	ARI E FOR	? TRAFF	IC CONT	ROL (SaFt)				
				BLE FOR TRAFFIC CONTROL (SqFt) 26th Street Lane Closure				eld mined	
		Sign	Width	Height	Sign Quantity	No. of	Total	No. of	Total
Sign Description	Symbol	Code	(in)	(in)	(SqFt)	Signs	SqFt	Signs	SqFt
ROAD WORK AHEAD	Α	W20-1	48	48	16.0	3	48.0	5	80.0
RIGHT LANE CLOSED AHEAD	В	W20-5R	48	48	16.0	1	16.0		
MERGE LEFT	С	W4-2L	48	48	16.0	1	16.0		

36

24

18

24

4.5

4.0

Grand Total

Total

G20-2

R8-3

Traffic Control Tables

END ROAD WORK

NO PARKING

22.5

20.0 122.5

13.5


93.5

216.0

3

OTHER TRAFFIC CONTROL QUANTITIES									
ltem	Unit	26th Street Lane Clousre	26th Street PED Detour	Field Determined	Total Quantity				
Flagging	Hour			20	20				
Type C Advance Warning Arrow Panel	Each	1			1				
Longitudinal Pedestrian Barricade	Ft		18	30	48				
Type 3 Double Sided Barricade	Each			2	2				

TABLEFO	OR DETOU	RSIGNING	(SqFt)								
						26th Street PED Detour					
					Sign						
		Sign	Width	Height	Quantity	No. of	Total	No. of	Total		
Sign Description	Symbol	Code	(in)	(in)	(SqFt)	Signs	SqFt	Signs	SqFt		
SIDEWALK CLOSED	A1	R9-9	24	12	2.0	3	6.0	5	10.0		
PED DETOURARROW LEFT	B1	M4-9b L	30	24	5.0	7	35.0				
PED DETOURARROW RIGHT	C1	M4-9b R	30	24	5.0	5	25.0				
SIDEWALK CLOSED AHEAD	D1	Special	24	24	4.00	1	4.0	5	20.0		
	,				Total		70.0		30.0		
				Gr	and Total		10	0.0			

















SPECIAL
24"X24"
3" LETTERS, TYPE D
2" SPACING
BLACK ON WHITE

11/1/1/1/8/21/2024

SALVAGE AND PLACE TOPSOIL

Prior to beginning of surfacing operations, a 6" depth of topsoil will be removed or bladed away from the construction area. Following completion of construction, topsoil will be spread evenly over the disturbed areas.

The estimated amount of topsoil to be salvaged is 1,510 CuYd. Topsoil that is salvaged will be paid for once as "Unclassified Excavation".

The estimated amount of topsoil to be placed based on a shrinkage factor of 50% is 1,510 CuYd. Salvaged topsoil that is placed by the Contractor will be paid for once as "Placing Topsoil". Any excess topsoil will be disposed of by the Contractor or spread out evenly across the project as directed by the Engineer. All cost for disposing of or spreading out additional topsoil will be incidental to the bid item "Placing Topsoil" and no additional quantity will be paid for.

MYCORRHIZAL INOCULUM

Mycorrhizal inoculum will consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier will provide certification of the fungal species claimed and the live propagule count. The inoculum will include a minimum 25% the fungal species *Rhizophagus intraradices*. The remaining 75% may include other endomycorrhizal fungal species.

Type G seed will be inoculated by the seed supplier with a minimum of 100,000 live propagules of mycorrhizal fungi per acre. All costs of inoculating the seed will be incidental to the contract unit price per pound for the corresponding permanent seed mixture.

Type D seed will be inoculated by the seed supplier with a minimum of 20,000 live propagules of mycorrhizal fungi per 1,000 square feet. All costs of inoculating the seed will be incidental to the contract unit price per pound for the corresponding permanent seed mixture.

Prior to placing sod, apply a minimum of 25,000 live propagules of inoculum per 1,000 square feet on bare soil. All costs of inoculating for the sod will be incidental to the contract unit price per square yard for "Sodding".

The mycorrhizal inoculum will be as shown below or an approved equal:

<u>Product</u>	<u>Manufacturer</u>
MycoApply	Mycorrhizal Applications, Inc. Grants Pass, OR Phone: 1-866-476-7800 www.mycorrhizae.com
AM 120 Multi Species Blend	Reforestation Technologies Int. Gilroy, CA Phone: 1-800-784-4769 www.reforest.com
LALRISE Prime and Max WP	Lallemand Specialties Inc. Milwaukee, WI Phone: 1-844-590-7781

www.lallemandplantcare.com

FERTILIZING

Perfect Bl

The Contractor will apply an all-natural slow release fertilizer prior to seeding or placing sod. The all-natural fertilizer will have a minimum guaranteed analysis of 4-4-4 and be USDA Certified BioBased. It should provide a minimum of 4% (N) nitrogen with a minimum water insoluble nitrogen (WIN) fraction of 2.07%, a minimum of 4% (P2O5) available phosphate, a minimum of 4% (K2O) soluble potash, and a maximum carbon to nitrogen ratio (C:N ratio) of 5:1. The all-natural fertilizer will be free of weed-seed and pathogens accomplished through thermophilic composting, and not mechanical or chemical sterilization, to assure presence of beneficial soil microbiology. The fertilizer will have a near neutral pH, a low salt index, a low biological oxygen demand, contain organic humic and fulvic acids, and have high aerobic organism counts. The fertilizer will also be stable, free of bad odors, and be unattractive as a food source for animals. It should also be in a granular form that is easily spread.

The fertilizer will be applied at a rate of 1,000 pounds per acre in accordance with the manufacturer's recommended method of application.

The all-natural slow release fertilizer will be as shown below or an approved equal:

Product	<u>Manufacturer</u>
Sustane	Sustane Corporate Headquarters Cannon Falls, Minnesota Phone: 1-800-352-9245 www.sustane.com

end	Perfect Blend, LLC
	Bellevue, WA

Phone: 1-866-456-8890 www.perfect-blend.com

Nature Safe Fertilizers

Irving, TX

Phone: 1-605-759-5622

www.naturesafe.com

FOR BIDDING PURPOSES ONLY

STATE OF	PROJECT	SHEET	TOTAL SHEETS
Y SOUTH DAKOTA	P TAPU(38)	13	70

Plotting Date: 7/10/2024

PERMANENT SEEDING

The areas to be seeded consist of all newly graded areas within the project limits except for the top of the shared use path and sidewalk.

Type D Permanent Seed Mixture will be used on mowed areas and consists of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/1000 SqFt)
Kentucky Bluegrass	Avalanche, Appalachian, Wildhorse, Blue Bonnet, Action	1.4
Perennial Ryegrass	Turf Type Varieties	1.4
Creeping Red Fescue	Epic, Boreal, Chantilly	1.4
Chewings Fescue	Ambrose, K2, Zodiac, Shadow III	1.4
Alkali Grass	Fults, Fults II, Quill, Salty	1.4
	Total:	7

Type G Permanent Seed Mixture will be used in non-maintained areas and consist of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/Acre)
Western Wheatgrass	Arriba, Flintlock, Rodan, Rosana, Walsh	7
Switchgrass	Dacotah, Forestburg, Nebraska 28, Pathfinder,	3
Indiangrass	Summer, Sunburst, Trailblazer Holt, Tomahawk, Chief, Nebraska 54	3
Big Bluestem	Bison, Bonilla, Champ, Sunnyview, Rountree, Bonanza	3
Oats or Spring Wheat: April through May;		10
Winter Wheat: August through November		
	Total:	26

ROFESSION REG. NO. TO SEG. NO.

SODDING

Sod will be placed at locations specified in the plans and at locations determined by the Engineer during construction.

Contractor will be responsible for watering the sod at the time of placement. After initial placement and watering of sod, property owner will be responsible for the establishment and continuing maintenance of the sod.

An estimated 3 Gallons of water per square yard of sod was used to compute the quantity for the bid item "Water for Vegetation". All costs involved for watering the sod at time of placement will be incidental to the contract unit price per MGal for "Water for Vegetation".

WATER FOR VEGETATION

Water for vegetation consists of applying water to seeded areas to enhance germination and/or root growth. When watering, use the following guidelines:

Immediately after seeding:

- Keep the topsoil moist but not excessively wet until the seed has germinated.
- Water a minimum of 3 days a week for 2 weeks preferably watering 2 or 3 times a day in small quantities.
- Use fine spray and low pressure to avoid topsoil wash and to prevent uncovering buried seeds.

After emergence:

- Topsoil will be kept thoroughly moistened by sprinkling, as necessary, for 6 weeks. After the 6-week period, an inspection will be made to determine if grass is established enough to suspend watering. Continue watering until grass has been thoroughly established.
- Never apply water at a rate faster than the topsoil can absorb.
- Water during early morning hours or early evening hours.
- Do not water when rain is forecasted for the area.
- If rainfall occurs, suspend watering according to rainfall amount.

An estimated 60 Gallons of water per square yard of seeding area was used to compute the quantity for the bid item "Water for Vegetation".

All costs for furnishing and applying the water including hauling, materials, equipment, labor, and incidentals necessary will be paid for at the contract unit price per MGal for "Water for Vegetation".

FOR BIDDING PURPOSES ONLY BAKOTA

Dandy Curb

STATE OF

PROJECT SHEET P TAPU(38) 14

70

Plotting Date: 7/10/2024

FIBER MULCHING

Fiber mulch will be applied in a separate operation following permanent seeding.

An additional 2% by weight of tackifier will be added to the fiber mulch product selected from the approved product list. If the product selected has guar gum tackifier included, then the additional 2% of tackifier will be guar gum. If the product selected has synthetic tackifier included, then the additional 2% of tackifier will be synthetic.

Fiber mulch will be applied at the rate of 2,000 pounds per acre.

The Contractor will allow the fiber mulch to cure a minimum of 18 hours prior to watering or any storm event to ensure proper cohesion between the soil and fiber particles.

All costs for the additional tackifier added to the fiber mulch including labor, equipment, and materials will be incidental to the contract unit price per ton for "Fiber Mulching".

The fiber mulch provided will be from the approved product list. The approved product list for fiber mulch may be viewed at the following internet site:

http://apps.sd.gov/HC60ApprovedProducts/main.aspx

LOW FLOW SILT FENCE

The low flow silt fence fabric provided will be from the approved product list. The approved product list for low flow silt fence may be viewed at the following internet site:

http://apps.sd.gov/HC60ApprovedProducts/main.aspx

Low flow silt fence will be placed at the locations noted in the table and at locations that will minimize siltation of adjacent streams, lakes, dams, or drainage areas as determined by the Engineer during construction. Refer to Standard Plate 734.04 for details.

An additional quantity of Low Flow Silt Fence has been added to the Estimate of Quantities for temporary sediment control.

SEDIMENT CONTROL AT TYPE S REINFORCED CONCRETE DROP INLETS

The sediment control device provided will be from the list shown below. Refer to Standard Plate 734.11 for details.

> **Product** Manufacturer

> > Powell. OH

Phone: 1-800-591-2284 www.dandyproducts.com

Dandy Products Inc.

ACF Environmental Gutterbuddy

Richmond, VA

Phone: 1-800-448-3636 www.acfenvironmental.com

Curb Inlet Guard ECTEC Environmental Systems LLC

Alameda, CA

Phone: 1-866-521-0724 www.ertecsystems.com

EZ-ClipGuard Flo-Water, LLC

> West Des Moines, IA Phone: 1-515-577-6763 www.flo-water.net

TSL E-Sock Three Sons Landscaping

Rapid City, SD

Phone: 1-605-391-1903

12" Silt Sock Aspen Ridge Lawn and Landscaping,LLC

Rapid City, SD

Phone: 1-605-716-4080

https://aspenridgelandscaping.com/

GeoSolutions, Inc. GeoCurve

Austin, TX

Phone: 1-512-330-0796 www.geosolutionsinc.com

Smart Curb Filter NoFlood, Inc.

Fort Myers, FL

Phone: 1-239-776-1671 http://www.noflood.com



STREET SWEEPING

Vehicle tracking of sediment from the construction site will be minimized. Street sweeping will be used if erosion and sediment control best management practices are not adequate to prevent sediment from being tracked onto the street.

The Contractor will use a pickup broom having integral self-contained storage to clean the roadway. The pickup broom used will be a minimum of 6 feet wide and have working gutter brooms.

All costs for cleaning the roadway with a pickup broom will be incidental to the contract unit price per hour for "Sweeping".

CONSTRUCTION ENTRANCE

The Contractor will install a Construction Entrance at locations where there is a potential for mud tracking and sediment flow from the construction site and work area onto a paved public roadway.

It is the Contractor's option to use the SDDOT Construction Entrance (See SDDOT Construction Entrance notes and details), a product from the list provided in these notes, or other products or processes as approved by the Engineer during construction.

If the Contractor elects to use one of the products listed in the table, then the Contractor will install the construction entrance product in accordance with the manufacturer's installation instructions or as directed by the Engineer.

The Contractor will maintain the construction entrance such that mud tracking and sediment flow will not enter the roadway or adjacent drainage areas. The construction entrance will be routinely inspected, and the Contractor will repair or replace material as deemed necessary by the Engineer.

All costs for furnishing, installing, maintaining, and removal of the construction entrance including equipment, labor, materials, and incidentals will be included in the contract unit price per each for "Construction Entrance".

The following table is a list of known construction entrance products available for use:

Product	
---------	--

Grizzly Rumble Grate (10' width and 24' length required)

Pro Grid (12' width and 24' length including combination of grids and ramps required)

Tracking Pad (12' width and 24' length (2 - 12'x12' pads)and 2 – 4'x4' turning flares)

FODS Trackout Control Mat (12' width and 5 mats to get a 35' length)

Manufacturer

Trackout Control, LLC Tempe, AZ

Phone: 1-800-761-0056 www.trackoutcontrol.com

Pro-Tec Equipment, Inc. Charlotte, MI

Phone: 1-800-292-1225 www.pro-tecequipment.com

Tracking Pads LLC Commerce City, CO Phone: 1-303-501-5640 www.trackingpads.com

FODS, LLC Denver, CO

Phone: 1-844-200-3637 http://www.getfods.com

Signature Systems Group, LLC Flower Mound, TX Phone: 1-800-931-7301

https://www.signature-systems.com/

RubberForm Recycled Products, LLC Lockport, NY

Phone: 1-716-478-0408 www.rubberform.com

SDDOT CONSTRUCTION ENTRANCE

DuraDeck and MegaDeck HD

An adequate quantity is needed to

prevent tires from becoming

muddy (does not remove mud)

Track-Out Control Mat

(10' width and 24' length

required)

If the SDDOT Construction Entrance is utilized, then the Contractor will install the SDDOT Construction Entrance in accordance with these notes and the detail drawings.

Pit run material will be obtained from a granular source and will conform to the following gradation:

Sieve Size	Percent Passing
6"	100%
#4	0-60%
#200	0-20%

The pit run material will be compacted to the satisfaction of the Engineer.

The aggregate for the granular material will conform to the following gradation requirements:

Sieve Size	Percent Passing
3"	100%
2 ½"	90-100%
1 ½"	25-60%
3/4"	0-10%
1/2"	0-5%

The granular material will be placed in 6" maximum lifts.

It is anticipated that the granular material will need to be periodically removed and replaced as it becomes inundated with mud and sediment.

The Reinforcement Fabric (MSE) will be in conformance with Section 831 of the Specifications. The Reinforcement Fabric (MSE) will be on the Approved

Products List for this material or will be certified by the supplier to meet this specification prior to installation.

The Reinforcement Fabric (MSE) should be kept as taut as possible prior to placing.

Equipment will not be allowed on the Reinforcement Fabric (MSE) until the first lift of granular material is in place.

All seams in the Reinforcement Fabric (MSE) will be overlapped at least 2' and shingled.

FOR BIDDING PURPOSES ONLY DAKOTA

STATE OF

PROJECT SHEET P TAPU(38) 15

70

Plotting Date: 7/10/2024

CONCRETE WASHOUT AREA

A concrete washout area will be installed on the project site at a location approved by the Engineer if concrete trucks deliver concrete to the site. No washout area is necessary if all concrete trucks will wash out at approved site constructed by the concrete supplier.



QUANTITY TABLES

	TABLE OF SEEDING, FERTILIZING AND MULCHING								
				Type D	Type G				
		Area	Area	Seed	Seed			Fiber	
		Type D	Type G	Mix 1 ¹	Mix 2 ²	Sodding	Fertilizer ³	Mulch ⁴	Water ⁵
Station to	Station	(SqYd)	(SqYd)	(Lb)	(Lb)	(SY)	(Lb)	(Ton)	(MGal)
West of Veter	ans Pkwy								
1+35	6+70	215		14			44	0.1	12.9
13+15	23+75	2902	730	183	4		751	0.8	218.0
24+00	37+50	392	261	25	2	3369	831	0.9	49.3
East of Vetera	ns Pkwy								
39+25	53+65	2512	2383	158	13	186	1050	1.1	294.3
	Total	6021	3374	380	18	3555	2676	2.9	574.5

- 1 Type D Seed Mix rate = 305 Lb/acre
 2 Type G Seed Mix = 26 Lb/acre
 3 Fertilizer rate = 1000 Lb/acre
 4 Fiber Mulching rate = 1.00 Ton/acre
 5 Watering = 60 gal/sqyd for seeding and 3 gal/sqyd for sodding
- Weed Control will be incidental to the various erosion control bid items

TABLE OF INLET PROTECTION								
	Inlet Protection							
			Type S	Silt Fence				
Station	Offes	t	(Ft)	(Ft)				
West of Vet	erans Pkv	NУ						
5+62	6'	L	12					
15+90	114'	R	12					
16+03	94'	R	12					
24+45	57'	R	12					
24+46	13'	R	12					
37+16	17'	R		24				
West of Vet	erans Pkv	NУ						
53+19	28'	L	12					
53+56	3'	L	12					
53+42	136'	Ĺ	12					
	Total 96 24							


FOR BIDDING PURPOSES OF

	STATE OF	PROJECT		TOTAL SHEET
DNL	NLY SOUTH DAKOTA P	P TAPU(38)	16	70

Plotting Date: 7/10/2024

TABLE OF SILT FENCE							
				Low Flow	Mucking	Repair	Remove
Station to	Station	L/R	Location	(Ft)	(CuYd)	(Ft)	(Ft)
West of Veterans Pkwy							
13+28	22+44	L	Perimeter	900	62	225	225
24+04	32+76	L	Perimeter	682	47	171	171
37+16	37+16	R	Inlet Protection	24	2	6	6
East of Veterans Pkwy							
44+61	52+50	L	Perimeter	810	56	203	203
52+63 L		Inlet end pipe	75	5	19	19	
			Field Determined	100	7	25	25
			Total Project	2,591	173	623	623

		TABLE OF I	RIPRAP AN	D DRAINA	GE FABRIC		
Station to	Station	L/R	Length (ft)	Width (ft)	Depth (ft)	Class B Riprap (ton)	Type B Drainage Fabric (SqYd)
Silverthorn	ne Ave	•					
200+69	201+21	46' L	20	42	3	143.7	103
					Total	143.7	103



STORMWATER POLLUTION PREVENTION PLAN CHECKLIST

(The numbers left of the title headings are **reference numbers** to the GENERAL PERMIT FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES (Stormwater Permit))

5.3 (2): STAFF TRAINING/SWPPP IMPLEMENTATION

To promote stormwater management awareness specific for this project, the Contractor's Erosion Control Supervisor should provide correspondence of how the SWPPP will be implemented. The Contractor's Erosion Control Supervisor is responsible for providing this information at the preconstruction meeting, and subsequently completing an attendance log, which should identify site-specific implementation of the SWPPP and the names of the personnel who attended the preconstruction meeting. Documentation of the preconstruction meeting will be filed with the SWPPP documents.

5.3 (3): DESCRIPTION OF CONSTRUCTION ACTIVITIES

- > 5.3 (3a): Project Limits (See Title Sheet)
- 5.3 (3a): Project Description (See Title Sheet)
- 5.3 (4): Site Map(s) (See Title Sheet and Plans)
- Major Soil Disturbing Activities (check all that apply)
 - Clearing and grubbing
 - ⊠Excavation/borrow
 - ⊠Grading and shaping
 - ⊠ Filling
- Other (describe):
- 5.3 (3b): Total Project Area 2.97 Acres
- 5.3 (3b): Total Area to be Disturbed 2.26 Acres
- > 5.3 (3c): Maximum Area Disturbed at One Time 2.26 Acres
- 5.3 (3d): Existing Vegetative Cover (%) 100%
- 5.3 (3d): Description of Vegetative Cover Grass
- > 5.3 (3e): Soil Properties: USDA-NRCS Soil Series Classification Silty Clays
- 5.3 (3f): Name of Receiving Water Body/Bodies Big Sioux River
- 5.3 (3g): Location of Construction Support Activity Areas N/A

5.3 (3h): ORDER OF CONSTRUCTION ACTIVITIES The Contractor will enter the Estimated Start Date.

Description	Estimated Start Date
Install stabilized construction entrance(s).	
Install perimeter protection where runoff may exit site.	
Install perimeter protection around stockpiles.	
Install channel and ditch bottom protection.	
Clearing and grubbing.	
Remove and stockpile topsoil.	
Stabilize disturbed areas.	
Install utilities, storm sewers, curb and gutter.	
Install inlet and culvert protection after completing storm drainage and other utility installations.	
Final grading.	
Final paving.	
Removal of protection devices.	
Reseed areas disturbed by removal activities.	

FOR BIDDING PURPOSES ONLY DAKOTA 5.3 (5): DESCRIPTION AND MAINTENANCE OF CONTROL MEASURES

SHEET STATE OF P TAPU(38) 17

Plotting Date: 7/10/2024

All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report. Include the technical reasoning for selecting each control. (check all that apply)

Perimeter Controls (See Detail Plan Sheets)

Description	Estimated Start Date
☐ Natural Buffers (within 50 ft of Waters of State)	
⊠ Silt Fence	
☐ Erosion Control Wattles	
☐ Temporary Berm / Windrow	
☐ Floating Silt Curtain	
Stabilized Construction Entrances	
☐ Entrance/Exit Equipment Tire Wash	
☐ Other:	

Structural Erosion and Sediment Controls

Description	Estimated Start Date
⊠ Silt Fence	
☐ Temporary Berm/Windrow	
☐ Erosion Control Wattles	
☐ Temporary Sediment Barriers	
☐ Erosion Bales	
☐ Temporary Slope Drain	
☐ Turf Reinforcement Mat	
□ Riprap	
Gabions	
☐ Rock Check Dams	
☐ Sediment Traps/Basins	
Culvert Inlet Protection	
☐ Transition Mats	
☐ Median/Area Drain Inlet Protection	
☐ Curb Inlet Protection	
☐ Interceptor Ditch	
□ Concrete Washout Facility	
☐ Work Platform	
☐ Temporary Water Barrier	
☐ Temporary Water Crossing	
☐ Permanent Stormwater Ponds	
☐ Permanent Open Vegetated Swales	
☐ Natural Depressions to allow for Infiltration	
☐ Sequential Systems that combine several practices	
Other:	

Dust Controls

Description	Estimated Start Date
☐ Tarps & Wind impervious fabrics	
☐ Watering	
☐ Stockpile location/orientation	
☐ Dust Control Chlorides	
Other	

Dewatering BMPs

Description	Estimated Start Date
☐ Sediment Basins	
☐ Dewatering bags	
☐ Weir tanks	
☐ Temporary Diversion Channel	
Other:	

Stabilization Practices (See Detail Plan Sheets)

(Stabilization measures will begin the following work day whenever earth disturbing activity on any portion of the site has temporarily or permanently ceased. Temporary stabilization will be completed as soon as practicable but no later than 14 days after initiating soil stabilization activities (3.18))

Description	Estimated Start Date	
☐Vegetation Buffer Strips		
☐ Temporary Seeding (Cover Crop Seeding)		
□ Permanent Seeding		
⊠ Sodding		
☐ Planting (Woody Vegetation for Soil Stabilization)		
☐ Mulching (Grass Hay or Straw)		
☐ Fiber Mulching (Wood Fiber Mulch)	OFESS/O	11.
☐ Soil Stabilizer		1/2
☐ Bonded Fiber Matrix	RED. NO.	
☐ Fiber Reinforced Matrix	15042	2
☐ Erosion Control Blankets	ODE	K
Surface Roughening (e.g. tracking)	OUT JOY.	Ex
Other:	14 DAN	
etland Avoidance	8/21/2024 //////////////////////////////////	III

Wetland Avoidance

Will construction and/or erosion and sediment controls impinge on regulated wetlands? Yes No If yes, the structural and erosion and sediment controls have been included in the total project wetland impacts and have been included in the 404 permit process with the USACE.

5.3 (6): PROCEDURES FOR INSPECTIONS

- Inspections will be conducted at least once every 7 days.
- All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report.
- Silt fence will be inspected for depth of sediment and for tears to ensure the fabric is securely attached to the posts and that the posts are well anchored. Sediment buildup will be removed from the silt fence when it reaches 1/3 of the height of the silt fence.
- Sediment basins and traps will be checked. Sediment will be removed when depth reaches approximately 50 percent of the structure's capacity, and at the conclusion of the construction.
- Check dams will be inspected for stability. Sediment will be removed when depth reaches ½ the height of the dam.
- All seeded areas will be checked for bare spots, washouts, and vigorous growth free of significant weed infestations.
- Inspection and maintenance reports will be prepared on form DOT 298 for each site inspection, this form will also be used to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents.
- The SDDOT Project Engineer and Contractor's Erosion Control Supervisor are responsible for inspections. Maintenance and repair activities are the responsibility of the Contractor. The SDDOT Project Engineer will complete the inspection and maintenance reports and distribute copies per the distribution instructions on DOT 298.

5.3 (7): POST CONSTRUCTION STORMWATER MANAGEMENT

Stormwater management will be handled by temporary controls outlined in "DESCRIPTION AND MAINTENANCE OF CONTROL MEASURES" above, and any permanent controls needed to meet permanent stormwater management needs in the post construction period will be shown in the plans and noted as permanent.

5.3 (8): POLLUTION PREVENTION PROCEDURES

5.3 (8a): Spill Prevention and Response Procedures

Material Management

- Housekeeping
- Only needed products will be stored on-site by the Contractor.
- Except for bulk materials the contractor will store all materials under cover and/or in appropriate containers.
- Products must be stored in original containers and labeled.
- Material mixing will be conducted in accordance with the manufacturer's recommendations.
- When possible, all products will be completely used before properly disposing of the container off-site.
- The manufacturer's directions for disposal of materials and containers will be followed.
- The Contractor's site superintendent will inspect materials storage areas regularly to ensure proper use and disposal.
- Dust generated will be controlled in an environmentally safe manner.

Hazardous Materials

- Products will be kept in original containers unless the container is not resealable and provide secondary containment as applicable.
- Original labels and material safety data sheets will be retained in a safe place to relay important product information.

- If surplus product must be disposed of, manufacturer's label RIDDING PURPOSES ONLY DAKOTA directions for disposal will be followed.
- Maintenance and repair of all equipment and vehicles involving oil changes, hydraulic system drain down, de-greasing operations, fuel tank drain down and removal, and other activities which may result in the accidental release of contaminants will be conducted on an impervious surface and under cover during wet weather to prevent the release of contaminants onto the ground.
- Wheel wash water will be collected and allowed to settle out suspended solids prior to discharge. Wheel wash water will not be discharged directly into any stormwater system or stormwater treatment system.
- Potential pH-modifying materials such as: bulk cement, cement kiln dust, fly ash, new concrete washings, concrete pumping, residuals from concrete saw cutting (either wet or dry), and mixer washout waters will be collected on site and managed to prevent contamination of stormwater runoff.

> Spill Control Practices

In addition to the previous housekeeping and management practices, the following practices will be followed for spill prevention and cleanup if needed.

- For all hazardous materials stored on site, the manufacturer's recommended methods for spill cleanup will be clearly posted. Site personnel will be made aware of the procedures and the locations of the information and cleanup supplies.
- Appropriate cleanup materials and equipment will be maintained by the Contractor in the materials storage area on-site. As appropriate, equipment and materials may include items such as brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for cleanup purposes.
- All spills will be cleaned immediately after discovery and the materials disposed of properly.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- After a spill a report will be prepared describing the spill, what caused it, and the cleanup measures taken. The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring, as well as clean up instructions in the event of reoccurrences.
- The Contractor's site superintendent, responsible for day-to-day operations, will be the spill prevention and cleanup coordinator.

> Spill Response

The primary objective in responding to a spill is to quickly contain the material(s) and prevent or minimize migration into stormwater runoff and conveyance systems. If the release has impacted on-site stormwater, it is critical to contain the released materials on-site and prevent their release into receiving waters. If a spill of pollutants threatens stormwater or surface water at the site, the spill response procedures outlined below must be implemented in a timely manner to prevent the release of pollutants.

- The Contractor's site superintendent will be notified immediately when a spill or the threat of a spill is observed. The superintendent will assess the situation and determine the appropriate response.
- If spills represent an imminent threat of escaping erosion and sediment controls and entering receiving waters, personnel will be directed to respond immediately to contain the release and notify the superintendent after the situation has been stabilized.

STATE OF PROJECT SHEET TOTAL SHEETS

Y SOUTH DAKOTA P TAPU(38) 18 70

Plotting Date: 7/10/2024

- Spill kits containing appropriate materials and equipment for spill response and cleanup will be maintained by the Contractor at the site
- If oil sheen is observed on surface water (e.g. settling ponds, detention ponds, swales), action will be taken immediately to remove the material causing the sheen. The Contractor will use appropriate materials to contain and absorb the spill. The source of the oil sheen will also be identified and removed or repaired as necessary to prevent further releases.
- If a spill occurs the superintendent or the superintendent's designee will be responsible for completing the spill reporting form and for reporting the spill to SDDANR.
- Personnel with primary responsibility for spill response and cleanup will receive training by the Contractor's site superintendent or designee. The training must include identifying the location of the spill kits and other spill response equipment and the use of spill response materials.
- Spill response equipment will be inspected and maintained as necessary to replace any materials used in spill response activities.

5.3 (8b): WASTE MANAGEMENT PROCEDURES

Waste Disposal


 All liquid waste materials will be collected and stored in approved sealed containers. All trash and construction debris from the site will be deposited in the approved containers. Containers will be serviced as necessary, and the trash will be hauled to an approved disposal site or licensed landfill. All onsite personnel will be instructed in the proper procedures for waste disposal and notices stating proper practices will be posted. The Contractor is responsible for ensuring waste disposal procedures are followed.

> Hazardous Waste

 All hazardous waste materials will be disposed of in a manner specified by local or state regulations or by the manufacturer. Site personnel will be instructed in these practices, and the Contractor will be responsible for seeing that these practices are followed.

> Sanitary Waste

 Portable sanitary facilities will be provided on all construction sites. Sanitary waste will be collected from the portable units which must be secured to prevent tipping and serviced in a timely manner by a licensed waste management Contractor or as required by any local regulations.



5.3 (9): CONSTRUCTION SITE POLLUTANTS

The following materials or substances are expected to be present on the site during the construction period. These materials will be handled as noted under the heading "POLLUTION PREVENTION PROCEDURES" (check all that apply).

	Concrete and Portland Cemen
	Detergents
	☐ Paints
	☐ Bituminous Materials
\triangleright	□ Petroleum Based Products
\triangleright	□ Diesel Exhaust Fluid
\triangleright	☐ Cleaning Solvents
	⊠ Wood
\triangleright	□ Cure
\triangleright	☐ Texture
	☐ Chemical Fertilizers
	Other:

Product Specific Practices

Petroleum Products

All on-site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

Fertilizers

Fertilizers will be applied only in the amounts specified by the SDDOT. Once applied, fertilizers will be worked into the soil to limit the exposure to stormwater. Fertilizers will be stored in an enclosed area. The contents of partially used fertilizer bags will be transferred to sealable containers to avoid spills.

Paints

All containers will be tightly sealed and stored when not required for use. The excess will be disposed of according to the manufacturer's instructions and any applicable state and local regulations.

Concrete Trucks

Contractors will provide designated truck washout facilities on the site. These areas must be self-contained and not connected to any stormwater outlet of the site. Upon completion of construction, the area at the washout facility will be properly stabilized.

5.3 (10): NON-STORMWATER DISCHARGES

The following non-stormwater discharges are anticipated during the course of this project (check all that apply).

	Discharges	from	water	line	flushing.

- Pavement wash-water, where no spills or leaks of toxic or hazardous materials have occurred.
- Uncontaminated ground water associated with dewatering activities.

5.3 (11): INFEASIBILITY DOCUMENTATION

If it is determined to be infeasible to comply with any of the requirements of the Stormwater Permit, the infeasibility determination must be thoroughly documented in the SWPPP. FOR BIDDING PURPOSES ONLY SOUTH DAKOTA

 PROJECT
 SHEET
 TOTAL SHEETS

 P TAPU(38)
 19
 70

Plotting Date: 7/10/2024

7.0: SPILL NOTIFICATION In the event of a spill, the Contractor's site superintendent will make the

In the event of a spill, the Contractor's site superintendent will make the appropriate notification(s), consistent with the following procedures:

- A release or spill of a regulated substance (includes petroleum and petroleum products) must be reported to SDDANR immediately **if any one of the following** conditions exists:
 - The release or spill threatens or is able to threaten waters of the state (surface water or ground water)
 - The release or spill causes an immediate danger to human health or safety
 - The release or spill exceeds 25 gallons
 - The release or spill causes a sheen on surface water
 - The release or spill of any substance that exceeds the ground water quality standards of ARSD Chapter 74:54:01
 - The release or spill of any substance that exceeds the surface water quality standards of ARSD Chapter 74:51:01
 - The release or spill of any substance that harms or threatens to harm wildlife or aquatic life
 - The release or spill is required to be reported according to Superfund Amendments and Reauthorization Act (SARA) Title III List of Lists, Consolidated List of Chemicals Subject to Reporting Under the Emergency Planning and Community Right to Know Act, US Environmental Protection Agency.
- ➤ To report a release or spill, call SDDANR at 605-773-3296 during regular office hours (8 a.m. to 5 p.m. Central Standard Time). To report the release after hours, on weekends or holidays, call South Dakota Emergency Management at 605-773-3231. Reporting the release to SDDANR does not meet any obligation for reporting to other state, local, or federal agencies. Therefore, you must also contact local authorities to determine the local reporting requirements for releases. A written report of the unauthorized release of any regulated substance, including quantity discharged, and the location of the discharge will be sent to SDDANR within 14 days of the discharge.



5.4: SWPPP CERTIFICATIONS

> Certification of Compliance with Federal, State, and Local Regulations

The Storm Water Pollution Prevention Plan (SWPPP) for this project reflects the requirements of all local municipal jurisdictions for storm water management and sediment and erosion control as established by ordinance, as well as other state and federal requirements for sediment and erosion control plans, permits, notices or documentation as appropriate.

> South Dakota Department of Transportation

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.


Authorized Signature (See the General Permit, Section 7.4 (1))

Prime Contractor

This section is to be executed by the General Contractor after the award of the contract. This section may be executed any time there is a change in the Prime Contractor of the project.

I certify under penalty of law that this document and all attachments will be revised or maintained under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Authorized	



FOR BIDDING PURPOSES ONLY DAKOTA

SHEET STATE OF P TAPU(38) 20

Plotting Date: 7/10/2024

CONTACT INFORMATION

The following personnel are duly authorized representatives and have signatory authority for modifications made to the SWPPP:

> Contractor Information:

Prime Contractor Name:
Contractor Contact Name:
Address:

•	City:	State:	Zip:	
	•			
	Office Phone:	Field:		

Cell Phone:
Fax:

> Erosion Control Supervisor

•	Name:	

•	Address:	

-	

•	Office Phone:	Field:	

Cell Phone:
Fax:

> SDDOT Project Engineer

•	Name:		
---	-------	--	--

•	Business Address:	

•	Job Office Location:	
---	----------------------	--

•	City:	State:	Zip:
	Office Phone:	Field:	

•	Cell Phone: _	Fax:

> SDDANR Contact Spill Reporting

- Business Hours Monday-Friday (605) 773-3296
- Nights and Weekends (605) 773-3231

SDDANR Contact for Hazardous Materials.

(605) 773-3153

National Response Center Hotline

(800) 424-8802.

SDDANR Stormwater Contact Information

- SDDANR Stormwater (800) 737-8676
- Surface Water Quality Program (605) 773-3351

5.5: REQUIRED SWPPP MODIFICATIONS

> 5.5 (1): Conditions Requiring SWPPP Modification The SWPPP must be modified, including the site map(s), in response to any of the following conditions:

- When a new operator responsible for implementation of any part the SWPPP begins work on the site.
- When changes to the construction plans, sediment and erosion control measures, or any best management practices on site that are no longer accurately reflected in the SWPPP. This includes changes made in response to corrective actions triggered by inspections.
- To reflect areas on the site map where operational control has been transferred (including the date of the transfer) or has been covered under a new permit since initiating coverage under this general permit.
- If inspections by site staff, local officials, SDDANR, or U.S. EPA determine that SWPPP modifications are necessary for compliance with the Stormwater Permit.
- To reflect any revisions to applicable federal, state, or local requirements that affect the control measures implemented at the
- If approved by the Secretary, to reflect any changes in chemical water treatment systems or controls, including the use of a different water treatment chemical, age rates, different areas, or methods of application.

> 5.5 (2): Deadlines for SWPPP Modification

Any required revisions to the SWPPP must be completed within 7 calendar days following any of the items listed above.

> 5.5 (3): Documentation of Modifications to the Plan

All SWPPP modification records are required to be maintained showing the dates of when the modification occurred. The records must include the name of the person authorizing each change and a brief summary of all changes.


> 5.5 (4): Certification Requirements


All modifications made to the SWPPP must be signed and certified as required in Section 7.4.

> 5.5 (5): Required Notice to Other Operators

If there are multiple operators at the site, the Contractor's Erosion Control Supervisor must notify each operator that may be impacted by the change to the SWPPP within 24 hours.

When modifications as described above occur, the SWPPP will be modified to provide appropriate protection to disturbed areas, all storm water structures, and adjacent waters. The SDDOT Project Engineer will modify the SWPPP using the DOT 298 form and drawings on the plan will be modified to reflect the needed changes. Copies of the DOT 298 forms and the SWPPP will be retained on site in a designated place for review throughout the course of the project. A copy of the DOT 298 form will be given to the Contractor Erosion Control Supervisor and a copy will be emailed to the SDDOT Environmental Section in accordance with the DOT 298 Form.





HORIZONTAL ALIGNMENT: 26th Path CL					
DESCRIPTION	STATION	LENGTH	COURSE	NORTHING	EASTING
1L	BEG:1+00.00 END:6+49.87	549.87'	N88°12'36.31"E'	BEG:15820997.50 END:15821014.68	BEG:2260408.58 END:2260958.19
1C	BEG:6+49.87 END:6+65.53	CL=14.81'	CL=S45°44'37.30"E' R=13.63	BEG:15821014.68 END:15821004.34	BEG:2260958.19 END:2260968.79
2L	BEG:6+65.53 END:8+72.58	207.05'	S79°41'12.16"E'	BEG:15821004.34 END:15820967.27	BEG:2260968.79 END:2261172.50
3L	BEG:8+72.58 END:9+37.56	64.98'	S89°40'51.62"E'	BEG:15820967.27 END:15820966.91	BEG:2261172.50 END:2261237.47
4L	BEG:9+37.56 END:11+62.60	225.04'	N78°02'09.95"E'	BEG:15820966.91 END:15821013.56	BEG:2261237.47 END:2261457.62
5L	BEG:11+62.60 END:12+33.73	71.13'	N88°15'21.29"E'	BEG:15821013.56 END:15821015.72	BEG:2261457.62 END:2261528.73
6L	BEG:12+33.73 END:13+11.76	78.03'	N88°15'21.29"E'	BEG:15821015.72 END:15821018.10	BEG:2261528.73 END:2261606.72
7L	BEG:13+11.76 END:15+93.91	282.15'	S02°06'05.93"E'	BEG:15821018.10 END:15820736.14	BEG:2261606.72 END:2261617.06
8L	BEG:15+93.91 END:19+02.19	308.29'	N89°43'15.42"E'	BEG:15820736.14 END:15820737.64	BEG:2261617.06 END:2261925.35
3C	BEG:19+02.19 END:19+12.60	CL=10.39'	CL=N83°52'33.19"E' R=51.00	BEG:15820737.64 END:15820738.75	BEG:2261925.35 END:2261935.67
9L	BEG:19+12.60 END:19+49.30	36.71'	N78°01'50.96"E'	BEG:15820738.75 END:15820746.36	BEG:2261935.67 END:2261971.58
4C	BEG:19+49.30 END:19+55.53	CL=6.22'	CL=N81°43'59.64"E' R=48.16	BEG:15820746.36 END:15820747.26	BEG:2261971.58 END:2261977.74
10L	BEG:19+55.53 END:20+28.07	72.54'	N85°26'08.32"E'	BEG:15820747.26 END:15820753.03	BEG:2261977.74 END:2262050.05
5C	BEG:20+28.07 END:20+38.71	CL=10.63'	CL=S88°12'30.37"E' R=48.00	BEG:15820753.03 END:15820752.70	BEG:2262050.05 END:2262060.67

HORIZONTAL ALIGNMENT: 26th Path CL					
DESCRIPTION STATION LENGTH COURSE NORTHING EASTING					
11L	BEG:20+38.71 END:21+08.60	69.89'	S81°51'09.06"E'	BEG:15820752.70 END:15820742.79	BEG:2262060.67 END:2262129.85
6C	BEG:21+08.60 END:21+19.25	CL=10.63'	CL=S75°29'47.28"E' R=48.00	BEG:15820742.79 END:15820740.13	BEG:2262129.85 END:2262140.14
12L	BEG:21+19.25 END:21+85.93	66.67'	S69°08'25.50"E'	BEG:15820740.13 END:15820716.39	BEG:2262140.14 END:2262202.44
7C	BEG:21+85.93 END:22+01.51	CL=15.52'	CL=S59°50'15.40"E' R=48.00	BEG:15820716.39 END:15820708.59	BEG:2262202.44 END:2262215.86
13L	BEG:22+01.51 END:22+51.42	49.90'	\$50°32'05.30"E'	BEG:15820708.59 END:15820676.87	BEG:2262215.86 END:2262254.39
8C	BEG:22+51.42 END:23+12.03	CL=52.93'	CL=S00°25'17.03"W' R=34.08	BEG:15820676.87 END:15820623.94	BEG:2262254.39 END:2262254.00
14L	BEG:23+12.03 END:23+87.32	75.29'	S51°22'39.36"W'	BEG:15820623.94 END:15820576.95	BEG:2262254.00 END:2262195.17
9C	BEG:23+87.32 END:25+92.52	CL=198.70'	CL=S26°26'22.01"E' R=234.15	BEG:15820576.95 END:15820399.03	BEG:2262195.17 END:2262283.65
15L	BEG:25+92.52 END:27+17.43	124.91'	S01°19'59.15"E'	BEG:15820399.03 END:15820274.16	BEG:2262283.65 END:2262286.55
10C	BEG:27+17.43 END:27+37.19	CL=19.20'	CL=S24°55'03.30"E' R=24.00	BEG:15820274.16 END:15820256.74	BEG:2262286.55 END:2262294.64
16L	BEG:27+37.19 END:28+34.73	97.54'	S48°30'07.46"E'	BEG:15820256.74 END:15820192.11	BEG:2262294.64 END:2262367.70
11C	BEG:28+34.73 END:28+61.54	CL=26.12'	CL=S71°07'07.66"E' R=33.96	BEG:15820192.11 END:15820183.66	BEG:2262367.70 END:2262392.41
17L	BEG:28+61.54 END:32+46.28	384.75'	N86°15'52.13"E'	BEG:15820183.66 END:15820208.72	BEG:2262392.41 END:2262776.34
12C	BEG:32+46.28 END:33+31.33	CL=76.52'	CL=S48°36'38.47"E' R=53.99	BEG:15820208.72 END:15820158.13	BEG:2262776.34 END:2262833.75

HORIZONTAL ALIGNMENT: 26th Path CL						
DESCRIPTION STATION LENGTH COURSE NORTHING EASTING						
18L	BEG:33+31.33 END:36+90.42	359.09'	S03°29'09.06"E'	BEG:15820158.13 END:15819799.71	BEG:2262833.75 END:2262855.58	
13C	BEG:36+90.42 END:37+36.34	CL=41.27'	CL=S48°50'59.44"E' R=29.00	BEG:15819799.71 END:15819772.55	BEG:2262855.58 END:2262886.66	
19L	BEG:37+36.34 END:39+31.83	195.49'	N85°47'10.17"E'	BEG:15819772.55 END:15819786.91	BEG:2262886.66 END:2263081.62	
14C	BEG:39+31.83 END:39+83.15	CL=44.88'	CL=N35°05'20.88"E' R=29.00	BEG:15819786.91 END:15819823.64	BEG:2263081.62 END:2263107.42	
20L	BEG:39+83.15 END:40+14.81	31.66'	N15°36'28.42"W'	BEG:15819823.64 END:15819854.13	BEG:2263107.42 END:2263098.90	
15C	BEG:40+14.81 END:40+27.97	CL=13.13'	CL=N08°37'33.93"W' R=54.00	BEG:15819854.13 END:15819867.11	BEG:2263098.90 END:2263096.93	
21L	BEG:40+27.97 END:44+42.67	414.70'	N01°38'39.44"W'	BEG:15819867.11 END:15820281.64	BEG:2263096.93 END:2263085.03	
16C	BEG:44+42.67 END:44+99.04	CL=50.13'	CL=N45°51'08.73"E' R=34.00	BEG:15820281.64 END:15820316.55	BEG:2263085.03 END:2263121.00	
22L	BEG:44+99.04 END:47+22.33	223.29'	S86°39'03.09"E'	BEG:15820316.55 END:15820303.51	BEG:2263121.00 END:2263343.91	
17C	BEG:47+22.33 END:47+32.55	CL=10.20'	CL=S81°07'38.66"E' R=53.00	BEG:15820303.51 END:15820301.93	BEG:2263343.91 END:2263353.99	
23L	BEG:47+32.55 END:49+43.29	210.74'	S75°36'14.22"E'	BEG:15820301.93 END:15820249.54	BEG:2263353.99 END:2263558.12	
18C	BEG:49+43.29 END:49+48.21	CL=4.92'	CL=S72°56'30.87"E' R=53.00	BEG:15820249.54 END:15820248.09	BEG:2263558.12 END:2263562.83	
24L	BEG:49+48.21 END:54+18.20	469.99'	S70°16'47.53"E'	BEG:15820248.09 END:15820089.51	BEG:2263562.83 END:2264005.25	


TYPICAL SECTIONS

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P TAPU(38)	23	70


FILE: TYPICALS PLOTTING DATE: 7/10/2024

REV DATE: INITIAL:




TYPICAL SECTION 1

STA 1+51 TO 6+45




TYPICAL SECTION 2

STA 16+20 TO 53+84



TYPICAL SECTION 3

STA 200+50 TO 202+20



FOR BIDDING PURPO	SES ONLY
-------------------	----------

D TADI 1/291	TE OF UTH COTA	PROJECT	SHEET	TOTAL SHEETS
		P TAPU(38)	24	70


STATE SOUT DAKO

REV DATE: INITIAL:

LE: LEGEND	
LOTTING DATE: 7/10/2024	

Anchor	-
Antenna	
Approach	
Assumed Corner	?
Azimuth Marker	
BBQ Grill/ Fireplace Bearing Tree	• •
Bench Mark	a
Box Culvert	
Bridge	
Brush/Hedge	
Buildings	
Bulk Tank	
Cattle Guard	
Cemetery	+
Centerline	
Cistern	©
Clothes Line	admin.
Concrete Symbol Control Point	A.
Creek Edge	<u> </u>
Curb/Gutter	
Curb	8 8 8
Dam Grade/Dike/Levee	
Deck Edge	
Ditch Block	×.A
Doorway Threshold	
Drainage Profile	
Drop Inlet	-
Edge Of Asphalt	
Edge Of Concrete Edge Of Gravel	
Edge Of Other	
Edge Of Shoulder	
Electric Transformer/Power Jur	nction Box 🕑
Fence Barbwire	
Fence Chainlink	
Fence Electric	
Fence Miscellaneous Fence Rock	'
Fence Snow	
Fence Wood	
Fence Woven	
Fire Hydrant	Ō₃
Flag Pole	ř
Flower Bed	ナナナナ
Gas Valve Or Meter	•
Gas Pump Island	
Grain Bin Guardrail	
Gutter	•
Guy Pole	D
Haystack	ŏ
Highway ROW Marker	0
Interstate Close Gate	N. C.
Iron Pin	⊙
Irrigation Ditch	• •
Lake Edge Lawn Sprinkler	
Lawii Spillikiei	30 °

NΛ	ailbox
	anhole Electric
	anhole Gas
	anhole Miscellaneous
	anhole Sanitary Sewer anhole Storm Sewer
	anhole Telephone
	anhole Water
	erry-Go-Round
	icrowave Radio Tower iscellaneous Line
	iscellaneous Property Corner
	iscellaneous Post
	verhang Or Encroachment
	verhead Utility Line arking Meter
	edestrian Push Button Pole
	pe With End Section
	pe With Headwall
	pe Without End Section
	ayground Slide ayground Swing
	ower And Light Pole
	ower And Telephone Pole
	ower Meter
	ower Pole ower Pole And Transformer
	ower Tower Structure
Pr	opane Tank
	operty Pipe
	operty Pipe With Cap operty Stone
	ublic Telephone
	ailroad Crossing Signal
	ailroad Milepost Marker
	ailroad Profile ailroad ROW Marker
	ailroad Signs
	ailroad Switch
	ailroad Track
	ailroad Trestle
	ebar ebar With Cap
	eference Mark
	etaining Wall
	prap
	ver Edge ock And Wire Baskets
	ockpiles
	itellite Dish
	eptic Tank
	nrub Tree
	dewalk gn Face
,	gn Post
Sl	ough Or Marsh
	oring
	ream Gauge reet Marker
Ji	i det ividi kei





Subsurface Utility Exploration Test Hole Telephone Fiber Optics Telephone Junction Box Telephone Pole Television Cable Jct Box Television Tower Test Wells/Bore Holes Traffic Sign Double Face Traffic Sign One Post Traffic Signal Trash Barrel Tree Belt Tree Coniferous Tree Deciduous Tree Stumps Triangulation Station Underground Electric Line Underground Gas Line Underground Sonitary Sewer Underground Storm Sewer Underground Tank Underground Telephone Line Underground Television Cable Underground Water Line Water Fountain Water Hydrant Water Meter Water Tower Water Valve Water Well Weir Rock Windmill Wingwall Witness Corner	T/F T/F T/F
With C35 COITICI	•


State and National Line County Line Section Line Quarter Line Sixteenth Line Property Line Construction Line ROW Line New ROW Line Cut and Fill Limits Control of Access New Control of Access Proposed ROW (After Property Disposal) Drainage Arrow	-0		
Remove Concrete Pavement			
Remove concrete ravement			
Remove Concrete Driveway Pavemer	nt		
Remove Asphalt Concrete Pavement			
Remove Concrete Sidewalk			
Remove Concrete Median Pavement			
Remove Concrete Curb and/or Gutte	r		
Mill and Overlay Asphalt Pavement			
Detectable Warning Pedestrian Push Button Pole and 30" x 48" Clear Space with 1.5% slope		— — —	





































FDR

S. DAYLIGHT DRIVE CURB RAMP OF ETPA (LPS POSES ONLY P TAPU(38) 36 67 **LEGEND** FILE: RAMP GRADING REV DATE: PLOTTING DATE: 7/10/2024 INITIAL: * TURNING SPACE WITH 1.5% (2% MAX.) SLOPE ① STA 23+81.51-4.00' RT (6) STA 23+92.60-8.77' RT 12 STA 24+35.19-2.46' LT TS ELEV = 1485.76 END TAPER TS ELEV = 1485.17 TC ELEV = 1485.11 7 STA 23+91.30-10.39' RT 13 STA 24+36.94-5.36' RT ② STA 23+80.22-4.00' LT TS ELEV = 1485.64 **BGN TAPER** TS ELEV = 1485.05 TC ELEV = 1485.55 2 (3) STA 23+91.81-1.98' LT 14) STA 24+30.89-6.49' RT 8 STA 23+87.32-3.91' RT TS ELEV = 1485.57 TS ELEV = 1485.02 TS ELEV = 1485.69 3 4 STA 23+95.63-1.26' LT 15 STA 24+28.08-9.17' RT 9 STA 23+87.32-4.51' RT **BGN TAPER BGN TAPER** TS ELEV = 1485.74 TC ELEV = 1485.61 TC ELEV = 1485.40 (5) STA 23+95.35-0.74' RT (10) STA 24+25.54-2.56' LT 16 STA 24+26.93-7.40' RT END TAPER **BGN TAPER END TAPER** TC ELEV = 1485.25 TC ELEV = 1485.52 TC ELEV = 1484.9011) STA 24+29.34-1.37' LT 17 STA 24+25.46-0.48' LT TS ELEV = 1485.14 **END TAPER** TC ELEV = 1485.02 (10) -(11) MANA DAK - O TO THE TOTAL OF THE TAXABLE TO THE TAX -(12)(16) <u>(15</u>)- $\overline{(14)}$ (13)

S. SILVERTHORNE AVENUE CURB RATION DETPARESES ONLY


P TAPU(38) 37 67

FILE: RAMP GRADING PLOTTING DATE: 7/10/2024

REV DATE:

* TURNING SPACE WITH 1.5% (2% MAX.) SLOPE

LEGEND



18) STA 53+21.74-4.00' LT TS ELEV = 1465.25

TS ELEV = 0.00

TS ELEV = 1465.00

TC ELEV = 1465.07

TC ELEV = 1464.81


BGN TAPER

END TAPER


- (23) STA 53+31.95-4.00' RT **END TAPER** TC ELEV = 1464.88
- 24) STA 53+31.47-6.00' RT **BGN TAPER** TC ELEV = 1465.04
- 25 STA 53+27.84-4.00' RT TS ELEV = 1465.12
- (26) STA 53+24.10-4.00' RT TS ELEV = 1465.34
- 27) STA 53+20.04-4.00' RT TS ELEV = 1465.41


- 28) STA 53+71.25-2.96' RT **BGN TAPER** TC ELEV = 1465.42
- 29 STA 53+74.72-5.78' RT TS ELEV = 1465.28
- 30 STA 53+78.38-6.59' RT TS ELEV = 1465.56
- (31) STA 53+82.14-7.42' RT TS ELEV = 1465.62
- 32) STA 53+80.40-15.21' RT TS ELEV = 1465.67


- 33) STA 53+76.64-14.39' RT TS ELEV = 1465.61
- 34) STA 53+73.00-13.59' RT TS ELEV = 1465.33
- 35) STA 53+68.66-14.68' RT **BGN TAPER** TC ELEV = 1465.49
- 36 STA 53+69.10-12.73' RT END TAPER TC ELEV = 1465.03
- 37) STA 53+70.82-4.92' RT **END TAPER** TC ELEV = 1464.98





S. SILVERTHORNE AVENUE CURB RAMPODETAPOSES ONLY P TAPU(38) 38 67 **LEGEND** FILE: RAMP_GRADING REV DATE: PLOTTING DATE: 7/10/2024 INITIAL: * TURNING SPACE WITH 1.5% (2% MAX.) SLOPE 38 STA 53+52.61-167.74' LT 43 STA 53+51.45-156.68' LT **BGN TAPER** TS ELEV = 1468.42 TC ELEV = 1468.5939 STA 53+55.61-164.99' LT 44 STA 53+48.64-160.46' LT **END TAPER** TS ELEV = 1468.49 Shafer Avenue TC ELEV = 1468.27 40 STA 53+58.13-161.72' LT 45 STA 53+49.46-164.39' LT **BGN TAPER** TS ELEV = 1468.51 TC ELEV = 1468.19 41) STA 53+60.01-158.14' LT 46 STA 53+52.97-163.02' LT TS ELEV = 1468.40 **END TAPER** TC ELEV = 1468.06 42 STA 53+56.48-156.76' LT 47 STA 53+55.43-159.72' LT TS ELEV = 1468.32 TS ELEV = 1468.34 <u>44</u>) (43) $\overline{42}$ 7777788/21/2024 11777777777777777




















































FOR BIDDING PURPOSES ONLY

,	STATE OF	PROJECT	SHEET	TOTAL SHEETS	
	SOUTH DAKOTA	P TAPU(38)	59	70	
		ECTIONS - 26TH ST PATH TE: 7/10/2024	REV D		









FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	P TAPU(38)	60	70


FILE: CROSS SECTIONS - 26TH ST PATH PLOTTING DATE: 7/10/2024


REV DATE: INITIAL:












PIPE SECTIONS


FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA P TAPU(38) SHEET TOTAL SHEETS 70 TAPU(38)

FILE: PIPE SECTIONS PLOTTING DATE: 7/10/2024

REV DATE: INITIAL:








PIPE SECTIONS


FOR BIDDING PURPOSES ONLY

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	P TAPU(38)	44	70

FILE: PIPE SECTIONS PLOTTING DATE: 7/10/2024

REV DATE: INITIAL:









STATE OF

PROJECT P TAPU(38)

SHEET 61 70 Rev 09/04/2024 KAO

Plotting Date: 9/4/2024


roadway. The signs illustrated will be used where there are distracting situations; such as: vehicles parked on shoulder, vehicles

The ROAD WORK AHEAD sign may be replaced with other appropriate signs, such as

should also be placed on the left side of the directional roadway.

operations, all signs and channelizing devices may be eliminated if a vehicle with

Posted	Spacing of
Speed	Advance WarnIng
Prior to	Signs
Work	(Feet)
(M.P.H.)	(A)
0 - 30	200
35 - 40	350
45 - 50	500
55	750
60 - 80	1000



January 22, 2021

WORK BEYOND THE SHOULDER

S D D O T

PLATE NUMBER 634.01 Sheet I of I

The signs illustrated are not required if the work space is behind a barrier, more than 2 feet behind the curb, or 15 feet or more from the edge of any

accessing the work site via the highway, and equipment traveling on or crossing the roadway to perform work operations.

the SHOULDER WORK sign. The SHOULDER WORK sign may be used for work adjacent to the shoulder.

If the work space is on a divided highway, an advance warning sign

For short term, short duration, or mobile an activated flashing or revolving yellow light is used.

Published Date: 2025

Rac or Risc Len Wal	dial din less o e and ngth o II thick an 5%	ES IN DI mensions and ± ½ Span: ± of Joint kness (T or ¾; ength: sh	at joir 4" for lo 2% of 1 (J): ± ½): not le whicheve	nts: <u>+</u> ! onger s tabular 4". ess thar er is gr	value n desi eater	s. gn T∣	by mo	re (for 10 to a Span : confor for gr	02" to thickn x Leng rm to ravel s reened	169"s less o gth of the surfac	pans. f 6"(N f culv grada cing e	It sha Min.) x ert a tion r	all be 85% o nd sh equire mate	ements rial ma	d
		Approx. Wt./Ft. (lb.)		Span (in.)	T (in.)	a (in.)	b (in.)	c (in.)	j (in.)	e (in.)	f (in.)	g (in.)	RI (in.)	R2 (in.)	R3 (in.)	
	18	170	131/2	22	21/2	13/8	⅓	7/4	2	11/8	⅓	ı	271/2	13 3/4	51/4	

Span

END VIEW

Size (in.)	Approx. Wt./Ft. (lb.)	Rise (in.)	Span (in.)	(in.)	a (in.)	b (in.)	c (in.)	j (in.)	e (in.)	f (in.)	g (in.)	RI (in.)	R2 (in.)	R3 (in.)
18	170	131/2	22	21/2	13%	⅓	₹4	2	11/8	3/8	ı	271/2	13¾	51/4
24	320	18	281/2	31/2	15/8	1/2	13%	3	13/8	1/2	15%	40 ^{II} / _{I6}	14 3/4	45/8
30	450	221/2	361/4	4	113/6	5/8	1%	31/2	1%	5/8	113/16	51	18¾	61/8
36	600	26%	43¾	41/2	2	7/4	13/4	4	13/4	₹4	2	62	221/2	61/2
42	740	31%	511/8	41/2	2	₹4	13/4	4	13/4	₹4	2	73	261/4	7 3/4
48	890	36	581/2	5	21/4	7/4	2	5	2	₹4	21/4	84	30	81/8
54	1100	40	65	51/2	21/2	₹4	21/4	5	21/4	₹4	21/2	921/2	33¾	10
60	1400	45	731/2	6	3%	¥4	15%	5	23/4	₹4	21/2	105	371/2	- 11
72	1900	54	88	7	31¾6	- 1	23/6	6	31/4	- 1	23/4	126	45	13%
84	2500	62	102	8	41/8	1	21/8	6	31/2	I	31/2	1621/2	52	141/2
96	3300	78	1223/8	9	41/2	-	31/2	7	4	- 1	4	218	62	20
108	4200	88	1381/2	10	5	I	4	7	41/2	1	41/2	269	70	22
120	5100	96%	154	- 11	51/2	1	41/2	7	5	ı	5	3013/8	78	24
132	5100	1061/2	168¾	10			4	7	41/2	ı	41/2	329	85%	26 1/8

* Equivalent Diameter of Circular R.C.P.

Laying Length

LONGITUDINAL SECTION

GENERAL NOTES:

Construction of R.C.P. Arch shall conform to the requirements of Section 990 of the Specifications. Not more than 2 four-foot sections shall be permitted near the ends of any culvert. Four-foot lengths shall be used only to secure the required length of culvert.

			June 26, 2015
	S D D	REINFORCED CONCRETE PIPE ARCH	PLATE NUMBER 450.02
Published Date: 2025	0		Sheet Lof L

Published Date: 2025		S D D O T	5-	LANE, OU	TSIDE LANE CLOSED	PL	ATE NUMBER 634.60
	 	 	 			ROAD WORK AHE AD	,
END (Optional)					*	RICHT LANE CLOSED AHEAD 550	,
Additional channelizing devices at 4' spacing may be needed to control traffic entering and leaving ntersections.				M. A	Sec	quential Chev	
12" cones may be used in place of the drums shown in the taper if setup will not be used during night time hours.		1	<u>+</u>			pe 3 Barricad ouble Sided)
The channelizing devices will be 42" cones or drums,			🧗	WORK			
Femporary pavement markings will be used if raffic control must remain overnight.				4-1	INTERSECTING	ROAD	STOP
The length of A and L may be adjusted to fit field conditions.					A	G20-2 (Optional)	ROAD WORK AHEAD
Pavement Marking Jrban areas and Intersecting streets may Imit sign spacing.			9		*Spac	END ROAD WORK	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
Channelizing Device 4" White Temporary					50 500 55 750 60 - 65 1000		50 *
Reflectorized Drum		l			35 - 40 350 45 500	320 600	25 25
AROW J		ļ	(S) 1	1	Work (Feet) (M.P.H.) (A) 0 - 30 200		
AHEAD	1		1 1	١	Posted Spacing Speed Advance W Prior to Signs	arning Lengt	r Spacing of h Channeizing Devices


FOR BIDDING PURPOSES ONL YDAKOTA

 PROJECT
 SHEET
 TOTAL SHEETS

 P TAPU(38)
 62
 70

Plotting Date: 9/4/2024

Rev 09/04/2024 KAO




STATE OF


PROJECT SHEET P TAPU(38) 63

Plotting Date: 9/4/2024

Rev 09/04/2024 KAO

70






Curb ramp slopes are designed at 7.5% unless stated otherwise in the plans. The curb ramp may have a maximum slope of 8.3% and will not exceed 15' in length unless stated otherwise in the plans.


The curb ramp length may be computed based on the intersection of a continuous 1.5% theoretical slope from theoretical top of curb (TTOC) with the curb ramp using a continuous 7.5% curb ramp slope. The #— elevation of point TCR will always be higher than the elevation of point TTOC unless specified otherwise in the plans. The curb ramp length dimension as shown in the plans will be adjusted as necessary to meet all slope and length requirements based on field geometrics.

The cross slope of the ramp will not be steeper than 2%. Plans are designed using a 1.5% slope unless stated otherwise in the plans.

- ★★ The slope in the turning space will not be steeper than 2% in any direction of pedestrian travel. Plans are designed using a 1.5% slope unless stated otherwise in the plans.
- ***The curb transition will be a minimum of 6' long, a maximum of 10' long, and the curb transition slope will not be steeper than 10% unless stated otherwise in the plans. The curb transition length will be adjusted as necessary to meet slope and length requirements based on field geometrics.
- **** The ramp width is 5' unless stated otherwise in the plans.



SECTION A-A



TYPE 1 CURB RAMP

(PERPENDICULAR CURB RAMP)

651.01

Sheet 2 of 3

D

D

0

Published Date: 2025

FOR BIDDING PURPOSES ONLY DAKOTA

STATE OF SOUTH DAKOTA P 7

 PROJECT
 SHEET
 TOTAL SHEETS

 P TAPU(38)
 64
 70

Plotting Date: 9/4/2024

Rev 09/04/2024 KAO

GENERAL NOTES:

For Illustrative purpose only, type 1 detectable warnings are shown in the drawings.

For Illustrative purpose only, PCC fillet sections are shown in the drawings. The curb ramp depicted on this standard plate may be used with a PCC fillet section or curb and gutter.

For Illustrative purpose only, the curb ramp location is shown at the center of a PCC filet section. The curb ramp will be placed at the location stated in the plans.

Sidewalk will not be placed adjacent to the curb ramp flares when a 2-foot curb transition is used unless shown otherwise in the plans.

* Care w■ be taken to ensure a uniform grade on the curb ramp, free of sags and short grade changes.

Surface texture of the curb ramp will be obtained by coarse brooming transverse to the slope of the curb ramp.

The normal gutter line profile will be maintained through the area of the ramp opening.

Joints will be sawed or tooled into the concrete adjacent to the detectable warnings to alleviate possible corner cracking.

Care will be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform color.

The detectable warnings will be cut as necessary to fit the plan specified limits of the detectable warnings. Cost for cutting the detectable warnings will be incidental to the corresponding detectable warning contract item.

There will be no separate payment for curb ramps. The curb ramp will be measured and paid for at the contract unit price per square foot for the corresponding concrete sidewalk contract item. The square foot area of the detectable warnings will be included in the measured and paid for quantity of sidewalk.

If rebar is placed in the turning space as depicted in detail E, the cost of the materials, labor, and equipment to furnish and install the rebar will be incidental to the contract unit price per square foot for the corresponding concrete sidewalk contract item.

The curb transitions and ramp opening will be measured and paid for at the contract unit price per foot for the corresponding curb and gutter contract Item when curb and gutter is used. The curb transitions and ramp opening will be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section contract Item when a PCC fillet section is used.

The type 1 detectable warnings will be measured to the nearest square foot, All costs for furnishing and installing the type 1 detectable warnings including labor, equipment, materials, and incidentals will be paid for at the contract unit price per square foot for "Type 1 Detectable Warnings".

The type 2 detectable warnings will be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding will be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".


February 14, 2020

Published Date: 2025

TYPE 1 CURB RAMP
(PERPENDICULAR CURB RAMP)

PLATE NUMBER 651.01

Sheet 3 of 3




FOR BIDDING PURPOSES ONLY SOUTH DAKOTA

 PROJECT
 SHEET
 TOTAL SHEETS

 P TAPU(38)
 65
 70

Plotting Date: 9/4/2024

Rev 09/04/2024 KAO



GENERAL NOTES:

For Illustrative purpose only, type 1 detectable warnings are shown in the drawings.

The curb ramp depicted on this standard plate may be used with a PCC fillet section or curb and gutter. The curb ramp will be placed at the location stated in the plans.

Sidewalk will not be placed adjacent to the curb ramp flares when a 2-foot curb transition is used unless shown otherwise in the plans.

* Care will be taken to ensure a uniform grade on the curb ramp, free of sags and short grade changes.

Surface texture of the curb ramp will be obtained by coarse brooming transverse to the slope of the curb ramp.

The normal gutter Ine profile will be maintained through the area of the ramp opening.

Joints will be sawed or tooled into the concrete adjacent to the detectable warnings to alleviate possible corner cracking.

Care will be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform

The detectable warnings will be cut as necessary to fit the plan specified limits of the detectable warnings. Cost for cutting the detectable warnings will be incidental to the corresponding detectable warning contract item.

There will be no separate payment for curb ramps. The curb ramp will be measured and paid for at the contract unit price per square foot for the corresponding concrete sidewalk contract item. The square foot area of the detectable warnings will be included in the measured and paid for quantity of sidewalk.

If rebar is placed in the Turning Space as depicted in DETAIL E, the cost of the materials, labor, and equipment to furnish and install the rebar will be incidental to the contract unit price per square foot for the corresponding concrete sidewalk contract item.

The curb transitions and ramp opening will be measured and paid for at the contract unit price per foot for the corresponding curb and gutter contract Item when curb and gutter is used. The curb transitions and ramp opening will be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section contract item when a PCC fillet section is used.

All costs for furnishing and installing the transition area at the base of the curb ramp will be incidental to the contract unit price per foot for the corresponding curb and gutter contract item when curb and gutter is used and will be incidental to the contract unit price per square yard for the corresponding PCC fillet section contract Item when a PCC fillet section is used.

The type 1 detectable warnings will be measured to the nearest square foot. All costs for furnishing and installing the type 1 detectable warnings including labor, equipment, materials, and incidentals will be paid for at the contract unit price per square foot for "Type 1 Detectable Warnings".

The type 2 detectable warnings will be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding will be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".


			February 14, 2020
	S D D	TYPE 2 CURB RAMP	PLATE NUMBER 651.02
Published Date: 2025	O	(DIRECTIONAL CURB RAMP)	Sheet 3 of 3

STATE OF FOR BIDDING PURPOSES ONLY BOAKOTA

PROJECT SHEET P TAPU(38) 66 70

Plotting Date: 9/4/2024

Rev 09/04/2024 KAO



GENERAL NOTES:

The PCC sidewalk will be constructed in accordance with Section 651 of the Specifications.

*** The cross slope of the sidewalk is designed at 1.5% and the maximum slope allowed is 2% unless specified otherwise in the plans.


The maximum length between expansion joints in the PCC sidewalk is 75 feet.

PCC sidewalk placed adjacent to intersection of roadways will have an expansion joint placed transversely a maximum of 37.5 feet from the intersection, See Plan View,

An expansion joint in the PCC sidewalk will consist of a ½ Inch thick preformed expansion joint filler material placed full depth and width of the PCC sidewalk.

** Large areas of PCC pavement adjacent to the PCC sidewalk may require a different joint treatment than shown in the detail. If a different joint detail is necessary, plans will contain the joint detail and the Contractor will construct the joint treatment in accordance with the plans. February 14, 2020

	S D D	PCC SIDEWALK	PLATE NUMBER 651.75
Published Date: 2025	O		Sheet I of 2




FOR BIDDING PURPOSES ONLY BOAKOTA

STATE OF

PROJECT SHEET P TAPU(38) 67 70

Plotting Date: 9/4/2024

Rev 09/04/2024 KAO



AND SILT TRAP

Sheet 2 of 2

Published Date: 2025

T


FOR BIDDING PURPOSES ONLY BOAKOTA

STATE OF

PROJECT SHEET P TAPU(38) 68 70

Plotting Date: 9/4/2024

Rev 09/04/2024 KAO



GENERAL NOTES:

The type of sediment control device shown is for Illustrative purposes only.

The type of sediment control device used will be one of the types as specified in the plans.

The sediment control device will be placed at the drop injets according to the manufacturer's installation nstructions.

ISOMETRIC VIEW

The sediment control at inlet for type S reinforced concrete drop inlet will be placed at locations stated in the plans or at locations determined by the Engineer.

The Contractor and Engineer will inspect the sediment control device in accordance with the storm water permit. The Contractor will maintain the sediment control device by removing the device, removing accumulated sediment, and resetting the device.

The removed sediment will be placed at a location away from the drop inlet where the sediment will not be washed back into the drop injet or other storm sewer system.

Payment for the "Sediment Control at Type S Drop Inlet" will be based on the minimum length required at the drop inlets. Some of the sediment control devices specified in the plans will have to be longer due to avallable length.

All costs for furnishing, installing, inspecting, maintaining, removing, and resetting the sediment control device at the drop inlet including labor, equipment, and materials will be incidental to the contract unit price per foot for "Sediment Control at Type S Reinforced Concrete Drop Inlet".

February 14, 2020

SDD 0

SEDIMENT CONTROL AT INLETS FOR TYPE S REINFORCED CONCRETE DROP INLETS

PLATE NUMBER 734.11

Sheet I of I

Published Date: 2025


for RCP Type B Installation


FOR BIDDING PURPOSES ONLY BOAKOTA


STATE OF

PROJECT SHEET P TAPU(38) 69 70

Plotting Date: 6/17/2024







Drop Curb for Driveway Approach

T₁ = Thickness shall be equal to the depth of the adjacent pavement but not less than 6" $T_2 = T_T 7/8"$

GENERAL NOTES:

- 1) On PCC pavement a keyway longitudinal joint with tie bars shall be used when curb and gutter is poured separately.
- Curb and gutter shall be constructed using M-6 concrete unless monolithically constructed with the adjacent pavement. In monolithic paving, concrete mix for the curb and gutter may be the same as the adjacent concrete pavement.
- The curb transition length at ADA curb ramps will be dependent on the type of curb ramp being installed. The plans should call out the length of the transitions. Refer to plate 651.02 for additional curb transition information.

Issued: January 2017




450.06

Special

Concrete Curb and Gutter

Specification Reference No. 650


Plate Number 650.01





Notes

- 1. Concrete washout facility shall be installed prior to any concrete placement on site.
- A sign shall be installed adjacent to each washout facility to inform concrete equipment operators to utilize the CWF.
- The concrete washout facility shall be repaired and enlarged or cleaned out as necessary to maintain capacity for wasted concrete.
- When CWF are no longer required for the work, the hardened concrete and materials used to construct the CWF shall be removed and disposed of.
- When the concrete washout facility is removed, the holes, depressions or other ground disturbance shall be backfilled, repaired and stabilized.



Cross Sectional View

Revised: December 2008



Concrete Washout Facility

Specification Reference No. 734

Plate Number 734.28 FOR BIDDING PURPOSES ONLY SOUTH YDAKOTA

 PROJECT
 SHEET
 TOTAL SHEETS

 P TAPU(38)
 70
 70

Plotting Date: 6/17/2024