

# STATE OF SOUTH DAKOTA <u>DEPARTMENT OF TRANSPORTATION</u> PLANS FOR PROPOSED **PROJECT NH-P 0013(169) SD HWYS 28, 26 & 45**

US HWY 14 HAND & CLARK COUNTIES ROUT & SEAL PCN 09KL



	STATE OF	PROJECT	SHEET	TOTAL
	SOUTH DAKOTA	NH-P 0013(169)	1	12
	Plotting I	Date: 01/06/2025		

# **Index of Sheets**

Sheet: 1-4	Title Sheet & Layout Map
Sheet: 5-6	Estimate of Quantities and
	Environmental Commitments
Sheet: 7	Plan Notes
Sheet: 8	Typical Reservoir Drawings
Sheet: 9-10	Standard Plates
Sheet: 11	Traffic Control
Sheet: 12	Typical Pavement Marking



ILE - ... \CLRK@9KL\DESIGN\TITLE @9KL.DC

# SD HIGHWAY 28 SEGMENT #1 CLARK COUNTY LENGTH: 11.956 MILES



ŚEGMENT #1 BEGIN PROJECT Sta. 0+00 MRM 295.98+ 0.000 MILEAGE 25.946



PROJECT LENGTH								
Gross Length:	11.956 Miles							
Deductions:	0.00'	0.000 Miles						
Net Length:	63,127.7'	11.956 Miles						

STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS
SOUTH DAKOTA	NH-P 0013(169)	2	12
Plotting (	Date: 01/06/2025		



SEGMENT #1 END PROJECT Sta. 631+27.7 MRM 307.00 + 0.957 MILEAGE 37.902



TLE - ... NDESIGNNHWY 28 SEGMENT 1.DC





PROJECT LENGTH							
Gross Length: 75577.48' 14.314 Miles							
Deductions:	1720.00'	0.326 Miles					
Net Length:	73857.48'	13.988 Miles					

PLOTTED FROM - TRHUINTØ4



SEGMENT #3 SD 26 Sta. 854+71.85 MRM 253.85+0.000 MILEAGE 23.728

											/												
=	-	205 ¥∧E	- E	24	25	۴ ۴	-	<u>∾</u>	Ē	24	25	36			E E	24	25	36	-		Ē	24	
_	15 2			23	58	35	N	=	0.1	23	26	35	~	=	4	23	26	35	~		4	23	
=	4- 	01	<u>s</u>	52	27	34	ν Γ	01	15	22	27	34	۳ ۲	01	- 15 ,	22	27 6.4	ы 4	m	0	-5	22	
	359 AVE	σ 		5	88	33	4	6	99	~		33	4	σ	9	5	58	33	4	 б <sup>-</sup>	<u>ب</u>	21	

SEGMENT #3 SD 45 END PROJECT Sta. 1335+54.59 MRM 137.72+ 0.000 MILEAGE 103.890

SEGMENT #3 SD 26 STA 907+47.73 MRM 252.85+ 0.000 MILEAGE 22.728

 DESIGN\_DESIGNATION

 AADT (2023)
 842

 AADT (2043)
 1121

 DHV
 124

 D
 51

 DHV T%
 10.3%

 AADT T%
 22.6%

 V
 65MPH

PROJECT LENGTH								
Gross Length: 133,554.6' 25.294 Miles								
Deductions:	0.00'	0.000 Miles						
Net Length:	133,554.6'	25.294 Miles						

PLOTTED FROM - TRHUINT@4



	Estimate of Quantitie	STATE OF SOUTH DAKOTA Plotting D	PROJECT NH-P 0013(169) ote: 03/04/2024	SHEET NO. 5	TOTAL SHEETS 12		
BID ITEM	ITEM	QUANTITY	UNIT				
009E0010	Mobilization	Lump Sum	LS				
350E0010	Asphalt Concrete Crack Sealing	53,000	Lb				
633E1200	High Build Waterborne Pavement Marking Paint, White	1,693	Gal				
633E1205	High Build Waterborne Pavement Marking Paint, Yellow	316	Gal				
634E0010	Flagging	200.0	Hour				
634E0020	Pilot Car	100.0	Hour				
634E0110	Traffic Control Signs	210.0	SqFt				
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS				
	Table of Quantities (For Info	rmation Only)					

		Tab	le of Quantities (For Information O	nly)	
ITEM	Segment 1 – SD 28	Segment 2 – US 14	Segment 3 – SD 45 & SD 26	QUANTITY	UNIT
Mobilization	Lump Sum	Lump Sum	Lump Sum	Lump Sum	LS
Asphalt Concrete Crack Sealing	24732	851	27417	53000	Lb
High Build Waterborne Pavement	538	-	1155	1693	Gal
Marking Paint, White					
High Build Waterborne Pavement	118	-	198	316	Gal
Markings Paint, Yellow					
Flagging	80	-	120	200	Hour
Pilot Car	40	-	60	100	Hour
Traffic Control Signs	105.0	-	105.0	210.0	SqFt
Traffic Control, Miscellaneous	Lump Sum	Lump Sum	Lump Sum	Lump Sum	LS

### **SPECIFICATIONS**

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications and Special Provisions as included in the Proposal.

#### **ENVIRONMENTAL COMMITMENTS**

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: <https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf >

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

#### COMMITMENT B: FEDERALLY THREATENED, ENDANGERED, AND PROTECTED SPECIES

#### **COMMITMENT B2: WHOOPING CRANE**

The Whooping Crane is a spring and fall migratory bird in South Dakota that is about 5 feet tall and typically stops on wetlands, rivers, and agricultural lands along their migration route. An adult Whooping Crane is white with a red crown and a long, dark, pointed bill. Immature Whooping Cranes are cinnamon brown. While in flight, their long necks are kept straight and their long dark legs trail behind. Adult Whooping Cranes' black wing tips are visible during flight.

#### Action Taken/Required:

Harassment or other measures to cause the Whooping Crane to leave the site is a violation of the Endangered Species Act. If a Whooping Crane is sighted roosting in the vicinity of the project, borrow pits, or staging areas associated with the project, cease construction activities in the affected area until the Whooping Crane departs and immediately contact the Project Engineer. The Project Engineer will contact the Environmental Office so that the sighting can be reported to USFWS.

#### COMMITMENT B4: BALD EAGLE

Bald eagles are known to occur in this area

#### Action Taken/Required:

If a nest is observed within one mile of the project site, notify the Project Engineer immediately so that he/she can consult with the Environmental Office for an appropriate course of action.

#### **COMMITMENT E: STORM WATER**

Construction activities constitute less than 1 acre of disturbance.

#### Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

#### COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

#### Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

Construction and/or demolition debris consisting of concrete, asphalt 1. concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, "No Dumping Allowed".

Concrete and asphalt concrete debris may be stockpiled within view 2. of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

#### **COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES**

The SDDOT has obtained concurrence with the State Historical Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

#### Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another gualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow 30 Days from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 100 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified.

The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS
DAKOTA	NH-P 0013(169)	6	12
Plotting [	)ate: 03/04/2024		

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

#### **SEQUENCE OF OPERATIONS**

The Contractor will submit a sequence of operations for approval two weeks prior to the preconstruction meeting. If changes to the sequence of operations are proposed during the project, these must be submitted for review a minimum of one week prior to potential implementation. Approval for changes to the sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work.

#### **GENERAL TRAFFIC CONTROL**

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices, including delineation, will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost will be replaced by the Contractor at no cost to the State.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation.

All construction operations will be conducted in the general direction of traffic movement.

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Fixed location signing placed more than 4 calendar days prior to the start of construction will be covered or laid down until the time of construction. The covers must be approved by the Engineer prior to installation. The cost of materials, labor, and equipment necessary to complete this work will be incidental to other contract items. No separate payment will be made.

All fixed location signs, sign posts, and breakaway bases will be removed within 7 calendar days following pavement marking.

Traffic will be maintained on the driving lanes. Use of the shoulder as a driving lane will not be permitted. Any damage to the shoulder due to rerouted traffic or Contractor's equipment will be repaired at no expense to the Department.

#### **FLAGGING**

Operations will be conducted so that the traveling public will not have to wait longer than 15 minutes at the flagger station.

It is required that the flaggers and pilot car operators be able to communicate with one another. If an emergency vehicle needs to pass through the project, the Contractor will be required to expedite traffic movement. All costs associated with this will be incidental to the contract unit price per hour for "Flagging"

#### **CONSTRUCTION REQUIREMENTS**

Shoulder bevel slopes greater than 3/8 inch per foot will not be routed and sealed unless directed by the Engineer.

The contract unit price per pound for Asphalt Concrete Crack Sealing will be nonnegotiable regardless of changes in quantity.

#### ASPHALT CONCRETE AGGREGATES

SDDOT asphalt mixes are known to contain crushed ledge rock such as granite. The Contractor can expect to encounter various percentages of crushed ledge rock both in larger aggregates and the fines. For information only, all segments are known or believed to contain ledge rock.

#### **ROADWAY CLEANING**

The Contractor will be responsible for removing the router tailings from the roadway surface, including shoulders, intersecting roads, and/or as directed by the Engineer.

Router tailings must be blown entirely off the roadway prior to placement of sealant.

#### PERMANENT PAVEMENT MARKINGS

The Contractor will be required to repaint all existing pavement markings including centerline and edge lines. Traffic Control will be incidental to the Cost of the application. The striper and advance tailing warning vehicle must be equipped with flashing amber lights or advance warning arrow boards. All materials will be applied as per manufacturer's recommendations.

#### HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT

All materials will be applied as per manufacturer's recommendations. High build waterborne pavement marking paint will conform to the supplemental specifications for Section 980.1 B.

Reflective media will consist of glass beads. Reflective media will require a Certificate of Compliance for Certification for each source and lot. Acceptance sampling will not be required.

#### RATES OF MATERIALS FOR HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT

Solid 4" line = 22.5 Gals/Mile Dashed 4" line = 6.2 Gal/Mile Glass Beads = 8 Lbs/Gal.

All cost for materials, labor and equipment necessary to furnish and install the pavement markings will be incidental to the contract unit price for the respective High Build Waterborne Pavement Marking Paint items.

### RETROREFLECTIVITY FOR PAVEMENT MARKING PAINT

The Department may take retroreflectivity readings on the pavement marking lines after 2 days and within 30 days of the line application using either a portable or mobile retroreflectometer that conforms to 30-meter geometry. If the Department chooses to take retroreflectivity readings, three retroreflectivity readings will be taken on each line at each test location. The three readings will be averaged and become the reading for that test location.

If the Department chooses to take retroreflectivity readings, three readings will be taken on the edge lines and lane lines in the direction of application. For combination solid yellow and skip yellow lines for turn lanes and for centerline markings on two-way roadways, three readings will be taken in one direction, the reflectometer will be turned 180 degrees and three more readings will be taken. The six readings for the centerline markings will be averaged and become the test reading for that test location.

If the Department chooses to take readings, the minimum retroreflectivity values will be 275 mc/m2/lux for white and 170 mc/m2/lux for yellow.

#### TRAFFFIC CONTROL SIGNS

Traffic control signs have been included in a table for each route. Payment will only be for those signs used on each route.

#### **COORDINATION OF WORK**

A Pavement Restoration Project on US 14 from Miller to Wessington Springs will take place in the 2025 construction season. Contractor will need to coordinate work with Contractor on PCN 09LC.

#### MOBILE OPERATION

Mobile Operations on Shoulders (Standard Plate 634.04) will be used on segment #2. All costs associated with the traffic control for mobile operation including signs, arrow boards and equipment will be incidental to the contract lump sum price for "Traffic Control, Miscellaneous". Contractor will only be allowed to work on one shoulder at a time on Segment #2.

A	R
	•••

STATE OF	PROJECT	SHEET	TOTAL SHEETS	
SOUTH DAKOTA	NH-P 0013(169)	7	12	
Plotting [				



\* Inert compressible material required for cracks 3/8" or more in width. The backer rod will be a nonmoisture absorbing, resilient material approximately 25 percent larger in diameter than the width of the joint to be sealed. The backer rod will be compatible with the sealant and no bond or reaction will occur between the rod and the sealant.

D & W = 3/4"

Recommended Backer Rod				
Diameter fo	r Joint Width			
Joint Width	Rod Diameter			
3/16" - 1/4"	3/8''			
1/4" - 3/8"	1/2"			
3/8" - 1/2"	5/8''			
5/8" - 3/4"	7/8''			
3/4" - 7/8" 1"				
7/8" - 1"	1 1/4"			
1" - 1 1/4"	1 1/2"			
1 1/4" - 1 1/2"	2"			

STATE OF	PROJECT	SHEET NO.	TOTAL Sheets
SOUTH DAKOTA	NH-P 0013(169)	8	12
Plotting [	)ate: 03/04/2024	1	

PLOT NAME - 1

<ul> <li>*In situations where multiple work locations in a limited distance make it practical to place stationary signs, the distance between the advance warning sign and the work should not exceed 5 miles.</li> <li>The ROAD WORK NEXT xx MILES sign may be used instead of the ROAD WORK AHEAD sign if the work locations occur over a distance of more than 2 miles.</li> <li>Arrow board is required for intermittently and continuously moving mobile operations when work exceeds 1 hour.</li> <li>**If the work space is on a divided highway, an advance warning sign should also be placed on the left side of the directional roadway.</li> </ul>		
In situations where the distance between the advance warning signs and the work is 2 miles to 5 miles, a Supplemental Distance plaque should be used with the ROAD WORK AHEAD sign. All costs associated with the traffic control for mobile operation including signs, arrow boards and equipment will be incidental to the contract lump sum price for "Traffic Control, Miscellaneous".	Image: State of the state o	Arrow Board ing Caution Mode d Attenuator inal)
Published Date: 2025	MOBILE OPERATIONS ON SHOULDERS	January 22, 2021 PLATE NUMBER 634.04 Sheet 1 of 1





Posted	Spacing of	Spacing of	of			1	
Speed	Advance Warning	Channelizi	ina	War	nina sian	sequence —	
Prior to	Signs	Devices		in or	posite di	rection same	
Work	(Foot)	(Feet)	,	ae h			
				as D			' // . /
	(A)						
0 - 30	200	25				×.	
35 - 40	350	25				/ /•	
45	500	25					///_
50	500	50				//. <i></i> ///	
55	750	50					
60 - 65	1000	50				│	▼ <u>∕</u> <u>∕                                 </u>
	Flagger				/	′ /	
<b>–</b>	0						
-	Channelizing De	vice					
For low-	volume traffic situa	itions					Not
with sho	rt work zones on st	traight					
roadway	s where the flagge	r is visible					$\langle \mathbf{v} \rangle$
to road u	isers approaching	from both			CA >	′ ↘/ /	autter co
direction	s, a single flagger	may be use	ed.	//	♥∥ 🌾		C & C & C & C & C & C & C & C & C & C &
	-,			//	H	$/ \wedge$	- <u>J</u> .
The ROA	AD WORK AHEAD	and the El	ND ROAD	//	H		
WORK s	igns may be omitte	ed for short	t		4	1 /	
duration	operations (1 hour	r or less).			Π /		
		,			ff	1 2 P	
For tack	and/or flush seal of	operations,			<b>#</b>	ka)	
when fla	ggers are not being	g used, the		ų.	₩	er y	
FRESH	ÖİL sign (W21-2) v	will be displ	ayed		■_	ab K	•
n advan	ce of the liquid asp	phalt areas.			╢╴ <b>┛</b> ╸│		$\land$
				50			
Flashing	warning lights and	d/or flags			║_┛	+• — ↓ ⊐`ਛ 〈'	
may be i	used to call attention	on to the			■		$\times \Pi \mathscr{A}^{\Lambda}$
advance	warning signs.					Ō /	
The chai	nnelizing devices v	will be drum	ns				FEET
or 42" co	ones.						W16-2P
<b>.</b>							(Optional)
Channel	izing devices are n	not required	1				
along the	e centerline adjace	ent to work					$\wedge$
area whe	en pilot cars are ut	ilized for					$/ \setminus$
escorting	g traffic through the	e work					ONE LANE
area.	G20-2						
	ROAD WORK	1					AIRAD
	END						$\wedge \gamma_{s}$
			7				
			*				^
Channeli	izing devices and f	flaggers wil					$ \land $
be used	at intersecting road	ds to					(ROAD
control ir	ntersecting road tra	affic as					WORK >
required.							AHEAD
							V AN
The buffe	er space should be	e extended					~
so that th	ne two-way traffic t	aper is					
placed b	etore a horizontal (	or vertical					
curve to	provide adequate	sight					
	tor the flagger and	d queue					
distance							
distance of stoppe	ed vehicles.						
distance of stoppe	ed vehicles. th of A may be add	illeted to					
distance of stoppe The leng	ed vehicles. th of A may be adj anditions	usted to		'			
distance of stoppe The leng	ed vehicles. th of A may be adj onditions.	justed to					January 22, 202
distance of stoppe The leng fit field co	ed vehicles. th of A may be adj onditions.	justed to	S		'		January 22, 202 PLATE NUMBER
distance of stoppe The leng fit field co	ed vehicles. th of A may be adj onditions.	usted to	S D				January 22, 202 PLATE NUMBER
distance of stoppe The leng	ed vehicles. th of A may be adj onditions.	usted to	S D D	LANE CLO	SURE WI	TH FLAGGER PROVIDEL	January 22, 202 PLATE NUMBER 634.23
distance of stoppe The leng fit field co	ed vehicles. th of A may be adj onditions. <b>bliched Date<sup>,</sup> 2025</b>	justed to	S D D O	LANE CLO	SURE WI	TH FLAGGER PROVIDEL	January 22, 202 PLATE NUMBER 634.23

STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS			
DAKOTA	NH-P 0013(169)	10	12			
Plotting Date: 03/04/2024						

PLOT NAME - 1

# SEGMENT #1 (SD 28)

			CONVENTIO	NAL ROAD	
SIGN CODE	SIGN DESCRIPTION	NUM BER	SIGN SIZE	SQFT PER SIGN	SQFT
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0
W20-4	ONE LANE ROAD AHEAD	2	48" x 48"	16.0	32.0
W20-7	FLAGGER (symbol)	2	48" x 48"	16.0	32.0
G20-2	END ROAD WORK	2	36" x 18"	4.5	9.0
			VENTIONAL CONTROL SI	ROAD IGNS SQFT	105.0

# SEGMENT #3 (SD 45/26)

		CONVENTIONAL ROAD			
SIGN CODE	SIGN DESCRIPTION	NUM BER	SIGN SIZE	SQFT PER SIGN	SQFT
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0
W20-4	ONE LANE ROAD AHEAD	2	48" x 48"	16.0	32.0
W20-7	FLAGGER (symbol)	2	48" x 48"	16.0	32.0
G20-2	END ROAD WORK	2	36" x 18"	4.5	9.0
CONVEN TRAFFIC CON		VENTIONAL CONTROL SI	ROAD IGNS SQFT	105.0	

PAR	

STATE OF SOUTH DAKOTA	PROJECT	SHEET NO.	TOTAL SHEETS				
	NH-P 0013(169)	11	12				
Plotting Date: 03/04/2024							

LOT NAME - 1



		STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS
		DAKOTA	NH-P 0013(169)	12	12
		Plotting (	)ate: 03/04/2024		
$\rightarrow$					
					1
					i
	×				
		EDG	E LINE		
		EDG	BE LINE		
	<i>¥</i>				
Ь					
q					
A					

#### FURNISHING AND APPLYING HIGH BUILD WATERBORNE PAVEMENT MARKING PAINT

1. The approximate paint application rates will be as follows:

Undivided Roadway

Dashed 4" Line 6.2.Gallons/Pass-Mile

Solid 4" Line 22.5 Gallons/Pass-Mile

The typical pavement markings as shown on this sheet will be applied throughout the entire length of the project.

3. Exact location of the NO PASSING ZONE lines will be determined in the field by the Engineer. A dash of white paint will mark the beginning and end of all no passing zones. NO PASSING ZONE signs and the ending post in fence lines, if present, will not be used as the beginning and ending NO PASSING ZONE lines.

 Traffic Control will be incidental to the cost of application. The striper and advance or trailing warning vehicle will be equipped with flashing amber lights or advance warning arrow panel.