

PROJECT LOCATION

STATE OF SOUTH DAKOTA **FOR BIDDING PURPOSES ONLY**
 DEPARTMENT OF TRANSPORTATION
 PLANS FOR PROPOSED



PROJECT BRF-B 6136(01)
MINER COUNTY

STRUCTURE REPLACEMENT AND APPROACH GRADING
 STRUCTURE No. 49-093-020
 PCN 09MC

INDEX OF SHEETS

PROJECT	1	49
STATE OF SOUTH DAKOTA	BRF-B 6136(01)	
SHEET	1	49
TOTAL SHEETS		

- SHEET 1: TITLE SHEET
- SHEET 2-8: ESTIMATE OF QUANTITIES & NOTES
- SHEET 9-12: SWPPP
- SHEET 13-15: TYPICAL SECTION
- SHEET 16: TRAFFIC CONTROL
- SHEET 17: EROSION CONTROL
- SHEET 18: SURVEY DATA & EASEMENTS
- SHEET 19-20: PLAN & PROFILE
- SHEET 21-28: STANDARD PLATES
- SHEET 29-39: STRUCTURE SHEETS
- SHEET 40-49: CROSS SECTIONS



1

February 4, 2026

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	BRF-B 6136(01)	2	49

REV BDS 12-30-2025

GRADING

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
009E3230	Grade Staking	0.200	Mile
009E3250	Miscellaneous Staking	0.200	Mile
009E3280	Slope Staking	0.200	Mile
009E3290	Structure Staking	1	Each
009E3301	Engineer Directed Surveying/Staking	40.0	Hour
009E4200	Construction Schedule, Category II	Lump Sum	LS
100E0100	Clearing	Lump Sum	LS
110E0500	Remove Pipe Culvert	127	Ft
110E1010	Remove Asphalt Concrete Pavement	3,323.0	SqYd
110E5010	Salvage Delineator	19	Each
110E5020	Salvage Traffic Sign	2	Each
120E0010	Unclassified Excavation	5,535	CuYd
120E0600	Contractor Furnished Borrow Excavation	445	CuYd
230E0010	Placing Topsoil	1,990	CuYd
450E4758	18" CMP 14 Gauge, Furnish	120	Ft
450E4760	18" CMP, Install	120	Ft
450E4768	24" CMP 14 Gauge, Furnish	36	Ft
450E4770	24" CMP, Install	36	Ft
450E5406	18" CMP Safety End, Furnish	4	Each
450E5407	18" CMP Safety End, Install	4	Each
450E5410	24" CMP Safety End, Furnish	2	Each
450E5411	24" CMP Safety End, Install	2	Each
634E0110	Traffic Control Signs	109.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0275	Type 3 Barricade	8	Each
634E1002	Detour and Restriction Signing	88.0	SqFt
734E0010	Erosion Control	Lump Sum	LS
734E0102	Type 2 Erosion Control Blanket	10,335	SqYd
734E0154	12" Diameter Erosion Control Wattle	900	Ft
734E0325	Surface Roughening	1.1	Acre
734E0510	Shaping for Erosion Control Blanket	1,700	Ft
734E0604	High Flow Silt Fence	800	Ft
734E0610	Mucking Silt Fence	56	CuYd
734E0620	Repair Silt Fence	200	Ft
734E0900	Temporary Diversion Channel for Fish Passage	1	Each

STRUCTURE No. 49-093-020

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
250E0030	Incidental Work, Structure	Lump Sum	LS
420E0200	Structure Excavation, Box Culvert	104	CuYd
421E0200	Box Culvert Undercut	299	CuYd
460E0120	Class A45 Concrete, Box Culvert	245.1	CuYd
480E0100	Reinforcing Steel	37,970	Lb
700E0210	Class B Riprap	67.3	Ton
831E0110	Type B Drainage Fabric	81	SqYd

ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: <https://dot.sd.gov/media/3677d319/EnvironmentalProceduresManual.pdf>

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT A: AQUATIC RESOURCES

COMMITMENT A2: STREAMS

All efforts to avoid and minimize stream impacts from the project have resulted in approximately 0.21 acres of stream (includes temporary and permanent) becoming impacted. Refer to plans for location and boundaries of the impacted streams.

Table of Impacted Streams

Stream Name	Station	Perm. Impact Left (Acres)	Perm. Impact Right (Acres)	Temp. Impact Left (Acres)	Temp. Impact Right (Acres)	Total Impact (Acres)
Rock Creek	17+10.15	0.046	0.046	0.066	0.055	0.21

Action Taken/Required:

Final compensatory mitigation requirements will be determined by the USACE during the Section 404 permitting process. It is anticipated that SDDOT will acquire up to 0.736 credits from the Ducks Unlimited stream mitigation bank site or In-Lieu Fee program to mitigate permanent impacts.

The Contractor will notify the Project Engineer if additional easement is needed to complete work adjacent to any stream. The Project Engineer will obtain an appropriate course of action from the Environmental Office before proceeding with construction activities that affect any streams beyond the work limits and easements shown in the plans.

COMMITMENT B: FEDERALLY THREATENED, ENDANGERED, AND PROTECTED SPECIES

COMMITMENT B1: CONSTRUCTION PRACTICES FOR STREAMS INHABITED BY THE TOPEKA SHINER

The SDDOT Environmental Office has identified the following as Topeka Shiner streams.

Table of Topeka Shiner Streams

Station	Stream Name	Ordinary High-Water Elevation
17+10.15	Rock Creek	1,460.46 feet

Action Taken/Required:

The Contractor will adhere to the "Special Provision for Construction Practices in Streams Inhabited by the Topeka Shiner".

Stream turbidity will be monitored during all stages of the project. Turbidity measurements are to be taken in conjunction with normal storm water inspections but can also be taken at the Project Engineer's discretion during construction activities that may result in increased turbidity (e.g., placing riprap or installing a coffer dam).

Prior to the pre-construction meeting the Contractor will produce and provide the SDDOT Environmental Office a comprehensive Construction Plan that includes all products, materials, and methods of installation and removal for temporary water barriers, cofferdams, and diversion channels including dewatering, handling, storage, and disposal of excavated material and pumped effluent throughout all phases of construction, including post-construction stabilization. Work will not proceed on any of the streams identified in the Table of Topeka Shiner Streams without approval of the Construction Plan by the SDDOT Environmental Office. Upon plan approval, the Construction Plan will be amended to the SWPPP.



FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	sheet	total sheets
	BRF-B 6136(01)	3	49

COMMITMENT C: WATER SOURCE

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species (AIS) positive waters within South Dakota without prior approval from the SDDOT Environmental Office. To prevent and control the introduction and spread of invasive species into the project vicinity, all equipment will be power washed with hot water ($\geq 140^{\circ}\text{F}$) and completely dried for a minimum of 7 days prior to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the possession and transport of AIS; therefore, all attached dirt, mud, debris and vegetation must be removed and all compartments and tanks capable of holding standing water must be drained. This includes, but is not limited to, all equipment, pumps, lines, hoses and holding tanks.

The Contractor will not withdraw water directly from streams of the James, Big Sioux, and Vermillion watersheds without prior approval from the SDDOT Environmental Office.

Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Agriculture and Natural Resources (DANR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of water sources impacted by Aquatic Invasive Species in South Dakota can be accessed at:

< <https://sdleastwanted.sd.gov/maps/default.aspx> >

< South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species: <https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04> >

COMMITMENT D: WATER QUALITY STANDARDS

COMMITMENT D1: SURFACE WATER QUALITY

Rock Creek is classified as warm water, marginal fishery with a total suspended solids standard of less than 150 mg/L 30-day average, less than 263 mg/L daily maximum.

This project may be in the vicinity of multiple streams and wetlands. These waters are considered waters of the state and are protected under Administrative Rules of South Dakota (ARSD) Chapter 74:51. Special construction measures may have to be taken to ensure that this water body is not impacted.

Action Taken/Required:

The Contractor is advised that the South Dakota Surface Water Quality Standards, administered by the South Dakota Department of Agriculture and Natural Resources (DANR), apply to this project. Special construction measures will be taken to ensure the above standard(s) of the surface waters are maintained and protected.

COMMITMENT D2: SURFACE WATER DISCHARGE

The DANR General Permit for Temporary Discharge is required for temporary dewatering and discharges to waters of the state. The effluent limit for total suspended solids will be 90 mg/L 30-day average. The effluent limit applies to discharges to all waters of the state except discharges to waters classified as cold water permanent fish life propagation waters according to the ARSD 74:51:01:45. For discharges to waters of the state classified as cold water permanent fish life propagation waters, the effluent limit for total suspended solids will be 53 mg/L daily maximum.

The permittee has the option of completing effluent testing or implementing a pollution prevention plan for compliance with this permit. If the permittee develops a pollution prevention plan instead of total suspended solids sampling, the plan must be developed and implemented prior to discontinuing total suspended solids sampling. Refer to Section 4.0 of the permit. If any pollutants are suspected of being discharged, a sample must be taken for those parameters listed in Section 3.4 of the permit.

Refer to Commitment D1: Surface Water Quality for stream classification.

Action Taken/Required:

If construction dewatering is required and this project is currently covered under a General Permit for Stormwater Discharges Associated with Construction Activities, the contractor will need to submit the dewatering information to the SDDANR using the following form:

< https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR_AddTempInfoFillable.pdf >

The Contractor will provide a copy of the approved permit or the submitted dewatering information to the Project Engineer prior to proceeding with any dewatering activities. The approved permit or submitted dewatering information must be kept on-site and as part of the project records.

Effluent monitoring, as a result of dewatering activities, will be summarized for each month and recorded on a separate Discharge Monitoring Report (DMR) and submitted to DANR monthly. Additional information can be found at: < <https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/swdpermitting/Ereporting.aspx> >

COMMITMENT E: STORM WATER

Construction activities constitute 1 acre or more of earth disturbance and/or work in a waterway.

Action Taken/Required:

The DANR General Permit for Stormwater Discharges Associated with Construction Activities is required for construction activity disturbing one or more acres of earth and work in a waterway. The SDDOT is the owner of this permit and will submit the NOI to DANR 15 days prior to project start in order to obtain coverage under the General Permit. Work can begin once the DANR letter of approval is received.

The Contractor must adhere to the "Special Provision Regarding Storm Water Discharges to Waters of the State."

The Contractor will complete the DANR Contractor Certification Form prior to the pre-construction meeting. The form certifies under penalty of law that the Contractor understands and will comply with the terms and conditions of the permit for this project. Work may not begin on this project until this form is signed and submitted to DANR.

The form can be found at:

< https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/docs/DANR_CGPA AppendixCCA2023Fillable.pdf >

The Contractor is advised that permit coverage may also be required for off-site activities, such as borrow and staging areas, which are the responsibility of the Contractor.

Storm Water Pollution Prevention Plan

The Storm Water Pollution Prevention Plan (SWPPP) will be developed prior to the submittal of the NOI and will be implemented for all construction activities for compliance with the permit. The SWPPP must be kept on-site and updated as site conditions change. Erosion control measures and best management practices will be implemented in accordance with the SWPPP.

The DOT 298 Form will be used for site inspections and to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents and retained for a minimum of three years.

The inspection will include disturbed areas of the construction site that have not been finally stabilized, areas used for storage materials, structural control measures, and locations where vehicles enter or exit the site. These areas will be inspected for evidence of, or the potential for, pollutants entering the drainage system. Erosion and sediment control measures identified in the SWPPP will be observed to ensure that they are operating correctly, and sediment is not tracked off the site.

Information on storm water permits and SWPPPs are available on the following websites:

SDDOT: < <https://dot.sd.gov/doing-business/environmental/stormwater> >

DANR: < <https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/default.aspx> >

EPA: < <https://www.epa.gov/npdes> >



FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	BRF-B 6136(01)	4	49

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, "No Dumping Allowed".

2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historic Preservation Office (SHPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 150 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

SHPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

COMMITMENT N: SECTION 404 PERMIT

The SDDOT has obtained a Section 404 Permit from the USACE for the permanent actions associated with this project.

Action Taken/Required:

The Contractor will comply with all requirements contained in the Section 404 Permit.

The Contractor will also be responsible for obtaining a Section 404 Permit for any dredge, excavation, or fill activities associated with material sources, storage areas, waste sites, and Contractor work sites outside the plan work limits that affect wetlands, floodplains, or waters of the United States.

SEQUENCE OF OPERATIONS

The Contractor will use the following sequence of operations:

1. Install temporary traffic control signs as shown on the plans.
2. Install erosion control procedures and notify County to remove fence and install temporary fence.
3. Deconstruct and remove existing structure.
4. Undercut box culvert.
5. Construct new structure.
6. Grading operations, place topsoil, install riprap and final erosion control.
7. Notify County to install final surfacing, permanent signing, and permanent fence.
8. Remove temporary traffic control and open the roadway to through traffic.
9. Permanent seeding.
10. Complete miscellaneous cleanup under traffic.

Contractor requests to deviate from the sequence of operations will be submitted in writing to the Engineer for review. Approval of an alternate sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work. An alternate sequence will be submitted for review a minimum of two weeks prior to potential implementation.

COUNTY RESPONSIBILITIES

Miner County will be responsible for the following at no cost to the Contractor:

1. Right of way temporary and permanent easements.
2. Coordination of any utility adjustments.
3. Removal of existing fencing, Furnish and install temporary and/or permanent fencing.
4. Furnish and install final surfacing and pavement marking.
5. Furnish and install new permanent signing.
6. Remove silt fence and erosion control wattles in permanently seeded areas.
7. Remove salvaged items.
8. Mitigation for aquatic resources.



FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT BRF-B 6136(01)	SHEET	TOTAL SHEETS
		5	49

GENERAL MAINTENANCE OF TRAFFIC

The Contractor will maintain access to any field and farm entrances within the project limits throughout the duration of construction. All costs associated with the foregoing work will be incidental to the contract lump sum price for "Traffic Control, Miscellaneous".

GRADING OPERATIONS

Water for Embankment is estimated at the rate of 10 gallons of water per cubic yard of Embankment minus Waste. The estimated quantity of Water for Embankment is 20 MGal. No separate payment will be made for the Water for Embankment and all costs associated will be incidental to the contract unit price per cubic yard of "Unclassified Excavation".

The estimated cubic yards of excavation and/or embankment required to construct outlet ditches, ditch blocks, and approaches are included in the earthwork balance notes on the profile sheets.

Special ditch grades and other sections of the roadway different than the typical section(s) will be constructed to the limits shown on the cross sections. If significant changes to the cross sections are necessary during construction, the Engineer will contact the Designer for the proposed change.

Generally, all shallow inlet and outlet ditches as noted on the plan sheets will be cut with a 10-foot wide bottom with 5:1 backslopes. However, the Engineer may direct the Contractor to adjust the ditch width for proper alignment with the drainage structure.

Temporary fence and/or permanent fence will be placed ahead of the grading operation unless otherwise directed by the Engineer.

Compaction of earth embankment and box culvert backfill material will be governed by the Specified Density Method.

UTILITIES

The Contractor will be aware that the existing utilities shown in the plans were surveyed prior to the design of this project and might have been relocated or replaced by a new utility facility prior to construction of this project, might be relocated or replaced by a new utility facility during the construction of this project, or might not require adjustment and may remain in its current location. The Contractor will contact each utility owner and confirm the status of all existing and new utility facilities.

Location	Utility	Owner	Phone Number
11+40.87	to	Underground Communications	Alliance (605) 594-6411
22+31.42 Lt			
11+40.87	to	Overhead Electric	Central Electric (605) 996-7516
22+31.42 Rt			
11+40.87	to	Underground Water	Kingsbrook Rural Water District (605) 983-5074
22+31.42 Lt			

TABLE OF TEMPORARY DIVERSION CHANNEL FOR FISH PASSAGE

The Contractor will construct a temporary diversion channel in accordance with standard plate 734.30 at the locations listed in the following table:

Station	Quantity (Each)
17+10.15	1
Total:	1

SHRINKAGE FACTOR:

Embankment plus 35%

EARTHWORK BALANCE:

Excavation is the quantity of Unclassified Excavation less the quantity of topsoil, excavation for RCBC installation, and asphalt surfacing.

Other excavation includes the excavation for Class B Riprap (49 CuYd) and Box Culvert Undercut (299 CuYd).

These quantities are for informational purposes only, compensation for these is accounted for within the various bid items. These quantities include excavation and embankment to the catch point on the inslopes from the top of the subgrade in cut sections.

Excavation*	2,285	CuYd	Embankment	1,451	CuYd
Waste	326	CuYd	35% Shrinkage	508	CuYd
Total	1,959			1,959	CuYd

*Asphalt pavement removal volume subtracted from gross excavation quantity.

The Contractor may, at the discretion of the Engineer, use the material from other excavation in the inslopes and as sub-base with the condition that said material meets all requirements as set forth in the Standard Specifications for Roads and Bridges, 2015 Edition.

It is assumed (for the purpose of earthwork balance) that the Contractor will not be able to use any of the material from Other Excavation and will have to waste the material at (a) site(s) provided by the Contractor and approved by the Engineer. All cost for labor, materials, and equipment necessary to waste material as well as restoration of the waste site(s) will be incidental to the contract unit price per cubic yard of "Unclassified Excavation."

TABLE OF UNCLASSIFIED EXCAVATION

	(CuYd)
Excavation	2,285
Topsoil	1,990
Excavation for RCBC Installation	1,260
Total Unclassified Excavation:	5,535

PROCEDURES FOR DETERMINING UNCLASSIFIED EXCAVATION QUANTITY

Plan quantities will be used for final payment, the Unclassified Excavation quantity will be used for final payment and the plans quantity of Topsoil and removal of surfacing items shown in the plans will not be adjusted according to field measurements.

The following paragraphs are general earthwork information in regard to computing the Unclassified Excavation quantity.

The Topsoil quantity in the Placing Topsoil note will be used for final payment with no adjustment for final measurements. The quantity of Topsoil from the cuts will be paid for twice as Unclassified Excavation, as it will be in both the Excavation and Topsoil quantities. This will be full compensation for Excavation, which includes necessary undercutting to provide space for placement of topsoil.

The volume of in place asphalt surfacing removed will NOT be paid for as Unclassified Excavation.

The Excavation quantities from individual balances and the table above have been reduced by the volume of in place asphalt pavement that will be removed.

The estimated quantity of 494 cubic yards of asphalt pavement removed from the cut sections has been subtracted from the Unclassified Excavation quantity for final payment. The quantity of asphalt pavement from cut sections subtracted from the Unclassified Excavation quantity will be plans quantity and will not be adjusted according to field measurements.

CONTRACTOR FURNISHED BORROW EXCAVATION

The Contractor will provide a suitable site for Contractor furnished borrow excavation material. The Contractor is responsible for obtaining all required permits and clearances for the borrow site. The borrow material will be approved by the Engineer. The plans quantity for "Contractor Furnished Borrow Excavation" as shown in the Estimate of Quantities will be the basis of payment for this item.

Restoration of the Contractor furnished borrow excavation site will be the responsibility of the Contractor.



FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	BRF-B 6136(01)	6	49

REV BDS 12-30-2025

EXCAVATION FOR REINFORCED CONCRETE BOX CULVERT INSTALLATION

Included in the quantity of "Unclassified Excavation" are 1,260 cubic yards of excavation for installation of reinforced concrete box culverts.

All work necessary to excavate a trench for installation of reinforced concrete box culverts including labor, equipment, and incidentals will be incidental to the contract unit price per cubic yard for "Unclassified Excavation". Payment for excavation of reinforced concrete box culverts will be based only on plans quantity and measurement of these excavation quantities during construction will not be performed.

The excavation quantities for installation of reinforced concrete box culverts are not included with the earthwork balance quantities on the plans profile sheets. The quantities computed for excavation of the reinforced concrete box culverts are based on the limits shown in the drawing below.




TABLE OF EXCAVATION FOR REINFORCED CONCRETE BOX CULVERT INSTALLATION

Station	Quantity (CuYd)
17+10.15	1,260
Total:	1,260

CORRUGATED METAL PIPE

Corrugated metal pipes will have 2 $\frac{2}{3}$ -inch x $\frac{1}{2}$ -inch corrugations for 42-inch and smaller round pipe and 48-inch and smaller arch pipe unless otherwise stated in the plans. Corrugated metal pipes will have 3-inch x 1-inch or 5-inch x 1-inch corrugations for 48-inch and larger round pipe and 54-inch and larger arch pipe unless otherwise stated in the plans.

This project has soils that are highly corrosive to steel. Corrugated metal pipe on this project will be polymer coated 14 gauge steel as specified in the plans. Any required connection bands, elbows, tees, crosses, wyes, reducers, and transitions will also be polymer coated. The connection bands will be 24 inches

wide. All polymer coated corrugated metal pipe and components will be in conformance with AASHTO M245. Riveted pipe will not be allowed.

All damage to the polymer coating will be repaired in accordance with the manufacturer's recommendations prior to installation of the pipe.

All costs associated with the polymer coating including repair of polymer coating will be incidental to the corresponding CMP contract items.

Metal pipe end sections connected to polymer coated CMP will be aluminum-coated (Type 2) in accordance with AASHTO M36 as specified in the plans. All costs associated for gauge, coating, and connections will be incidental to the corresponding CMP End Section contract items.

REMOVAL OF EXISTING ASPHALT CONCRETE PAVEMENT

STA. 11+40 to STA. 22+31

Existing asphalt concrete and/or existing asphalt concrete patch work that was placed above the existing asphalt concrete pavement is included in the quantity for "Remove Asphalt Concrete Pavement". The Contractor will dispose of the asphalt concrete pavement and asphalt concrete at a site approved by the Engineer.

TABLE OF ASPHALT CONCRETE PAVEMENT REMOVAL

Station	to	Station	L/R	Quantity (SqYd)
				L/R
11+40		22+31	L/R	3,323
				Total: 3,323

PLACING TOPSOIL

The thickness will be approximately 4 inches within the right-of-way and 6 inches on temporary easements.

The estimated amount of topsoil to be placed is as follows:

Station	to	Station	Topsoil (CuYd)
11+40		22+31	LT 790
11+40		22+31	RT 1,200
			Total: 1,990

All costs associated with placing the topsoil along areas to be resurfaced will be incidental to the contract unit price per cubic yard for "Placing Topsoil".

The plans quantity for "Placing Topsoil" as shown in the Estimate of Quantities will be the basis for payment for this item.

SALVAGE DELINEATORS AND TRAFFIC SIGNS

All signs, object markers, and delineators listed for salvage in the Table of Salvage Delineators and Traffic Signs will become property of Miner County and will have the existing posts, bases, and signs dismantled and stockpiled within the right-of-way. The Contractor will contact the Miner County Highway Superintendent at (605) 772-4721 for pick-up of salvaged materials. All bolts, nuts, and washers will be placed in individual containers. Wooden posts will be stockpiled separately from steel posts. All signs listed for salvage will be

handled with care so that the signs are not damaged during removal or transport. The Contractor will replace and pay for any salvaged signs damaged in their care.

All costs for labor and equipment necessary to remove, dismantle, and stockpile signs, object markers, and delineators within the right-of-way will be incidental to the contract unit price per each for Salvage Traffic Sign and Salvage Delineator. The quantity of signs, object markers, and delineators to be salvaged is shown in the Table of Salvage Delineators and Signs. The plans quantity is shown as per assembly. Payment for salvaging signs, object markers, and delineators will be paid per assembly at the contract unit price per each for "Salvage Traffic Sign" and "Salvage Delineator".

TABLE OF SALVAGE DELINEATORS AND TRAFFIC SIGNS

Location	Work Item	Salvage Delineator	Salvage Traffic Sign
14+96 – 22' Lt.	Salvage Delineator	1	
14+97 – 22' Rt.	Salvage Delineator	1	
15+44 – 22' Lt.	Salvage Delineator	1	
15+46 – 20' Rt.	Salvage Delineator	1	
15+95 – 20' Lt.	Salvage Delineator	1	
15+95 – 19' Rt.	Salvage Delineator	1	
16+46 – 17' Lt.	Salvage Delineator	1	
16+45 – 17' Rt.	Salvage Delineator	1	
16+92 – 17' Lt.	Salvage Object Marker	1	
16+93 – 17' Rt.	Salvage Object Marker	1	
17+30 – 17' Lt.	Salvage Object Marker	1	
17+31 – 17' Rt.	Salvage Object Marker	1	
17+78 – 17' Lt.	Salvage Delineator	1	
17+77 – 17' Rt.	Salvage Delineator	1	
18+27 – 18' Lt.	Salvage Delineator	1	
18+28 – 19' Rt.	Salvage Delineator	1	
18+79 – 21' Rt.	Salvage Delineator	1	
19+28 – 21' Lt.	Salvage Delineator	1	
19+29 – 24' Rt.	Salvage Delineator	1	
15+94 – 24' Rt.	Salvage Weight Limit Sign		1
18+28 – 25' Lt.	Salvage Weight Limit Sign		1
		Total	19
			2



FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	BRF-B 6136(01)	7	49

EROSION CONTROL

The estimated area requiring erosion control is 3.0 acres with 2.15 acres being seeding and erosion control blanket and 0.85 acres being seeding and mulch. All costs for the erosion control work for furnishing, placing and maintaining erosion control including equipment, labor, seeding, mulching, and mycorrhizal inoculum will be incidental to the contract lump sum price for "Erosion Control".

The estimated area of Erosion Control is calculated from neat line dimensions of disturbed areas. Additional seeding and mulching of disturbed areas from the Contractor's operations are not eligible for additional payment.

Permanent Seeding

The areas to be seeded consist of all newly graded areas within the project limits except for the top of roadways, and top of riprap.

Permanent Seed Mixture will consist of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/Acre)
Western Wheatgrass	Arriba, Flintlock, Rodan, Rosana, Walsh	16
Canada Wildrye	Mandan	2
	Total:	18

Application of fertilizer will not be required on this project.

Mulching

Mulch will consist of grass hay or straw and will be blown on and punched in to a 3 inch depth at the rate of 2 tons per acre on all newly seeded areas.

Mycorrhizal Inoculum

Mycorrhizal inoculum will consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier will provide certification of the fungal species claimed and the live propagule count. The inoculum will include a minimum 25% the fungal species *Rhizophagus intraradices*. The remaining 75% may include other endomycorrhizal fungal species.

All seed will be inoculated by the seed supplier with a minimum of 100,000 live propagules of mycorrhizal fungi per acre. All costs of inoculating the seed will be incidental to the contract lump sum for "Erosion Control".

The Mycorrhizal Inoculum provided will be from the approved product list. The approved product list may be viewed at the following internet site:

<http://apps.sd.gov/HC60ApprovedProducts/main.aspx>

EROSION CONTROL WATTLE

Erosion control wattles for restraining the flow of runoff and sediment will be installed at locations noted in the table and at locations determined by the Engineer during construction. Refer to Standard Plate 734.06 for details.

The Contractor will provide certification that the erosion control wattles do not contain noxious weed seeds. Erosion control wattles will remain on the project to decompose.

An additional quantity of 12" Diameter Erosion Control Wattles has been added to the Estimate of Quantities for temporary erosion and sediment control in highway ditch channels and as an alternative to low flow or high flow silt fence at wetland areas adjacent to the highway.

The erosion control wattle provided will be from the approved product list. The approved product list for erosion control wattle may be viewed at the following internet site:

<http://apps.sd.gov/HC60ApprovedProducts/main.aspx>

TABLE OF EROSION CONTROL WATTLE

Station	Diameter (Inch)	Quantity (Ft)
12+95.69 L	12	40
12+98.54 R	12	40
14+44.91 R	12	40
14+51.54 L	12	40
16+17.01 L	12	40
16+19.89 R	12	40
16+53.51 L	12	140
16+71.08 R	12	140
17+28.78 L	12	100
17+56.00 L	12	100
17+81.00 L	12	40
19+22.74 L	12	40
Additional :		100
		Total: 900

HIGH FLOW SILT FENCE

The high flow silt fence fabric provided will be from the approved product list. The approved product list for high flow silt fence may be viewed at the following internet site:

<http://apps.sd.gov/HC60ApprovedProducts/main.aspx>

High flow silt fence will be placed at the locations noted in the table and at locations that will minimize siltation of adjacent streams, lakes, dams, or drainage areas as determined by the Engineer during construction. Refer to Standard Plate 734.05 for details.

An additional quantity of high flow silt fence has been added to the Estimate of Quantities for temporary sediment control.

TABLE OF HIGH FLOW SILT FENCE

Station	Location	Quantity (Ft)
17+80.88 to 22+31+41	Rt	451
19+02.72 to 22+31.41	Lt	329
	Additional Quantity:	20
	Total:	800

SURFACE ROUGHENING

Surface roughening will be done after topsoil placement and before permanent seeding, and mulching applications. Refer to Standard Plate 734.25 for details.

TABLE OF SURFACE ROUGHENING

Station	Location	Area (Acre)
16+00 to 17+80 R	Inslope/Backslope/Channel	0.4
15+90 to 17+80 L	Inslope/Backslope/ Channel	0.5
	Additional Quantity:	0.2
	Total:	1.1



FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	sheet	total sheets
	BRF-B 6136(01)	8	49

EROSION CONTROL BLANKET

Erosion control blanket will be installed as shown in the plans and at locations determined by the Engineer during construction.

The erosion control blanket provided will be from the approved product list. The approved product list for erosion control blanket may be viewed at the following internet site:

<http://apps.sd.gov/HC60ApprovedProducts/main.aspx>

An additional quantity of Type 2 Erosion Control Blanket has been added to the Estimate of Quantities for temporary erosion control.

TABLE OF EROSION CONTROL BLANKET

Station	Location	Type	Quantity (SqYd)
11+40.87 to 13+26.42	Lt	2	885
11+40.87 to 13+27.46	Rt	2	870
13+42.33 to 16+94.94	Lt	2	2045
13+48.15 to 17+45.39	Rt	2	3155
16+31.51 to 18+87.77	Lt	2	1530
17+25.31 to 22+31.41	Rt	2	1180
19+02.62 to 22+31.41	Lt	2	570
Additional Quantity:		2	100
Total Type 2 Erosion Control Blanket:			10,335

SHAPING FOR EROSION CONTROL BLANKET

The ditches will be shaped for the erosion control blanket as specified on Standard Plate 734.01.

TABLE OF SHAPING FOR EROSION CONTROL BLANKET

Station	Location	(Ft)
11+40 to 17+80	Rt	700
11+40 to 18+90	Lt	1,000
Total:		1,700

TABLE OF CONSTRUCTION STAKING

Grade Staking											
Roadway and Description	Begin Station	End Station	Number of Lanes	Length (Ft)	Length (Mile)	Lane Factor	Sets of Stakes	Grade Staking Quantity (Mile)	Miscellaneous Staking Quantity (Mile)	Slope Staking Quantity (Mile)	Structure Staking Quantity (Each)
222nd St (2 Lanes Asphalt)	11+40.87	22+31.42	2	1,091	0.2	1	1	0.2	0.2	0.2	1
							Totals:	0.2	0.2	0.2	1



STORMWATER POLLUTION PREVENTION PLAN CHECKLIST
*(The numbers left of the title headings are reference numbers to the
GENERAL PERMIT FOR STORM WATER DISCHARGES ASSOCIATED
WITH CONSTRUCTION ACTIVITIES (Stormwater Permit))*

5.3 (2): STAFF TRAINING/SWPPP IMPLEMENTATION

To promote stormwater management awareness specific for this project, the Contractor's Erosion Control Supervisor should provide correspondence of how the SWPPP will be implemented. The Contractor's Erosion Control Supervisor is responsible for providing this information at the preconstruction meeting, and subsequently completing an attendance log, which should identify site-specific implementation of the SWPPP and the names of the personnel who attended the preconstruction meeting. Documentation of the preconstruction meeting will be filed with the SWPPP documents.

5.3 (3): DESCRIPTION OF CONSTRUCTION ACTIVITIES

- 5.3 (3a): Project Limits (See Title Sheet)
- 5.3 (3a): Project Description (See Title Sheet)
- 5.3 (4): Site Map(s) (See Title Sheet and Plans)
- Major Soil Disturbing Activities (check all that apply)
 - Clearing and grubbing
 - Excavation/borrow
 - Grading and shaping
 - Filling
 - Other (describe):
- 5.3 (3b): Total Project Area 5.44 Acres
- 5.3 (3b): Total Area to be Disturbed 4.19 Acres
- 5.3 (3c): Maximum Area Disturbed at One Time 4.19 Acres
- 5.3 (3d): Existing Vegetative Cover (%) 70%
- 5.3 (3d): Description of Vegetative Cover Native Grasses and Crop Land
- 5.3 (3e): Soil Properties: AASHTO Soil Class A-6; USDA stratified loam to loamy fine sand to fine sandy loam to silty clay loam to clay loam to silt loam to sandy clay loam
- 5.3 (3f): Name of Receiving Water Body/Bodies Rock Creek
- 5.3 (3g): Location of Construction Support Activity Areas

5.3 (3h): ORDER OF CONSTRUCTION ACTIVITIES

- Special sequencing requirements (see notes sheet).

The Contractor will enter the Estimated Start Date.

Description	Estimated Start Date
Install temporary traffic control signs.	
Install erosion control procedures and notify County to remove fence and install temporary fence.	
Deconstruct and remove existing structure.	
Undercut box culvert.	
Construct new structure.	
Grading operations, place topsoil, install riprap and final erosion control.	
County to install final surfacing, permanent signing, and install permanent fence.	
Remove temporary traffic control and open the roadway to through traffic.	
Permanent seeding.	
Complete miscellaneous cleanup under traffic.	

5.3 (5): DESCRIPTION AND MAINTENANCE OF CONTROL MEASURES

All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report. Include the technical reasoning for selecting each control. (check all that apply)

Perimeter Controls (See Detail Plan Sheets)

Description	Estimated Start Date
<input type="checkbox"/> Natural Buffers (within 50 ft of Waters of State)	
<input checked="" type="checkbox"/> Silt Fence	
<input checked="" type="checkbox"/> Erosion Control Wattles	
<input type="checkbox"/> Temporary Berm / Windrow	
<input type="checkbox"/> Floating Silt Curtain	
<input type="checkbox"/> Stabilized Construction Entrances	
<input type="checkbox"/> Entrance/Exit Equipment Tire Wash	
<input type="checkbox"/> Other:	

Structural Erosion and Sediment Controls

Description	Estimated Start Date
<input checked="" type="checkbox"/> Silt Fence	
<input type="checkbox"/> Temporary Berm/Windrow	
<input checked="" type="checkbox"/> Erosion Control Wattles	
<input type="checkbox"/> Temporary Sediment Barriers	
<input type="checkbox"/> Erosion Bales	
<input type="checkbox"/> Temporary Slope Drain	
<input type="checkbox"/> Turf Reinforcement Mat	
<input checked="" type="checkbox"/> Riprap	
<input type="checkbox"/> Gabions	
<input type="checkbox"/> Rock Check Dams	
<input type="checkbox"/> Sediment Traps/Basins	
<input type="checkbox"/> Culvert Inlet Protection	
<input type="checkbox"/> Transition Mats	
<input type="checkbox"/> Median/Area Drain Inlet Protection	
<input checked="" type="checkbox"/> Curb Inlet Protection	
<input type="checkbox"/> Interceptor Ditch	
<input type="checkbox"/> Concrete Washout Facility	
<input type="checkbox"/> Work Platform	
<input type="checkbox"/> Temporary Water Barrier	
<input type="checkbox"/> Temporary Water Crossing	
<input type="checkbox"/> Permanent Stormwater Ponds	
<input type="checkbox"/> Permanent Open Vegetated Swales	
<input type="checkbox"/> Natural Depressions to allow for Infiltration	
<input type="checkbox"/> Sequential Systems that combine several practices	
<input type="checkbox"/> Other:	

Dust Controls

Description	Estimated Start Date
<input type="checkbox"/> Tarps & Wind impervious fabrics	
<input type="checkbox"/> Watering	
<input type="checkbox"/> Stockpile location/orientation	
<input type="checkbox"/> Dust Control Chlorides	
<input type="checkbox"/> Other	

Dewatering BMPs

Description	Estimated Start Date
<input type="checkbox"/> Sediment Basins	
<input type="checkbox"/> Dewatering bags	
<input type="checkbox"/> Weir tanks	
<input checked="" type="checkbox"/> Temporary Diversion Channel	
<input type="checkbox"/> Other:	

Stabilization Practices (See Detail Plan Sheets)

(Stabilization measures will begin the following work day whenever earth disturbing activity on any portion of the site has temporarily or permanently ceased. Temporary stabilization will be completed as soon as practicable but no later than 14 days after initiating soil stabilization activities (3.18))

Description	Estimated Start Date
<input type="checkbox"/> Vegetation Buffer Strips	
<input type="checkbox"/> Temporary Seeding (Cover Crop Seeding)	
<input checked="" type="checkbox"/> Permanent Seeding	
<input type="checkbox"/> Sodding	
<input type="checkbox"/> Planting (Woody Vegetation for Soil Stabilization)	
<input checked="" type="checkbox"/> Mulching (Grass Hay or Straw)	
<input type="checkbox"/> Fiber Mulching (Wood Fiber Mulch)	
<input type="checkbox"/> Soil Stabilizer	
<input type="checkbox"/> Bonded Fiber Matrix	
<input type="checkbox"/> Fiber Reinforced Matrix	
<input checked="" type="checkbox"/> Erosion Control Blankets	
<input type="checkbox"/> Surface Roughening (e.g. tracking)	
<input type="checkbox"/> Other:	

Wetland Avoidance

Will construction and/or erosion and sediment controls impinge on regulated wetlands? Yes No If yes, the structural and erosion and sediment controls have been included in the total project wetland impacts and have been included in the 404 permit process with the USACE.

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	BRF-B 6136(01)	10	49

5.3 (6): PROCEDURES FOR INSPECTIONS

- Inspections will be conducted at least once every 7 days.
- All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report.
- Silt fence will be inspected for depth of sediment and for tears to ensure the fabric is securely attached to the posts and that the posts are well anchored. Sediment buildup will be removed from the silt fence when it reaches $\frac{1}{3}$ of the height of the silt fence.
- Sediment basins and traps will be checked. Sediment will be removed when depth reaches approximately 50 percent of the structure's capacity, and at the conclusion of the construction.
- Check dams will be inspected for stability. Sediment will be removed when depth reaches $\frac{1}{2}$ the height of the dam.
- All seeded areas will be checked for bare spots, washouts, and vigorous growth free of significant weed infestations.
- Inspection and maintenance reports will be prepared on form DOT 298 for each site inspection, this form will also be used to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents.
- The SDDOT Project Engineer and Contractor's Erosion Control Supervisor are responsible for inspections. Maintenance and repair activities are the responsibility of the Contractor. The SDDOT Project Engineer will complete the inspection and maintenance reports and distribute copies per the distribution instructions on DOT 298.

5.3 (7): POST CONSTRUCTION STORMWATER MANAGEMENT

Stormwater management will be handled by temporary controls outlined in "DESCRIPTION AND MAINTENANCE OF CONTROL MEASURES" above, and any permanent controls needed to meet permanent stormwater management needs in the post construction period will be shown in the plans and noted as permanent.

5.3 (8): POLLUTION PREVENTION PROCEDURES

5.3 (8a): Spill Prevention and Response Procedures

➤ **Material Management**

- Housekeeping
 - Only needed products will be stored on-site by the Contractor.
 - Except for bulk materials the contractor will store all materials under cover and/or in appropriate containers.
 - Products must be stored in original containers and labeled.
 - Material mixing will be conducted in accordance with the manufacturer's recommendations.
 - When possible, all products will be completely used before properly disposing of the container off-site.
 - The manufacturer's directions for disposal of materials and containers will be followed.
 - The Contractor's site superintendent will inspect materials storage areas regularly to ensure proper use and disposal.
 - Dust generated will be controlled in an environmentally safe manner.

- Hazardous Materials

- Products will be kept in original containers unless the container is not resealable and provide secondary containment as applicable.

- Original labels and material safety data sheets will be retained in a safe place to relay important product information.
- If surplus product must be disposed of, manufacturer's label directions for disposal will be followed.
- Maintenance and repair of all equipment and vehicles involving oil changes, hydraulic system drain down, degreasing operations, fuel tank drain down and removal, and other activities which may result in the accidental release of contaminants will be conducted on an impervious surface and under cover during wet weather to prevent the release of contaminants onto the ground.
- Wheel wash water will be collected and allowed to settle out suspended solids prior to discharge. Wheel wash water will not be discharged directly into any stormwater system or stormwater treatment system.
- Potential pH-modifying materials such as: bulk cement, cement kiln dust, fly ash, new concrete washings, concrete pumping, residuals from concrete saw cutting (either wet or dry), and mixer washout waters will be collected on site and managed to prevent contamination of stormwater runoff.

➤ **Spill Control Practices**

In addition to the previous housekeeping and management practices, the following practices will be followed for spill prevention and cleanup if needed.

- For all hazardous materials stored on site, the manufacturer's recommended methods for spill cleanup will be clearly posted. Site personnel will be made aware of the procedures and the locations of the information and cleanup supplies.
- Appropriate cleanup materials and equipment will be maintained by the Contractor in the materials storage area on-site. As appropriate, equipment and materials may include items such as brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for cleanup purposes.
- All spills will be cleaned immediately after discovery and the materials disposed of properly.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- After a spill a report will be prepared describing the spill, what caused it, and the cleanup measures taken. The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring, as well as clean up instructions in the event of reoccurrences.
- The Contractor's site superintendent, responsible for day-to-day operations, will be the spill prevention and cleanup coordinator.

➤ **Spill Response**

The primary objective in responding to a spill is to quickly contain the material(s) and prevent or minimize migration into stormwater runoff and conveyance systems. If the release has impacted on-site stormwater, it is critical to contain the released materials on-site and prevent their release into receiving waters. If a spill of pollutants threatens stormwater or surface water at the site, the spill response procedures outlined below must be implemented in a timely manner to prevent the release of pollutants.

- The Contractor's site superintendent will be notified immediately when a spill or the threat of a spill is observed. The superintendent will assess the situation and determine the appropriate response.

- If spills represent an imminent threat of escaping erosion and sediment controls and entering receiving waters, personnel will be directed to respond immediately to contain the release and notify the superintendent after the situation has been stabilized.
- Spill kits containing appropriate materials and equipment for spill response and cleanup will be maintained by the Contractor at the site.
- If oil sheen is observed on surface water (e.g. settling ponds, detention ponds, swales), action will be taken immediately to remove the material causing the sheen. The Contractor will use appropriate materials to contain and absorb the spill. The source of the oil sheen will also be identified and removed or repaired as necessary to prevent further releases.
- If a spill occurs the superintendent or the superintendent's designee will be responsible for completing the spill reporting form and for reporting the spill to SDDANR.
- Personnel with primary responsibility for spill response and cleanup will receive training by the Contractor's site superintendent or designee. The training must include identifying the location of the spill kits and other spill response equipment and the use of spill response materials.
- Spill response equipment will be inspected and maintained as necessary to replace any materials used in spill response activities.

5.3 (8b): WASTE MANAGEMENT PROCEDURES

➤ **Waste Disposal**

- All liquid waste materials will be collected and stored in approved sealed containers. All trash and construction debris from the site will be deposited in the approved containers. Containers will be serviced as necessary, and the trash will be hauled to an approved disposal site or licensed landfill. All onsite personnel will be instructed in the proper procedures for waste disposal and notices stating proper practices will be posted. The Contractor is responsible for ensuring waste disposal procedures are followed.

➤ **Hazardous Waste**

- All hazardous waste materials will be disposed of in a manner specified by local or state regulations or by the manufacturer. Site personnel will be instructed in these practices, and the Contractor will be responsible for seeing that these practices are followed.

➤ **Sanitary Waste**

- Portable sanitary facilities will be provided on all construction sites. Sanitary waste will be collected from the portable units which must be secured to prevent tipping and serviced in a timely manner by a licensed waste management Contractor or as required by any local regulations.

5.3 (9): CONSTRUCTION SITE POLLUTANTS

The following materials or substances are expected to be present on the site during the construction period. These materials will be handled as noted under the heading "POLLUTION PREVENTION PROCEDURES" (check all that apply).

- Concrete and Portland Cement
- Detergents
- Paints
- Metals
- Bituminous Materials
- Petroleum Based Products
- Diesel Exhaust Fluid
- Cleaning Solvents
- Wood
- Cure
- Texture
- Chemical Fertilizers
- Other:

Product Specific Practices

▪ Petroleum Products

All on-site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

▪ Fertilizers

Fertilizers will be applied only in the amounts specified by the SDDOT. Once applied, fertilizers will be worked into the soil to limit the exposure to stormwater. Fertilizers will be stored in an enclosed area. The contents of partially used fertilizer bags will be transferred to sealable containers to avoid spills.

▪ Paints

All containers will be tightly sealed and stored when not required for use. The excess will be disposed of according to the manufacturer's instructions and any applicable state and local regulations.

▪ Concrete Trucks

Contractors will provide designated truck washout facilities on the site. These areas must be self-contained and not connected to any stormwater outlet of the site. Upon completion of construction, the area at the washout facility will be properly stabilized.

5.3 (10): NON-STORMWATER DISCHARGES

The following non-stormwater discharges are anticipated during the course of this project (check all that apply).

- Discharges from water line flushing.
- Pavement wash-water, where no spills or leaks of toxic or hazardous materials have occurred.
- Uncontaminated ground water associated with dewatering activities.

5.3 (11): INFEASIBILITY DOCUMENTATION

If it is determined to be infeasible to comply with any of the requirements of the Stormwater Permit, the infeasibility determination must be thoroughly documented in the SWPPP.

7.0: SPILL NOTIFICATION

In the event of a spill, the Contractor's site superintendent will make the appropriate notification(s), consistent with the following procedures:

- A release or spill of a regulated substance (includes petroleum and petroleum products) must be reported to SDDANR immediately **if any one of the following** conditions exists:
 - The release or spill threatens or is able to threaten waters of the state (surface water or ground water)
 - The release or spill causes an immediate danger to human health or safety
 - The release or spill exceeds 25 gallons
 - The release or spill causes a sheen on surface water
 - The release or spill of any substance that exceeds the ground water quality standards of ARSD Chapter 74:54:01
 - The release or spill of any substance that exceeds the surface water quality standards of ARSD Chapter 74:51:01
 - The release or spill of any substance that harms or threatens to harm wildlife or aquatic life
 - The release or spill is required to be reported according to Superfund Amendments and Reauthorization Act (SARA) Title III List of Lists, Consolidated List of Chemicals Subject to Reporting Under the Emergency Planning and Community Right to Know Act, US Environmental Protection Agency.
- To report a release or spill, call SDDANR at 605-773-3296 during regular office hours (8 a.m. to 5 p.m. Central Standard Time). To report the release after hours, on weekends or holidays, call South Dakota Emergency Management at 605-773-3231. Reporting the release to SDDANR does not meet any obligation for reporting to other state, local, or federal agencies. Therefore, you must also contact local authorities to determine the local reporting requirements for releases. A written report of the unauthorized release of any regulated substance, including quantity discharged, and the location of the discharge will be sent to SDDANR within 14 days of the discharge.

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT BRF-B 6136(01)	SHEET 12	TOTAL SHEETS 49
-----------------------------	---------------------------	-------------	-----------------------

5.4: SWPPP CERTIFICATIONS

➤ **Certification of Compliance with Federal, State, and Local Regulations**

The Storm Water Pollution Prevention Plan (SWPPP) for this project reflects the requirements of all local municipal jurisdictions for storm water management and sediment and erosion control as established by ordinance, as well as other state and federal requirements for sediment and erosion control plans, permits, notices or documentation as appropriate.

➤ **South Dakota Department of Transportation**

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.



Authorized Signature (See the General Permit, Section 7.4 (1))

➤ **Prime Contractor**

This section is to be executed by the General Contractor after the award of the contract. This section may be executed any time there is a change in the Prime Contractor of the project.

I certify under penalty of law that this document and all attachments will be revised or maintained under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Authorized Signature

CONTACT INFORMATION

The following personnel are duly authorized representatives and have signatory authority for modifications made to the SWPPP:

➤ **Contractor Information:**

- Prime Contractor Name: _____
- Contractor Contact Name: _____
- Address: _____

- City: _____ State: _____ Zip: _____
- Office Phone: _____ Field: _____
- Cell Phone: _____ Fax: _____

➤ **Erosion Control Supervisor**

- Name: _____
- Address: _____

- City: _____ State: _____ Zip: _____
- Office Phone: _____ Field: _____
- Cell Phone: _____ Fax: _____

➤ **SDDOT Project Engineer**

- Name: _____
- Business Address: _____
- Job Office Location: _____
- City: _____ State: _____ Zip: _____
- Office Phone: _____ Field: _____
- Cell Phone: _____ Fax: _____

➤ **SDDANR Contact Spill Reporting**

- Business Hours Monday-Friday (605) 773-3296
- Nights and Weekends (605) 773-3231

➤ **SDDANR Contact for Hazardous Materials.**

- (605) 773-3153

➤ **National Response Center Hotline**

- (800) 424-8802.

➤ **SDDANR Stormwater Contact Information**

- SDDANR Stormwater (800) 737-8676
- Surface Water Quality Program (605) 773-3351

5.5: REQUIRED SWPPP MODIFICATIONS

➤ **5.5 (1): Conditions Requiring SWPPP Modification**

The SWPPP must be modified, including the site map(s), in response to any of the following conditions:

- When a new operator responsible for implementation of any part of the SWPPP begins work on the site.
- When changes to the construction plans, sediment and erosion control measures, or any best management practices on site that are no longer accurately reflected in the SWPPP. This includes changes made in response to corrective actions triggered by inspections.
- To reflect areas on the site map where operational control has been transferred (including the date of the transfer) or has been covered under a new permit since initiating coverage under this general permit.
- If inspections by site staff, local officials, SDDANR, or U.S. EPA determine that SWPPP modifications are necessary for compliance with the Stormwater Permit.
- To reflect any revisions to applicable federal, state, or local requirements that affect the control measures implemented at the site.
- If approved by the Secretary, to reflect any changes in chemical water treatment systems or controls, including the use of a different water treatment chemical, age rates, different areas, or methods of application.

➤ **5.5 (2): Deadlines for SWPPP Modification**

Any required revisions to the SWPPP must be completed within 7 calendar days following any of the items listed above.

➤ **5.5 (3): Documentation of Modifications to the Plan**

All SWPPP modification records are required to be maintained showing the dates of when the modification occurred. The records must include the name of the person authorizing each change and a brief summary of all changes.

➤ **5.5 (4): Certification Requirements**

All modifications made to the SWPPP must be signed and certified as required in Section 7.4.

➤ **5.5 (5): Required Notice to Other Operators**


If there are multiple operators at the site, the Contractor's Erosion Control Supervisor must notify each operator that may be impacted by the change to the SWPPP within 24 hours.

When modifications as described above occur, the SWPPP will be modified to provide appropriate protection to disturbed areas, all storm water structures, and adjacent waters. The SDDOT Project Engineer will modify the SWPPP using the DOT 298 form and drawings on the plan will be modified to reflect the needed changes. Copies of the DOT 298 forms and the SWPPP will be retained on site in a designated place for review throughout the course of the project. A copy of the DOT 298 form will be given to the Contractor Erosion Control Supervisor and a copy will be emailed to the SDDOT Environmental Section in accordance with the DOT 298 Form.

TYPICAL SECTIONS


FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	BRF-B 6136(01)	13	49



TYPICAL GRADING SECTION

A circular registration stamp with a double-lined outer border. The top half of the inner border contains the text "REGISTERED PROFESSIONAL" and the bottom half contains "ENGINEER". The center of the stamp contains "REG. NO." above the registration number "5382", followed by the name "BRADLEY D. MANGOHR", and "SOUTH DAKOTA" below it. At the bottom, the expiration date "10/22/2025" is stamped, followed by a black star. The entire stamp is printed in black ink on a white background.



TYPICAL GRADING SECTION


NOTE: ALL BASE COURSE AND
ASPHALT WILL BE FURNISHED
AND INSTALLED BY THE COUNTY



TYPICAL SECTIONS


FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT BRF-B 6136(01)	Sheet 14	Total Sheets 49
-----------------------------	---------------------------	-------------	-----------------------



TYPICAL GRADING SECTION

Sta. 17+11.02 to Sta. 19+08.96



TYPICAL GRADING SECTION

Sta. 19+08.96 to Sta. 20+71.49


NOTE: ALL BASE COURSE AND
ASPHALT WILL BE FURNISHED
AND INSTALLED BY THE COUNTY



TYPICAL SECTIONS

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT BRF-B 6136(01)	sheet 15	total sheets 49
-----------------------------	---------------------------	-------------	-----------------------





TYPICAL GRADING SECTION
Sta. 20+71.49 to Sta. 22+31.42



NOTE: ALL BASE COURSE AND
ASPHALT WILL BE FURNISHED
AND INSTALLED BY THE COUNTY

TRAFFIC CONTROL

FOR BIDDING PURPOSES ONLY

STATE OF
SOUTH
DAKOTAPROJECT
BRF-B 6136(01)SHEET
16TOTAL
SHEETS
49


ITEMIZED LIST FOR DETOUR AND RESTRICTION SIGNING

CONVENTIONAL ROAD				
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN
W20-2	DETOUR AHEAD	2	48" x 48"	16.0
M4-8a	END DETOUR	2	24" x 18"	3.0
M4-9	DETOUR (ARROW L or R)	6	30" x 24"	5.0
SPECIAL	222ND ST	8	30" x 12"	2.5
CONVENTIONAL ROAD DETOUR AND RESTRICTION SIGNING SQFT				88.0

ITEMIZED LIST FOR TRAFFIC CONTROL SIGNS

CONVENTIONAL ROAD				
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN
R11-2	ROAD CLOSED	2	48" x 30"	10.0
R11-3a	ROAD CLOSED X MILES AHEAD LOCAL TRAFFIC ONLY	2	60" x 30"	12.5
W20-3	ROAD CLOSED XXX FEET	4	48" x 48"	16.0
CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT				109.0

TYPE 3 BARRICADES	
ITEM DESCRIPTION	QUANTITY
Type 3 Barricade	8 Each



EROSION CONTROL

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
BRF-B 6136(01)		17	49




TABLE OF EROSION CONTROL WATTERS

12" Diameter Wattle			
Station	L/R	Diameter (Inch)	Quantity (Ft)
12+95.69	L	12	40
12+98.54	R	12	40
14+44.91	R	12	40
14+51.54	L	12	40
16+17.01	L	12	40
16+19.89	R	12	40
16+53.51	L	12	140
16+71.08	R	12	140
17+28.78	L	12	100
17+56.00	L	12	100
17+81.00	L	12	40
19+22.74	L	12	40
Miscellaneous			100
Total			900

TABLE OF HIGH FLOW SILT FENCE

High Flow Silt Fence				
Station		Station	L/R	Quantity (Ft)
17+80.88	To	22+31.41	R	451
19+02.72	To	22+31.41	L	329
Miscellaneous			Total	800

TABLE OF EROSION CONTROL BLANKET

Type 2 Erosion Control Blanket				
Station		Station	L/R	Quantity (SqYd)
11+40.87	To	13+26.42	L	885
11+40.87	To	13+27.46	R	870
13+42.33	To	16+94.94	L	2045
13+48.15	To	17+45.39	R	3155
16+31.51	To	18+87.77	L	1530
17+25.31	To	22+31.41	R	1180
19+02.62	To	22+31.41	L	570
Miscellaneous			Total	10335


LEGEND

	EROSION CONTROL BLANKET
	CLASS B RIPRAP
	TEMPORARY CONSTRUCTION EASEMENT
	HIGH FLOW SILT FENCE
	12" DIAMETER EROSION CONTROL WATTLE

REGISTERED PROFESSIONAL ENGINEER
REG. NO. 5382
BRADLEY D. STANGOH
SOUTH DAKOTA
10/22/2025

SURVEY DATA & EASEMENTS FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	18	TOTAL SHEETS
	BRF-B 6136(01)		




Ulteig
We listen. We solve.®

PLAN & PROFILE


STATE OF SOUTH Dakota	PROJECT BRF-B 6136(01)	SHEET 20	TOTAL SHEETS 49
-----------------------------	---------------------------	-------------	-----------------------

FOR BIDDING PURPOSES ONLY




CONTROL POINT TABLE				
Point #	Northing	Easting	Station	Offset
1	680030.4020	266855.8370	13.65.35	21.51'L
2	680048.9280	266910.02390	19-10.04	23.25'L
3	679960.4250	266889.4010	16-16.73	56.68'R
4	680023.2210	266980.8380	17-78.66	34.44'R
				1485.89'
				100.5BAR W/OPC



17+00	18+00	19+00	20+00	21+00	22+00	23+00	24+00	25+00
1472.06								
1474.09								
1459.96								
1473.59								
1460.44								
1473.15								
1471.09								
1472.76								
1471.09								
1472.42								
1471.13								
1471.19								
1471.91								
1471.30								
1471.73								
1471.42								
1471.61								
1471.46								
1471.55								
1471.53								
1471.74								
1471.58								
1471.91								
1471.67								
1472.12								
1471.82								
1472.38								
1472.03								
1472.75								
1472.29								
1472.93								
1472.60								
1473.29								
1472.97								
1473.74								
1473.39								
1474.11								
1473.87								
1474.57								
1474.40								
1475.07								
1474.98								
1475.74								
1475.62								
1476.31								
1476.26								
1450								
1472.06								
1474.09								
1459.96								
1473.59								
1460.44								
1473.15								
1471.09								
1472.76								
1471.09								
1472.42								
1471.13								
1472.14								
1471.19								
1471.91								
1471.30								
1471.73								
1471.42								
1471.61								
1471.46								
1471.55								
1471.53								
1471.74								
1471.58								
1471.91								
1471.67								
1472.12								
1471.82								
1472.38								
1472.03								
1472.75								
1472.29								
1472.93								
1472.60								
1473.29								
1472.97								
1473.74								
1473.39								
1474.11								
1473.87								
1474.57								
1474.40								
1475.07								
1474.98								
1475.74								
1475.62								
1476.31								
1476.26								
1450								
1472.06								
1474.09								
1459.96								
1473.59								
1460.44								
1473.15								
1471.09								
1472.76								
1471.09								
1472.42								
1471.13								
1472.14								
1471.19								
1471.91								
1471.30								
1471.73								
1471.42								
1471.61								
1471.46								
1471.55								
1471.53								
1471.74								
1471.58								
1471.91								
1471.67								
1472.12								
1471.82								
1472.38								
1472.03								
1472.75								
1472.29								
1472.93								




Published Date: 2026	S D D O T	INTERSECTING ROADS AND ENTRANCES	PLATE NUMBER 120.01
		Sheet 1 of 2	Sheet 2 of 2



Published Date: 2026	S D D O T	INTERSECTING ROADS AND ENTRANCES	PLATE NUMBER 120.01
		Sheet 2 of 2	





Equiv. Dia. (Inch)	(Inches)		Dimensions (Inches)	L Dimensions						
	Span	Rise		Inch	Gage	A	H	W	Overall Width	Slope
18	21	15	.064	16	8	6	27	43	6:1	30
21	24	18	.064	16	8	6	30	46	6:1	48
24	28	20	.064	16	8	6	34	50	6:1	60
30	35	24	.079	14	12	9	41	65	6:1	84
36	42	29	.109	12	12	9	48	72	6:1	114
42	49	33	.109	12	16	12	55	87	6:1	138
48	57	38	.109	12	16	12	63	95	6:1	168
54	64	43	.109	12	16	12	70	102	6:1	198
60	71	47	.109	12	16	12	77	109	6:1	222
72	83	57	.109	12	16	12	89	121	6:1	282

Pipe Dia. (Inch)	(Min.) Thick.		Dimensions (Inches)	L Dimensions				
	Inch	Gage		A	H	W	Overall Width	Slope
15	.064	16	8	6	21	37	6:1	30
18	.064	16	8	6	24	40	6:1	48
21	.064	16	8	6	27	43	6:1	66
24	.064	16	8	6	30	46	6:1	84
30	.109	12	12	9	36	60	6:1	120
36	.109	12	12	9	42	66	6:1	156
42	.109	12	16	12	48	80	6:1	192
48	.109	12	16	12	54	86	6:1	228
54	.109	12	16	12	60	92	6:1	264
60	.109	12	16	12	66	98	6:1	300

GENERAL NOTES:

Safety bars will be provided when specified in the plans.

Safety ends will be fabricated from galvanized steel conforming to the requirements of the Specifications.

Safety bars will be fabricated from steel schedule 40 pipe in conformance with ASTM A53, grade B or HSS 3.5x.216 in conformance with ASTM A500, grade B or C.

Slotted holes for safety bar attachment will be provided for all end sections.

Attachment to circular pipes 15" through 24" diameter will be made with Type #1 straps. All other sizes will be attached with Type #2 rods and lugs.

When stated in the plans, optional toe plate extension will be punched and bolted to end section apron lip with $\frac{3}{8}$ " diameter galvanized bolts. Steel for toe plate extension will be same gauge as end section. Dimensions will be overall width less 6" by 8" high.

Installation will be performed in accordance with the Specifications.

Cost of all work and materials required for fabrication and installation of safety ends will be incidental to the bid items for the various sizes of safety ends.

April 8, 2025

Published Date: 2026	S D D O T	C.M.P. SAFETY ENDS			PLATE NUMBER 450.38
		C.M.P. SAFETY ENDS			
Published Date: 2026	S D D O T	C.M.P. SAFETY ENDS			Sheet 2 of 2


STANDARD PLATES

FOR BIDDING PURPOSES ONLY


STATE OF
SOUTH
DAKOTA

PROJECT
BRF-B 6136(01)


SHEET
24
TOTAL
SHEETS
49




RURAL DISTRICT



RURAL DISTRICT WITH
SUPPLEMENTAL PLATE



URBAN DISTRICT




RURAL DISTRICT
3 DAY MAXIMUM

(Not applicable to regulatory signs)


* If the bottom of supplemental plate is mounted lower than 7 feet above a pedestrian walkway, the supplemental plate should not project more than 4" into the pedestrian facility.

January 22, 2021

Published Date: 2026	S D D O T	CRASHWORTHY SIGN SUPPORTS (Typical Construction Signing)	PLATE NUMBER 634.85
			Sheet 1 of 1



PLAN VIEW
(Examples of stub height clearance checks)



ELEVATION VIEW

GENERAL NOTES:


The top of anchor posts and slip bases WILL NOT extend above a 60" chord line within a 120" diameter circle around the post with ends 4" above the ground.

At locations where there is curb and gutter adjacent to the breakaway sign support, the stub height will be a maximum of 4" above the ground line at the localized area adjacent to the breakaway support stub.

The 4" stub height clearance is not necessary for U-channel lap splices where the support is designed to yield (bend) at the base.

January 22, 2021

Published Date: 2026	S D D O T	BREAKAWAY SUPPORT STUB CLEARANCE	PLATE NUMBER 634.99
			Sheet 1 of 1






February 14, 2020

Published Date: 2026

S
D
D
O
T

EROSION CONTROL BLANKET

PLATE NUMBER
734.01
Sheet 1 of 1



GENERAL NOTES:

At cut or fill slope installations, wattles will be installed along the contour and perpendicular to the water flow.

At ditch installations, point A must be higher than point B to ensure that water flows over the wattle and not around the ends.

The Contractor will dig a 3" to 5" trench, install the wattle tightly in the trench so that daylight can not be seen under the wattle, and then compact the soil excavated from the trench against the wattle on the uphill side. See Detail B.

The stakes will be 1"x2" or 2"x2" wood stakes, however, other types of stakes such as rebar may be used only if approved by the Engineer. The stakes will be placed 6" from the ends of the wattles and the spacing of the stakes along the wattles will be 3' to 4'.


Where installing running lengths of wattles, the Contractor will butt the second wattle tightly against the first and will not overlap the ends. See Detail C.

The Contractor and Engineer will inspect the erosion control wattles in accordance with the storm water permit. The Contractor will remove, dispose, or reshape the accumulated sediment when necessary as determined by the Engineer.

Sediment removal, disposal, or necessary shaping will be as directed by the Engineer. All costs for removing accumulated sediment, disposal of sediment, and necessary shaping will be incidental to the contract unit price per cubic yard for "Remove Sediment".

All costs for furnishing and installing the erosion control wattles including labor, equipment, and materials will be incidental to the contract unit price per foot for the corresponding erosion control wattle contract item.

All costs for removing the erosion control wattle from the project including labor, equipment, and materials will be incidental to the contract unit price per foot for "Remove Erosion Control Wattle".

**GENERAL NOTES:**

Where practical, surface roughening will be done on slopes 3:1 and steeper and on slopes deemed necessary by the Engineer.

The equipment used for surface roughening will be equipped with tracks that are capable of creating ridges in the soil that are perpendicular to the slope. The final condition of the surface roughening will be approved by the Engineer.


Measurement for surface roughening will be to the nearest tenth of an acre.

All costs associated with surface roughening including labor, equipment, and materials will be incidental to the contract unit price per acre for "Surface Roughening".

February 14, 2020

Published Date: 2026	S D D O T	EROSION CONTROL WATTLE	PLATE NUMBER 734.06
			Sheet 2 of 2

Published Date: 2026	S D D O T	SURFACE ROUGHENING	PLATE NUMBER 734.25
			Sheet 1 of 1



February 14, 2020

Published Date: 2026	S D D O T	TEMPORARY DIVERSION CHANNEL FOR FISH PASSAGE	PLATE NUMBER 734.30
Sheet 1 of 1			

SPECIFICATIONS

1. Design Specifications: AASHTO LRFD Bridge Design Specification, 9th Edition.
2. Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, 10-1-2025 Version and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES

1. Design Live Load: HL-93. No construction loading in excess of legal load was considered.
2. The design of the barrel section is based on a minimum fill height of 2 feet and include all subsequent fill heights up to and including the maximum fill height of 5 feet (F5).
3. Design Material Strengths: Concrete $f'_c = 4,500$ psi
Reinforcing Steel $f_y = 60,000$ psi
4. All concrete will be Class A45 Concrete, Box Culvert conforming to Section 460 of the Construction Specifications.
5. All reinforcing steel will conform to ASTM A615 Grade 60.
6. All lap splices shown are contact lap splices unless noted otherwise.
7. All exposed concrete corners and edges will be chamfered $\frac{3}{4}$ -inch unless noted otherwise in the plans.
8. Use 1-inch clear cover on all reinforcing steel EXCEPT as shown.
9. The Contractor will imprint on the structure the date of construction as specified and detailed on Standard Plate 460.02.
10. Care will be taken to establish Working Points (W.P.) as shown on the wings.
11. Circled numbers in PLAN and ELEVATION views on the General Drawing are section I.D. Numbers (see SDDOT Materials Manual).
12. Cost of Preformed Expansion Joint Filler used in apron construction will be incidental to the other contract items.
13. Soils below the bottom of the proposed RCBC consist of brown silt sand.
14. Groundwater is anticipated at an elevation of 1457.85 feet based on the subsurface investigation conducted in June 2022. Dewatering will be required to construct the box culvert. All costs incurred for dewatering will be incidental to other contract items.
15. Compaction of earth embankment and box culvert backfill material will be governed by the Specified Density Method.

INCIDENTAL WORK, STRUCTURE

In place is a 32'-0" long, one span steel girder bridge with two precast concrete channel deck units on each side, with a concrete deck, concrete abutments and concrete wingwalls. The bridge has an asphalt overlay on top of the bridge deck.

Break down and remove the existing bridge in accordance with Section 110 of the Specifications. The abutments will be removed 1' minimum below the bottom of the undercut.

The Contractor will salvage the metal guard rail for Miner County. All items not salvaged for the County will become the property of the Contractor and will be properly disposed of by the Contractor.

The foregoing is a general description of the in-place bridge and should not be construed to be complete in all details. Before preparing the bid it will be the responsibility of the Contractor to make a visual inspection of the structure to verify the extent of the work and materials involved. All costs involved in this removal will be incidental to the contract lump sum price for "Incidental Work, Structure".

NOTICE - LEAD BASED PAINT

Be advised that the paint on the steel surfaces of the existing structure contains lead. The Contractor will plan operations accordingly and inform employees of the hazards of lead exposure.




FOR BIDDING PURPOSES ONLY


STATE OF
SOUTH
DAKOTA

PROJECT
BRF-B 6136(01)

SHEET
30
TOTAL
SHEETS
49



UNDERCUT LAYOUT
(Bottom Dimensions)



TYPICAL SECTION

(For Limits of Undercut)

PLANS BY: ULTEIG ENGINEERS, INC.



NOTES AND UNDERCUT DETAILS

**FOR
2 - 11' X 11' BOX CULVERT (C.I.P.)**

ROCK CREEK
STA. 17 + 10.15
STR. NO. 49-093-020
PCN 09MC

11° RHF SKEW
SEC. 10/15-T106N-R57W
BRF-B 6136(01)
HL-93



MINER COUNTY
S. D. DEPT. OF TRANSPORTATION

APRIL 2025

2 OF 11

DESIGNED BY BDS	CK. DES. BY MTH	DRAFTED BY BDS
--------------------	--------------------	-------------------

BRIDGE ENGINEER



INLET DETAILS (A)
FOR
141-LBOX GULVERT (2 L.D.)

ROCK CREEK
STA. 17 + 10.15
STR. NO. 49-093-020
PCN 09MC

11° RHF SKEW
SEC. 10/15-T106N-R57W
BRF-B 6136(01)
HI-93

MINER COUNTY
DEPT. OF TRANSPORTATION

APRIL 2025

3 QF 11




A circular registration stamp with a hatched outer border. The words "REGISTERED PROFESSIONAL" are at the top, "ENGINEER" are at the bottom, and "REG. NO." is in the center above the registration number. The registration number "5382" is in the center. The name "BRADLEY D. STANGOEHRL" is written in the center. Below the name, "SOUTH DAKOTA" is written. At the bottom, the date "10/22/2025" is stamped. A large, stylized blue signature "Bradley D. Stangoehr" is written across the center of the stamp. A small black star is at the bottom.

PLANS BY: ULTEIG ENGINEERS, II


DESIGNED BY BDS	CK. DES. BY MTH	DRAFTED BY BDS	BRIDGE ENGINEERED
--------------------	--------------------	-------------------	-------------------

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
BRF-B 6136(01)		32	49



LEGEND FOR PLACING RE-STEEL		
O.F.W.W. - Outside Face of Wing Wall		
I.F.W.W. - Inside Face of Wing Wall		
M.W.W. - Middle Wing Wall		




INLET DETAILS (B)
FOR
2 - 11' X 11' BOX CULVERT (C.I.P.)
ROCK CREEK
STA. 17 + 10.15
STR. NO. 49-093-020
PCN 09MC
11° RHF SKEW
SEC. 10/15-T106N-R57W
BRF-B 6136(01)
HL-93

MINER COUNTY
S. D. DEPT. OF TRANSPORTATION
APRIL 2025

(4) OF (11)

PLANS BY: ULTEIG ENGINEERS, INC.

DESIGNED BY BDS	CK. DES. BY MTH	DRAFTED BY BDS
BRIDGE ENGINEER		



SEC. F-F

ESTIMATED QUANTITIES

ESTIMATED QUANTITIES			
ITEM	Class A45 Concrete, Box Culvert	Reinforcing Steel	Structure Excavation, Box Culvert
UNIT	Cu. Yd.	Lb.	Cu. Yd.
Inlet	42.7	7201	27.2

PLANS BY: ULTEIG ENGINEERS, INC.

REINFORCING SCHEDULE

INITIAL DETAILS (C)

INLET DETAILS (S)
FOR
S-11LY-11L BOX SILVERT (S.L.P.)

Z-11 X 11
ROCK CREEK
STA. 17 + 10.15
STR. NO. 49-093-020
PCN 09MC

11° RHF SKEW
C. 10/15-T106N-R57W
BRF-B 6136(01)
HL-93

MINER COUNTY
PT. OF TRANSPORTATION

APRIL 2025


5 05 11

RO
STA
STI
PC


REGISTERED PROFESSIONAL ENGINEER
REG. NO.
5382
BRADLEY D.
STANGOHR
SOUTH DAKOTA
10/22/2025

Bradley D. Stangoehr

CD BY	CK. DES. BY MTH	DRAFTED BY BDS	REVIEWED BY BRIDGE ENGINEER
-------	--------------------	-------------------	--------------------------------




NOTE:
*Apron will NOT be built
monolithic with the Box Culvert.*



PLANS BY: UU FIG ENGINEERS, INC.

PLANS BY: ULTEIG ENGINEERS, INC.



PLAN (Outlet Approach)

OUTLET DETAILS (A)

2 - 11' X 11' BOX CULVERT (C.I.P.)
OCK CREEK 11° RHF SKE
TA. 17 + 10.15 SEC. 10/15-T106N-R57
TR. NO. 49-093-020 BRF-B 6136(0)
CN 09MC HI -

ERT (CH-1)
11° RHF SKEW
C. 10/15-T106N-R57W
BRF-B 6136(01)
HI -93


MINER COUNTY
PT. OF TRANSPORTATION

APRIL 2025


6 QF 11

APRIL 2020


DESIGNED BY BDS	CK. DES. BY MTH	DRAFTED BY BDS	
--------------------	--------------------	-------------------	--




SECTION A - A




SEC. B - B



SEC. E - E



SECTION G - G



VIEW F-F

OUTLET DETAILS (B)

FOR

2 - 11' X 11'
OCK CREEK
TA. 17 + 10.15
TR. NO. 49-093-020
CN 09MC

11° RHF SKEW
0/15-T106N-R57W
BRF-B 6136(01)
HI-93

MINER COUNTY
D. DEPT. OF TRANSPORTATION
APRIL 2025

APRIL 2025

3 25 11

LEGEND FOR PLACING RE-STEEL

O.F.W.W. - Outside Face of Wing V

I.F.W.W. - Inside Face of Wing Wa

ESTIMATED QUANTITIES

ESTIMATED QUANTITIES			
ITEM	Class A45 Concrete, Box Culvert	Reinforcing Steel	Structure Excavation, Box Culvert
UNIT	Cu. Yd.	Lb.	Cu. Yd.
Outlet	27.4	2260	13.5
Outlet Apron	10.1	711	10.1

PLANS BY: ULTEIG ENGINEERS, INC.


DESIGNED BY CK. DES. BY DRAFTED BY
BDS MTH BDS

LEGEND FOR PLACING RE-STEEL

T. T. S. - Top of Top Slab
 B. T. S. - Bottom of Top Slab
 T. B. S. - Top of Bottom Slab
 B. B. S. - Bottom of Bottom Slab


FOR BIDDING PURPOSES ONLY

 STATE OF
 SOUTH
 DAKOTA

 PROJECT
 BRF-B 6136(01)
 SHEET
 36
 TOTAL
 SHEETS
 49


FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
BRF-B 6136(01)		37	49



LEGEND FOR PLACING RE-STEEL		
O. F. O. W. - Outside Face of Outside Wall		
I. F. O. W. - Inside Face of Outside Wall		
M. W. - Middle Wall		

PLANS BY: ULTEIG ENGINEERS, INC.

REINFORCING SCHEDULE				
(For Two F5 Barrel End Sections @ 33'-0")				
Mk.	No.	Size	Length	Type
h5	154	4	13'-3"	17A
j0	8	6	24'-6"	Str.
j5	152	6	22'-9"	Str.
k5	202	4	19'-6"	17
m0	7	5	27'-6"	Str.
m5	126	5	24'-9"	Str.
n0	7	5	26'-6"	Str.
n5	126	5	23'-9"	Str.
p1	36	4	31'-3"	Str.
p2	36	4	35'-9"	Str.
p3	34	4	33'-6"	Str.
p4	20	4	64'-9"	Str.
p5	20	4	69'-3"	Str.
p6	22	4	64'-3"	Str.
p7	22	4	69'-0"	Str.
q5	404	4	7'-3"	17A
s0	4	6	4'-9"	Str.
s5	156	6	6'-9"	Str.
w5	90	4	27'-3"	S11A
z1	65	5	3'-6"	Str.

Bending Details

OPTIONAL FILLET DETAIL (At Bottom Slab)

NOTE: Contractor may form the optional full fillet, with 2" Chamfer, as detailed. The cost of the additional concrete will be borne by the Contractor.

OPTIONAL POUR - BOTTOM SLAB

The Bottom Slab may be poured continuously, at the option of the Contractor, with the use of Preformed Metal keyway conforming to the keyway dimensions and location as shown on the plans. The keyway length will be full width of the bottom slab. Care will be taken to maintain the proper alignment of the keyway during the pour sequence. All additional costs of this option will be borne by the Contractor.

△ Place z1 bars through construction joint between barrel sections as shown on Standard Plate No. 460.10. Quantity of z1 bars is for one construction joint.

OPTIONAL k5 & w5 SPLICE DETAIL

Contractor may use optional reinforcing steel splices as shown. The cost of the additional reinforcing steel will be borne by the Contractor.

NOTES:
All dimensions are out to out of bars.
△ See cutting diagram.
Request for additional reinforcing steel splices at points other than those shown, must be submitted to the Engineer for prior approval. If additional splices are approved, no payment will be made for the added quantity of reinforcing steel.



F5 BARREL SECTION DETAILS (33' - 0") (B)
FOR
2 - 11' X 11' BOX CULVERT (C.I.P.)
11° RHF SKEW
SEC. 10/15-T106N-R57W
BRF-B 6136(01)
HL-93

ROCK CREEK
STA. 17 + 10.15
STR. NO. 49-093-020
PCN 09MC

MINER COUNTY
S. D. DEPT. OF TRANSPORTATION
APRIL 2025


9 OF 11

DESIGNED BY BDS CK. DES. BY MTH DRAFTED BY BDS


BRIDGE ENGINEER

FOR BIDDING PURPOSES ONLY


STATE OF SOUTH DAKOTA	PROJECT BRF-B 6136(01)	SHEET 39	TOTAL SHEETS 49
-----------------------------	---------------------------	-------------	-----------------------



DETAIL FOR FENCE ANCHORS



VIEW A - A



EYEBOLT DETAILS

December 23, 2012

PLATE NUMBER
620.16

Sheet 1 of 1

Published Date: 2026

S
D
D
O
T

FENCE ANCHORS FOR
BOX CULVERT WING WALLS

2 - 11' X 11' BOX CULVERT

STR. NO. 49-093-020



APRIL 2025

11 OF 11

CROSS-SECTION

FOR BIDDING PURPOSES ONLY




STATE OF SOUTH DAKOTA	PROJECT	40	TOTAL SHEETS
	BRF-B 6136(01)		



CROSS-SECTION




FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	BRF-B 6136(01)		



CROSS-SECTION

FOR BIDDING PURPOSES ONLY

STATE OF
SOUTH
DAKOTAPROJECT
BRF-B 6136(01)SHEET
42
TOTAL
SHEETS
49222nd Street
STA 14+00.00222nd Street
STA 13+50.00



CROSS-SECTION

FOR BIDDING PURPOSES ONLY



STATE OF
SOUTH
DAKOTA

PROJECT

SHEET	TOTAL SHEETS
43	49



REGISTERED PROFESSIONAL
REG. NO.
5382
BRADLEY D.
STANGOEHRL
SOUTH DAKOTA
10/22/2025




A circular registration stamp with a hatched outer border. The words "REGISTERED PROFESSIONAL" are at the top, "ENGINEER" are on the right, and "SOUTH DAKOTA" are on the bottom. The registration number "5382" is in the center, surrounded by "REG. NO.". The name "BRADLEY D. STANGOIR" is printed in the center. Handwritten blue ink signatures are over the printed text: "Bradley D. Stangoir" on the left and "AIA" on the right. A black star is at the bottom.

CROSS-SECTION

FOR BIDDING PURPOSES ONLY





STATE OF SOUTH DAKOTA	PROJECT BRF-B 6136(01)	SHEET 45	TOTAL SHEETS 49
-----------------------------	---------------------------	-------------	-----------------------



CROSS-SECTION

FOR BIDDING PURPOSES ONLY




STATE OF SOUTH DAKOTA	PROJECT	46	TOTAL SHEETS
	BRF-B 6136(01)		



CROSS-SECTION

FOR BIDDING PURPOSES ONLY





STATE OF SOUTH DAKOTA	PROJECT	47	TOTAL SHEETS
	BRF-B 6136(01)		



CROSS-SECTION

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT BRF-B 6136(01)	SHEET 48	TOTAL SHEETS 49
-----------------------------	---------------------------	-------------	-----------------------



CROSS-SECTION

FOR BIDDING PURPOSES ONLY

STATE OF SOUTH DAKOTA	PROJECT	49	TOTAL SHEETS
	BRF-B 6136(01)		

