3

DEPARTMENT OF TRANSPORTATION

DEPARTMENT OF TRANSPORTATION

NOTICE TO CONTRACTORS,

PROPOSAL, SPECIAL PROVISIONS,

CONTRACT AND CONTRACT BOND

FOR

STRUCTURES ((2) 3-12X12 CIP OR PRECAST, (3) 3-14X14 CIP OR PRECAST, 106' STEEL GIRDER BRIDGE) & APPROACH GRADING

FEDERAL **PROJECT NO.** **P-B 0248(12)217**
(PCN 06G7)

SD HIGHWAY 248

IN JONES, LYMAN COUNTIES

December 2, 2026

NOTICE TO ALL BIDDERS

TO REPORT BID RIGGING ACTIVITIES, CALL: 1-800-424-9071

THE U.S. DEPARTMENT OF TRANSPORTATION (DOT) OPERATES THE ABOVE TOLL-FREE "HOTLINE" MONDAY THROUGH FRIDAY, 8:00 A.M. TO 5:00 P.M., EASTERN TIME. ANYONE WITH KNOWLEDGE OF POSSIBLE BID RIGGING, BIDDER COLLUSION, OR OTHER FRAUDULENT ACTIVITIES SHOULD USE THE "HOTLINE" TO REPORT SUCH ACTIVITIES.

THE "HOTLINE" IS PART OF THE DOT'S CONTINUING EFFORT TO IDENTIFY AND INVESTIGATE HIGHWAY CONSTRUCTION CONTRACT FRAUD AND ABUSE AND IS OPERATED UNDER THE DIRECTION OF THE DOT INSPECTOR GENERAL.

ALL INFORMATION WILL BE TREATED CONFIDENTIALLY, AND CALLER ANONYMITY WILL BE RESPECTED.

*** * * ***

PLANS, PROPOSALS AND ADDENDA

AFTER AWARD OF CONTRACT, THE LOW BIDDER WILL RECEIVE TEN (10) COMPLIMENTARY SETS OF PLANS, PROPOSALS, PROJECT Q & A FORUM, AND ADDENDA FOR FIELD AND OFFICE USE. AN ELECTRONIC COPY WILL ALSO BE PROVIDED. ANY ADDITIONAL COPIES REQUIRED WILL BE THE RESPONSIBILITY OF THE CONTRACTOR.

*** * * ***

Project Number: P-B 0248(12)217

Revised 10/8/25
PCN 06G7

NOTICE TO CONTRACTORS

Bid proposals for this project will be prepared, transmitted, and received electronically by the South Dakota Department of Transportation (SDDOT) via the South Dakota Electronic Bid System until 10 A.M. Central time, on December 2, 2026, at which time the SDDOT will open bids. All bids will be checked for qualifications with results posted on the SDDOT website. The South Dakota Transportation Commission will consider all bids at a scheduled Commission meeting.

The work for which proposals are hereby requested is to be completed within the following requirement(s):

SUBSTANTIAL COMPLETION: **NOVEMBER 3, 2028**

FIELD WORK COMPLETION: **JUNE 15, 2029**

The project category is Category II
The project type is Structural
The geographic zone is Zone 2

THE DBE GOAL FOR THIS PROJECT IS: **N/A**

WORK TYPE FOR THIS PROJECT IS: **WORK TYPE 2 OR WORK TYPE 9 OR WORK TYPE 12**

Bidding package for the work may be obtained at:
http://apps.sd.gov/hc65bidletting/ebslettings1.aspx#no-back-button

The South Dakota Standard Specifications for Roads and Bridges, 10-7-26 Version, may be obtained at https://dot.sd.gov/doing-business/contractors/standard-specifications/ .

The electronic bid proposal must be submitted by a valid bidder as designated by their company's https://apps.sd.gov/HC65C2C/EBS/BidAdminAuthorizationForm.pdf. A bidding administrator will have privileges in the SDEBS to prepare bids, submit bids, and authorize additional company employees to prepare and submit bids. Additionally, a bidding administrator will be responsible for maintaining the list of authorized bidders for the company and will have the ability to add employees, remove employees, and set-up bidder identifications and passwords within the SDEBS. Bidding Administrator authorization will remain in full force and effect until written notice of termination of this authorization is sent by an Officer of the company and received by the Department.

A bidder identification and password, coupled with a company identification previously assigned by the Department, will serve as authentication that an individual is a valid bidder for the company.

Contact information to schedule a preconstruction meeting prior to commencing with the work on this project.

Dean VanDeWiele
104 S Garfield
Pierre, SD 57501-5405
Phone: 605/773-5294

PROPOSAL Revised 8/10/11

SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION, STATE OF SOUTH DAKOTA:

Ladies / Gentlemen:

The following proposal is made on behalf of the undersigned and no others. It is in all respects fair and is made without collusion on the part of any other person, firm or corporation not appearing in the signature to this proposal.

The undersigned certifies that she / he has carefully examined the plans listed herein, the Specifications hereinbefore referred to, the Special Provisions and the form of contract, both of which are attached hereto. The undersigned further certifies that she / he has personally inspected the actual location of the work, together with the local sources of supply and that she / he understands the conditions under which the work is to be performed, or, that if she / he has not so inspected the actual location of the work, that she / he waives all right to plea any misunderstanding regarding the location of the work or the conditions peculiar to the same.

On the basis of the plans, Specifications, Special Provisions and form of contract proposed for use, the undersigned proposes to furnish all necessary machinery, tools, apparatus and other means of construction, to do all the work and furnish all the materials in the manner specified, to finish the entire project **within the contract time specified** and to accept as full compensation therefore the amount of the summation of the products of the actual quantities, as finally determined, multiplied by the unit prices bid.

The undersigned understands that the quantities as shown in the Bid Schedule are subject to increase or decrease, and hereby proposes to perform all quantities of work, as increased or decreased, in accordance with the provisions of the specifications, and subject to any applicable special provisions, and at the unit prices bid.

The undersigned understands that the "Total or Gross Amount Bid" as immediately hereinbefore set forth is not the final amount which will be paid if this proposal is accepted and the work done, but that such amount is computed for the purpose of comparison of the bids submitted and the determination of the amount of the performance bond.

The undersigned further proposes to perform all extra work that may be required on the basis provided in the specifications, and to give such work personal attention in order to see that it is economically performed.

The undersigned further proposes to both execute the contract agreement and to furnish a satisfactory performance bond, in accordance with the terms of the specifications, within twenty (20) calendar days after the date of Notice of Award from the South Dakota Department of Transportation that this proposal has been accepted.

CERTIFICATION REGARDING LOBBYING

I certify, to the best of my knowledge and belief, that: No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any agency, a member of Congress, an officer or employee of Congress, or an employee of a member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of a Federal contract, grant, loan, or cooperative agreement. If any funds other than Federal appropriated funds have been paid or will be paid to any of the above mentioned parties, the undersigned shall complete and submit Standard Form LLL, “Disclosure Form to Report Lobbying,” in accordance with its instructions.

The undersigned shall require that the language of this certification be included in the award documents for all subawards at all tiers (including subcontracts, subgrants, and contracts under grants, loans, and cooperative agreements) and that all subrecipients shall certify and disclose accordingly. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty or not less than $10,000 and not more than $100,000 for each such failure.

REV 11/2/26

INDEX OF SPECIAL PROVISIONS

PROJECT NUMBER(S): P-B 0248(12)217 PCN: 06G7

TYPE OF WORK: STRUCTURES ((2) 3-12X12 CIP OR PRECAST, (3) 3-14X14 CIP OR PRECAST, 106' STEEL GIRDER BRIDGE) & APPROACH GRADING

COUNTIES: JONES, LYMAN

The following clauses have been prepared subsequent to the Standard Specifications for Roads and Bridges and refer only to the above described improvement, for which the following Proposal is made.

The Contractor's attention is directed to the need for securing from the Department of Environment & Natural Resources, Foss Building, Pierre, South Dakota, permission to remove water from public sources (lakes, rivers, streams, etc.). The Contractor should make his request as early as possible after receiving his contract, and insofar as possible at least 30 days prior to the date that the water is to be used.

Bobbie Country is the official in charge of the Pierre Career Center for Jones, Lyman Counties.

THE FOLLOWING ITEMS ARE INCLUDED IN THIS PROPOSAL FORM:

Special Provision for Contract Time, dated 11/5/26.

Special Provision Regarding Combination Bids, dated 11/3/26.

Special Provision for Subletting of Contract, dated 11/2/26.

Special Provision Regarding Section 404 of the Clean Water Act, dated 9/22/26.

Fact Sheet #23.

Special Provision for On-The-Job Training Program, dated 3/10/16.

Special Provision Regarding Railroad Insurance Requirements for Ringneck & Western Railroad, dated 10/14/26.
NOTE: The Contractor WILL NOT be granted permission to proceed with any work on Railroad Right-of-Way until he has been notified by the Railroad that the insurance has been approved and the insurances and certificates has been provided to the SDDOT area office.
Special Provision Regarding Working on Railroad Property for Ringneck & Western Railroad, dated 10/14/26.

Special Provision for Contractor Staking with Machine Control Grading Option, dated 10/30/26.

List of Utilities.

Special Provision for Submission of Bid Proposals (SDEBS Lettings), dated 10/29/26.
Special Provision for Aggregates for Granular Bases and Surfacing, dated 10/26/26.
Special Provision for Acknowledgment and Certification Regarding Article 3, Section 12 of the South Dakota Constitution, dated 8/24/23.
Fuel Adjustment Affidavit, DOT form 208 dated 11/25.
Standard Title VI Assurance, dated 3/1/16.
Special Provision for Equal Employment Opportunity Requirements for Highway Construction Contracts, dated 10/7/26.
Special Provision for Contract Provisions for Federal-Aid Construction Contracts, Form FHWA 1273 (Rev. June 25, 2026), dated 10/7/26.
Contract Provisions for Federal-Aid Construction Contracts, Form FHWA 1273 (Rev. 6/25/26).
Special Provision Regarding Minimum Wage on Federal-Aid Projects, dated 10/24/19.
Wage and Hour Division US Department of Labor Washington DC. - US Dept. of Labor Decision Number SD20260001, dated 1/30/26.
Special Provision Regarding Stormwater Discharges to Waters of the State, dated 11/5/25.
General Permit Authorizing Stormwater Discharges Associated with Construction Activities, dated 11/1/23.
https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/StormWaterConstruction.aspx

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
CONTRACT TIME

PROJECT P-B 0248(12)217; PCN 06G7
JONES & LYMAN COUNTIES

NOVEMBER 5, 2026

Work Zone 1 (Str. Nos. 38-348-174 & 43-014-188) Interim Completion Requirement

The Contractor will complete all work in the work zone 1 (Str. Nos. 38-348-174 & 43-014-188) portion of the project by the November 5, 2027 interim completion date.

If the Contractor does not complete the required work by the interim completion requirement, the Department will assess liquidated damages in accordance with Section 8.9 (Table A). The Department will assess liquidated damages for each working day the required work is late until the Contractor completes the work. The Department will count working days in accordance with Section 8.7 C.

Substantial Completion

The Contractor will substantially complete the project by the November 3, 2028 substantial completion date. The Department will consider the work substantially complete in accordance with Section 8.7 A.1.

The Contractor will substantially complete the project prior to the substantial completion requirement. If the Contractor does not complete the work by the substantial completion requirement, the Department will assess liquidated damages in accordance with Section 8.9. The Department will assess liquidated damages for each working day the work (project) is late until the Contractor substantially completes the work.

In the event the Contractor does not substantially complete the work on time, the Department will count working days in accordance with Section 8.7 B.

Field Work Completion

The Contractor will complete the project by the June 15, 2029 field work completion date.

The Contractor will complete all work on the project prior to the field work completion requirement. If the Contractor does not complete all work by the field work completion requirement, the Department will assess liquidated damages in accordance with Section

8.9 The Department will assess liquidated damages for each working day the work (project) is late until the Contractor completes all field work.

In the event the Contractor does not complete all field work on time, the Department will count working days in accordance with Section 8.7 B.

* * * * *

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION REGARDING
COMBINATION BIDS

P-B 0248(12)217, PCN 06G7
STRUCTURES ((2) 3-12X12 CIP OR PRECAST, (3) 3-14X14 CIP OR PRECAST, 106' STEEL GIRDER BRIDGE) & APPROACH GRADING
JONES, LYMAN COUNTY

NOVEMBER 3, 2026

Bidders submitting a bid on this project **MUST ALSO** submit a bid on project:

P-B 0248(16)173, PCN 06NH
SD HIGHWAY 248
STRUCTURES (3-12X9 CIP OR PRECAST RCBC & 4-12X8 CIP OR PRECAST RCBC),
APPROACH GRADING
JACKSON COUNTY

Award of both projects will be to the same bidder based on the total of the two projects.

Work on PCN (06NH) CANNOT be used to meet the DBE Goal established for this project.

After award, the contracts will be administered as entirely separate contracts.

* * * *

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
SUBLETTING OF CONTRACT

PROJECT P-B 0248(16)173 & P-B 0248(12)217, PCN 06NH & 06G7
JACKSON, JONES, & LYMAN COUNTY

NOVEMBER 2, 2026

Delete the 2nd paragraph of Section 8.1 and replace with the following:

The Contractor may subcontract up to 75% of the combined original contract amounts, based on the contract unit prices, but must perform not less than 25% of the combined total amount of the original contracts with the Contractor's own organization.

To calculate the total amount subcontracted and the total amount performed with the Contractor's own organization, the Department will combine the figures from PCN 06NH & 06G7.

* * * * *

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION REGARDING SECTION 404 OF THE CLEAN WATER ACT

Project # P-B 0248(12)217; PCN 06G7
Jones County

SEPTEMBER 22, 2026
NATIONWIDE PERMIT NO 23

The above referenced project is authorized by the Department of the Army Nationwide Permit, found in the January 8, 2026 Federal Register publication "*91 FR 768 - Reissuance and Modification of Nationwide Permits.*"

The following general conditions must be adhered to in order for any authorization by a nationwide permit to be valid:

Please refer to the attached ***Fact Sheet Nationwide Permit 23 and 2026 Nationwide Permits Regional Conditions***

The above authorization permits placement of fill in the drainage crossings or wetlands identified in the Section A plan notes.

PLEASE REFER TO THE TABLE OF WETLANDS IN THE SECTION A ENVIRONMENTAL COMMITMENTS.

Nationwide Permit 23
Approved Categorical Exclusions

Expires March 15, 2031

23. ***Approved Categorical Exclusions.***

Activities undertaken, assisted, authorized, regulated, funded, or financed, in whole or in part, by another Federal agency or department where:

(a) That agency or department has determined, pursuant to Section 106, 109, and 111(1) of the National Environmental Policy Act, that the activity is categorically excluded from the requirement to prepare an environmental impact statement or environmental assessment analysis, because it is included within a category of actions which neither individually nor cumulatively have a significant effect on the human environment; and

(b) The Office of the Chief of Engineers (Attn: CECW–CO) has concurred with that agency's or department's determination that the activity is categorically excluded and approved the activity for authorization under NWP 23.

The Office of the Chief of Engineers may require additional conditions, including pre-construction notification, for authorization of an agency's categorical exclusions under this NWP.

Notification: Certain categorical exclusions approved for authorization under this NWP require the permittee to submit a pre-construction notification to the district engineer prior to commencing the activity (see general condition 32). The activities that require pre-construction notification are listed in the appropriate Regulatory Guidance Letter(s) (Authorities: Sections 10 and 404)

Note: The agency or department may submit an application for an activity believed to be categorically excluded to the Office of the Chief of Engineers (Attn: CECW–CO). Prior to approval for authorization under this NWP of any agency's activity, the Office of the Chief of Engineers will solicit public comment. As of the date of issuance of this NWP, agencies with approved categorical exclusions are: the Bureau of Reclamation, Federal Highway Administration, and U.S. Coast Guard. Activities approved for authorization under this NWP as of the date of this notice are found in Corps Regulatory Guidance Letter 05–07. Any changes to approved categorical exclusions applicable to this NWP will be announced in the Federal Register and posted on this same website.

C. Nationwide Permit General Conditions

Note: To qualify for NWP authorization, the prospective permittee must comply with the following general conditions, as applicable, in addition to any regional or case-specific conditions imposed by the division engineer or district engineer. Prospective permittees should contact the appropriate Corps district office to determine if regional conditions have been imposed on an NWP. Prospective permittees should also contact the appropriate Corps district office to determine the status of Clean Water Act Section 401 water quality certification and/or Coastal Zone Management Act consistency for an NWP. Every person who may wish to obtain permit authorization under one or more NWPs, or who is currently relying on an existing or prior permit authorization under one or more NWPs, has been and is on notice that all of the provisions of 33 CFR 330.1 through 330.6 apply to every NWP authorization. Note especially 33 CFR 330.5 relating to the modification, suspension, or revocation of any NWP authorization.

1. Navigation. (a) No activity may cause more than a minimal adverse effect on navigation.

(b) Any safety lights and signals prescribed by the U.S. Coast Guard, through regulations or otherwise, must be installed and maintained at the permittee's expense on authorized facilities in navigable waters of the United States.

(c) The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his or her authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

2. Aquatic Life Movements. No activity may substantially disrupt the necessary life cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. All permanent and temporary crossings of waterbodies shall be suitably culverted, bridged, or otherwise designed and constructed to maintain low flows to sustain the movement of those aquatic species. If a bottomless culvert cannot be used, then the crossing should be designed and constructed to minimize adverse effects to aquatic life movements.

3. Spawning Areas. Activities in spawning areas during spawning seasons must be avoided to the maximum extent practicable. Activities that result in the physical destruction (e.g., through excavation, fill, or downstream smothering by substantial turbidity) of an important spawning area are not authorized.

4. Migratory Bird Breeding Areas. Activities in waters of the United States that serve as breeding areas for migratory birds must be avoided to the maximum extent practicable.

5. Shellfish Beds. No activity may occur in areas of concentrated shellfish populations, unless the activity is directly related to a shellfish harvesting activity authorized by NWPs 4 and 48, or is a shellfish seeding or habitat restoration activity authorized by NWP 27.

6. Suitable Material. No activity may use unsuitable material (e.g., trash, debris, car bodies, asphalt, etc.). Material used for construction or discharged must be free from toxic pollutants in toxic amounts (see section 307 of the Clean Water Act).

7. Water Supply Intakes. No activity may occur in the proximity of a public water supply intake, except where the activity is for the repair or improvement of public water supply intake structures or adjacent bank stabilization.

8. Adverse Effects From Impoundments. If the activity creates an impoundment of water, adverse effects to the aquatic system due to accelerating the passage of water, and/or restricting its flow must be minimized to the maximum extent practicable.

9. Management of Water Flows. To the maximum extent practicable, the pre-construction course, condition, capacity, and location of open waters must be maintained for each activity, including stream channelization, storm water management activities, and temporary and permanent road crossings, except as provided below. The activity must be constructed to withstand expected high flows, including tidal flows. The activity must not restrict or impede the passage of normal or high flows, including tidal flows, unless the primary purpose of the activity is to impound water or manage high flows. The activity may alter the pre-construction course, condition, capacity, and location of open waters if it benefits the aquatic environment (e.g., stream restoration or relocation activities).

10. Fills Within 100-Year Floodplains. The activity must comply with applicable FEMA-approved state or local floodplain management requirements.

11. Equipment. Heavy equipment working in wetlands or mudflats must be placed on mats, or other measures must be taken to minimize soil disturbance. If mats are used to minimize soil disturbance, the affected areas must be returned to pre-construction elevations, and revegetated as appropriate. In circumstances where the use of mats has caused significant soil compaction, efforts using techniques (e.g., soil reaeration techniques) to break up the compaction should be employed to return the soil to a pre-construction state prior to returning to pre-construction elevations.

12. Soil Erosion and Sediment Controls. Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during construction, and all exposed soil and other fills, as well as any work below the ordinary high water mark or high tide line, must be permanently stabilized at the earliest practicable date. Permittees are encouraged to perform work within waters of the United States during periods of low-flow or no-flow, or during low tides.

13. Removal of Temporary Structures and Fills. Temporary structures must be removed, to the maximum extent practicable, after their use has been discontinued. Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations. The affected areas must be revegetated, as appropriate.

14. Proper Maintenance. Any authorized structure or fill shall be properly maintained, including maintenance to ensure public safety and compliance with applicable NWP general conditions, as well as any activity-specific conditions added by the district engineer to an NWP authorization.

15. Single and Complete Project. The activity must be a single and complete project. The same NWP cannot be used more than once for the same single and complete project.

16. Wild and Scenic Rivers. (a) No NWP activity may occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, unless the appropriate Federal agency with direct management responsibility for such river has determined in writing that the proposed activity will not adversely affect the Wild and Scenic River designation or study status.

(b) If a proposed NWP activity will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, the permittee must submit a pre-construction notification (see general condition 32). The district engineer will coordinate the PCN with the Federal agency with direct management responsibility for that river. Permittees shall not begin the NWP activity until notified by the district engineer that the Federal agency with direct management responsibility for that river has determined in writing that the proposed NWP activity will not adversely affect the Wild and Scenic River designation or study status.

(c) Information on Wild and Scenic Rivers may be obtained from the appropriate Federal land management agency responsible for the designated Wild and Scenic River or study river (e.g., National Park Service, U.S. Forest Service, Bureau of Land Management, U.S. Fish and Wildlife Service). Information on these rivers is also available at: http://www.rivers.gov/.

17. Tribal Rights. No activity or its operation may impair reserved tribal rights, including, but not limited to, reserved water rights and treaty fishing and hunting rights.

18. Endangered Species. (a) No activity is authorized under any NWP which is likely to directly or indirectly jeopardize the continued existence of a threatened or endangered species or a species proposed for such designation, as identified under the federal Endangered Species Act (ESA), or which will directly or indirectly destroy or adversely modify designated critical habitat or critical habitat proposed for such designation. No activity is authorized under any NWP which "may affect" a listed species or critical habitat, unless ESA section 7 consultation addressing the consequences of the proposed activity on listed species or critical habitat has been completed. See 50 CFR 402.02 for the definition of "effects of the action" for the purposes of ESA section 7 consultation.

(b) Federal agencies should follow their own procedures for complying with the requirements of the ESA (see 33 CFR 330.4(f)(1)). If pre-construction notification is required for the proposed activity, the federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate documentation has not been submitted, additional ESA section 7 consultation may be necessary for

the activity and the respective federal agency would be responsible for fulfilling its obligation under section 7 of the ESA.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if any listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed such designation) might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat or critical habitat proposed for such designation, and shall not begin work on the activity until notified by the district engineer that the requirements of the ESA have been satisfied and that the activity is authorized. For activities that might affect federally-listed endangered or threatened species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation), the pre-construction notification must include the name(s) of the endangered or threatened species (or species proposed for listing) that might be affected by the proposed activity or that utilize the designated critical habitat (or critical habitat proposed for such designation) that might be affected by the proposed activity. The district engineer will determine whether the proposed activity "may affect" or will have "no effect" to listed species and designated critical habitat and will notify the non-federal applicant of the Corps' determination within 45 days of receipt of a complete pre-construction notification. For activities where the non-federal applicant has identified listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation) that might be affected or is in the vicinity of the activity, and has so notified the Corps, the applicant shall not begin work until the Corps has provided notification that the proposed activity will have "no effect" on listed species (or species proposed for listing or designated critical habitat (or critical habitat proposed for such designation), or until ESA section 7 consultation or conference has been completed. If the non-federal applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(d) As a result of formal or informal consultation or conference with the FWS or NMFS the district engineer may add species-specific permit conditions to the NWPs.

(e) Authorization of an activity by an NWP does not authorize the "take" of a threatened or endangered species as defined under the ESA. In the absence of separate authorization (e.g., an ESA Section 10 Permit, a Biological Opinion with "incidental take" provisions, etc.) from the FWS or the NMFS, the Endangered Species Act prohibits any person subject to the jurisdiction of the United States to take a listed species, where "take" means to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect, or to attempt to engage in any such conduct. The word "harm" in the definition of "take" means an act which actually kills or injures wildlife. Such an act may include significant habitat modification or degradation where it actually kills or injures wildlife by significantly impairing essential behavioral patterns, including breeding, feeding or sheltering.

(f) If the non-federal permittee has a valid ESA section 10(a)(1)(B) incidental take permit with an approved Habitat Conservation Plan for a project or a group of projects that includes the proposed NWP activity, the non-federal permittee should provide a copy of that ESA section 10(a)(1)(B) permit with the PCN required by paragraph (c) of this general condition. The district engineer will coordinate with the agency that issued the ESA section 10(a)(1)(B) permit to determine whether the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation conducted for the ESA section 10(a)(1)(B) permit. If that coordination results in concurrence from the agency that the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation for the ESA section 10(a)(1)(B) permit, the district engineer does not need to conduct a separate ESA section 7 consultation for the proposed NWP activity. The district engineer will notify the non-federal applicant within 45 days of receipt of a complete pre-construction notification whether the ESA section 10(a)(1)(B) permit covers the proposed NWP activity or whether additional ESA section 7 consultation is required.

(g) Information on the location of threatened and endangered species and their critical habitat can be obtained directly from the offices of the FWS and NMFS or their web pages at http://www.fws.gov/ or http://www.fws.gov/ipac and http://www.nmfs.noaa.gov/pr/species/esa/ respectively.

19. Migratory Birds and Bald and Golden Eagles. The permittee is responsible for ensuring that an action authorized by an NWP complies with the Migratory Bird Treaty Act and the Bald and Golden Eagle

Protection Act. The permittee is responsible for contacting the appropriate local office of the U.S. Fish and Wildlife Service to determine what measures, if any, are necessary or appropriate to reduce adverse effects to migratory birds or eagles, including whether "incidental take" permits are necessary and available under the Migratory Bird Treaty Act or Bald and Golden Eagle Protection Act for a particular activity.

20. Historic Properties. (a) No activity is authorized under any NWP which may have the potential to cause effects on properties listed, or eligible for listing, in the National Register of Historic Places until the requirements of Section 106 of the National Historic Preservation Act (NHPA) have been satisfied.

(b) Federal permittees should follow their own procedures for complying with the requirements of section 106 of the National Historic Preservation Act (see 33 CFR 330.4(g)(1)). If pre-construction notification is required for the proposed NWP activity, the federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate documentation is not submitted, then additional consultation under section 106 may be necessary. The respective federal agency is responsible for fulfilling its obligation to comply with section 106.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if the NWP activity might have the potential to cause effects on any historic properties listed on, determined to be eligible for listing on, or potentially eligible for listing on the National Register of Historic Places, including previously unidentified properties. For such activities, the pre-construction notification must state which historic properties might have the potential to be affected by the proposed NWP activity or include a vicinity map indicating the location of the historic properties or the potential for the presence of historic properties. Assistance regarding information on the location of, or potential for, the presence of historic properties can be sought from the State Historic Preservation Officer, Tribal Historic Preservation Officer, or designated tribal representative, as appropriate, and the National Register of Historic Places (see 33 CFR 330.4(g)). When reviewing pre-construction notifications, district engineers will comply with the current procedures for addressing the requirements of section 106 of the National Historic Preservation Act. The district engineer shall make a reasonable and good faith effort to carry out appropriate identification efforts commensurate with potential impacts, which may include background research, consultation, oral history interviews, sample field investigation, and/or field survey. Based on the information submitted in the PCN and these identification efforts, the district engineer shall determine whether the proposed NWP activity has the potential to cause effects on historic properties. Section 106 consultation is not required when the district engineer determines that the activity does not have the potential to cause effects on historic properties (see 36 CFR 800.3(a)). Section 106 consultation is required when the district engineer determines that the activity has the potential to cause effects on historic properties. The district engineer will conduct consultation with consulting parties identified under 36 CFR 800.2(c) when he or she makes any of the following effect determinations for the purposes of section 106 of the NHPA: no historic properties affected, no adverse effect, or adverse effect.

(d) Where the non-federal applicant has identified historic properties on which the proposed NWP activity might have the potential to cause effects and has so notified the Corps, the non-federal applicant shall not begin the activity until notified by the district engineer either that the activity has no potential to cause effects on historic properties or that NHPA section 106 consultation has been completed. For non-federal permittees, the district engineer will notify the prospective permittee within 45 days of receipt of a complete pre-construction notification whether NHPA section 106 consultation is required. If NHPA section 106 consultation is required, the district engineer will notify the non-federal applicant that he or she cannot begin the activity until section 106 consultation is completed. If the non-federal applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(e) Prospective permittees should be aware that section 110k of the NHPA (54 U.S.C. 306113) prevents the Corps from granting a permit or other assistance to an applicant who, with intent to avoid the requirements of section 106 of the NHPA, has intentionally significantly adversely affected a historic property to which the permit would relate, or having legal power to prevent it, allowed such significant adverse effect to occur, unless

the Corps, after consultation with the Advisory Council on Historic Preservation (ACHP), determines that circumstances justify granting such assistance despite the adverse effect created or permitted by the applicant. If circumstances justify granting the assistance, the Corps is required to notify the ACHP and provide documentation specifying the circumstances, the degree of damage to the integrity of any historic properties affected, and proposed mitigation. This documentation must include any views obtained from the applicant, SHPO/THPO, appropriate Indian tribes if the undertaking occurs on or affects historic properties on tribal lands or affects properties of interest to those tribes, and other parties known to have a legitimate interest in the impacts to the permitted activity on historic properties.

21. Discovery of Previously Unknown Remains and Artifacts. Permittees that discover any previously unknown historic, cultural or archeological remains and artifacts while accomplishing the activities authorized by NWPs, must immediately notify the district engineer of what they have found, and to the maximum extent practicable, avoid construction activities that may affect the remains and artifacts until the required coordination has been completed. The district engineer will initiate the federal, tribal, and state coordination required to determine if the items or remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.

22. Designated Critical Resource Waters. Critical resource waters include, NOAA-managed marine sanctuaries and marine monuments, and National Estuarine Research Reserves. The district engineer may designate, after notice and opportunity for public comment, additional waters officially designated by a state as having particular environmental or ecological significance, such as outstanding national resource waters or state natural heritage sites. The district engineer may also designate additional critical resource waters after notice and opportunity for public comment.

(a) Discharges of dredged or fill material into waters of the United States are not authorized by NWPs 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, 44, 49, 50, 51, 52, 57 and 58 for any activity within, or directly affecting, critical resource waters, including wetlands adjacent to such waters.

(b) For NWPs 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37, 38, and 54, notification is required in accordance with general condition 32, for any activity proposed by permittees in the designated critical resource waters including wetlands adjacent to those waters. The district engineer may authorize activities under these NWPs only after she or he determines that the impacts to the critical resource waters will be no more than minimal.

23. Mitigation. The district engineer will consider the following factors when determining appropriate and practicable mitigation necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal:

(a) The activity must be designed and constructed to avoid and minimize adverse effects, both temporary and permanent, to waters of the United States to the maximum extent practicable at the project site (i.e., on site).

(b) Mitigation in all its forms (avoiding, minimizing, rectifying, reducing, or compensating for resource losses) will be required to the extent necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal.

(c) Compensatory mitigation at a minimum one-for-one ratio will be required for all wetland losses that exceed 1/10-acre and require pre-construction notification, unless the district engineer determines in writing that either some other form of mitigation would be more environmentally appropriate or the adverse environmental effects of the proposed activity are no more than minimal, and provides an activity-specific waiver of this requirement. For wetland losses of 1/10-acre or less that require pre-construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in only minimal adverse environmental effects.

(d) Compensatory mitigation at a minimum one-for-one ratio will be required for all losses of stream bed that exceed 3/100-acre and require pre-construction notification, unless the district engineer determines in writing

that either some other form of mitigation would be more environmentally appropriate or the adverse environmental effects of the proposed activity are no more than minimal, and provides an activity-specific waiver of this requirement. This compensatory mitigation requirement may be satisfied through the restoration or enhancement of riparian areas next to streams in accordance with paragraph (e) of this general condition. For losses of stream bed of 3/100-acre or less that require pre-construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in only minimal adverse environmental effects. Compensatory mitigation for losses of streams should be provided, if practicable, through stream rehabilitation, enhancement, or preservation, because streams are difficult-to-replace resources (see 33 CFR 332.3(e)(3)).

(e) Compensatory mitigation plans for NWP activities in or near streams or other open waters will normally include a requirement for the restoration or enhancement, maintenance, and legal protection (e.g., conservation easements) of riparian areas next to open waters. In some cases, the restoration or maintenance/protection of riparian areas may be the only compensatory mitigation required. If restoring riparian areas involves planting vegetation, only native species should be planted. The width of the required riparian area will address documented water quality or aquatic habitat loss concerns. Normally, the riparian area will be 25 to 50 feet wide on each side of the stream, but the district engineer may require slightly wider riparian areas to address documented water quality or habitat loss concerns. If it is not possible to restore or maintain/protect a riparian area on both sides of a stream, or if the waterbody is a lake or coastal waters, then restoring or maintaining/protecting a riparian area along a single bank or shoreline may be sufficient. Where both wetlands and open waters exist on the project site, the district engineer will determine the appropriate compensatory mitigation (e.g., riparian areas and/or wetlands compensation) based on what is best for the aquatic environment on a watershed basis. In cases where riparian areas are determined to be the most appropriate form of minimization or compensatory mitigation, the district engineer may waive or reduce the requirement to provide wetland compensatory mitigation for wetland losses.

(f) Compensatory mitigation projects provided to offset losses of aquatic resources must comply with the applicable provisions of 33 CFR part 332.

(1) The prospective permittee is responsible for proposing an appropriate compensatory mitigation option if compensatory mitigation is necessary to ensure that the activity results in no more than minimal adverse environmental effects. For the NWPs, the preferred mechanism for providing compensatory mitigation is mitigation bank credits or in-lieu fee program credits (see 33 CFR 332.3(b)(2) and (3)). However, if an appropriate number and type of mitigation bank or in-lieu credits are not available at the time the PCN is submitted to the district engineer, the district engineer may approve the use of permittee-responsible mitigation.

(2) The amount of compensatory mitigation required by the district engineer must be sufficient to ensure that the authorized activity results in no more than minimal individual and cumulative adverse environmental effects (see 33 CFR 330.1(e)(3)). (See also 33 CFR 332.3(f).)

(3) Since the likelihood of success is greater and the impacts to potentially valuable uplands are reduced, aquatic resource restoration should be the first compensatory mitigation option considered for permittee-responsible mitigation.

(4) If permittee-responsible mitigation is the proposed option, the prospective permittee is responsible for submitting a mitigation plan. A conceptual or detailed mitigation plan may be used by the district engineer to make the decision on the NWP verification request, but a final mitigation plan that addresses the applicable requirements of 33 CFR 332.4(c)(2) through (14) must be approved by the district engineer before the permittee begins work in waters of the United States, unless the district engineer determines that prior approval of the final mitigation plan is not practicable or not necessary to ensure timely completion of the required compensatory mitigation (see 33 CFR 332.3(k)(3)). If permittee-responsible mitigation is the proposed option, and the proposed compensatory mitigation site is located on land in which another federal agency holds an easement, the district engineer will coordinate with that federal agency to determine if proposed compensatory mitigation project is compatible with the terms of the easement.

(5) If mitigation bank or in-lieu fee program credits are the proposed option, the mitigation plan needs to address only the baseline conditions at the impact site and the number of credits to be provided (see 33 CFR 332.4(c)(1)(ii)).

(6) Compensatory mitigation requirements (e.g., resource type and amount to be provided as compensatory mitigation, site protection, ecological performance standards, monitoring requirements) may be addressed through conditions added to the NWP authorization, instead of components of a compensatory mitigation plan (see 33 CFR 332.4(c)(1)(ii)).

(g) Compensatory mitigation will not be used to increase the acreage losses allowed by the acreage limits of the NWPs. For example, if an NWP has an acreage limit of 1/2-acre, it cannot be used to authorize any NWP activity resulting in the loss of greater than 1/2-acre of waters of the United States, even if compensatory mitigation is provided that replaces or restores some of the lost waters. However, compensatory mitigation can and should be used, as necessary, to ensure that an NWP activity already meeting the established acreage limits also satisfies the no more than minimal impact requirement for the NWPs.

(h) Permittees may propose the use of mitigation banks, in-lieu fee programs, or permittee-responsible mitigation. When developing a compensatory mitigation proposal, the permittee must consider appropriate and practicable options consistent with the framework at 33 CFR 332.3(b). For activities resulting in the loss of marine or estuarine resources, permittee-responsible mitigation may be environmentally preferable if there are no mitigation banks or in-lieu fee programs in the area that have marine or estuarine credits available for sale or transfer to the permittee. For permittee-responsible mitigation, the special conditions of the NWP verification must clearly indicate the party or parties responsible for the implementation and performance of the compensatory mitigation project, and, if required, its long-term management.

(i) Where certain functions and services of waters of the United States are permanently adversely affected by a regulated activity, such as discharges of dredged or fill material into waters of the United States that will convert a forested or scrub-shrub wetland to a herbaceous wetland in a permanently maintained utility line right-of-way, mitigation may be required to reduce the adverse environmental effects of the activity to the no more than minimal level.

24. Safety of Impoundment Structures. To ensure that all impoundment structures are safely designed, the district engineer may require non-federal applicants to demonstrate that the structures comply with established state or federal, dam safety criteria or have been designed by qualified persons. The district engineer may also require documentation that the design has been independently reviewed by similarly qualified persons, and appropriate modifications made to ensure safety.

25. Water Quality. (a) Where the certifying authority (state, authorized tribe, or EPA, as appropriate) has not previously certified compliance of an NWP with CWA section 401, a CWA section 401 water quality certification for the proposed activity which may result in any discharge from a point source into waters of the United States must be obtained or waived (see 33 CFR 330.4(c)). If the permittee cannot comply with all of the conditions of a water quality certification previously issued by the certifying authority for the issuance of the NWP, then the permittee must obtain a water quality certification or waiver for the proposed activity which may result in any discharge from a point source into waters of the United States in order for the activity to be authorized by an NWP.

(b) If the NWP activity requires pre-construction notification and the certifying authority has not previously certified compliance of an NWP with CWA section 401, the proposed activity which may result in any discharge from a point source into waters of the United States is not authorized by an NWP until water quality certification is obtained or waived. If the certifying authority issues a water quality certification for the proposed discharge into waters of the United States, the permittee must submit a copy of the certification to the district engineer. The discharge into waters of the United States is not authorized by an NWP until the district engineer has notified the permittee that the water quality certification requirement has been satisfied (i.e., by the issuance of a water quality certification or a waiver and completion of the Section 401(a)(2) process).

(c) The district engineer or certifying authority may require additional water quality management measures to ensure that the authorized activity does not result in more than minimal degradation of water quality.

26. Coastal Zone Management. In coastal states where an NWP has not previously received a state coastal zone management consistency concurrence, an individual state coastal zone management consistency concurrence must be obtained, or a presumption of concurrence must occur (see 33 CFR 330.4(d)). If the permittee cannot comply with all of the conditions of a coastal zone management consistency concurrence previously issued by the state, then the permittee must obtain an individual coastal zone management consistency concurrence or presumption of concurrence in order for the activity to be authorized by an NWP. The district engineer or a state may require additional measures to ensure that the authorized activity is consistent with state coastal zone management requirements.

27. Regional and Case-By-Case Conditions. The activity must comply with any regional conditions that may have been added by the division engineer (see 33 CFR 330.4(e)) and with any case specific conditions added by the Corps or by the state, Indian Tribe, or U.S. EPA in its CWA section 401 Water Quality Certification, or by the state in its Coastal Zone Management Act consistency determination.

28. Use of Multiple Nationwide Permits. The use of more than one NWP for a single and complete project is authorized, subject to the following restrictions:

(a) The total acreage loss of waters of the United States for a single and complete project cannot exceed the acreage limit of the NWP with the highest specified acreage limit when multiple NWPs are used to authorize an activity.

(b) If only one of the NWPs used to authorize the single and complete project has a specified acreage limit, the acreage loss of waters of the United States for that single and complete project cannot exceed that specified acreage limit. For example, if a road crossing over tidal waters is constructed under NWP 14 (which has an acreage limit of 1/3 acre in tidal waters), with associated bank stabilization authorized by NWP 13 (which does not have a specified acreage limit), the maximum acreage loss of waters of the United States for the total project cannot exceed 1/3-acre.

(c) If two or more of the NWPs used to authorize the single and complete project have specified acreage limits, the acreage loss of waters of the United States authorized by each of those NWPs cannot exceed the specified acreage limits of each of those NWPs. For example, if a commercial development is constructed under NWP 39 (which as a 1/2-acre limit), and the single and complete project includes the filling of a ditch authorized by NWP 46 (which has a 1-acre limit), the maximum acreage loss of waters of the United States for the construction of the commercial development under NWP 39 cannot exceed 1/2-acre, and the total acreage loss of waters of United States caused by the combination of the NWP 39 and NWP 46 activities cannot exceed 1 acre.

29. Transfer of Nationwide Permit Verifications. If the permittee sells the property associated with a nationwide permit verification, the permittee may transfer the nationwide permit verification to the new owner by submitting a letter to the appropriate Corps district office to validate the transfer. A copy of the nationwide permit verification must be attached to the letter, and the letter must contain the following statement and signature:

"When the structures or work authorized by this nationwide permit are still in existence at the time the property is transferred, the terms and conditions of this nationwide permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this nationwide permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below."

US Army Corps of Engineers®
Omaha District

(Transferee)

_____

(Date)

30. Compliance Certification. Each permittee who receives an NWP verification letter from the Corps must provide a signed certification documenting completion of the authorized activity and implementation of any required compensatory mitigation. The successful completion of any required permittee-responsible mitigation, including the achievement of ecological performance standards, will be addressed separately by the district engineer. The Corps will provide the permittee the certification document with the NWP verification letter. The certification document will include:

(a) A statement that the authorized activity was done in accordance with the NWP authorization, including any general, regional, or activity-specific conditions;

(b) A statement that the implementation of any required compensatory mitigation was completed in accordance with the permit conditions. If credits from a mitigation bank or in-lieu fee program are used to satisfy the compensatory mitigation requirements, the certification must include the documentation required by 33 CFR 332.3(l)(3) to confirm that the permittee secured the appropriate number and resource type of credits; and

(c) The signature of the permittee certifying the completion of the activity and mitigation.

The completed certification document must be submitted to the district engineer within 30 days of completion of the authorized activity or the implementation of any required compensatory mitigation, whichever occurs later.

31. Activities Affecting Structures or Works Built by the United States. If an NWP activity also requires review by, or permission from, the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers (USACE) federally authorized Civil Works project (a "USACE project"), the prospective permittee must submit a pre-construction notification. See paragraph (b)(10) of general condition 32. An activity that requires section 408 permission and/or review is not authorized by an NWP until the appropriate Corps office issues the section 408 permission or completes its review to alter, occupy, or use the USACE project, and the district engineer issues a written NWP verification.

32. Pre-Construction Notification. (a) *Timing*. Where required by the terms of the NWP, the prospective permittee must notify the district engineer by submitting a pre-construction notification (PCN) as early as possible. The district engineer must determine if the PCN is complete within 30 calendar days of the date of receipt and, if the PCN is determined to be incomplete, notify the prospective permittee within that 30 day period to request the additional information necessary to make the PCN complete. The request must specify the information needed to make the PCN complete. As a general rule, district engineers will request additional information necessary to make the PCN complete only once. However, if the prospective permittee does not provide all of the requested information, then the district engineer will notify the prospective permittee that the PCN is still incomplete and the PCN review process will not commence until all of the requested information has been received by the district engineer. The prospective permittee shall not begin the activity until either:

(1) He or she is notified in writing by the district engineer that the activity may proceed under the NWP with any special conditions imposed by the district or division engineer; or

(2) 45 calendar days have passed from the district engineer's receipt of the complete PCN and the prospective permittee has not received written notice from the district or division engineer. However, if the permittee was required to notify the Corps pursuant to general condition 18 that listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation) might be affected or are in the vicinity of the activity, or to notify the Corps pursuant to general condition 20 that the activity

might have the potential to cause effects to historic properties, the permittee cannot begin the activity until receiving written notification from the Corps that there is “no effect” on listed species or “no potential to cause effects” on historic properties, or that any consultation required under Section 7 of the Endangered Species Act (see 33 CFR 330.4(f)) and/or section 106 of the National Historic Preservation Act (see 33 CFR 330.4(g)) has been completed. If the proposed activity requires a written waiver to exceed specified limits of an NWP, the permittee may not begin the activity until the district engineer issues the waiver. If the district or division engineer notifies the permittee in writing that an individual permit is required within 45 calendar days of receipt of a complete PCN, the permittee cannot begin the activity until an individual permit has been obtained. Subsequently, the permittee’s right to proceed under the NWP may be modified, suspended, or revoked only in accordance with the procedure set forth in 33 CFR 330.5(d)(2).

(b) *Contents of Pre-Construction Notification*: The PCN must be in writing and include the following information:

(1) Name, address and telephone numbers of the prospective permittee;

(2) Location of the proposed activity;

(3) Identify the specific NWP or NWP(s) the prospective permittee wants to use to authorize the proposed activity;

(4) (i) A description of the proposed activity; the activity’s purpose; direct and indirect adverse environmental effects the activity would cause, including the anticipated amount of loss of wetlands, other special aquatic sites, and other waters expected to result from the NWP activity, in acres, linear feet, or other appropriate unit of measure; a description of any proposed mitigation measures intended to reduce the adverse environmental effects caused by the proposed activity; and any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity, including other separate and distant crossings for linear projects that require Department of the Army authorization but do not require pre-construction notification. The description of the proposed activity and any proposed mitigation measures should be sufficiently detailed to allow the district engineer to determine that the adverse environmental effects of the activity will be no more than minimal and to determine the need for compensatory mitigation or other mitigation measures.

(ii) For linear projects where one or more single and complete crossings require pre-construction notification, the PCN must include the quantity of anticipated losses of wetlands, other special aquatic sites, and other waters for each single and complete crossing of those wetlands, other special aquatic sites, and other waters (including those single and complete crossings authorized by an NWP but do not require PCNs). This information will be used by the district engineer to evaluate the cumulative adverse environmental effects of the proposed linear project, and does not change those non-PCN NWP activities into NWP PCNs.

(iii) Sketches should be provided when necessary to show that the activity complies with the terms of the NWP. (Sketches usually clarify the activity and when provided results in a quicker decision. Sketches should contain sufficient detail to provide an illustrative description of the proposed activity (e.g., a conceptual plan), but do not need to be detailed engineering plans);

(5) The PCN must include a delineation of waters, wetlands, and other special aquatic sites on the project site. Wetland delineations must be prepared in accordance with the current method required by the Corps. The permittee may ask the Corps to delineate the special aquatic sites and other waters on the project site, but there may be a delay if the Corps does the delineation, especially if the project site is large or contains many wetlands, other special aquatic sites, and other waters. Furthermore, the 45-day period will not start until the delineation has been submitted to or completed by the Corps, as appropriate. For NWP 27 activities that require PCNs because of other general conditions or regional conditions imposed by division engineers, see Note 2 of that NWP;

(6) If the proposed activity will result in the loss of greater than 1/10-acre of wetlands or 3/100-acre of stream bed and a PCN is required, the prospective permittee must submit a statement describing how the compensatory mitigation requirement will be satisfied, or explaining why the adverse environmental effects are no more than minimal and why compensatory mitigation should not be required. As an alternative, the prospective permittee may submit a conceptual or detailed mitigation plan.

(7) For non-federal permittees, if any listed species (or species proposed for listing) or designated critical habitat (or critical habitat proposed for such designation) might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat (or critical habitat proposed for such designation), the PCN must include the name(s) of those endangered or threatened species (or species proposed for listing) that might be affected by the proposed activity or utilize the designated critical habitat (or critical habitat proposed for such designation) that might be affected by the proposed activity. For NWP activities that require pre-construction notification, federal permittees must provide documentation demonstrating compliance with the Endangered Species Act;

(8) For non-federal permittees, if the NWP activity might have the potential to cause effects to a historic property listed on, determined to be eligible for listing on, or potentially eligible for listing on, the National Register of Historic Places, the PCN must state which historic property might have the potential to be affected by the proposed activity or include a vicinity map indicating the location of the historic property. For NWP activities that require pre-construction notification, federal permittees must provide documentation demonstrating compliance with section 106 of the National Historic Preservation Act;

(9) For an activity that will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a “study river” for possible inclusion in the system while the river is in an official study status, the PCN must identify the Wild and Scenic River or the “study river” (see general condition 16); and

(10) For an NWP activity that requires permission from, or review by, the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers federally authorized civil works project, the pre-construction notification must include a statement confirming that the project proponent has submitted a written request for section 408 permission from, or review by, the Corps office having jurisdiction over that USACE project.

(c) *Form of Pre-Construction Notification*: The nationwide permit pre-construction notification form (Form ENG 6082) should be used for NWP PCNs. A letter containing the required information may also be used. Applicants may provide electronic files of PCNs and supporting materials if the district engineer has established tools and procedures for electronic submittals.

(d) *Agency Coordination*: (1) The district engineer will consider any comments from federal and state agencies concerning the proposed activity’s compliance with the terms and conditions of the NWPs and the need for mitigation to reduce the activity’s adverse environmental effects so that they are no more than minimal.

(2) Agency coordination is required for: (i) all NWP activities that require pre-construction notification and result in the loss of greater than 1/2-acre of waters of the United States; (ii) NWP 13 activities in excess of 500 linear feet, fills greater than one cubic yard per running foot, or involve discharges of dredged or fill material into special aquatic sites; and (iii) NWP 54 activities in excess of 500 linear feet, or that extend into the waterbody more than 30 feet from the mean low water line in tidal waters or the ordinary high water mark in the Great Lakes.

(3) When agency coordination is required, the district engineer will immediately provide (e.g., via e-mail, facsimile transmission, overnight mail, or other expeditious manner) a copy of the complete PCN to the appropriate federal or state offices (FWS, state natural resource or water quality agency, EPA, and, if appropriate, the NMFS). With the exception of NWP 37, these agencies will have 10 calendar days from the date the material is transmitted to notify the district engineer via telephone, facsimile transmission, or e-mail that they intend to provide substantive, site-specific comments. The comments must explain why the agency believes the adverse

environmental effects will be more than minimal. If so contacted by an agency, the district engineer will wait an additional 15 calendar days before making a decision on the pre-construction notification. The district engineer will fully consider agency comments received within the specified time frame concerning the proposed activity's compliance with the terms and conditions of the NWPs, including the need for mitigation to ensure that the net adverse environmental effects of the proposed activity are no more than minimal. The district engineer will provide no response to the resource agency, except as provided below. The district engineer will indicate in the administrative record associated with each pre-construction notification that the resource agencies' concerns were considered. For NWP 37, the emergency watershed protection and rehabilitation activity may proceed immediately in cases where there is an unacceptable hazard to life or a significant loss of property or economic hardship will occur. The district engineer will consider any comments received to decide whether the NWP 37 authorization should be modified, suspended, or revoked in accordance with the procedures at 33 CFR 330.5.

(4) In cases where the prospective permittee is not a federal agency, the district engineer will provide a response to NMFS within 30 calendar days of receipt of any Essential Fish Habitat conservation recommendations, as required by section 305(b)(4)(B) of the Magnuson-Stevens Fishery Conservation and Management Act.

(5) Applicants are encouraged to provide the Corps with either electronic files or multiple copies of pre-construction notifications to expedite agency coordination.

E. Further Information

1. District engineers have authority to determine if an activity complies with the terms and conditions of an NWP.

2. NWPs do not obviate the need to obtain other federal, state, or local permits, approvals, or authorizations required by law.

3. NWPs do not grant any property rights or exclusive privileges.

4. NWPs do not authorize any injury to the property or rights of others.

5. NWPs do not authorize interference with any existing or proposed Federal project (see general condition 31).

F. Nationwide Permit Definitions

Best management practices (BMPs): Policies, practices, procedures, or structures implemented to mitigate the adverse environmental effects on surface water quality resulting from development. BMPs are categorized as structural or non-structural.

Compensatory mitigation: The restoration (re-establishment or rehabilitation), establishment (creation), enhancement, and/or in certain circumstances preservation of aquatic resources for the purposes of offsetting unavoidable adverse impacts which remain after all appropriate and practicable avoidance and minimization has been achieved.

Currently serviceable: Useable as is or with some maintenance, but not so degraded as to essentially require reconstruction.

Direct effects: Effects that are caused by the activity and occur at the same time and place.

Discharge: The term "discharge" means any discharge of dredged or fill material into waters of the United States.

Ecological reference: A model used to plan and design an aquatic ecosystem restoration, enhancement, or establishment activity under NWP 27. An ecological reference may be based on: (1) the structure, functions, and dynamics of an aquatic ecosystem type or a riparian area type that currently exists in the region; (2) the structure, functions, and dynamics of an aquatic ecosystem type or riparian area type that existed in the region in the past; and/or (3) indigenous and local ecological knowledge that apply to the aquatic ecosystem type or riparian area type (i.e., a cultural ecosystem). Cultural ecosystems are ecosystems that have developed under the joint influence of natural processes and human management activities (e.g., fire stewardship). An ecological reference takes into account the range of variation of the aquatic habitat type or riparian area type in the region.

Enhancement: The manipulation of the physical, chemical, or biological characteristics of an aquatic resource to heighten, intensify, or improve a specific aquatic resource function(s). Enhancement results in the gain of selected aquatic resource function(s), but may also lead to a decline in other aquatic resource function(s). Enhancement does not result in a gain in aquatic resource area.

Establishment (creation): The manipulation of the physical, chemical, or biological characteristics present to develop an aquatic resource that did not previously exist at an upland site. Establishment results in a gain in aquatic resource area.

High Tide Line: The line of intersection of the land with the water's surface at the maximum height reached by a rising tide. The high tide line may be determined, in the absence of actual data, by a line of oil or scum along shore objects, a more or less continuous deposit of fine shell or debris on the foreshore or berm, other physical markings or characteristics, vegetation lines, tidal gages, or other suitable means that delineate the general height reached by a rising tide. The line encompasses spring high tides and other high tides that occur with periodic frequency but does not include storm surges in which there is a departure from the normal or predicted reach of the tide due to the piling up of water against a coast by strong winds such as those accompanying a hurricane or other intense storm.

Historic Property: Any prehistoric or historic district, site (including archaeological site), building, structure, or other object included in, or eligible for inclusion in, the National Register of Historic Places maintained by the Secretary of the Interior. This term includes artifacts, records, and remains that are related to and located within such properties. The term includes properties of traditional religious and cultural importance to an Indian tribe or Native Hawaiian organization and that meet the National Register criteria (36 CFR part 60).

Independent utility: A test to determine what constitutes a single and complete non-linear project in the Corps Regulatory Program. A project is considered to have independent utility if it would be constructed absent the construction of other projects in the project area. Portions of a multi-phase project that depend upon other phases of the project do not have independent utility. Phases of a project that would be constructed even if the other phases were not built can be considered as separate single and complete projects with independent utility.

Indirect effects: Effects that are caused by the activity and are later in time or farther removed in distance, but are still reasonably foreseeable.

Loss of waters of the United States: Waters of the United States that are permanently adversely affected by filling, flooding, excavation, or drainage because of the regulated activity. The loss of stream bed includes the acres of stream bed that are permanently adversely affected by filling or excavation because of the regulated activity. Permanent adverse effects include permanent discharges of dredged or fill material that change an aquatic area to dry land, increase the bottom elevation of a waterbody, or change the use of a waterbody. The acreage of loss of waters of the United States is a threshold measurement of the impact to jurisdictional waters or wetlands for determining whether a project may qualify for an NWP; it is not a net threshold that is calculated after considering compensatory mitigation that may be used to offset losses of aquatic functions and services. Waters of the United States temporarily filled, flooded, excavated, or drained, but restored to pre-construction contours and elevations after construction, are not included in the measurement of loss of waters of the United States. Impacts resulting from activities that do not require Department of the Army

authorization, such as activities eligible for exemptions under section 404(f) of the Clean Water Act, are not considered when calculating the loss of waters of the United States.

Nature-based solutions: Actions to protect, sustainably manage, and restore natural or modified ecosystems, that address societal challenges effectively and adaptively, simultaneously providing human well-being and biodiversity benefits.

Navigable waters: Waters subject to section 10 of the Rivers and Harbors Act of 1899. These waters are defined at 33 CFR part 329.

Non-tidal wetland: A non-tidal wetland is a wetland that is not subject to the ebb and flow of tidal waters. Non-tidal wetlands contiguous to tidal waters are located landward of the high tide line (i.e., spring high tide line).

Open water: For purposes of the NWPs, an open water is any area that in a year with normal patterns of precipitation has water flowing or standing above ground to the extent that an ordinary high water mark can be determined. Aquatic vegetation within the area of flowing or standing water is either non-emergent, sparse, or absent. Vegetated shallows are considered to be open waters. Examples of “open waters” include rivers, streams, lakes, and ponds.

Ordinary High Water Mark: The term ordinary high water mark means that line on the shore established by the fluctuations of water and indicated by physical characteristics such as a clear, natural line impressed on the bank, shelving, changes in the character of soil, destruction of terrestrial vegetation, the presence of litter and debris, or other appropriate means that consider the characteristics of the surrounding areas.

Perennial stream: A perennial stream has surface water flowing continuously year-round during a typical year.

Practicable: Available and capable of being done after taking into consideration cost, existing technology, and logistics in light of overall project purposes.

Pre-construction notification: A request submitted by the project proponent to the Corps for confirmation that a particular activity is authorized by nationwide permit. The request may be a permit application, letter, or similar document that includes information about the proposed work and its anticipated environmental effects. Pre-construction notification may be required by the terms and conditions of a nationwide permit, or by regional conditions. A pre-construction notification may be voluntarily submitted in cases where pre-construction notification is not required and the project proponent wants confirmation that the activity is authorized by nationwide permit.

Preservation: The removal of a threat to, or preventing the decline of, aquatic resources by an action in or near those aquatic resources. This term includes activities commonly associated with the protection and maintenance of aquatic resources through the implementation of appropriate legal and physical mechanisms. Preservation does not result in a gain of aquatic resource area or functions.

Re-establishment: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/historic functions to a former aquatic resource. Re-establishment results in rebuilding a former aquatic resource and results in a gain in aquatic resource area and functions.

Rehabilitation: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of repairing natural/historic functions to a degraded aquatic resource. Rehabilitation results in a gain in aquatic resource function, but does not result in a gain in aquatic resource area.

Restoration: The manipulation of the physical, chemical, or biological characteristics of a site with the goal of returning natural/historic functions to a former or degraded aquatic resource. For the purpose of tracking net gains in aquatic resource area, restoration is divided into two categories: re-establishment and rehabilitation.

Riffle and pool complex: Riffle and pool complexes are special aquatic sites under the 404(b)(1) Guidelines. Riffle and pool complexes sometimes characterize steep gradient sections of streams. Such stream sections are recognizable by their hydraulic characteristics. The rapid movement of water over a course substrate in riffles results in a rough flow, a turbulent surface, and high dissolved oxygen levels in the water. Pools are deeper areas associated with riffles. A slower stream velocity, a streaming flow, a smooth surface, and a finer substrate characterize pools.

Riparian areas: Riparian areas are lands next to streams, lakes, and estuarine-marine shorelines. Riparian areas are transitional between terrestrial and aquatic ecosystems, through which surface and subsurface hydrology connects riverine, lacustrine, estuarine, and marine waters with their adjacent wetlands, non-wetland waters, or uplands. Riparian areas provide a variety of ecological functions and services and help improve or maintain local water quality. (See general condition 23.)

Shellfish seeding: The placement of shellfish seed and/or suitable substrate to increase shellfish production. Shellfish seed consists of immature individual shellfish or individual shellfish attached to shells or shell fragments (i.e., spat on shell). Suitable substrate may consist of shellfish shells, shell fragments, or other appropriate materials placed into waters for shellfish habitat.

Single and complete linear project: A linear project is a project constructed for the purpose of getting people, goods, or services from a point of origin to a terminal point, which often involves multiple crossings of one or more waterbodies at separate and distant locations. The term “single and complete project” is defined as that portion of the total linear project proposed or accomplished by one owner/developer or partnership or other association of owners/developers that includes all crossings of a single water of the United States (i.e., a single waterbody) at a specific location. For linear projects crossing a single or multiple waterbodies several times at separate and distant locations, each crossing is considered a single and complete project for purposes of NWP authorization. However, individual channels in a braided stream or river, or individual arms of a large, irregularly shaped wetland or lake, etc., are not separate waterbodies, and crossings of such features cannot be considered separately.

Single and complete non-linear project: For non-linear projects, the term “single and complete project” is defined at 33 CFR 330.2(i) as the total project proposed or accomplished by one owner/developer or partnership or other association of owners/developers. A single and complete non-linear project must have independent utility (see definition of “independent utility”). Single and complete non-linear projects may not be “piecemealed” to avoid the limits in an NWP authorization.

Stormwater management: Stormwater management is the mechanism for controlling stormwater runoff for the purposes of reducing downstream erosion, water quality degradation, and flooding and mitigating the adverse effects of changes in land use on the aquatic environment.

Stormwater management facilities: Stormwater management facilities are those facilities, including but not limited to, stormwater retention and detention ponds and best management practices, which retain water for a period of time to control runoff and/or improve the quality (i.e., by reducing the concentration of nutrients, sediments, hazardous substances and other pollutants) of stormwater runoff.

Stream bed: The substrate of the stream channel between the ordinary high water marks. The substrate may be bedrock or inorganic particles that range in size from clay to boulders. The substrate may also be comprised, in part, of organic matter, such as large or small wood fragments, leaves, algae, and other organic materials. Wetlands contiguous to the stream bed, but outside of the ordinary high water marks, are not considered part of the stream bed.

Stream channelization: The manipulation of a stream’s course, condition, capacity, or location that causes more than minimal interruption of normal stream processes. A channelized jurisdictional stream remains a water of the United States.

Structure: An object that is arranged in a definite pattern of organization. Examples of structures include, without limitation, any pier, boat dock, boat ramp, wharf, dolphin, weir, boom, breakwater, bulkhead, revetment, riprap, jetty, artificial island, artificial reef, permanent mooring structure, power transmission line, permanently moored floating vessel, piling, aid to navigation, or any other manmade obstacle or obstruction.

Tidal wetland: A tidal wetland is a jurisdictional wetland that is inundated by tidal waters. Tidal waters rise and fall in a predictable and measurable rhythm or cycle due to the gravitational pulls of the moon and sun. Tidal waters end where the rise and fall of the water surface can no longer be practically measured in a predictable rhythm due to masking by other waters, wind, or other effects. Tidal wetlands are located channelward of the high tide line.

Tribal lands: Any lands title to which is either: 1) held in trust by the United States for the benefit of any Indian tribe or individual; or 2) held by any Indian tribe or individual subject to restrictions by the United States against alienation.

Tribal rights: Those rights legally accruing to a tribe or tribes by virtue of inherent sovereign authority, unextinguished aboriginal title, treaty, statute, judicial decisions, executive order or agreement, and that give rise to legally enforceable remedies.

Vegetated shallows: Vegetated shallows are special aquatic sites under the 404(b)(1) Guidelines. They are areas that are permanently inundated and under normal circumstances have rooted aquatic vegetation, such as seagrasses in marine and estuarine systems and a variety of vascular rooted plants in freshwater systems.

Waterbody: For purposes of the NWPs, a waterbody is a “water of the United States.” If a wetland is adjacent to a waterbody determined to be a water of the United States, that waterbody and any adjacent wetlands are considered together as a single aquatic unit (see 33 CFR 328.4(c)(2)).

US Army Corps of Engineers ®
Omaha District

2026 Nationwide Permits
Final Regional Conditions
Omaha District
State of South Dakota

The following Nationwide Permit (NWP) regional conditions will be used in the State of South Dakota. The issuance of the 2026 NWPs was announced in the June 18, 2025, publication of the Federal Register (90 FR 26100); the final action was published in the Federal Register (91 FR 768) on January 8, 2026. Regional conditions are placed on NWPs to ensure projects result in no more than minimal adverse impacts to the aquatic environment and to address local resources concerns.

A. PRECONSTRUCTION NOTIFICATION REQUIREMENTS APPLICABLE TO ALL NWPs

For all NWPs, permittees must notify the Corps in accordance with General Condition 32 Preconstruction Notification (PCN) requirements for regulated activities located within or comprised of the following:

1. Aquatic Resources of Special Concern:

Aquatic resources of special concern are resources that are difficult to replace, unique, and/or have high ecological function. PCN required for any regulated activity located in aquatic resources of special concern that fall into the categories listed below. The District Engineer may authorize activities under NWPs only after determining that the impacts to the following aquatic resources of special concern will be no more than minimal:

a. **Wetlands classified as peatlands:** For the purposes of this condition, peatlands are permanently or seasonally waterlogged areas with a surface accumulation of peat (organic matter) 30 centimeters (12 inches) or more thick. Under cool, anaerobic, and acidic conditions, the rate of organic matter accumulation exceeds organic decay. Any peat-covered areas, including fens, bogs, and muskegs, are all peatlands.

   i. PCN required for NWP 3, 5, 6, 20, 27, 32, 38 and 45.

   ii. All NWPs not listed above are revoked for use in peatlands.

b. **Natural Springs:** Within 100 feet of the water source in natural spring areas. For the purpose of this condition, a spring water source is defined as any location where there is flow emanating from a distinct point at any time during the growing season. Springs do not include seeps and other groundwater discharge areas where there is no distinct point source of waters. Springs do not include drain tile outlets.

2. Tribal Reservations and Tribal Trust Lands:

PCN required for any regulated activity located within Tribal Reservations and Tribal Trust Lands. The following link provides a map showing Tribal Reservations and Tribal Trust Lands: https://onemap-bia-geospatial.hub.arcgis.com/apps/718497a94a15450d8d48b51625dc330f/explore

B. CONSTRUCTION PRACTICES:

1. Suitable Material:

Permittees are reminded of General Condition No. 6 which prohibits use of unsuitable material. A list of materials prohibited or restricted as fill material in waters of the United States within the Omaha District can be found at: http://www.nwo.usace.army.mil/Media/FactSheets/FactSheetArticleView/tabid/2034/Article/12320/ prohibited-restricted-materials.aspx

2. Revegetation of Disturbed Areas:

All jurisdictional waters disturbed by construction shall be revegetated with appropriate perennial, native grasses and forbs and maintained in this condition. Seed mixes shall not include invasive or noxious species. The following link provides information and resources on invasive species: https://www.invasivespeciesinfo.gov/us

3. Culvert Countersinking:

For all NWPs in streams with relatively permanent flow and a stable stream bed, culvert stream crossings shall be installed with the bottom of the culvert set below the natural stream channel flow line. This regional condition does not apply in instances where the lowering of the bottom of the culvert would allow a headcut to migrate upstream of the project into an unaffected stream reach or result in lowering the elevation of the stream reach.

a. The stream's flow line (or the main path of the water) will be determined by calculating the average elevation along the streambed during periods when the stream is at its lowest flow levels.

b. The slope of the culvert should be parallel to the slope of the stream flow line.

c. Riprap inlet and outlet protection shall be placed to match the height of the bottom of the culvert.

DEPARTMENT of AGRICULTURE and NATURAL RESOURCES
JOE FOSS BUILDING
523 E CAPITOL AVE
PIERRE SD 57501-3182
danr.sd.gov

November 24, 2025

Nathan Morey
US Army Corps of Engineers
South Dakota Regulatory Office
28563 Powerhouse Road, Room 118
Pierre, SD 57501

RE: 2026 Renewal Section 404/10 Nationwide Permits
South Dakota 401 Water Quality Certification

Dear Mr. Morey:

The South Dakota Department of Agriculture and Natural Resources (DANR) has reviewed the request for water quality certification under Section 401 of the Clean Water Act regarding the 2026 reissuance of the US Army Corps of Engineers' Nationwide Permits. Section 401 of the Clean Water Act requires this review before a federal permit is granted.

DANR is granting water quality certification for Nationwide Permits #12 (Oil or Natural Gas Pipeline Activities), #57 (Electric Utility Line and Telecommunications Activities), and #58 (Utility Line Activities for Water and Other Substances) with conditions. DANR prohibits the Typical Open Cut Wet Crossing Method (flowing waterbody) in South Dakota waterbodies that have flowing water OR in waters specifically listed in Administrative Rules of South Dakota (ARSD) 74:51:02 or 74:51:03. Other crossing method alternatives include the Dry Flume Method, Dry Dam and Pump Method, and Horizontal Directional Drill. Any other methods not expressly listed must receive prior written approval. The Typical Open Cut Wet Crossing Method consists of digging a trench through the waterbody. This method could cause high sediment suspension in the water body and result in high sediment transport during the digging process, while the trench is stabilizing in the waterbody, and when the trench is backfilled and the pipeline is buried. This crossing method is prohibited because DANR cannot certify that water quality will be protected if that crossing method is used.

Additionally, if horizontal directional drilling is used, the applicant must prepare an emergency response and remediation plan for use in the event of a spill or frac-out. Spills and frac-outs must be reported to DANR at (605) 773-3296 (605-773-3231 after hours).

These conditions are required to ensure compliance with surface water quality standards including ARSD 74:51:01:06; 74:51:01:12, and 74:51:01:45-49; and South Dakota Codified Laws (SDCL) 34A-2-10 and 34A-2-11.

DANR is granting water quality certification for Nationwide Permit #16 (Return Water from Upland Contained Disposal Areas) with conditions. The project proponent must properly install, operate, and maintain sediment and erosion controls surrounding all dredged disposal areas. Best management practices must be in place to ensure that return water does not violate any surface water quality standards under ARSD 74:51:01-03. The return water shall not contain toxic pollutants in toxic amounts (ARSD 74:51:01:55), shall not cause a sheen or film on the receiving water (ARSD 74:51:01:10); shall not contain visible pollutants (74:51:01:06), shall not contain sediment in excess of state water quality standards, (74:51:01:45-49), and shall not impact the biological integrity of the receiving waters (ARSD 74:51:01:12). To ensure compliance, the applicant shall develop a DANR-approved water quality monitoring plan and submit weekly compliance reports to DANR. These conditions are collectively required to ensure compliance with surface water quality standards and are supported under ARSD 74:51:01 and SDCL 34A-2-10, 34A-2-11, and 34A-2-21.

DANR is granting water quality certification for Nationwide Permits #19 (Minor Dredging), #27 (Aquatic Ecosystem Restoration, Enhancement, and Establishment Activities), #35 (Maintenance Dredging of Existing Basins), #53 (Removal of Low-Head Dams), and Nationwide A with conditions. Under ARSD 74:51:01.60, DANR approval is required on water resource enhancement or restoration projects. A public notice published in a local newspaper serving the project areas is required by ARSD 74:51:01:60 to inform the public and solicit comments on the proposed project. The applicant must submit the required information detailed in ARSD 74:51:01:60 for DANR review and approval before the project can begin. Therefore, DANR will grant 401 certification of Nationwide Permits #19, 27, 35, 53, and A with the condition that the project proponent gain project approval through DANR. More information is available at: https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/waterqualitystandards/swqrestoration.aspx.

Water resource enhancement and restoration project approval is necessary to ensure that the project will adequately address restoration/enhancement objectives, provide appropriate erosion control Best Management Practices to protect water quality, and provide the public the opportunity to comment on the project activities.

The project proponent must properly install, operate, and maintain sediment and erosion controls surrounding all dredged disposal areas and install, operate, and maintain sediment control barriers within the affected waterbody. Additionally, project construction notification is required for these NWP authorizations. These conditions are required under ARSD 74:51:01.60 and are supported under SDCL 34A-2-10 and 34A-2-11.

DANR is granting water quality certification for Nationwide Permits #29 (Residential Developments) and #39 (Commercial and Institutional Developments) with conditions. Nationwide Permits #29 and #39 allow attendant features, including the construction of on-site septic systems in wetland areas. DANR has determined that these attendant features conflict with state water pollution control laws and regulations. Allowing this type of activity compromises the integrity of the state's surface and ground water resources and the state's efforts to protect them. Therefore, DANR will grant 401 certification of Nationwide Permits #29 and #39 with the condition that the project proponent follow all rules under ARSD 74:53:01 and SDCL 34A-2-20 through 34A-2-22, and 34A-2-93. These conditions are supported by ARSD 74:53:01 and SDCL 34A-2-1, 34A-2-20 through 22, 34A-2-36, 34A-2-36.1, and 34A-2-104.

DANR is granting water quality certification for Nationwide Permits #29 (Residential Developments), #39 (Commercial and Institutional Developments), #40 (Agricultural Activities), #42 (Recreational Facilities), #43 (Stormwater Management Facilities), #51 (Land-Based Renewable Energy Generation Facilities), and #52 (Water-Based Renewable Energy Generation Pilot Projects) with conditions. DANR is granting water quality certification for Nationwide Permits # 29, 39, 40, 42, 43, 51, and 52 with the condition that a maximum 300 linear foot limit be placed on impact. This condition applies to all waters of the state. This is measured along the ordinary high-water mark along the shoreline of a lake or reservoir. For a wetland, this is measured along the delineated boundary between wetland characteristics and upland. Along a stream, creek, or river, the 300 linear feet is measured along the center of the streambed. This limit is necessary to ensure that the project does not individually or cumulatively result in more than minimal adverse impacts to water quality. South Dakota has many small intermittent and perennial streams that are narrow in width. Simply using the ½ acre limit to apply to these Nationwide Permits would not adequately protect small South Dakota Streams and could potentially result in the loss of hundreds or thousands of miles of small South Dakota streams. Under SDCL 34A-2-1, the public policy is to conserve the waters of South Dakota and to protect, maintain, and improve the quality thereof for water supplies, for the propagation of wildlife, fish, and aquatic life. Not having any maximum linear limit to this Nationwide Permit does not meet the stated policy of SDCL 34-A-2-1.

The following general conditions apply to all Nationwide Permits:

1) Coverage under the General Permit Authorizing Stormwater Discharges Associated with Construction Activities (aka: Construction General Permit, CGP) must be obtained from DANR if construction activities disturb one or more acre of land. A copy of the general permit and the notice of intent for coverage are available on DANR's website at: https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/StormWaterConstruction.aspx.

   This requirement is authorized under Administrative Rule of South Dakota (ARSD) 74:52:02:36 and South Dakota Codified Law (SDCL) 34A-2-36.

2) Excavated and dredged material from wetland areas must be removed and disposed of in an upland location away from streams and wetlands. Return water from excavated or dredged material may not be allowed to re-enter waters of the state without authorization of a DANR-approved water quality monitoring plan (see NWP #16 conditions). This condition is authorized under ARSD 74:51:01:12 and SDCL 34-A-2-21.

3) Methods shall be implemented to minimize the spillage of petroleum, oils, and lubricants used in equipment, machinery, and vehicles during construction activities. If a spill occurs during construction activity, that spill must be reported to DANR at (605) 773-3296 (605-773-3231 after hours). These materials may not be discharged or caused to be discharged into waters of the state per ARSD 74:51:01:06 and 74:51:01:10 and SDCL 34A-2-93.

DANR is waiving certification for Nationwide Permit #34 (Cranberry Production Activities), #48 (Commercial Shellfish Mariculture Activities), #54 (Living Shorelines), and #55 (Seaweed Mariculture Activities). These activities are unlikely to occur in South Dakota.

DANR is denying water quality certification for Nationwide Permit #21 (Surface Coal Mining Activities), #44 (Mining Activities), #49 (Coal Remining Activities), and #50 (Underground Coal Mining Activities). State law directs any disturbances to the prevailing hydrologic cycle, including water quality and quantity, be minimized during mining and reclamation activities. DANR cannot certify that the uncontrolled use of these permits would result in minimal disturbance or meet state surface water quality standards due to the potential of acid rock drainage or metal-laden waters occurring in mining areas. Nationwide Permits #21, #44, #49, and #50 conflict with state water pollution control laws and regulations that require activities be permitted and follow strict guidelines. This denial is based upon ARSD 74:11, 74:12, 74:29, SDCL 45-6B-41, 45-6B-81, and the potential inability of mining operations to adequately protect surface waters under ARSD 74:51:01.

DANR is granting water quality certification for all other Nationwide Permits not expressly listed with conditions, waived, or denied. DANR has determined that any potential discharge associated with the Nationwide Permits, following the Corps' limits and notification requirements, general guidelines, and regional conditions will comply with South Dakota water quality standards.

This certification has met applicable public notice requirements per ARSD 74:51:01:64, 74:51:01:64.01, 74:51:01:64.02, and 74:51:01:64.03 pursuant to CWA 401(a)(1).

South Dakota's water quality certification is based upon the draft 2026 Nationwide Permits published in the Federal Register. The Corps is requiring the water quality certification to be completed while the Nationwide Permits are still under public comment and prior to the final permits being published.

If you have questions pertaining to this certification, please contact Shannon Minerich at Shannon.Minerich@state.sd.us. Thank you for ensuring the continued protection of our natural resources.

Sincerely,

Hunter Roberts
Secretary

cc: Estella Moore, US EPA, Denver
Aaron M. Blair, US EPA, Denver

REGION 8
DENVER, CO 80202

December 16, 2025

SENT VIA EMAIL

Nathan Morey
U.S. Army Corps of Engineers
Omaha District
South Dakota Regulatory Office
Nathan.M.Morey@usace.army.mil

RE: Clean Water Act Section 401 Water Quality Certification of the U.S. Army Corps of Engineers 2026 Nationwide Permits in South Dakota

Dear Mr. Morey:

Please find enclosed the water quality certification decisions consistent with Section 401 of the Clean Water Act (CWA) for the reissuance of the Nationwide Permits (NWP). On June 18, 2025, the U.S. Environmental Protection Agency, Region 8 received the U.S. Army Corps of Engineers' requests for water quality certification under CWA Section 401 for the proposed 2026 NWPs. The EPA reviewed the June 18, 2025, Federal Register[1] notice announcing the reissuance of the NWPs, along with the regional conditions proposed by the Omaha District for South Dakota. The enclosed CWA section 401 water quality certification decision applies where the EPA is the certifying authority and includes Indian country[2] lands within the state of South Dakota[3] and lands of exclusive federal jurisdiction in relevant respects within the state of South Dakota.[4]

[1] See 90 FR 26100 (June 18, 2025).
[2] Indian country is defined at 18 U.S.C. § 1151.
[3] Indian country in South Dakota generally includes (1) lands within the exterior boundaries of the following Indian reservations located within South Dakota: the Cheyenne River Reservation, the Crow Creek Reservation, the Flandreau Indian Reservation, the Lower Brule Reservation, the Pine Ridge Reservation, the Rosebud Indian Reservation, the Standing Rock Reservation, and the Yankton Reservation (subject to federal court decisions removing certain lands from Indian country status within the Yankton Reservation); (2) any land held in trust by the United States for an Indian Tribe (including but not limited to the Sisseton-Wahpeton Oyate Tribe and the Turtle Mountain Band of Chippewa Indians); and (3) any other areas that are "Indian country" within the meaning of 18 U.S.C. Section 1151. The enclosed CWA Section 401 certification document specifies where these decisions apply.
[4] An inventory report compiled by the U.S. General Services Administration for federal properties as of 1962 identifies properties that may contain exclusive federal jurisdiction. This document is accessible at https://www.congress.gov/116/meeting/house/110088/documents/HHRG-116-II13-20191017-SD044.pdf. The EPA notes that this inventory report is not all-inclusive and that the information contained within it has not been recently confirmed

Please provide this certification to any project proponent (or their designated agent) contacting the Corps regarding applicable projects that may be authorized under the 2026 NWPs. If a project proposal does not meet either the general or NWP-specific certification conditions contained herein, the project proponent must request an individual certification from EPA Region 8 at R8CWA401@epa.gov. Project proponents are encouraged to contact EPA Region 8 during the project planning phase if there are any questions about relevant best management practices (e.g., bioengineering techniques, biodegradable erosion control measures, revegetation using native plant species, suitable fill materials, and disposal of debris/construction materials preventing runoff) and resources that can assist with compliance. Prior to work commencing, EPA recommends that project proponents notify the appropriate Tribal Environmental Office, if applicable.

Thank you for your ongoing partnership and coordination in implementing CWA regulatory programs. Please contact Tanya Code with any questions at (303) 312-6110 or Code.Tanya@epa.gov. If your staff have questions, please have them contact Estella Moore at (303) 312-6357 or R8CWA401@epa.gov.

Sincerely,

Stephanie DeJong, Manager
Clean Water Branch

Enclosure

CC: David Nelson, Environmental Program Director, Cheyenne River Sioux Tribe
Wanda Gourneau, Environmental Program Director, Crow Creek Sioux Tribe
Terance Elder, Water Quality Coordinator, Flandreau Santee Sioux Tribe
Mary Jane Gourneau, Environmental Director, Lower Brule Sioux Tribe
Delinda Simmons, Acting Environmental Director, Oglala Sioux Tribe
Ivan Crow Eagle, Environmental Program Director, Rosebud Sioux Tribe
Scott Walz, Director of Natural Resources, Shakopee Mdewakanton Sioux Community
Darin Wright, Water Quality Coordinator, Sisseton-Wahpeton Oyate
Adam Rookey, Environmental Director, Standing Rock Sioux Tribe
Faye Corey, Acting Environmental Director, Yankton Sioux Tribe
Kerryanne Weaver, Wetland Section Supervisor, EPA Region 5

and/or updated. Please contact EPA Region 8 at R8CWA401@epa.gov with questions regarding the jurisdictions where this certification decision applies.

U.S. Environmental Protection Agency Region 8's Clean Water Act Section 401 Certification of the 2026 Nationwide Permits in the State of South Dakota

December 16, 2026

Clean Water Act (CWA) Section 401 requires applicants for Federal licenses or permits to conduct any activity which may result in any discharge into waters of the United States to obtain a certification or waiver from the certifying authority where the discharge originates or will originate. Where no state or Tribe has authority to give such certification, the U.S. Environmental Protection Agency is the certifying authority. 33 U.S.C. 1341(a)(1). In this case, the Cheyenne River Sioux Tribe, Crow Creek Sioux Tribe, Flandreau Santee Sioux Tribe, Lower Brule Sioux Tribe, Oglala Sioux Tribe, Rosebud Sioux Tribe, Sisseton-Wahpeton Oyate, Standing Rock Sioux Tribe, and Yankton Sioux Tribe do not have authority to provide CWA Section 401 certifications for projects occurring on their reservations, or any other Indian country lands[1], within the State of South Dakota. The Turtle Mountain Band of Chippewa Indians and the Shakopee Mdewakanton Sioux Community also do not have that authority for their Tribal trust lands within the State of South Dakota. Therefore, the EPA is making the CWA Section 401 certification decision for the 2026 Nationwide Permit reissuance in Indian Country in the state of South Dakota. Additionally, the state of South Dakota does not have authority to provide CWA section 401 certification for project lands of exclusive federal jurisdiction in relevant respects.[2] Therefore, EPA is also making the certification decision for the 2026 NWP reissuance for projects within lands of exclusive federal jurisdiction in relevant respects that may be authorized under the 2026 NWPs.

[1] Indian country in South Dakota generally includes (1) lands within the exterior boundaries of the following Indian reservations located within South Dakota: the Cheyenne River Reservation, the Crow Creek Reservation, the Flandreau Indian Reservation, the Lower Brule Reservation, the Pine Ridge Reservation, the Rosebud Indian Reservation, the Standing Rock Reservation, and the Yankton Reservation (subject to federal court decisions removing certain lands from Indian country status within the Yankton Reservation); (2) any land held in trust by the United States for an Indian Tribe (including but not limited to the Sisseton-Wahpeton Oyate Tribe and the Turtle Mountain Band of Chippewa Indians); and (3) any other areas that are "Indian country" within the meaning of 18 U.S.C. Section 1151.

[2] An inventory report compiled by the U.S. General Services Administration for federal properties as of 1962 identifies properties that may contain exclusive federal jurisdiction. This document is accessible at https://www.congress.gov/116/meeting/house/110088/documents/HHRG-116-II13-20191017-SD044.pdf. The EPA notes that this inventory report is not all-inclusive and that the information contained within it has not been recently confirmed and/or updated. Please contact EPA Region 8 at R8CWA401@epa.gov with questions regarding the jurisdictions where this certification decision applies.

Project Description

On June 18, 2025, the Corps proposed to reissue 56 NWPs and 1 new NWP that would expire in March 2026. 90 FR 26100 (June 18, 2025). The purpose of the NWPs is to authorize categories of activities under CWA Section 404 and Section 10 of the Rivers and Harbors Act of 1899 that have no more than minimal individual and cumulative adverse environmental impacts. For more details see: https://www.usace.army.mil/Missions/Civil-Works/Regulatory-Program-and-Permits/Nationwide-Permits/.

The EPA's Public Notice Process

On June 18, 2025, the EPA received a request for certification from the project proponent. On July 2, 2025, the EPA issued a public notice regarding the proposed project and provided the opportunity for the public to submit comments until August 2, 2025. EPA received no public comments during the public notice period.

General Information

The general information provided in this section does not constitute a certification condition(s).

General Applicability

- The Corps did not request for certification for NWPs 1, 2, 8, 9, 10, 11, 24, 28, 35 and 55, and as such, the certification process did not begin and EPA neither certified nor waived certification. Consequently, if any activity authorized by this NWP may result in a discharge into a water of the United States, on lands that EPA acts as the certifying authority, the Corps must seek CWA 401 certification from EPA.
- If a project proposal does not meet either the general or NWP-specific certification conditions, or if certification is denied for a specific NWP, the project proponent must request an individual certification from EPA Region 8.

Documentation Recommendations

- Project proponents for potential projects authorized under the NWPs should retain this certification in their files with the applicable NWPs as documentation of EPA's certification decisions for the above-referenced proposed NWPs. This certification is specifically associated with the proposed NWPs described above and expires when those NWPs expire, five years from Corps issuance date, or are otherwise superseded by subsequent reissuance if less than five years.
- Copies of this certification should be kept on the job site and made readily available for reference.

Contact Information

- The project proponents for potential projects authorized under an NWP are encouraged to contact EPA Region 8 during the project planning phase if there are any questions about relevant best management practices (e.g., bioengineering techniques, biodegradable erosion control measures, revegetation using native plant species, suitable fill materials, and disposal of debris/construction materials preventing runoff) and resources that can assist with compliance.

- Prior to work commencing, EPA recommends that project proponents notify the appropriate Tribal Environmental Office, if applicable.
- In the case of a spill, EPA recommends that the project proponent notify EPA Region 8 within 8 hours from discovery. For emergency spills, EPA recommends that the project proponent contact the EPA's National Response Center at 1-800-424-8802 as well as the appropriate personnel identified in the project's Spill Prevention Control and Countermeasures, or similar plan, if applicable.
- If you have any questions regarding this certification, please contact R8CWA401@epa.gov.

Waiver of Certification

EPA Region 8 is expressly waiving its authority to act on the CWA § 401 request for certification for NWPs 4, 22, 34, 48, and 54.

Grants of Certification without Conditions

EPA is granting certification without conditions for NWPs 5, 20, 27, and 32. For NWPs that EPA grants certification without conditions, EPA has determined that the activity will comply with the applicable water quality requirements, including any limitation, standard, or other requirement under sections 301, 302, 303, 306, and 307 of the CWA; any Federal and State or Tribal laws or regulations implementing those sections; and any other water quality-related requirement of State or Tribal law.

Grants of Certification with Conditions

EPA is granting certification with conditions for NWPs 3, 6, 7, 12, 13, 14, 15, 16, 17, 18, 19, 21, 23, 25, 29, 30, 31, 33, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 49, 50, 51, 52, 53, 57, 58, 59, and A. For NWPs that EPA grants certification with conditions, EPA has determined that the activity will comply with the applicable water quality requirements, including any limitation, standard, or other requirement under sections 301, 302, 303, 306, and 307 of the CWA; any Federal and State or Tribal laws or regulations implementing those sections; and any other water quality-related requirement of State or Tribal law, subject to the conditions listed under the NWP below, pursuant to CWA Section 401(d).

Condition #1: Plan Development and Implementation for Projects that require Pre-Construction Notification (PCN)

Prior to construction for projects that require a PCN, the project proponent shall develop a plan that includes a copy of the PCN and the following information (if not already included in the PCN):

- Time stamped photo-documentation of the baseline conditions (i.e., 50 feet upstream of the project area, within the project area, and 100 feet downstream of the project area).
- Identifies on a site map, as applicable:
  - Project site with all waters of the U.S. demarcated. Identify all locations where the project will cross jurisdictional waterbodies and identify the ordinary high-water mark and/or wetland boundaries; the planned work area where wetlands/aquatic resources will be removed, disturbed, and/or protected; buffer zones; and areas to be

restored/reclaimed, as well as site access points and other approved work areas.
    - Staging areas and stockpiling of materials and equipment, including locations for containment booms and/or absorbent materials, and/or hazardous materials. Stockpiles (e.g., sediment, soil, or other construction materials) shall be stored at least 50 feet from where it may enter waters of the U.S.
    - Construction access points.
    - Disturbance limits.
    - Locations where site dredging and placement of dredged material activities will occur.
    - Locations where dewatering activities will occur including as applicable locations of cofferdams, temporary berms, piling, and/or dikes.
    - Locations of undergrounding or directional drilling (including bore pits).
    - Locations where hazardous materials are stored. Identify where containment booms and/or absorbent materials are located for corrective action if needed. Hazardous materials shall be stored in leak-proof containers with appropriate secondary containment measures (e.g., spill berms, dikes, spill containment pallets, absorbent materials).
    - Any silt/sediment fencing.
    - Photo-reference sites. The project proponent shall indicate the directional view and location where photos were taken on the site map.
- A description of how the site will be restored to pre-construction conditions, as applicable, including measures that will be used to promote and maintain:
    - Stream hydrology and stability.
    - Aquatic resource composition.
    - Diversity of native species existing on site and as introduced via restoration activities.
    - Stability of soils.
    - Establishment of vegetation at the same percent cover as pre-construction activities.
- The timeframe/schedule for revegetation following completion of construction. Revegetation should occur at the earliest practicable date following completion of construction. Drill seeding is the preferred method, where applicable.
- Non-native and invasive species shall not be used for restoration activities.
- Includes the following, as applicable:
    - <u>Cofferdams, temporary berms, pilings, and/or dikes</u>: Describe installation and maintenance practices for any cofferdams, temporary berms, pilings, and/or dikes.
    - <u>Dredging</u>: Describe how contaminated materials will be managed (e.g., sediment testing data and information to identify whether sediments are clean or contaminated), if included in the project dredged area. Describe methods for minimizing dredging impacts (*i.e.*, sedimentation resuspension) in the water column.
    - <u>Erosion and sediment control</u>: Identify the types and locations of sediment and erosion control features that shall be used onsite, including sediment control fences, haybales, heavy mud mats, and/or other structures. Biodegradable blankets and/or loose-weave mesh shall be used for erosion control matting. If using velocity dissipation structures (e.g., riprap aprons, check dams etc.), structures shall be constructed to include both peak flow rates and total stormwater volume, and provide protection from the erosive potential of high-velocity flows to minimize channel and streambank erosion and scour

in the immediate vicinity of discharge points. The project proponent shall ensure all erosion and sediment control measures are in place prior to the onset of construction.
    - Bank stabilization and channel modification: If the project requires bank stabilization or stream channel modification, include pre-construction cross sections. If the project includes steep bank slopes of 3:1 or greater, include revetment cross sections. Bioengineering techniques suitable for steep slope disturbances are preferred (e.g., vegetated toe, bioengineered boulder toe, etc.) Slopes of disturbed banks shall be designed and installed to not reduce the bottom width of the stream.
    - Dewatering: Work shall be completed in the dry unless coordinated with EPA Region 8. Describe methods for dewatering, including the equipment that would be used to conduct the dewatering activities. Identify the locations and timing, including length of time the area is to be dewatered. Explain removal method of the temporary structures and/or fill and what measures will be taken to minimize downstream turbidity and adaptive management measures that will be taken and employed to prevent the draining of waters of U.S., including wetlands.
    - Ditching and trenching: Explain ditching/trenching and material placement techniques and stabilization methods to be employed, as well as timing. In wetlands, the top 6 to 12 inches of the ditch/trench shall be backfilled with topsoil from the trench, unless other techniques are approved. Include activity timing needs for ditching and stabilization.
    - Undergrounding or directional drilling: Describe measures taken to prevent, contain and cleanup any inadvertent return of drilling fluid to the surface (i.e., "frac-outs").
- Submit the plan to EPA Region 8 at R8CWA401@epa.gov at least 30 days prior to commencing construction activities.

During construction for projects that require a PCN, the project proponent shall:

- Visually inspect construction activities daily.
- Prevent sediment, debris, silt, sand, cement, concrete, oil or petroleum, organic materials, or other construction debris or wastes from entering waters of the U.S. The discharge of unset cement, concrete, grout, or water that has contacted uncured concrete or cement, or related washout to waters of the U.S. is prohibited.
- Maintain documentation onsite that all equipment was cleaned of dirt, mud, and other materials prior to arriving on the project site.
- Inspect all equipment daily and prior to entering any waters of the U.S. for oil, gas, diesel, anti-freeze, hydraulic fluid, and other petroleum leaks. If the project proponent detects a leak from any equipment, they shall immediately remove the equipment from waters of the U.S.; and within 24 hours of detection of a leak, repair the equipment in a staging area or move it offsite.
- Limit vegetation clearing and disturbance to waters. Limit the clearing and grubbing of vegetation and disturbance to areas demarcated on the site map submitted as part of the vegetation restoration and monitoring plan. The boundaries of vegetation to protect shall be flagged in the field prior to beginning construction activities.
- Limit restoration of the channel bed to pre-existing contours and conditions. Any proposed deviations must be specified in advance. For example, if any improvements will be made

using natural channel design.

- Photo-document any failures or increased turbidity due to construction activities.
  - Within 24 hours of observing a failure or marked increase in turbidity associated with construction, the project proponent shall remedy and implement any additional adaptive management measures to stabilize the activity and prevent further unauthorized discharges into waters of the U.S. The project proponent shall photo-document the failure (i.e., 50 feet upstream of failure, at the incident site, and at least 100 feet downstream of the failure) and the adaptive management measures taken immediately following implementation. The project proponent shall take remediation condition photos at the same location(s) and direction(s) as in the failure condition photos.
  - Within 48 hours of observing any failure, the project proponent shall provide EPA Region 8 with the required photo-documentation, and descriptions of all observed failures and implemented remedies.
  - Within three weeks of observing a failure, the project proponent shall provide EPA Region 8 with a description of the impacts and effectiveness of the employed adaptive management measures.
- Carry out as applicable:
  - Erosion control: Inspect sediment and erosion control measures daily during project implementation and within 12 hours of precipitation events. After construction is complete, remove sediment and erosion control structures once vegetation is established to the same percent cover as pre-construction conditions, unless they are needed for long term stabilization purposes.
  - Dewatering: Assess all dewatering measures within 24 hours after a severe storm event.

Post construction for projects that require a PCN, the project proponent shall, as applicable:

- Submit a post-construction report, as defined below, within 90 days of completing construction activity to EPA Region 8 at R8CWA401@epa.gov or, if the Corps requires a post-construction report for the project activity, the applicant may submit that report to EPA to fulfill this post-construction requirement. The project proponent shall include the following items in the post-construction report:
  - Construction dates.
  - As-built drawings.
  - Documentation of site restoration activities using photographs and any field data sheets showing that the site was restored to pre-existing conditions or better. Include photographs of the site restoration areas on a map.
  - Any water quality data gathered before, during, and post-construction and associated maps showing the sample locations.
  - A description of any adaptive management strategies that were employed during construction, with a focus on strategy effectiveness.
  - Details on the removal of any sediment and erosion control structures, unless they are needed for long term stabilization purposes.
  - Effectiveness of the plan developed and implemented as required under this condition, and recommendations to remedy any deficiencies in plan development and

implementation where employed measures were ineffective.

- For activities that require dredging, submit a copy of the as-builts and a post dredged and disposal report within 45 days of each dredging or disposal event to EPA Region 8 at R8CWA401@epa.gov. The project proponent shall include the following items in the post-dredged and disposal report:
  - Dredging and disposal dates.
  - Updated site map displaying the disposal location(s).
  - Dredging and disposal volumes.
  - Water quality monitoring data.
  - Post-dredged bathymetry.
  - Updated site maps displaying any new ditches, spoil piles, widths, and depths.

Why these conditions are necessary: This condition is necessary to minimize suspended particulates /turbidity caused by construction activities and is necessary to ensure water quality is not degraded by toxic pollutants in toxic amounts, including construction materials, oil, grease, gasoline, or other types of fluids used to operate and maintain equipment used to complete the project, or discharges from dust abatement activities as well as contaminants in dredged material. This condition also appropriately minimizes impacts from access roads, staging areas, and stockpiling to further ensure that construction activities will result in no more than minimal individual and cumulative adverse environmental effects. This condition will protect water quality because it ensures that the project proponent is using planning and construction practices that will maintain the integrity of the site hydrology and maintain the aquatic resource functions and values and ensures that appropriate revegetation measures are used to re-establish riparian/wetland vegetation to minimize the adverse impacts of discharges of sediment and pollutants that enter waterways. Limiting the amount of vegetation that is disturbed will minimize the adverse environmental impacts of any potential discharges. Monitoring for at least three growing seasons, or until replanted areas meet monitoring success criteria, will provide an adequate indication that the restoration effort is able to demonstrate restoration is successful.

The general conditions in the Corps' NWP package do not address concerns about resuspension and turbidity caused by construction and dredging activities, thereby justifying the inclusion of this condition. GC 32 only requires agency coordination in certain circumstances. Additionally, GC 11 (equipment), GC 12 (soil erosion and sediment controls), and GC 13 (removal of temporary structures and fills) provide some aquatic resource protections, but greater specificity is needed to determine what measures are suitable to comply with applicable water quality requirements.

Citations: 33 U.S.C. 1341(a)(4); 40 CFR 230.10(c)-(d);40 CFR 230.10(d); 40 CFR 230.21(a); 40 CFR 230.70; 40 CFR 230.71; 40 CFR 230.72; 40 CFR 230.74; 40 CFR 230.75; Tribal Water Quality Requirements[3]

Condition #2: Special Aquatic Resources

Projects or activities expected to have potential discharges into the below special aquatic resources areas are not covered by this certification and applicants must request a project-specific CWA Section 401 certification from EPA Region 8 consistent with 40 CFR 121.5.

- **Wetlands Classified as Peatlands**: For the purposes of this condition, peatlands are permanently or seasonally waterlogged areas containing organic soils classified as a Histosol with a specific thickness of an accumulation of peat (i.e., organic matter) and include fens, bogs and muskegs.[4]
- **Natural Springs**: Within 100 feet of the water source in natural spring areas. For the purposes of this condition, a spring water source is defined as any location where there is flow emanating from a distinct point at any time during the growing season. Some examples of spring-fed wetlands are hanging gardens. Some examples of spring-fed headwater slopes are peat-accumulating wet meadows and fens (see above). These resources may be identified using U.S. Fish and Wildlife Service's online digital National Wetland Inventory maps, or other aquatic resource mapping tools.
- **Riffle and Pool Complexes**: For the purposes of this condition, riffle and pool complexes are steep gradient sections of streams recognizable by their hydraulic characteristics. The rapid

[3] Oglala Sioux Tribe: Water Quality Management Code, Antidegradation Policy § 1-2-206. Rosebud Sioux Indian Tribe: Title 19: Environmental Protection § 19-6-103 and § 19-6-104. Sisseton-Wahpeton Oyate: Title III Water Quality: Section 61-03-08, Antidegradation Policy, Narrative WQS. Standing Rock Sioux Tribe: WQS Sections 3(a) designated uses, Section 4(a)(5) criteria, Section 9 Narrative WQS, Section 10 Outstanding Tribal Resource Waters, and Section 11 Antidegradation Policy and Review Process; Cultural Resource Ordinance 189; Section 9-1501 establishes "Protected Areas... for fish and wildlife management, propagation, (or) scientific research." Section 9-1502 may include wetlands "to offset losses" and protect under Sections 9-1501 and 9-1502.

[4] It is a general rule that a soil is classified as an organic soil (Histosol) if more than half of the upper 80 cm (32 inches) of the soil is organic or if organic soil material of any thickness rests on rock or on fragmental material having interstices filled with organic materials. Generally, organic soil materials have organic carbon content by weight of 12 percent or more. See the following for more information on what constitutes "organic soil material", limits between Histosols and soils of other orders, problematic hydric soils situations, and other indicators to identify peatlands: Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service. U.S. Department of Agriculture Handbook 436. https://www.nrcs.usda.gov/resources/guides-and-instructions/soil-taxonomy; United States Department of Agriculture, Natural Resources Conservation Service. 2025. Hydric soils of problematic conditions and altered materials, Version 1.0. https://usace.contentdm.oclc.org/utils/getfile/collection/p266001coll1/id/11824; United States Department of Agriculture, Natural Resources Conservation Service. 2024. Field Indicators of Hydric Soils in the United States, Version 9.0. https://www.nrcs.usda.gov/sites/default/files/2024-09/Field-Indicators-of-Hydric-Soils.pdf.

movement of water over a coarse substrate in riffles results in a rough flow, a turbulent surface, and high dissolved oxygen levels in the water. Pools are deeper areas associated with riffles. Pools are characterized by a slower stream velocity, a steaming flow, a smooth surface, and a finer substrate.

- **Wild rice (*Manoomin/Manomin*) Waters:** Wild rice is especially sensitive to changes in water quality, hydrology changes, competition with invasive plants, and habitat loss.[5]

Why this condition is necessary: This condition is necessary to ensure a case-by-case review of any point source discharges into waters of the United States that are proposed in these specific aquatic resource site types which are inherently difficult to replace and have important ecological functions and values. Discharges into these systems have the potential to alter water circulation patterns and hydroperiods, release nutrients causing shifts in native to non-native species composition, release chemicals that adversely impact biota (plants and animals), increase turbidity levels, reduce light penetration and photosynthesis, or otherwise change the capacity of these systems to support aquatic life uses and other beneficial uses of these special aquatic sites, including impairing their diverse and unique communities of aquatic organisms, including fish, wildlife and the habitats upon which they depend. Project specific information is needed to ensure compliance with water quality requirements.

Citations: 40 C.F.R. 230.1(d); 40 C.F.R. 230.10(a)(3); 40 C.F.R. 230.10(c); 40 C.F.R. 230.10(d); 40 C.F.R. 230.20-24; 40 C.F.R. 230.21-22; 40 CFR 230.41; 40 C.F.R. 230.45; 40 C.F.R. 230.75(c); Tribal Water Quality Requirements[6]

Condition #3: Specific Condition for Bridges for NWPs 3, 14, 15, 57, 58 and A

Project proponents shall use an established bridge analysis and hydraulic design tool when designing and constructing bridges (e.g., HEC-RAS, FHWA, etc.). Bridges shall be constructed in a manner such that stormwater does not drain directly into the waterbody. Bridges shall span greater than or equal to 1.2 times the bankfull width and adjacent wetlands of the affected waterbody, where feasible. Crossings shall be placed perpendicular to the direction of the stream flow where possible and account for potential future lateral migration in the stream, unless the project proponent can document that this would result in increased impacts to aquatic resources or compromise the safety of the structure.

---

[5] https://plants.usda.gov/DocumentLibrary/plantguide/pdf/pg_ZIAQ.pdf, last visited 11 Dec 2025.

[6] Oglala Sioux Tribe: Water Quality Management Code, Antidegradation Policy § 1-2-206. Rosebud Sioux Indian Tribe: Title 19: Environmental Protection § 19-6-103 and § 19-6-104. Sisseton-Wahpeton Oyate: Title III Water Quality: Section 61-03-08, Antidegradation Policy, Narrative WQS. Standing Rock Sioux Tribe: WQS Sections 3(a) designated uses, Section 4(a)(5) criteria, Section 9 Narrative WQS, Section 10 Outstanding Tribal Resource Waters, and Section 11 Antidegradation Policy and Review Process; Cultural Resource Ordinance 189; Section 9-1501 establishes "Protected Areas... for fish and wildlife management, propagation, (or) scientific research." Section 9-1502 may include wetlands "to offset losses" and protect under Sections 9-1501 and 9-1502.

Why this condition is necessary: This condition is necessary to ensure that discharges associated with bridge design and placement minimally affect water quality and aquatic resource functions and values. Perpendicular stream crossings minimize the impacts of bank erosion and scouring from length of stream bed and bank impacts for a project. Drainage directly from the bridge decks may cause erosion and scouring, and introduce additional pollutants, such as oil, gas, sediment, and toxics. Directing bridge deck drainage into constructed runoff water quality control systems will help prevent erosion and keep pollutants from directly entering the waterway. This condition will ensure that physical habitat and hydrologic characteristics of waters are not degraded, will maintain the habitat and biology of the waters and will ensure the hydrogeomorphology is not negatively impacted by the project.

Citation: 40 CFR 230.10(d); 40 CFR 230.72; 40 CFR 122.26; Tribal Water Quality Requirements[7]

Condition #4: Specific condition for NWP 7

Outfall design and placement shall include an appropriate energy dissipation structure (e.g., rip rap aprons) and shall be sized to prevent high pressure discharge. For intake structures, project proponents shall use an intake screen that reduces the size of aquatic organisms that can be entrained (e.g., a Johnson-type screen/intake), where feasible. Intake velocities shall not exceed 0.5 feet per second.[8]

Why this condition is necessary: This condition is necessary to ensure that outfall structures and intakes are constructed such that they provide localized erosion control at the point(s) of discharge while minimizing habitat degradation and assimilative capacity of the waterbody. Erosion from outfall structures due to improperly designed and placed structures increases sedimentation that alters stream and wetland hydrology (e.g., scouring and deposition) and uncontrolled stormwater contaminants harm aquatic organisms and habitat. Impingement controls for intake structures reduce the size of aquatic organisms that can be entrained and minimize impacts to aquatic species.

Citations: 40 CFR 230.10(c)-(d); 40 CFR 230.30; 40 CFR 230.70; 40 CFR 230.73; 40 CFR 230.74; 40 CFR 230.75; Tribal Water Quality Requirements[9]

---

[7] Ibid.

[8] Additional guidance on water intakes is available from the U.S. Fish and Wildlife Service: https://www.fws.gov/sites/default/files/documents/water-intake-recommendations.pdf.

[9] Oglala Sioux Tribe: Water Quality Management Code, Antidegradation Policy § 1-2-206. Rosebud Sioux Indian Tribe: Title 19: Environmental Protection § 19-6-103 and § 19-6-104. Sisseton-Wahpeton Oyate: Title III Water Quality: Section 61-03-08, Antidegradation Policy, Narrative WQS. Standing Rock Sioux Tribe: WQS Sections 3(a) designated uses, Section 4(a)(5) criteria, Section 9 Narrative WQS, Section 10 Outstanding Tribal Resource Waters, and Section 11 Antidegradation Policy and Review Process; Cultural Resource Ordinance 189; Section 9-1501 establishes "Protected Areas... for fish and wildlife management, propagation, (or) scientific research." Section 9-1502 may include wetlands "to offset losses" and protect under Sections 9-1501 and 9-1502.

Condition #5: Specific Condition for NWP 13

For projects using gabions, the project proponent shall visually inspect and repair any damage to gabions and the gabion installation area after construction is completed at least once a year after spring flows.

Why this condition is necessary: This condition is necessary to reduce the individual and cumulative adverse environmental effects caused by hard bank stabilization structures on aquatic biodiversity, habitat, and aquatic resource functions and services. This condition is also necessary to minimize the potential for gabion failure and corresponding water quality impacts. Gabion failure leads to erosion and sediment release, which can significantly affect aquatic ecosystem diversity, productivity and stability, and can potentially release wire into the environment that can impact aquatic habitat. Rock released from damaged gabions can impact channel flow, which can interfere with aquatic habitat processes and infrastructure.

Citations: 40 CFR 230.10(c)-(d); 40 CFR 230.72; 40 CFR 230.74; Tribal Water Quality Requirements[10]

Condition #6: Specific Condition for NWP 16

The project proponent shall provide EPA Region 8 with a description of the return water from the upland disposal area prior to discharge, including a description of the nature of the dredged material and a description of any contaminants present in the discharge. The project proponent shall also provide an analysis of how the return water may impact the physiochemical conditions of the receiving water prior to discharge, including a description of how the project proponent will ensure controls are in place to ensure compliance with applicable water quality requirements.

Why this condition is necessary: This condition is necessary to ensure any return water meets applicable water quality requirements and does not degrade receiving waters. Dredged material from industrial and urban areas, stormwater and agricultural runoff, as well as from areas of natural deposits of minerals and other natural substances, often contain contaminants from these sources and may have the potential to alter the chemistry of receiving waters, including but not limited to, nutrients, metals, organic carbon, and invasive species. To ensure that all appropriate and practicable measures to minimize harm to the aquatic ecosystem from contaminants are addressed, the project proponent should consider the unique nature of dredged material and the related contaminant pathway to understand the physicochemical conditions of each disposal site under consideration.

Citation: 40 CFR 230.10(b)-(d); 40 CFR 230.11; 40 CFR 230.12; 40 CFR 230.22; 40 CFR 230.31; 40 CFR 230.32; 40 CFR 230.61; Tribal Water Quality Requirements[11]

[10] Ibid.

[11] Ibid.

Condition #7: Specific Condition for NWP 40

The project proponent shall ensure that any return water flows back into waters of the U.S. does not contain levels of toxic and priority pollutants in excess of effluent limitation guidelines established under Section 307 of the Clean Water Act.

Why these conditions are necessary: This condition is necessary to ensure that return water to waters of the U.S. meets water quality requirements. Agricultural runoff can degrade receiving waters due to contaminants, including toxic and priority pollutants that are subject to effluent limitations pursuant to Section 307 of the Clean Water Act. Project specific information is needed to consider the contaminants proposed for discharge and the aquatic environment at the proposed discharge site to ensure that all appropriate and practicable measures to minimize harm to the aquatic ecosystem are addressed.

Citations: 33 U.S.C. 1317(a)(1); 40 CFR 401.15; 40 CFR 230.10(c); 40 CFR 230.31; 40 CFR 230.32; Tribal Water Quality Requirements[12]

[12] Ibid.

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION FOR ON-THE-JOB TRAINING PROGRAM

MARCH 10, 2016

This Training Special Provision supersedes Part II, Nondiscrimination, Section 6, Training and Promotion, paragraph "b" on Page 2 of the Required Contract Provisions Federal-Aid Construction Contracts (FHWA 1273 – Rev. 5/1/2012).

PURPOSE

The purpose of the On-the-Job (OJT) Program is to provide training in the highway construction industry for minority, female, and economically disadvantaged individuals, hereafter known as the target group. Pursuant to 23 Code of Federal Regulations Part 230, Subpart A, Appendix B – Training Special Provisions, this program provides for on-the-job training aimed at developing full journeyworkers in the type of trade or job classification involved.

INTRODUCTION

A signature from a bidder on the proposal sheet indicates that the bidder agrees to take part in the OJT Program and to follow the OJT Program Special Provision. Contractors that fail to follow the special provision will be subject to sanctions up to and including revocation of bidding privileges.

In order for the OJT Program to be successful, contractors must follow basic and uniform procedures in training such as, keeping monthly records of trainee progress towards journeyworker status and reporting trainee's successful completion/termination from the OJT Program.

SELECTION OF TRAINING PROGRAM

A. The minimum length and type of training for each classification will be as established in the training program selected by the Contractor and approved by the South Dakota Department of Transportation (Department or SDDOT) and the Federal Highway Administration (FHWA).

B. The Department and FHWA have currently approved one OJT program for use in South Dakota and that is the OJT program designed and implemented by the

department. Any trainee who has begun training in the previously approved OJT program will be allowed to transfer to the current approved OJT program.

C. There may be other training programs which some Contractors might wish to utilize. If the Contractor intends to use such a program to meet the OJT requirements on a federal-aid contract with training requirements, approval or acceptance of such program shall be obtained from the Department and FHWA **prior** to beginning training on any classification covered by that program.

It is the intention of these provisions that training is to be provided in the construction crafts rather than administrative support type positions or lower level management positions. Training for any job classification not listed in the current OJT program manual may be permitted provided that significant and meaningful training is provided and prior approval is obtained by the Department Civil Rights Office and the FHWA Division office.

RECRUITMENT AND SELECTION PROCEDURES

A. Prerequisite for Trainees

1. To be qualified for enrollment in the OJT Program, a trainee applicant should be a member of one of the targeted groups (unless an alternate selection is authorized by the Department), must possess basic physical ability for the work to be performed, should have demonstrated qualities of dependability, willingness to learn, ability to understand and follow instructions and an aptitude to maintain a safe work environment.

2. No person shall be employed as a trainee in any classification in which that person has successfully completed a training course leading to journeyworker status or in which the individual has been employed as a journeyworker. The Contractor should satisfy this requirement by including appropriate questions in the employee application or by other suitable means. Regardless of the method used, the Contractor's records should document the findings in each case.

B. Licenses

Truck driver trainees must possess appropriate driver permits or licenses for the operation of Class A, B, and C trucks. When an instructional permit is used in lieu of a license, the trainee must be accompanied by an operator who:

1. Holds a license corresponding to the vehicle being operated;

2. Has had at least one year of driving experience; and

3. Is occupying the seat next to the driver trainee.

C. Recruitment

1. Notices and posters setting forth the Contractor's Equal Employment Opportunity Policy and the availability of training programs will be placed in areas readily accessible to employees, applicants for employment and potential employees.

2. Training and upgrading of minorities, women, and socially and economically disadvantaged persons toward journeyworker status is the primary objective of this Special Provision. Accordingly, the Contractor shall make every effort to enroll minority trainees, women and disadvantaged persons by conducting systematic and direct recruitment through public and private sources likely to yield minority and female applicants to the extent that such persons are available within a reasonable area of recruitment.

3. Full consideration will be given to upgrading current minority and female employees.

D. Selection

1. The selection and employment of an eligible person by a participating Contractor, in accord with the above Parts A, B, and C, shall qualify the person of the OJT Program.

2. Employment of trainees will be in accordance with the work force requirements of the Contractor. Each Contractor will hire and train the trainees for use in his own organization.

3. Contractors must follow the registration procedures as set out for the South Dakota Department of Transportation. An original registration form must be sent to the Department Civil Rights Office for review and approval. In the event that the Department OJT Registration Form(s) are not received by the Civil Rights Office within two weeks of the date the contractor begins significant work on the project, progress payments may be suspended. This suspension will be lifted upon receipt and approval of the form(s).

4. To be acceptable as an economically disadvantaged trainee, the applicant must meet current disadvantaged guidelines (relative to employment and income) as set out by the United States Department of Labor. These guidelines are available from South Dakota Department of Labor offices and contractors must maintain the necessary documentation on file for review by the department.

5. The Department expects that Contractors will employ minority, female, and disadvantaged persons for all trainee positions assigned through this OJT Special Provision unless such persons are not available within a

reasonable area of recruitment. The Civil Rights office may withhold approval of any trainee who is not a member of one of the targeted groups unless the Contractor can demonstrate a good faith effort to recruit and select a minority, female, or economically disadvantaged person and was unsuccessful in recruiting from the target group.

DEPARTMENT RESPONSIBILITES

The Department (Civil Rights office):

A. Will monitor Contractor payrolls and OJT reports for payment of correct wage rates and for evidence of providing a continuing instructional process. The Civil Rights office will maintain records of Contractor participation in the program; names, and training classifications of trainees and other information necessary to assess program participation and results.

B. Will assist contractors with trainee recruitment, will encourage minority/female recruitment sources to refer suitable applicants, and will monitor Contractor instructional efforts and record keeping.

C. Reserves the right to do EEO (Equal Employment Opportunity) or OJT reviews on the contractor, at any time without prior notice, to ensure that trainees are getting the proper instruction from their trainer/supervisor.

CONTRACTOR RESPONSIBILITIES

The Contractor:

A. Will furnish the trainee a copy of the training program to be followed in providing the training and will provide each trainee graduate with a certificate showing the type of training satisfactorily completed.

B. Will identify all trainees on the registration forms, training reports and project payroll by proper classification title, (see SDDOT Training program booklet) e.g. *heavy duty mechanic, form builder,* etc. **Do not use** coding letters/numbers from the wage scale. On payrolls, contractors must include the designation “trainee” following the job classification title.

C. Will provide a monthly training report to the Department Civil Rights office within thirty (30) days of the last full pay period of the month on the form supplied by the Department and will use this same form to promptly notify the Department (within thirty days) whenever a trainee leaves the OJT program (voluntarily or involuntarily) or when a trainee completes the program.

D. Will pay not less than the minimum wage rates as set forth in the specific requirements of the applicable training program and as noted on the copy of the registration form returned to the contractor.

E. Assign the trainee to a skilled craftsman, foreman, supervisor or mentor who will be responsible for the day-to-day training and mentoring of the trainee and who will share the appropriate skills associated with the classification for which the trainee is enrolled. The contractor attests to providing verification, if requested, that the trainee is being trained and is gaining knowledge to achieve full journeyman status by a supervisor/trainer.

F. Shall only count, for credit; hours spent training within the classification for which the trainee is enrolled. If such classification is not necessary for a period of time or a particular project, the contractor should attempt to continue to employ the trainee by assigning him/her other duties. A percentage of hours worked on other pieces of equipment are required to be counted in the total hours worked. Approximately 25% of other duties can be counted towards graduation.

G. Shall count all hours worked in a training program regardless of whether the work was in South Dakota or outside the state. For trainees in required training slots, the contractor will only be reimbursed for eligible hours for work performed in South Dakota.

H. Will provide a program orientation to the training foreman, superintendent, and OJT trainee. This orientation shall include at a minimum, a review of individual responsibilities during the training program and copies of the training syllabus for the job classification.

I. Will instruct the trainee in safe and healthful work practices and shall ensure that the trainee is trained in facilities and other environments that are in compliance with all applicable safety and health laws and regulations of the United States and the State of South Dakota.

J. Provide the trainee a copy of the training program to be used. The contractor must also designate the employee as a “trainee” on weekly certified payrolls. The contractor is responsible for ensuring that proper training is taking place on the job by meeting with the supervisor/foreman of the project that the trainee is working.

K. In the event that a contractor may be unable to fill the required trainee slot during the current construction season, the Civil Rights Compliance Officer must be notified and contacted by December 1 of the current construction season. Proper documentation must be provided as to why the trainee position was not filled, such as project carry-over until next year.

L. Certify the trainee hours and be able to show that the trainee is receiving the proper training for their classification. Failure to do so may result in project sanction.

M. Is expected to begin training trainees on a project as soon as feasible after the start of work utilizing the job classification involved. After training has started the contractor should strive to provide monitoring efforts to retain and successfully train employees.

ADDITIONAL APPLICABLE PROVISIONS

A. The minimum number of hours of training to be provided on this project is as specified in the bid documents. The Contractor shall select whatever training classification specified in the current training program that best meet his employment needs and training hours and minimum wage shall be in accord with that classification.

B. For the purposes of bidding required trainee slots each trainee is assigned a bid quantity of 500 hours. For example if there is 1000 hours in the bidding documents, that is requiring 2 trainees. The contractor has the option to register multiple trainees to fulfill the training requirement. For example if there is a 1000 hour bid quantity, which equals 2 required trainees, the contractor could have three or more trainees registered in the program as long as there enough work for additional trainees to successfully complete the curriculum and not exceed the allowable ratio of trainees to journeyworkers (generally considered to fall between 1:10 or 1:4)

C. Please note that 500 hours for each training slot is for bidding purposes only. If a contractor does not achieve the bid quantity on a project, there is no penalty as long as a good faith effort was made to fulfill the training requirement. Also the contractor is not limited to just the bid quantity for reimbursement. If the total hours achieved on a project is higher than the bid quantity, the contractor will be reimbursed for all hours worked. For example if the bid quantity is 1000 hours and the total hours of the trainees are 1450 hours, the contractor will receive reimbursement for 1450 hours.

D. Registration and reporting requirements shall be as set forth in the program documents; printed instructions and this provision.

E. Contractors using the current training program may meet the training obligations by either 1) enrolling a new trainee in one of the classifications, or 2) using a trainee currently enrolled in one of the current training program classifications, provided that person has sufficient training hours remaining to meet the minimum project requirements as specified in bid documents. In either case, prospective trainees must meet the program requirements as set forth in “Recruitment and Selection Procedures” above.

F. The department is responsible for long term maintenance of records regarding trainee registration in various training classifications and for total trainee hours as provided by one or more contractors.

WAGE RATES

A. Minimum wage rates shall be in accord with program requirements for each classification and trainee placement within the training hours requirement. In no case shall the minimum wage be less than the common laborer classification of the applicable wage rate information contained in the bid documents. Where applicable, trainees shall be paid full fringe benefit amounts.

B. At the completion of the OJT program, the trainee shall receive the wages of a skilled journeyworker for that specific classification.

C. For the purpose of the OJT program, a quarter of the program is twenty-five percent (25%) of the training hours credited to the trainee for a particular classification and does not represent three months of the year. Other wage benchmarks are calculated in a similar manner.

BASIS OF PAYMENT

A. All program reimbursements will be made directly to the Contractor at the project conclusion. The Contractor will be paid, as reimbursement for the extra cost involved in providing the training, the amount per training hour bid for the item "Training" for each hour of training provided and reported.

B. All hours of onsite and approved offsite training provided in accordance with the approved program and this provision and as shown in trainee reports and on project payrolls will be credited as trainee hours for purpose of contract payment.

C. No payment will be made to the Contractor if either the failure to provide the required training, or the failure to hire the trainee as a journeyworker, is caused by the Contractor and evidences a lack of good faith on the part of the Contractor in meeting the requirements of this Special Provision.

D. Liquidated damages will be assessed the contractor for failure to make a good faith effort to enroll the number of trainees necessary to meet the training requirements of this Special Provision. For each trainee slot left unfilled, damages will be assessed at the rate of 100% of the bid amount for the training item times the minimum number of hours specified in the item quantity. For each trainee for whom contractor training is determined to be inadequate and which evidences a lack of good faith to fulfill the training requirements, damages will be assessed at the rate of 100% of the bid amount for the training item times the minimum number of hours specified in the item quantity.

E. Failure to furnish required documents and reports in the manner and time specified may result in forfeiture of all or a portion of the amounts due the Contractor for reimbursement for training.

*****

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION REGARDING
RAILROAD INSURANCE REQUIREMENTS FOR
RINGNECK & WESTERN RAILROAD

P-B 0248(12)217 PCN 06G7, JONES COUNTY

SD248 – STRUCTURE REPLACEMENT OVER MEDICINE CR 2.1 W OF LYMAN COUNTY LINE

October 14, 2026

Prior to commencing any work in the vicinity of the railroad property on this project, the successful Contractor will provide and maintain in effect insurance covering all of the work and services to be performed by the Contractor and each of its subcontractors in the coverage and minimum amounts as noted below:

(1) Railroad Protective Liability: The **Ringneck & Western Railroad will be the Named Insured** for bodily injury and property damage of $2,000,000 per occurrence and $6,000,000 in the aggregate.

(2) Workers' Compensation Insurance: As required under the South Dakota Workmen's Compensation Law.

(3) Commercial General Liability: For public liability, personal injury and property damage, as well as Contractual Liability in the amount of $2,000,000 per occurrence, with an aggregate of $4,000,000.

(4) Automobile Liability: For bodily injury and property damage of at least $1,000,000 combined single limit or the equivalent covering any and all vehicles owned or hired and used in performing services.

Insurances must provide for coverage of incidents occurring within fifty (50) feet of the railroad track, and any provision to the contrary in the insurance policy must be specifically deleted.

POLICY & CERTIFICATE OF INSURANCE

The successful Contractor will issue to the following railroad Certificates of Insurance evidencing the issuance of insurance coverage as prescribed in 2, 3 and 4 above, **plus** the original Railroad Protective Liability insurance policy, and certify that the Railroad will be given not less than 30 days written notice prior to any material change, substitution or cancellation prior to normal expiration dates. Cancellation expiration of any of said policies of insurance will not preclude Railroad from recovery there under for any liability arising under this contract. Certificates of Insurance and Railroad Protective Liability insurance policy to be issued to:

Watco Companies, and its affiliates, subsidiaries and assigns
315 W. 3rd Street
Pittsburg, KS 66762
Attn: Real Estate

The Contractor will submit the Certificates of Insurance to the Railroad at the following address:

Justin Mahr
Manager Real Estate- Contracts
Watco
315 W 3rd Street
Pittsburg, KS, 66762

Any questions or clarifications of Railroad's insurance requirements may be directed to Justin Mahr, at justin.mahr@watco.com or 402-651-8238, or to Cassidy Schnabel with the SDDOT at cassidy.schnabel@state.sd.us or 605-773-5230.

The Contractor will also send a copy of all certificates and insurance to Doug Sherman, South Dakota Department of Transportation, PO Box 771, Winner, SD 57580-0771, email Doug.Sherman@state.sd.us.

The successful Contractor will not be granted permission to proceed with any work on, over, or near railroad property (at a minimum of 50 feet from centerline of any track) until the Contractor has been notified by the Railroad that the required insurances have been approved and documentation of approval has been provided to the Area Engineer.

All costs associated with these insurance requirements, including increasing policy limits, when required, will be incidental to the bid item RAILROAD PROTECTIVE INSURANCE.

It is mutually understood and agreed that the purchase of insurance will not in any way limit the liability of the Contractor to the Railroad.

Failure to obtain the required insurances and approvals prior to working on, over, or near Railroad property will result in suspension of all work until required insurances are obtained and approved.

# # # # # # #

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION REGARDING WORKING ON RAILROAD PROPERTY FOR
RINGNECK & WESTERN RAILROAD

P-B 0248(12)217 PCN 06G7, JONES COUNTY

SD248 – STRUCTURE REPLACEMENT OVER MEDICINE CR 2.1 W OF LYMAN COUNTY LINE

October 14, 2026

The Contractor is to contact Chadd Thimesch, General Manager, Ringneck & Western Railroad, cthimesch@watco.com or 316-775-8009 at least five working days in advance whenever it is to enter the Railroad property. However, a **thirty- day** notice is required before beginning of project to coordinate work. Manager may designate others to represent the Railroad.

Absolutely no piling of construction materials or any other material including dirt, sand, etc., on property of the railroad not covered by Construction Easement or Contractor's ROE License.

# # # # # # # # # # # # # #

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
CONTRACTOR STAKING
WITH MACHINE CONTROL GRADING OPTION

PROJECT P-B 0248(12)217, PCN 06G7
JONES & LYMAN COUNTY

OCTOBER 30, 2026

Delete Section 5.8 of the specifications and insert the following:

SECTION 5.8
CONSTRUCTION STAKES, LINES AND GRADES
CONTRACTOR GRADE STAKING

A. DESCRIPTION

The Contractor will perform all construction staking. The Contractor may elect to use grading equipment with an automated machine control system for Machine Control Grading (MCG) provided the equipment and methods used provide the same results in the finished work as conventional construction staking. The Engineer may require the Contractor to revert to conventional staking methods for all or part of the work at any point during construction if, in the Engineer's own opinion, the MCG produces unacceptable results.

The Contractor may use MCG as a substitute for conventional construction staking for grade staking only but will not use MCG for slope staking and slope stake reference hubs, paving hub staking, structure staking, miscellaneous staking, or final cross section surveying.

The staking work includes, but is not limited to, establishing or re-establishing the project centerline; establishing control points and benchmarks as needed; setting additional benchmarks as needed; perform measurement and volume calculations of all Contractor secured borrow sources, State designated borrow sources, and topsoil stockpiles; perform measurement and volume calculations for earthwork quantities; and staking right-of-way, easements, and fence. The Contractor will perform measurement and volume computations by the average end area method at the slope stake stations and plus stations, surface-to-surface method, or alternate measurement and computation method approved by the Engineer.

The Contractor will perform all construction layout and reference staking necessary for the accurate control and completion of all structures, grading, paving, drainage, median crossovers, signing, pavement marking, permanent benchmarks, detours, fence, and all other appurtenances required for the complete construction and acceptance of the work. The layout will include, but is not limited to, staking easement lines, staking clearing line, slope staking and slope stake reference hubs, grade staking (blue tops), structure staking, and performing the miscellaneous staking as described in the plans and in this specification.

The Department has established horizontal and vertical control as shown on the plans. Each horizontal and vertical control point will be preserved or reset out of the work limits and available during and after construction is complete. Prior to the Department's final acceptance of the project, the Contractor will replace or reset any control that is disturbed during the construction of the project. The Contractor will provide the Department a list of the in-place control points, including coordinates and elevations relevant to the project control, at the end of the project.

The Department will provide a MCG packet to all prospective bidders consisting of a XML file containing the original surface Digital Terrain Model (DTM) and 4 design files for each new alignment on the project. The electronic design files will include, a XML file containing mainline alignment data, a XML file containing mainline design surface DTM, a DGN file containing triangles for mainline surface, and a DWG file containing triangles for mainline surface. The MCG packet will be available on the Department's electronic bid letting website when the project is advertised for bid letting.

The Contractor will convert the electronic information provided by the Department into the format required by the Contractor's MCG system. The Department makes no guarantee the information provided is directly compatible with the Contractor's MCG system.

The information shown in the plans will govern over the provided electronic information. The Contractor assumes the risk of error if the information is used for any purpose for which the information was not intended. The Contractor assumes all risk of any assumptions made regarding the electronic information.

The Contractor bears all costs, including but not limited to the cost of actual reconstruction of work, that may be incurred due to errors in application of MCG techniques. Grade elevation errors, rework resulting from errors or failures of the MCG system, and associated quantity adjustments resulting from the Contractor's activities are at no cost to the Department. Delays due to late submittals or satellite reception of signals to operate the MCG system will not result in adjustment to any contract unit prices or be justification for granting contract extensions.

The electronic information is not to be considered a representation of actual conditions to be encountered during construction. Providing the Contractor this

information does not relieve the Contractor from the responsibility of making an investigation of conditions to be encountered, including but not limited to, site visits and basing the bid on information obtained from these investigations and the Contractor's professional interpretations and judgment. The Contractor assumes the risk of error if the information is used for any purposes for which the information was not intended. Any assumptions the Contractor makes from this electronic information or manipulation of the electronic information is at the Contractor's own risk.

The Contractor will perform the staking work in accordance with the Department's Survey Manual, except as modified by this specification.

If the Contractor elects to use MCG, the Contractor will submit a comprehensive written MCG work plan to the Engineer for review prior to scheduling the preconstruction meeting. The Department will review the plan to determine if the plan conforms to the requirements of the contract.

The Contractor will include in the MCG work plan how MCG will be incorporated into other technologies used on the project. The Contractor's MCG work plan will include, but is not limited to, the following:

1. A designation of which portions of the subgrade will be completed using MCG and which portions, if any, will be completed using conventional subgrade staking methods.
2. A description of the manufacturer, model, and software version of all MCG equipment.
3. Information on the qualifications of the Contractor's staff including, but not limited to, formal training and field experience.
4. A designation of a single person as the primary contact for MCG technology issues.
5. A description of site calibration procedures.
6. A description of site calibration and checking frequency and procedures for documenting site calibration and checking.
7. A description of the Contractor's quality control procedures including procedures for checking, mechanical calibration, and maintenance of equipment.
8. A description of the frequency and types of checks the Contractor will perform to ensure the constructed subgrade conforms to the contract requirements.

B. MATERIALS

The Contractor will furnish all staking materials of adequate quality for the purpose intended including all stakes, stake chasers, paint, field note books, and all other materials and equipment necessary to perform the required work.

C. CONSTRUCTION REQUIREMENTS

1. **General:** The Department will set control points. The Contractor is responsible for the preservation of ties and references to all control points necessary for the accurate re-establishment of all base lines and centerlines shown in the plans, whether established by the Contractor or found on or adjacent to the project. The Department will also establish benchmark elevations. It is the responsibility of the Contractor to verify the accuracy of the benchmark elevations prior to use on the project.

   The Engineer may check the accuracy and control of the Contractor's survey, staking work, and MCG at any time. The checks performed by the Engineer will not relieve the Contractor of the responsibility for the accuracy of the survey layout or the construction work. If the random checks show the grade is out of tolerance, the Engineer may require the Contractor to set additional stakes at the discretion of the Engineer, at no additional cost to the Department. If the Engineer orders additional stakes, the Contractor will perform the additional staking until the Contractor can show the staking operations achieve the specified grade tolerances.

   Prior to any project staking, the Contractor will run a level circuit to check the plan benchmarks the full length of the project. At structure sites, the circuit will include two benchmarks, one on each end of the structure.

   The Contractor will perform all staking and MCG work under the supervision of a qualified surveyor or engineer who is experienced and competent in road and bridge construction surveying, staking, and MCG procedures. The surveyor or engineer will be available to review work, resolve problems, and make decisions in a timely manner. A crew chief, competent to perform all required surveying duties, will supervise the staking in the absence of the surveyor or engineer from the project. The Contractor will submit the qualifications and work experience history of the surveyor or engineer who will supervise the construction survey and MCG work to the Engineer for review at least 14 calendar days prior to beginning the staking or MCG work.

   a. **Conventional Construction Staking:** The Contractor will also submit the proposed starting date of the staking and the anticipated surveying work schedule.

      The Contractor will furnish, set, and properly reference all stakes, references, lines, grades, and batter boards required. Minimum reference notations will be for type, location, and alignment (when there are multiple alignments in the same area). The Contractor will perform the survey and staking work in a manner consistent with standard engineering practices and approved by the Engineer.

The Contractor is solely responsible for the accuracy of the survey and staking work. The Contractor will notify the Engineer of any errors and discrepancies found in previous surveys, plans, specifications, or special provisions prior to proceeding with the survey work.

The Contractor will be responsible for the supervision of the construction staking personnel. The Contractor will correct any deficient survey or staking work that results in construction errors at no additional cost to the Department.

The Contractor will keep field notes in conventional handwritten notebooks or in a computerized form acceptable to the Engineer in a clear, orderly, and neat manner. The notebooks will become the property of the Department upon completion of the project. The notebooks will provide enough information such that quantity measurements are verifiable by the Department. Field notes are subject to inspection by the Engineer at any time.

The Contractor is required to submit any remaining required quantity calculations and notes to the Engineer no later than 60 calendar days after completion of the survey and staking work.

The Contractor will furnish stakes and wooden hubs or steel pins of sufficient length to provide a solid set in the ground. The Contractor will place half-length lath stakes or stake chasers or an alternate, acceptable to the Engineer, adjacent to or on the blue top hubs for guards. Stakes set not meeting these requirements will be reset at the Contractors expense. The Contractor will replace stakes damaged, destroyed, illegible, or made unusable at no additional expense to the Department.

b. **Machine Control Grading:** If the Contractor elects to use MCG as a substitute for conventional staking for grade staking, the Contractor will confirm the design surface DTM agrees with the contract plans, make adjustments to the design surface DTM as approved by the Engineer, and will maintain the design surface DTM for all areas of the project where MCG is used. The Contractor will also provide constructed surface DTM information to the Department in LandXML or other Engineer approved format.

   The Contractor will notify the Department of any errors or discrepancies in Department provided information. The Department will determine what revisions may be required. The Department will revise the contract plans, if necessary, to address errors or discrepancies the Contractor identifies. The Department will provide the best available information related to those contract plan revisions.

The Contractor will revise the design surface DTM as required to support construction operations and to reflect any contract plan revisions the Department makes. The Contractor will perform checks to confirm the revised design surface DTM agrees with the contract plan revisions. The Contractor will provide a copy of the resultant revised design surface DTM to the Engineer in LandXML. The Department will pay for costs incurred to incorporate contract plan revisions as extra work.

The Contractor will designate a set of control points, including a total of at least 6 horizontal and vertical points or 2 per mile, whichever is greater, for site calibration for the portion of the project employing MCG. The Contractor will incorporate the Department provided control framework used for the original survey and design.

The Contractor will calibrate the site by determining the parameters governing the transformation of satellite information into the project coordinate system. The Contractor will use the control points provided by the Department for the initial site calibration. The Contractor will provide the resulting site calibration file to the Engineer before beginning subgrade construction.

In addition to the site calibration, the Contractor will perform site calibration checks at individual control points not used in the initial site calibration. At a minimum, the Contractor will check the calibration at the start of each day as described in the contractor's MCG work plan. The Contractor will report out-of-tolerance checks to the Engineer. The measured position must match the established position at each individual control point within the horizontal tolerance of ±0.1 foot and the vertical tolerance of ±0.05 foot.

The Contractor will construct the subgrade as the Contractor’s MCG work plan indicates and in accordance with the contract requirements. The Contractor will update the plan as necessary during construction of the subgrade. The Contractor will perform periodic sensor calibrations, checks for blade wear, and other routine adjustments as required to ensure the final subgrade conforms to the contract requirements.

The Department may use Department supplied GPS rover and data collector (GPS inspection equipment) to aid in the inspection of the work. The Department supplied GPS inspection equipment will require a connection to the Contractor’s Machine Control Grading (MCG) system, through the Contractor’s base station, used for MCG equipment.

The Contractor will configure the radio settings of the base station to allow the Department’s rover to receive corrections directly from the Contractor’s base station. The radio settings must be configured properly to ensure

continuous communication across multiple brands of GPS equipment. The radio settings will be as follows:

- Frequency: 461.050 to 464.750 MHz
- Narrow Bandwidth: 12.5 kHz
- Protocol: PDL or PDL Tx
- Modulation: 4fSK
- Forward Error Correction (FEC): On
- Scrambler: Off
- Free Channel Scan (FCS): On

The connection of the Department's GPS inspection equipment will allow the Engineer the ability to positively and efficiently determine plan station, offset, and elevations in all MCG sections.

The Department will not make payment for the ability to connect or the connection to the Contractor's MCG system.

2. **Slope Staking:** The Contractor will set slope stakes at the catch points. The slope stake reference hubs will be offset behind the slope stake. The Contractor will place slope stake reference hubs behind the slope stakes at the right-of-way line, easement line, or other locations as approved by the Engineer.

   The slope stakes will be set at 200-foot intervals on tangents and at 50-foot intervals in horizontal curves. The horizontal tolerance is ±0.2 foot and the vertical tolerance is ±0.1 foot. The Contractor will reference the subgrade shoulders with slope stake reference hubs set with a horizontal tolerance of ±0.2 foot and a vertical tolerance of ±0.05 foot.

   The Contractor will retain the slope stakes and hub references until the final survey computations are completed and accepted by the Department.

   Contractor will set slope stakes based on the information included in the MCG files provided by the Department.

3. **Grade Staking:** In accordance with the requirements of this provision, the Contractor may elect to use MCG equipment or may use conventional construction staking methods for all or part of the grade staking work, excluding paving hub staking.

   a. **Conventional Blue Tops:** The Contractor will set grade finishing stakes (blue tops) for grade elevations and horizontal alignment on the roadway centerline and at each shoulder at the top of the subgrade. Where additional lanes or turnouts are to be constructed, The Contractor will set blue tops at centerline, the normal shoulder distance, and the extended shoulder distance or outside the additional lane edge.

The transverse distance between blue tops will not exceed 20 feet. The Contractor will be required to set intermediate blue tops when the transverse distance is greater than 20 feet. When intermediate blue tops are required, The Contractor will set the intermediate blue tops at locations approved by the Engineer.

The blue top grade stakes will be set at 100-foot intervals on tangents and 50-foot intervals on horizontal curves. The horizontal tolerance for blue tops is ±0.2 foot and the vertical tolerance is ±0.02 foot.

Contractor will set grade stakes based on the information included in the MCG files provided by the Department.

The Contractor will retain the shoulder blue tops and guards through placement of the granular material.

The Contractor will not be required to set grade stakes at the top of the base course. If the Contractor deems it necessary to place grade stakes to achieve typical section as per section 260.3 A of the specifications, the staking will be incidental to the contract unit price for base course.

b. **Machine Control Grading:** The Contractor will set conventional construction staking grade finishing stakes (blue tops) for grade elevations and horizontal alignment on the roadway centerline and at each shoulder at the top of the subgrade (and gravel cushion for PCC paving projects) at a minimum of 500 foot intervals on mainline and slide repairs or at least one location for sections less than 500 foot long; at least two locations on side roads, side streets, and ramps; and at least one location within 100 feet of each bridge end. In addition, the Contractor will set blue tops for grade elevations and horizontal alignment on the roadway centerline and at each shoulder at the top of the subgrade (and gravel cushion for PCC paving projects) at critical transition points including, but not limited to, PC's, PT's, super elevations transition points, and other critical points required for the construction of drainage and roadway structures. The Contractor will also provide conventional construction staking grade finishing stakes (blue tops) at additional locations designated by the Engineer.

   The Contractor will establish these grade staking (blue top) grades using the information included in the MCG files provided by the Department, plan typical sections, and cross sections. The Contractor will use these stakes to check the accuracy of the MCG during construction. The Contractor will notify the Engineer at least 3 calendar days before making subgrade checks to allow the Engineer to observe the process.

The Contractor will ensure at least four of any five consecutive conventional construction staking grade finishing stakes (blue tops) locations are within the horizontal and vertical tolerances specified in Section 120.3. The Contractor will notify the Engineer if more than one of any five consecutive conventional construction staking grade finishing stakes (blue tops) locations is not within the horizontal or vertical tolerance.

The Department may conduct periodic independent subgrade checks. The Department will notify the Contractor if any individual check is not within the horizontal or vertical tolerance.

4. **Structure Staking:** The Contractor will stake and reference bridges and box culverts to ensure adequate horizontal and vertical control of the substructure and superstructure components. The Contractor will stake and reference the bridge chord or the bridge tangent and centerline of each pier, bent, and abutments for bridges. The Contractor will stake the box culvert centerline(s) in both longitudinal and transverse directions.

   When the work requires bridge rehabilitation work, the structure staking will include all surveying and staking required for completion of the project. The staking work may include, but not be limited to, setting the rail for the deck overlay. The plans will indicate the grade line for the deck overlay; and if necessary, the Engineer may modify the grade line.

   When staking retaining walls (except Type C), the Contractor will survey and record the original ground profile along the front face of the proposed wall at the elevation break points. The Contractor will supply the wall designer the original ground profile data prior to the wall designer performing the design. Set adequate stakes and references for horizontal and vertical control during construction.

   For structures and retaining walls, the horizontal tolerance is ±0.04 foot and vertical tolerance is ±0.02 foot.

   The Contractor is responsible for all notes required to stake structures including bridges, box culverts, and walls.

5. **Miscellaneous Staking:** Miscellaneous staking includes the following work:

   a. Easement line for items including, but not limited to, setting temporary fence, utility relocation, and landowner reference and property use;
   b. Clearing line for items identified by the clearing contract unit item when provided in the plans;
   c. Approach road staking and all tie-in checks. The Contractor will submit profiles and elevations of all approach roads and other tie-ins throughout the project to the Engineer at least 3 business days prior to staking;

d. Topsoil measurement and computation of quantities;
e. Special ditch staking;
f. Staking of signs, delineators, pavement markings, rumble strips/stripes, guardrail, curb & gutter, light poles, conduit, mailboxes, junction boxes, and related items (Staking is for all aspects, i.e. detours, temporary and permanent);
g. Right-of-way staking including fence post panels;
h. Pipe and storm sewer staking including drop inlets, manholes, cattle passes, and related items. If additional pipe, storm sewer, drop inlets, manholes, or cattle passes are required which are not shown on the plans, the staking will be paid in accordance with the bid item Engineer Directed Surveying/Staking;
i. Mark limits of removal items (trees, foundations, curb & gutter, sidewalk, etc.);
j. Detours, roadway diversions, and crossovers. (This work includes all design and staking notes required to design and stake the detour, roadway diversion, or crossover in accordance with the plan requirements. The Contractor will submit the completed design including profile and alignment and staking notes to the Engineer at least 3 business days prior to staking.);
k. Final and original cross sections of Contractor and State furnished borrow pits and computations. The Contractor will perform earthwork computations by the average end area method, surface-to-surface method, or alternate computation method approved by the Engineer;
l. Resetting horizontal and vertical control, if disturbed;
m. Approach slab and sleeper slab staking;
n. Staking of sidewalks and curb ramps; and,
o. Staking of steps and wheel chair ramps.

The Contractor will perform the pipe staking so the pipe will fit the field conditions. The plans show only approximate pipe locations and grades. The Contractor will not install pipe prior to gaining the Engineer's approval of minor location and grade adjustments necessary for proper staking of the pipe.

The Contractor will stake the slope catch points to determine the inlet and outlet locations, set reference stakes for the inlet and outlet locations, and stake ditches and special inlet and outlet grades to ensure proper drainage. The staking of manholes and drop inlets will be included in pipe and storm sewer staking. The Contractor will stake precast cattle passes similar to drainage pipes.

The horizontal tolerance for the pipe and storm sewer staking is $\pm$0.05 foot and the vertical tolerance is $\pm$0.03 foot.

The Contractor will keep pipe staking notes on a DOT Form 214.

6. **Engineer Directed Surveying/Staking:** The use of the engineer directed surveying/staking contract item is intended for surveying/staking not included in the plan notes and this special provision. The Contractor may use a survey crew to perform additional survey/staking work caused or required by the Department. The Engineer will use a written order to authorize the hourly engineer directed surveying/staking item and describe the surveying/staking work required of the Contractor.

7. **Final Cross Section Survey:** When the contract allows an option for the measurement of final earthwork quantities by survey or by plan quantities, the Contractor and Engineer must agree to the method of measurement for final earthwork quantities prior to using this item. If this item is not used for the final measurement, the Department will remove this item by a contract change order. If the Contractor and Engineer agree to use this item for measurement of final earthwork quantities, the resulting quantities will be used for payment of the excavation quantities.

   Final Cross Section Survey includes final earthwork (or terrain data) measurement and calculation of as-built quantities. The Contractor will include the blue top subgrade elevations, both shoulders, and centerline in the final earthwork (or terrain data). The Contractor will perform earthwork computations by the average end area method at the same intervals, stations, and plus stations as the slope stakes, surface-to-surface method, or alternate computation method approved by the Engineer.

D. METHOD OF MEASUREMENT

Refer to the Table of Contractor Staking in the plans for more detail on how quantities were calculated.

1. **Slope Staking:** The Department will not measure slope staking. The Department will pay the plan quantity as the final quantity unless the Engineer orders additional slope staking in writing.

   The Department will consider all combinations of roadway widths as one set of slope stakes. On projects with ramps, the Department will consider ramps as roadway and include the ramps in the slope staking quantity. All additional slope staking for intersections will be incidental to the contract unit price for slope staking.

2. **Grade Staking:** The Department will not measure grade staking. The Department will pay the plan quantity as the final quantity unless the Engineer orders additional grade staking in writing. The Department will make no adjustment to the plan quantity of grade staking regardless if the Contractor elects to use MCG on all or part of the project.

The Department will consider a two-lane roadway as one set of grade stakes. The Department will proportionately increase the plan quantity for multi-lane roadways in excess to two-lanes as shown in the table of construction staking (lane factor). For example, a three-lane roadway is equivalent to 1.5 times the quantity for a two-lane roadway. On projects requiring grade staking on ramps, the Department will consider ramps as a two-lane roadway for measurement as shown in the table of construction staking. The Department will not consider Acceleration/deceleration lanes and turning lanes for intersecting roads, and median crossovers as an additional roadway. All cost for additional grade staking for acceleration/deceleration lanes, turning lanes, intersecting roads, grade adjustments, and median crossovers will be incidental to the contract unit price for grade staking. All additional grade staking for intersections and medians will be incidental to the roadway grade staking. Any additional staking the Contractor feels necessary to complete the grade staking work is the responsibility of the contractor and will be incidental to the contract unit price for grade staking.

3. **Structure Staking:** The Department will measure structure staking by the each for bridges, box culverts, and retaining walls.

4. **Miscellaneous Staking:** The Department will not measure miscellaneous staking. The Department will pay the plan quantity as the final quantity.

5. **Engineer Directed Surveying/Staking:** The Department will measure engineer directed surveying/staking to the nearest 0.1 hour with the following restrictions:

   The use of engineer directed surveying/staking will be for the work ordered by the Engineer. The measured quantity will be the actual time the survey crew is working on the project, physically performing the field survey/staking work and office time dedicated to the work specific to engineer directed surveying/staking. The Department will not include travel time for the survey crew in the measurement.

   The Contractor will provide the Engineer documentation, such as an invoice, showing the actual days/hours worked.

6. **Final Cross Section Survey:** The Department will measure final cross section survey to the nearest 0.001 mile for the plan earthwork balances requiring a final survey to determine as-built unclassified excavation quantities. The Engineer will determine which balances (if any) require a final survey during construction. The plan quantity will be the length of the project mainline. This item will be decreased if the Contractor and Engineer agree to accept the plan excavation quantity prior to performing the work for any or all earthwork balances.

E. BASIS OF PAYMENT

Payment for all survey items will be considered full compensation for furnishing all necessary personnel, vehicles, surveying equipment, software, supplies, materials, recording fees, transportation, and incidentals to accurately and satisfactory complete the work.

The Department reserves the right to omit any of these bid items without providing compensation to the contractor if the Department deems the bid prices are unreasonable.

1. **Slope Staking:** The Department will pay slope staking at the contract unit price per mile.

2. **Grade Staking:** The Department will pay grade staking at the contract unit price per mile.

3. **Structure Staking:** The Department will pay structure staking at the contract unit price per each.

4. **Miscellaneous Staking:** The Department will pay miscellaneous staking at the contract unit price per mile.

   The Department will make partial payment as follows:

   a. Upon submission of the name, experience, and qualifications of the surveyor or engineer who will supervise the staking, the proposed starting date, and the staking schedule, the Department will pay the Contractor 25 percent of the plan quantity for the miscellaneous staking.

   b. The Department will make intermediate payments based on the amount of the staking work completed.

   c. The Department will make full payment at the plan quantity for miscellaneous staking upon completion of all surveying and staking and when the Contractor has furnished all field notebooks and records to the Engineer.

   The Department will not adjust the contract unit price or plan quantity for miscellaneous staking due to overruns or under runs in the other contract items.

5. **Engineer Directed Surveying/Staking:** The Department will pay engineer directed surveying/staking on an hourly basis as per the Price Schedule for Miscellaneous Items. The value listed in the Price Schedule for Miscellaneous Items includes salaries, travel time, equipment, staking supplies, payroll additive, and all incidental expenses related to providing the survey crew.

6. **Final Cross Section Survey:** The Department will pay final cross section survey at the contract unit price per mile.

* * * * *

THE FOLLOWING UTILITY COMPANIES ARE INVOLVED ON

PROJECT P-B 0248(12)173, Jones, Lyman County, PCN 06G7

The contractor shall contact the following utilities in a sufficient amount of time prior to starting work. The companies will identify their facilities and it is the responsibility of the contractor and the company to coordinate their work to avoid damage to existing facilities and to allow for relocation of facilities as may be required for grading work:

The following utilities were determined to be involved and were formally notified on August 28, 2024, that if their facility is located within the existing public right-of-way, any adjustment of their facility would have to be accomplished at no cost to the State, **within 90 days from receipt of the notice, unless other arrangements are made with the Area Engineer.**

(1) Golden West Telecommunications Coop
525 E 4th Street
Dell Rapids, SD, 57022
CONTACT: Mr. Ryan Cuny TELE: #605-428-1125 EMAIL: RyanCuny@GoldenWest.com

The Company has existing underground telecommunication facilities through the project. A 12ct fiber roughly parallels the Left (North) side existing Right of Way line. 144ct and 288ct fiber lines roughly parallel the Right (South) side existing Right of Way line in or near the same trench. All facilities present with project as follows.

The existing 12ct fiber on the Left (North) side will be retired for construction.

Existing 144ct and 288ct fiber lines roughly parallel the Right (South) side as follows.

- Structure 38-302-173 (Station 10+08 – Station 33+75) – existing facilities include (1) 144 BFO, (1) 288 on the South side of the road (RIGHT). All facilities are in the PRIVATE. From Station 16+00 to 21+00, GW facilities will need to be relocated.
- Structure 38-312-173 (Station 63+27 – Station 94+38) – existing facilities include (1) 144 BFO, (1) 288 on the South side of the road (RIGHT). All facilities are in the PRIVATE. From Station 69+27 to 94+38, GW facilities will need to be relocated.
- Structure 38-319-174 (Station 108+69 to Station 141+97) – existing facilities include (1) 144 BFO, (1) 288 on the South side of the road (RIGHT). All facilities are in the PRIVATE. From Station 108+69 to 141+97, GW facilities will need to be relocated.
- Structure 38-330-175 (Station 170+90 to Station 186+90) – existing facilities include (1) 144 BFO, (1) 288 on the South side of the road (RIGHT). All facilities are in the PRIVATE. From Station 170+90 to Station 186+90, GW facilities will need to be relocated.
- Structure 38-348-174 (Station 271+61 – 280+00) – existing facilities include (1) 144 BFO, (1) 288 on the South side of the road (RIGHT). All facilities are in the PRIVATE. From Station 271+61 to Staton 280+00, GW facilities are clear.
- Structure 43-014-188 (Station 357+00 – 369+00) – existing facilities include (1) 144 BFO, (1) 288 on the South side of the road (RIGHT). All facilities are in the PRIVATE. From Station 375+00 – 369+00, GW facilities are clear.

(2) Lumen Technologies
612 Mount Rushmore Road
Rapid City, SD, 57701-2753
CONTACT: Mr. Arthur Turner TELE: #605-394-4720 EMAIL: Arthur.turner@lumen.com
The Company will have abandoned underground telecommunications facilities through the project. Facilities will have been relocated in full to Interstate 90 Right of Way.

(3) West Central Electric Cooperative, Inc.
PO Box 17
Murdo, SD, 57559
CONTACT: Mr. Jeff Birkeland TELE: #605-669-8100 EMAIL: scott.kittelson@wce.coop
The Company has overhead and underground electric facilities through the project. Facilities will be temporarily relocated and/or de-energized in place during construction. Remain in place facilities will be de-energized or be clear of highway construction. Temporary facilities will be placed clear of highway construction. Facilities placed or remaining within temporary highway easements will be approved by Area Engineer. Facilities as follows.

- Overhead (OH) lines, poles, and all other facilities at the following locations will be temporarily relocated South clear of work limits before construction. These facilities will be moved back upon project completion.
  - Approximately Station 13+00 to 34+00 L
  - Approximately Station 60+00 to 94+00 L
  - Approximately Station 105+00 to 142+00 L
  - Approximately Station 170+00 to 188+00 L
  - Approximately Station 271+00 to 282+00 L
- Overhead (OH) line crossing at approximately Station 91+00 will be raised to avoid construction. Poles and other facilities will relocate outside of limits of construction. This line will remain energized during construction.
- Underground, "URD line", going South at approximately Station 178+00 will be adjusted with a riser on OH line added to keep line energized during construction.
- Underground, "URD line", from approximately Station 356+00 to 369+00 will be isolated/de-energized during construction and then reinstalled to the depth required by code when the project is complete.

(4) West River / Lyman-Jones Rural Water Systems, Inc.
PO Box 407
Murdo, SD, 57559
CONTACT: Mr. Jake Fitzgerald TELE: #605-669-2931 EMAIL: jfitzgerald@wrlj.com
The Company has water distribution facilities present and in conflict at one structure in project. All facilities present within project as follows. All Stations approximate.
- Structure 38-302-173 – No Facilities Present
- Structure 38-312-173 – Facilities approximately 400ft South of Right of Way, no conflict.
- Structure 38-319-174 – existing facilities to be relocated South (Right) from Station 112+00 to Station 136 R. All relocated facilities to accommodate highway construction.
- Structure 38-330-175 (Station 170+90 to Station 173+00) – Facilities to remain in place. Existing facilities present on Right (South) existing Right of Way line enter work limits from West and turn South to leave project at approximately Station 173+00 R.

- Structure 38-348-174 – No Facilities Present
- Structure 43-014-188 – No Facilities Present

The requirements relating to Cooperation Between Contractors, as set forth in Section 5.7 of the Standards Specifications for Roads and Bridges, 2015 edition, shall prevail throughout the limits of this project.

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
SUBMISSION OF BID PROPOSALS
(SDEBS Lettings)

OCTOBER 29, 2026

Add the following to the end of Section 2.10 B:

Bidders are strongly encouraged to complete and submit the bid proposal well in advance of the deadline. Bidders assume full responsibility for the timely and successful submission of their bid proposals. The Department is not responsible for a bidder's inability to submit a bid proposal using SDEBS. The Department reserves the right to cancel the opening of bid proposals if in the judgment of the Department canceling the opening of bid proposals promotes the best interest of the Department.

* * * * *

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
AGGREGATES FOR GRANULAR BASES AND SURFACING

OCTOBER 26, 2026

Section 882 – Delete Table 2 and replace it with the following:

Table 2 – Other Properties

Property	Subbase	Gravel Cushion	Base Course	Limestone Ledge Rock Base Course	Limestone Ledge Rock Gravel Cushion	Gravel Surfacing	Pit Run	Granular Bridge End Backfill
Liquid Limit (max)		25	25	25	25			25
Plasticity Index (max) *1	0-6	0-6	0-6	0-3	0-3	4-12		0-6
LA Abrasion Loss (max)	50	40	40	40	40	40		40
Crushed Particles (min) +#4 Sieve	30% 1-CF	30% 1-CF	30% 1-CF	30% 1-CF	30% 1-CF	30% 1-CF		30% 1-CF
Foot Notes		*2	*1, *2				*3	

*1 The fraction passing the #200 sieve will not be greater than 2/3 of the fraction passing the #40 sieve. In no case will the upper limit specified for the #200 sieve be exceeded.

*2 Requirements apply to ledge rock other than limestone ledge rock.

*3 Acceptance of pit run will be by visual inspection. The Engineer may require a sieve analysis to verify the material meets the specified gradation. Independent Assurance will not be required.

* * * * *

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
ACKNOWLEDGEMENT AND CERTIFICATION REGARDING
ARTICLE 3, SECTION 12
OF THE SOUTH DAKOTA CONSTITUTION

AUGUST 24, 2023

In accordance with the State of South Dakota Office of the Governor Executive Order 2023-13, the following will apply to all contracts:

The Contractor acknowledges and certifies that the following information is correct:

CERTIFICATION OF NO STATE LEGISLATOR INTEREST:

Contractor (i) understands neither a state legislator nor a business in which a state legislator has an ownership interest may be directly or indirectly interested in any contract with the State that was authorized by any law passed during the term for which that legislator was elected, or within one year thereafter, and (ii) has read South Dakota Constitution Article 3, Section 12 and has had the opportunity to seek independent legal advice on the applicability of that provision to this contract. By signing this contract, Contractor hereby certifies that this contract is not made in violation of the South Dakota Constitution Article 3, Section 12.

It is understood and agreed that, if this certification is false, such false certification will constitute grounds for the Department to terminate the contract.

The Contractor further agrees to provide immediate written notice to the Department if during the term of the contract it no longer complies with this certification and agrees such noncompliance may be grounds for contract termination.

* * * * *

DOT-208
(11/25)

FUEL ADJUSTMENT AFFIDAVIT

Project Number _____
PCN _____
County _____

For projects let using the SDEBS) and in accordance with Section 9.10, the bidder is not required to notify the Department at the time of submitting bids whether the Contractor will or will not participate in the fuel cost adjustment program. Prior to execution of the contract, the successful bidder must submit this completed form to the Department for approval. The Fuel Adjustment Affidavit will include the anticipated fuel cost of subcontractors.

Does your company elect to participate in a fuel adjustment for this contract for the fuels that do not have a fixed price? No adjustments in fuel prices will be made if "No" is checked.

☐ Yes ☐ No

If yes, provide the total dollars for each of the applicable fuels. No adjustments in fuel price will be made for the fuel types that are left blank or completed with a $0.00 value.

Diesel (x) $_____

Unleaded (y) $_____

Burner Fuel (z) $_____ Type of Burner Fuel Used: _____

Sum (x + y + z) = $_____

Note: The sum of the x, y, and z must not exceed 15% of the original contract amount.

The following must be completed regardless of whether the Contractor elects to participate in the fuel adjustment affidavit

Under the penalty of law for perjury or falsification, the undersigned, _____,
(Printed Name)

_____ of _____,
(Title) *(Contractor)*

hereby certifies that the documentation is submitted in good faith, that the information provided is accurate and complete to the best of their knowledge and belief, and that the monetary amount identified accurately reflects the cost for fuel, and that they are duly authorized to certify the above documentation on behalf of the company.

I hereby agree that the Department or its authorized representative will have the right to examine and copy all Contractor records, documents, work sheets, bid sheets, and other data pertinent to the justification of the fuel costs shown above.

Dated _____ Signature _____

Notarization is required only when the Contractor elects to participate in the fuel adjustment affidavit

Subscribed and sworn before me this _____ day of _____ , 20___.

_____ _____
Notary Public *My Commission Expires*

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

STANDARD TITLE VI / NONDISCRIMINATION ASSURANCES APPENDIX A & E

MARCH 1, 2016

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees as follows:

1. **Compliance with Regulations**: The contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.

2. **Non-discrimination**: The contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.

3. **Solicitations for Subcontracts, Including Procurements of Materials and Equipment**: In all solicitations, either by competitive bidding, or negotiation made by the contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the contractor of the contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.

4. **Information and Reports**: The contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a contractor is in the exclusive possession of another who fails or refuses to furnish the information, the contractor will so certify to the Recipient or the Federal Highway Administration, as appropriate, and will set forth what efforts it has made to obtain the information.

5. **Sanctions for Noncompliance**: In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:

    a. withholding payments to the contractor under the contract until the contractor complies; and/or
    b. cancelling, terminating, or suspending a contract, in whole or in part.

6. **Incorporation of Provisions**: The contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the contractor becomes involved in, or

is threatened with litigation by a subcontractor, or supplier because of such direction, the contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the contractor may request the United States to enter into the litigation to protect the interests of the United States.

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the "contractor") agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d et seq., 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 et seq.), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 et seq.), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 et seq.), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);
- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures Non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of Limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 et seq).

****

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION FOR EQUAL EMPLOYMENT OPPORTUNITY REQUIREMENTS FOR HIGHWAY CONSTRUCTION CONTRACTS

OCTOBER 7, 2026

---

1. General

a. Equal employment opportunity requirements prohibiting discrimination, imposed pursuant to 23 U.S.C. §140, Section 22 of the Federal-Aid Highway Act of 1968, and 23 CFR 230, apply to this contract. This Special Provision constitutes the specific equal employment opportunity requirements for all project activities and supplements those found in the Standard Title VI / Nondiscrimination Assurances Appendix A & E and the FHWA 1273 Contract Provisions for Federal-aid Construction Contracts.

b. The Contractor will work with the Department and the Federal Government in meeting equal employment opportunity obligations and participating in reviews of Contractor activities under the contract.

c. The Contractor and all subcontractors (excluding material suppliers) holding subcontracts of $10,000 or more will comply with the minimum equal employment opportunity requirements in this Special Provision. The Contractor will include these requirements in every subcontract of $10,000 or more, modifying language as needed to ensure they are binding on the subcontractor.

2. Equal Employment Opportunity Policy

The Contractor adopts the following operating policy to ensure equal employment opportunity for all persons without regard to race, color, religion, sex, national origin, age, or disability:

Company Policy Statement:
It is the policy of this company to ensure that applicants are employed, and employees are treated during employment without regard to race, color, religion, sex, national origin, age, or disability. This includes actions related to employment, upgrading, demotion, transfer, recruitment, recruitment advertising, layoff, termination, rates of pay, other compensation, and selection for training—including apprenticeship, pre-apprenticeship, and on-the-job training.

3. Equal Employment Opportunity Officer

The Contractor will designate an Equal Employment Opportunity Officer (EEO Officer) and provide that information to the Department. The EEO Officer must be

capable of effectively administering and promoting an active equal employment opportunity program and must have sufficient authority and responsibility to do so.

4. Dissemination of Policy

a. All members of the Contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's equal employment opportunity policy and contractual responsibilities to provide equal employment opportunity in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

1) Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's equal employment opportunity policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer or other knowledgeable company official.

2) All new supervisory or personnel office employees will be given a thorough orientation by the EEO Officer or other knowledgeable company official, covering all major aspects of the Contractor's equal employment opportunity obligations within thirty days following their reporting for duty with the contractor.

3) All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer or appropriate company official in the contractor's procedures for locating and hiring employees.

b. In order to make the Contractor's equal employment opportunity policy known to all employees, prospective employees, and potential sources of employees, *i.e.*, schools, employment agencies, labor unions (where appropriate), college placement officers, etc., the Contractor will take the following actions:

1) Notices and posters setting forth the Contractor's equal employment opportunity policy and identifying the Company EEO Officer or Project EEO Representative will be placed in areas readily accessible to employees, applicants for employment and potential employees at the home office and project site (EEO #7 Poster).

2) The Contractor's equal employment opportunity policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

5. **Recruitment**

   a. **Advertising**
   All employment advertisements will include the phrase “An Equal Opportunity Employer” and must be published in media with broad circulation in the project’s recruitment area.

   b. **Direct Recruitment**
   Unless precluded by a valid bargaining agreement, the Contractor will conduct systematic and direct recruitment through sources likely to yield qualified applicants, including state employment agencies, schools, colleges, and community organizations. The EEO Officer will identify referral sources and establish procedures for referring applicants to the Contractor.

   Where exclusive hiring or bargaining agreements exist, the Contractor will follow their provisions to the extent they permit compliance with equal employment opportunity requirements.

   c. **Employee Referrals**
   The Contractor will encourage current employees to refer applicants by posting notices and discussing referral procedures with employees.

6. **Personnel Actions**
   All personnel actions—including wages, working conditions, benefits, hiring, upgrading, promotion, transfer, demotion, layoff, and termination—must be conducted without regard to race, color, religion, sex, national origin, age, or disability. The Contractor will:

   a. Conduct periodic inspections of project sites to ensure working conditions and facilities do not indicate discriminatory treatment.

   b. Periodically evaluate wage spreads within each classification to detect potential discriminatory practices.

   c. Review selected personnel actions to determine whether discriminatory patterns exist and promptly correct any identified issues.

   d. Investigate all complaints of alleged discrimination, resolve them when possible, take appropriate corrective action within a reasonable time, and upon completion of each investigation, notify complainants of all available avenues of appeal.

7. **Training and Promotion**

   a. Assist in locating, qualifying, and improving the skills of current employees and applicants.

b. Utilize training programs—such as apprenticeship and on-the-job training—as permitted under Federal and State regulations. Where feasible, 25% of apprentices or trainees in each occupation will be in their first year of apprenticeship or training. (If a Training Special Provision applies, it supersedes this subparagraph.)

c. Inform employees and applicants of available training programs and entrance requirements.

d. Periodically review employees' training and promotion potential and encourage eligible employees to apply.

8. Unions

If unions are used as a source of employees, the Contractor will make best efforts to secure their cooperation in supporting equal employment opportunity. Contractor's actions will include:

a. Working with unions to develop joint training programs that expand opportunities for employees.

b. Incorporate an equal employment opportunity clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age, or disability.

c. Obtaining information about union referral practices and policies. Contractor will certify to the Department its efforts made to acquire the information where the union refuses to provide such information.

d. Using independent recruitment efforts to fill vacancies if union referrals are insufficient and notifying the Department if union practices impede compliance.

9. Subcontracting

a. The Contractor will make best efforts to solicit bids from and utilize Disadvantaged Business Enterprise (DBE) subcontractors. All certified DBEs are listed in the State's DBE Directory.

b. The Contractor will ensure that all subcontractors comply with equal employment opportunity requirements.

c. The Contractor will insert this Special Provision, the Contract Provisions for Federal-aid Construction Contracts (FHWA 1273)and the Special Provision for Contract Provisions for Federal-aid Construction Contracts FHWA 1273 in all subcontracts.

10. Records and Reports

a. Required Records

The Contractor will maintain records necessary to determine compliance with equal employment opportunity requirements. The records kept by the Contractor will be designed to indicate:

1) Number of employees in each work classification, identified by minority status and sex.

2) Efforts made in cooperation with unions to improve employment opportunities (for Contractors relying on unions).

3) Progress and efforts made to locate, hire, train, qualify, and upgrade employees.

4) Progress and efforts made to secure DBE subcontractors.

b. Retention

Records must be retained for three years after project completion and be available at reasonable times and places for inspection by the Department and the Federal Highway Administration.

c. Annual Report

Each July, the Contractor will submit a consolidated Form PR-1391 to the Department reporting the number of minority, women, and non-minority employees in each work classification engaged on all projects worked during the reporting period.

* * * * *

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION FOR
CONTRACT PROVISIONS FOR
FEDERAL-AID CONSTRUCTION CONTRACTS
FHWA 1273 (JUNE 25, 2026)

OCTOBER 7, 2026

This Special Provision must be physically incorporated in each construction contract. The Contractor (or subcontractor) must insert this Special Provision in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements, and other agreements for supplies or services).

The following are amendments to the Contract Provisions for Federal-aid Construction Contract FHWA 1273.

Section I.1.

Delete the first paragraph of this section and replace it with the following:

Form FHWA-1273 must be physically incorporated in each construction contract. The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements, and other agreements for supplies or services).

Section I.4.

Delete this section and replace with the following:

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a Federal-aid construction project unless it is labor performed by convicts who are on parole, supervised release, or probation.

Section III.

Delete the first three sentences of the first paragraph and replace with the following:

This section is applicable to all Federal-aid construction projects exceeding $2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway and to all portions of Transportation Alternatives Program (TAP) funded projects.

Section III.3.b.(1)

Delete this section and replace with the following:

The Contractor and each related subcontractor must submit weekly, for each week in which any contract work is performed, an electronic certified weekly payroll report. The Contractor is responsible for the submission of certified payroll reports by all subcontractors. The payroll report must be submitted electronically to the Elation System website. The Contractor must submit a legally valid electronic signature. The Elation System website can be accessed by logging onto the State of South Dakota's single sign-on website at https://mysd.sd.gov/ or can also be accessed at https://elationsys.com/. First time users will need to use the Promotion Code SDDOT-19. The payroll report must be submitted within fourteen (14) calendar days after the end of the workweek.

Section III.3.b.(2)

Delete the third sentence.

Section III.3.b.(3)

Delete the first paragraph and replace with the following:

Each certified weekly payroll report must include the most recent South Dakota Department of Transportation (SDDOT) Statement of Compliance Form, signed by the Contractor or related subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract. The Instructions for the SDDOT Statement of Compliance Form are found at https://dot.sd.gov/doing-business/contractors/labor-compliance/certified-payrolls-let-after-6/5/19. The SDDOT will not accept any payroll report which does not include the most recent SDDOT Statement of Compliance Form. The SDDOT Statement of Compliance Form must certify the following:

Section III.3.b.(4)

Delete this paragraph and replace with the following:

The weekly submission of a properly executed SDDOT Statement of Compliance Form shall satisfy the requirement for submission of the "Statement of Compliance Form" required by paragraph 3.b.(3) of this section.

Section III.4.a.(1)

Delete the first sentence and replace with the following:

Apprentices will be permitted to work at less than the predetermined rate for the work they perform, but not less than the Common Laborer wage rate contained in the bid documents, when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship (OA), or with a State Apprenticeship Agency recognized by the OA.

* * * * *

CONTRACT PROVISIONS FOR FEDERAL-AID CONSTRUCTION CONTRACTS

I. General
II. Nondiscrimination
III. Davis-Bacon and Related Act Provisions
IV. Contract Work Hours and Safety Standards Act Provisions
V. Subletting or Assigning the Contract
VI. Safety: Accident Prevention
VII. False Statements Concerning Highway Projects
VIII. Implementation of Clean Air Act and Federal Water Pollution Control Act
IX. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion
X. Certification Regarding Use of Contract Funds for Lobbying
XI. Use of United States-Flag Vessels

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only).

I. GENERAL

1. Historically, contracting agencies using Federal-aid highway funds were required to ensure Form FHWA-1273 was physically incorporated into all contracts and subcontracts. Effective June 10, 2026, this requirement was eliminated [91 FR 25492]. Future use of Form FHWA-1273 is now optional on the part of the contracting agency using Federal-aid highway funds. FHWA continues to make Form FHWA-1273 available as a convenience to contracting agencies. Contracting agencies must continue to ensure compliance with the provisions cited in Form FHWA-1273 in accordance with the provisions regardless of the use of Form FHWA-1273. Accordingly, the contracting agency retains the authority to determine whether the contractor must use Form FHWA-1273 to physically incorporate required contract provisions in each subcontract and in lower tier contracts. Where permitted by the contracting agency, the contractor may choose other ways to include required contract provisions in each subcontract, besides incorporating Form FHWA-1273. Contract provisions in Form FHWA-1273 are not required to be physically included in subcontracts for design services on Federal-aid design-build contracts, or in purchase orders, rental agreements and other agreements for supplies or services.

The applicable provisions of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor or design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in solicitation-for-bids or request-for-proposals documents.

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. 23 U.S.C. 114(b). The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors. 23 U.S.C. 101(a).

II. NONDISCRIMINATION

The contractor and all subcontractors must comply with the following policies: 29 CFR Parts 1625-1627, 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27, including any amendments thereto.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with 29 CFR Parts 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with 23 U.S.C. 140, Section 504 of the Rehabilitation Act of 1973, as amended (29 U.S.C. 794), and Title VI of the Civil Rights Act of 1964, as amended (42 U.S.C. 2000d et seq.), and related regulations including 49 CFR Parts 21, 26, and 27, including any amendments thereto.

The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR Part 35 and 29 CFR Part 1630 are incorporated by reference in this contract.

1. Assurances Required:

a. The requirements of 49 CFR Part 26, including any amendments thereto, and the State DOT's FHWA-approved Disadvantaged Business Enterprise (DBE) program are incorporated by reference.

b. The contractor, subrecipient or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR part 26, including any amendments thereto, in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

(1) Withholding monthly progress payments;
(2) Assessing sanctions;
(3) Liquidated damages; and/or
(4) Disqualifying the contractor from future bidding as non-responsible.

c. The Title VI and nondiscrimination provisions of U.S. DOT Order 1050.2A at Appendixes A and E, including any amendments thereto, are incorporated by reference. 49 CFR Part 21.

III. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding $2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size), in accordance with 29 CFR 5.5. The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. 23 U.S.C. 113. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. 23 U.S.C. 101. Where applicable law requires that projects be treated as a project on a Federal-aid highway, the provisions of this subpart will apply regardless of the location of the project. Examples include: Surface Transportation Block Grant Program projects funded under 23 U.S.C. 133 [excluding recreational trails projects], the Nationally Significant Freight and Highway Projects funded under 23 U.S.C. 117, and National Highway Freight Program projects funded under 23 U.S.C. 167.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 “Contract provisions and related matters” with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages (29 CFR 5.5)

a. *Wage rates and fringe benefits.* All laborers and mechanics employed or working upon the site of the work (or otherwise working in construction or development of the project under a development statute), will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of basic hourly wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics. As provided in paragraphs (d) and (e) of 29 CFR 5.5, the appropriate wage determinations are effective by operation of law even if they have not been attached to the contract. Contributions made or costs reasonably anticipated for bona fide fringe benefits under the Davis-Bacon Act (40 U.S.C. 3141(2)(B)) on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions of paragraph 1.e. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics must be paid the appropriate wage rate and fringe benefits on the wage determination for the classification(s) of work actually performed, without regard to skill, except as provided in paragraph 4. of this section. Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: *Provided,* That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classifications and wage rates conformed under paragraph 1.c. of this section) and the Davis-Bacon poster (WH–1321) must be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b. *Frequently recurring classifications.* (1) In addition to wage and fringe benefit rates that have been determined to be prevailing under the procedures set forth in 29 CFR part 1, a wage determination may contain, pursuant to § 1.3(f), wage and fringe benefit rates for classifications of laborers and mechanics for which conformance requests are regularly submitted pursuant to paragraph 1.c. of this section, provided that:

(i) The work performed by the classification is not performed by a classification in the wage determination for which a prevailing wage rate has been determined;

(ii) The classification is used in the area by the construction industry; and

(iii) The wage rate for the classification bears a reasonable relationship to the prevailing wage rates contained in the wage determination.

(2) The Administrator will establish wage rates for such classifications in accordance with paragraph 1.c.(1)(iii) of this section. Work performed in such a classification must be paid at no less than the wage and fringe benefit rate listed on the wage determination for such classification.

c. *Conformance.* (1) The contracting officer must require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract be classified in conformance with the wage determination. Conformance of an additional classification and wage rate and fringe benefits is appropriate only when the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(ii) The classification is used in the area by the construction industry; and

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) The conformance process may not be used to split, subdivide, or otherwise avoid application of classifications listed in the wage determination.

(3) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the

classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken will be sent by the contracting officer by email to *DBAconformance@dol.gov*. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.

(4) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer will, by email to *DBAconformance@dol.gov*, refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Administrator for determination. The Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30–day period that additional time is necessary.

(5) The contracting officer must promptly notify the contractor of the action taken by the Wage and Hour Division under paragraphs 1.c.(3) and (4) of this section. The contractor must furnish a written copy of such determination to each affected worker or it must be posted as a part of the wage determination. The wage rate (including fringe benefits where appropriate) determined pursuant to paragraph 1.c.(3) or (4) of this section must be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

d. *Fringe benefits not expressed as an hourly rate.* Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor may either pay the benefit as stated in the wage determination or may pay another bona fide fringe benefit or an hourly cash equivalent thereof.

e. *Unfunded plans.* If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program, *Provided,* That the Secretary of Labor has found, upon the written request of the contractor, in accordance with the criteria set forth in § 5.28, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

f. *Interest.* In the event of a failure to pay all or part of the wages required by the contract, the contractor will be required to pay interest on any underpayment of wages.

2. Withholding (29 CFR 5.5)

a. *Withholding requirements.* The contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for the full amount of wages and monetary relief, including interest, required by the clauses set forth in this section for violations of this contract, or to satisfy any such liabilities required by any other Federal contract, or federally assisted contract subject to Davis-Bacon labor standards, that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to Davis-Bacon labor standards requirements and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld. In the event of a contractor's failure to pay any laborer or mechanic, including any apprentice or helper working on the site of the work all or part of the wages required by the contract, or upon the contractor's failure to submit the required records as discussed in paragraph 3.d. of this section, the contracting agency may on its own initiative and after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

b. *Priority to withheld funds.* The Department has priority to funds withheld or to be withheld in accordance with paragraph 2.a. of this section or Section IV, paragraph 3.a., or both, over claims to those funds by:

(1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;

(2) A contracting agency for its reprocurement costs;

(3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;

(4) A contractor's assignee(s);

(5) A contractor's successor(s); or

(6) A claim asserted under the Prompt Payment Act, 31 U.S.C. 3901–3907.

3. Records and certified payrolls (29 CFR 5.5)

a. *Basic record requirements* (1) *Length of record retention.* All regular payrolls and other basic records must be maintained by the contractor and any subcontractor during the course of the work and preserved for all laborers and mechanics working at the site of the work (or otherwise working in construction or development of the project under a development statute) for a period of at least 3 years after all the work on the prime contract is completed.

(2) *Information required.* Such records must contain the name; Social Security number; last known address, telephone number, and email address of each such worker; each worker's correct classification(s) of work actually performed; hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in 40 U.S.C. 3141(2)(B) of the Davis-Bacon Act); daily and weekly number

of hours actually worked in total and on each covered contract; deductions made; and actual wages paid.

(3) *Additional records relating to fringe benefits.* Whenever the Secretary of Labor has found under paragraph 1.e. of this section that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in 40 U.S.C. 3141(2)(B) of the Davis-Bacon Act, the contractor must maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits.

(4) *Additional records relating to apprenticeship.* Contractors with apprentices working under approved programs must maintain written evidence of the registration of apprenticeship programs, the registration of the apprentices, and the ratios and wage rates prescribed in the applicable programs.

b. *Certified payroll requirements* (1) *Frequency and method of submission.* The contractor or subcontractor must submit weekly, for each week in which any DBA- or Related Acts-covered work is performed, certified payrolls to the contracting agency. The prime contractor is responsible for the submission of all certified payrolls by all subcontractors. A contracting agency or prime contractor may permit or require contractors to submit certified payrolls through an electronic system, as long as the electronic system requires a legally valid electronic signature; the system allows the contractor, the contracting agency, and the Department of Labor to access the certified payrolls upon request for at least 3 years after the work on the prime contract has been completed; and the contracting agency or prime contractor permits other methods of submission in situations where the contractor is unable or limited in its ability to use or access the electronic system.

(2) *Information required.* The certified payrolls submitted must set out accurately and completely all of the information required to be maintained under paragraph 3.a.(2) of this section, except that full Social Security numbers and last known addresses, telephone numbers, and email addresses must not be included on weekly transmittals. Instead, the certified payrolls need only include an individually identifying number for each worker (*e.g.,* the last four digits of the worker's Social Security number). The required weekly certified payroll information may be submitted using Optional Form WH–347 or in any other format desired. Optional Form WH–347 is available for this purpose from the Wage and Hour Division website at *https://www.dol.gov/sites/dolgov/files/WHD/legacy/files/wh347/.pdf* or its successor website. It is not a violation of this section for a prime contractor to require a subcontractor to provide full Social Security numbers and last known addresses, telephone numbers, and email addresses to the prime contractor for its own records, without weekly submission by the subcontractor to the contracting agency.

(3) *Statement of Compliance.* Each certified payroll submitted must be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor, or the contractor's or subcontractor's agent who pays or supervises the payment of the persons working on the contract, and must certify the following:

(i) That the certified payroll for the payroll period contains the information required to be provided under paragraph 3.b. of this section, the appropriate information and basic records are being maintained under paragraph 3.a. of this section, and such information and records are correct and complete;

(ii) That each laborer or mechanic (including each helper and apprentice) working on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in 29 CFR part 3; and

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification(s) of work actually performed, as specified in the applicable wage determination incorporated into the contract.

(4) *Use of Optional Form WH–347.* The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH–347 will satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(3) of this section.

(5) *Signature.* The signature by the contractor, subcontractor, or the contractor's or subcontractor's agent must be an original handwritten signature or a legally valid electronic signature.

(6) *Falsification.* The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under 18 U.S.C. 1001 and 31 U.S.C. 3729.

(7) *Length of certified payroll retention.* The contractor or subcontractor must preserve all certified payrolls during the course of the work and for a period of 3 years after all the work on the prime contract is completed.

c. *Contracts, subcontracts, and related documents.* The contractor or subcontractor must maintain this contract or subcontract and related documents including, without limitation, bids, proposals, amendments, modifications, and extensions. The contractor or subcontractor must preserve these contracts, subcontracts, and related documents during the course of the work and for a period of 3 years after all the work on the prime contract is completed.

d. *Required disclosures and access* (1) *Required record disclosures and access to workers.* The contractor or subcontractor must make the records required under paragraphs 3.a. through 3.c. of this section, and any other documents that the contracting agency, the State DOT, the FHWA, or the Department of Labor deems necessary to determine compliance with the labor standards provisions of any of the applicable statutes referenced by § 5.1, available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and must permit such representatives to interview workers during working hours on the job.

(2) *Sanctions for non-compliance with records and worker access requirements.* If the contractor or subcontractor fails to submit the required records or to make them available, or refuses to permit worker interviews during working hours on the job, the Federal agency may, after written notice to the contractor, sponsor, applicant, owner, or other entity, as the case may be, that maintains such records or that employs such workers, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available, or to permit worker interviews during working hours on the job, may be grounds for debarment action pursuant to § 5.12. In addition, any contractor or other person that fails to submit the required records or make those records available to WHD within the time WHD requests that the records be produced will be precluded from introducing as evidence in an administrative proceeding under 29 CFR part 6 any of the required records that were not provided or made available to WHD. WHD will take into consideration a reasonable request from the contractor or person for an extension of the time for submission of records. WHD will determine the reasonableness of the request and may consider, among other things, the location of the records and the volume of production.

(3) *Required information disclosures.* Contractors and subcontractors must maintain the full Social Security number and last known address, telephone number, and email address of each covered worker, and must provide them upon request to the contracting agency, the State DOT, the FHWA, the contractor, or the Wage and Hour Division of the Department of Labor for purposes of an investigation or other compliance action.

4. Apprentices and equal employment opportunity (29 CFR 5.5)

a. *Apprentices* (1) *Rate of pay.* Apprentices will be permitted to work at less than the predetermined rate for the work they perform when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship (OA), or with a State Apprenticeship Agency recognized by the OA. A person who is not individually registered in the program, but who has been certified by the OA or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice, will be permitted to work at less than the predetermined rate for the work they perform in the first 90 days of probationary employment as an apprentice in such a program. In the event the OA or a State Apprenticeship Agency recognized by the OA withdraws approval of an apprenticeship program, the contractor will no longer be permitted to use apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

(2) *Fringe benefits.* Apprentices must be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringe benefits must be paid in accordance with that determination.

(3) *Apprenticeship ratio.* The allowable ratio of apprentices to journeyworkers on the job site in any craft classification must not be greater than the ratio permitted to the contractor as to the entire work force under the registered program or the ratio applicable to the locality of the project pursuant to paragraph 4.a.(4) of this section. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated in paragraph 4.a.(1) of this section, must be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under this section must be paid not less than the applicable wage rate on the wage determination for the work actually performed.

(4) *Reciprocity of ratios and wage rates.* Where a contractor is performing construction on a project in a locality other than the locality in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyworker's hourly rate) applicable within the locality in which the construction is being performed must be observed. If there is no applicable ratio or wage rate for the locality of the project, the ratio and wage rate specified in the contractor's registered program must be observed.

b. *Equal employment opportunity.* The use of apprentices and journeyworkers under this part must be in conformity with 29 CFR part 30, including any amendments thereto.

c. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section III. 23 CFR 230.111(e)(2). The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeyworkers shall not be greater than permitted by the terms of the particular program.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract as provided in 29 CFR 5.5.

6. Subcontracts. The contractor or subcontractor must insert in any subcontracts the clauses set forth in paragraphs (1) through (11) of this section, along with the applicable wage determination(s) and such other clauses or contract modifications as the contracting agency may by appropriate instructions require, and a clause requiring the subcontractors to include these clauses and wage determination(s) in any lower tier subcontracts. The prime contractor is responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in this section. In the event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lower-tier subcontractors, and may be subject to debarment, as appropriate. 29 CFR 5.5.

7. Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the

contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract as provided in 29 CFR 5.5.

9. Disputes concerning labor standards. As provided in 29 CFR 5.5, disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility. a. By entering into this contract, the contractor certifies that neither it nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of 40 U.S.C. 3144(b) or § 5.12(a).

b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of 40 U.S.C. 3144(b) or § 5.12(a).

c. The penalty for making false statements is prescribed in the U.S. Code, Title 18 Crimes and Criminal Procedure, 18 U.S.C. 1001.

11. Anti-retaliation. It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:

a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the DBA, Related Acts, this part, or 29 CFR part 1 or 3;

b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under the DBA, Related Acts, this part, or 29 CFR part 1 or 3;

c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under the DBA, Related Acts, this part, or 29 CFR part 1 or 3; or

d. Informing any other person about their rights under the DBA, Related Acts, this part, or 29 CFR part 1 or 3.

IV. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

Pursuant to 29 CFR 5.5(b), the following clauses apply to any Federal-aid construction contract in an amount in excess of $100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchpersons and guards.

1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek. 29 CFR 5.5.

2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph 1. of this section the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages and interest from the date of the underpayment. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchpersons and guards, employed in violation of the clause set forth in paragraph 1. of this section, in the sum currently provided in 29 CFR 5.5(b)(2)* for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph 1. of this section.

* $33 as of January 15, 2025 (See 90 FR 1859) as may be adjusted annually by the Department of Labor, pursuant to the Federal Civil Penalties Inflation Adjustment Act of 1990.

3. Withholding for unpaid wages and liquidated damages

a. *Withholding process.* The FHWA or the contracting agency may, upon its own action, or must, upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor so much of the accrued payments or advances as may be considered necessary to satisfy the liabilities of the prime contractor or any subcontractor for any unpaid wages; monetary relief, including interest; and liquidated damages required by the clauses set forth in this section on this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract subject to the Contract Work Hours and Safety Standards Act that is held by the same prime contractor (as defined in § 5.2). The necessary funds may be withheld from the contractor under this contract, any other Federal contract with the same prime contractor, or any other federally assisted contract that is subject to the Contract Work Hours and Safety Standards Act and is held by the same prime contractor, regardless of whether the other contract was awarded or assisted by the same agency, and such funds may be used to satisfy the contractor liability for which the funds were withheld.

b. *Priority to withheld funds.* The Department has priority to funds withheld or to be withheld in accordance with Section III paragraph 2.a. or paragraph 3.a. of this section, or both, over claims to those funds by:

(1) A contractor's surety(ies), including without limitation performance bond sureties and payment bond sureties;

(2) A contracting agency for its reprocurement costs;

(3) A trustee(s) (either a court-appointed trustee or a U.S. trustee, or both) in bankruptcy of a contractor, or a contractor's bankruptcy estate;

(4) A contractor's assignee(s);

(5) A contractor's successor(s); or

(6) A claim asserted under the Prompt Payment Act, 31 U.S.C. 3901–3907.

4. Subcontracts. The contractor or subcontractor must insert in any subcontracts the clauses set forth in paragraphs 1. through 5. of this section and a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor is responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs 1. through 5. In the event of any violations of these clauses, the prime contractor and any subcontractor(s) responsible will be liable for any unpaid wages and monetary relief, including interest from the date of the underpayment or loss, due to any workers of lower-tier subcontractors, and associated liquidated damages and may be subject to debarment, as appropriate.

5. Anti-retaliation. It is unlawful for any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, or to cause any person to discharge, demote, intimidate, threaten, restrain, coerce, blacklist, harass, or in any other manner discriminate against, any worker or job applicant for:

a. Notifying any contractor of any conduct which the worker reasonably believes constitutes a violation of the Contract Work Hours and Safety Standards Act (CWHSSA) or its implementing regulations in this part;

b. Filing any complaint, initiating or causing to be initiated any proceeding, or otherwise asserting or seeking to assert on behalf of themselves or others any right or protection under CWHSSA or this part;

c. Cooperating in any investigation or other compliance action, or testifying in any proceeding under CWHSSA or this part; or

d. Informing any other person about their rights under CWHSSA or this part.

V. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System pursuant to 23 CFR 635.116.

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).

a. The term “perform work with its own organization” in paragraph 1. of this section refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions: (based on longstanding interpretation)

(1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;
(2) the prime contractor remains responsible for the quality of the work of the leased employees;
(3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and
(4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.

b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract. 23 CFR 635.102.

2. Pursuant to 23 CFR 635.116(a), the contract amount upon which the requirements set forth in paragraph 1. of this section is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. Pursuant to 23 CFR 635.116(c), the contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract. (based on long-standing interpretation of 23 CFR 635.116).

5. The 30-percent self-performance requirement of paragraph (1) is not applicable to design-build contracts; however,

contracting agencies may establish their own self-performance requirements. 23 CFR 635.116(d).

VI. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR Part 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract. 23 CFR 635.108.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR Part 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704). 29 CFR 1926.10.

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

VII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR Part 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 11, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

VIII. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT (42 U.S.C. 7606; 2 CFR 200.88; EO 11738)

This provision is applicable to all Federal-aid construction contracts in excess of $150,000 and to all related subcontracts. 48 CFR 2.101; 2 CFR 200.327.

By submission of this bid/proposal or the execution of this contract or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, subcontractor, supplier, or vendor agrees to comply with all applicable standards, orders or regulations issued pursuant to the Clean Air Act (42 U.S.C. 7401-7671q) and the Federal Water Pollution Control Act, as amended (33 U.S.C. 1251-1387). Violations must be reported to the Federal Highway Administration and the Regional Office of the Environmental Protection Agency. 2 CFR Part 200, Appendix II.

The contractor agrees to include or cause to be included the requirements of this Section in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements. 2 CFR 200.327.

IX. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost $25,000 or more – as defined in 2 CFR Parts 180 and 1200. 2 CFR 180.220 and 1200.220.

1**. Instructions for Certification – First Tier Participants:**

a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction. 2 CFR 180.320.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default. 2 CFR 180.325.

d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances. 2 CFR 180.345 and 180.350.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900-180.1020, and 1200. “First Tier Covered Transactions” refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). “Lower Tier Covered Transactions” refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). “First Tier Participant” refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). “Lower Tier Participant” refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction. 2 CFR 180.330.

g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the $25,000 threshold. 2 CFR 180.220 and 180.300.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. 2 CFR 180.300; 180.320, and 180.325. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. 2 CFR 180.335. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (https://www.sam.gov/). 2 CFR 180.300, 180.320, and 180.325.

i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default. 2 CFR 180.325.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.335;

(2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State, or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property, 2 CFR 180.800;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification, 2 CFR 180.700 and 180.800; and

(4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default. 2 CFR 180.335(d).

(5) Are not a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and

(6) Are not a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability (USDOT Order 4200.6 implementing appropriations act requirements).

b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal. 2 CFR 180.335 and 180.340.

* * * * *

3. **Instructions for Certification - Lower Tier Participants:**

(Applicable to all subcontracts, purchase orders, and other lower tier transactions requiring prior FHWA approval or estimated to cost $25,000 or more - 2 CFR Parts 180 and 1200). 2 CFR 180.220 and 1200.220.

a. By signing and submitting this proposal, the prospective lower tier participant is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances. 2 CFR 180.365.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180, Subpart I, 180.900 – 180.1020, and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. “First Tier Covered Transactions” refers to any covered transaction between a recipient or subrecipient of Federal funds and a participant (such as the prime or general contract). “Lower Tier Covered Transactions” refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). “First Tier Participant” refers to the participant who has entered into a covered transaction with a recipient or subrecipient of Federal funds (such as the prime or general contractor). “Lower Tier Participant” refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated. 2 CFR 1200.220 and 1200.332.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the $25,000 threshold. 2 CFR 180.220 and 1200.220.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the System for Award Management website (https://www.sam.gov/), which is compiled by the General Services Administration. 2 CFR 180.300, 180.320, 180.330, and 180.335.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment. 2 CFR 180.325.

* * * * *

4. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

a. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals:

(1) is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency, 2 CFR 180.355;

(2) is a corporation that has been convicted of a felony violation under any Federal law within the two-year period preceding this proposal (USDOT Order 4200.6 implementing appropriations act requirements); and

(3) is a corporation with any unpaid Federal tax liability that has been assessed, for which all judicial and administrative remedies have been exhausted, or have lapsed, and that is not being paid in a timely manner pursuant to an agreement with the authority responsible for collecting the tax liability. (USDOT Order 4200.6 implementing appropriations act requirements)

b. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant should attach an explanation to this proposal.

* * * * *

X. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed $100,000. 49 CFR Part 20, App. A.

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than $10,000 and not more than $100,000 for each such failure.

3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed $100,000 and that all such recipients shall certify and disclose accordingly.

XI. USE OF UNITED STATES-FLAG VESSELS:

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, or any other covered transaction. 46 CFR Part 381.

This requirement applies to material or equipment that is acquired for a specific Federal-aid highway project. 46 CFR 381.7. It is not applicable to goods or materials that come into inventories independent of an FHWA funded-contract.

When oceanic shipments (or shipments across the Great Lakes) are necessary for materials or equipment acquired for a specific Federal-aid construction project, the bidder, proposer, contractor, subcontractor, or vendor agrees:

1. To utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage (computed separately for dry bulk carriers, dry cargo liners, and tankers) involved, whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels. 46 CFR 381.7.

2. To furnish within 20 days following the date of loading for shipments originating within the United States or within 30 working days following the date of loading for shipments originating outside the United States, a legible copy of a rated, ‘on-board’ commercial ocean bill-of-lading in English for each shipment of cargo described in paragraph (b)(1) of this section to both the Contracting Officer (through the prime contractor in the case of subcontractor bills-of-lading) and to the Office of Cargo and Commercial Sealift (MAR-620), Maritime Administration, Washington, DC 20590. (MARAD requires copies of the ocean carrier's (master) bills of lading, certified onboard, dated, with rates and charges. These bills of lading may contain business sensitive information and therefore may be submitted directly to MARAD by the Ocean Transportation Intermediary on behalf of the contractor). 46 CFR 381.7.

ATTACHMENT A - EMPLOYMENT AND MATERIALS PREFERENCE FOR APPALACHIAN DEVELOPMENT HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS ROAD CONTRACTS (40 U.S.C. sections 14501(d) and 14701 and the Appalachian Regional Commission Code as authorized under 40 U.S.C. section 14302)
This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:

a. To the extent that qualified persons regularly residing in the area are not available.

b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.

c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.

2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.

3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.

4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.

5. The provisions of 40 U.S.C. 14501 allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION REGARDING
MINIMUM WAGE ON FEDERAL-AID PROJECTS

OCTOBER 24, 2019

This proposal contains a copy of the most recent United States Department of Labor (USDOL) Davis-Bacon Act Wage Decision.

The Contractor and each related subcontractor will pay their respective employees not less than the USDOL minimum wage for each work classification an employee actually performs at the site of the work.

The Contractor and each related subcontractor must submit weekly, for each week in which any contract work is performed, an electronic certified weekly payroll report. The payroll report must be submitted electronically to the Elation System website. The Elation System website can be accessed by logging onto the State of South Dakota's single sign-on website at https://mysd.sd.gov/ or can also be accessed at https://elationsys.com/. First time users will need to use the Promotion Code SDDOT-19. The payroll report must be submitted within fourteen (14) calendar days after the end of the workweek. The payroll reports submitted shall set out accurately and completely all the information required to be maintained under 29 C.F.R. 5.5(a)(3)(i). Weekly transmittals must include an individually identifying number for each employee, such as the last four digits of the employee's social security number, but these weekly transmittals must not include full social security numbers or home addresses. The Contractor is responsible for the submission of certified payroll reports by all subcontractors.

Each certified weekly payroll report must include the most recent South Dakota Department of Transportation (SDDOT) Statement of Compliance Form, signed by the Contractor or related subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract. The Instructions for the SDDOT Statement of Compliance Form are found at https://dot.sd.gov/doing-business/contractors/labor-compliance/certified-payrolls-let-after-6/5/19. The SDDOT will not accept any payroll report which does not include the most recent SDDOT Statement of Compliance Form.

* * * * *

Wage and Hour Division
U.S. Department of Labor (DOL)
200 Constitution Avenue, N.W.
Washington, DC 20210

Davis-Bacon Act Wage Decision
State: South Dakota
Construction Types: Heavy and Highway
Counties: South Dakota Statewide

Agency: U.S. DOL
Wage Decision Number: **SD20260001 SD1**
Counties: SD Statewide
Wage Decision Date: **01/30/2026 (Mod-0)**

***SASD2025-001 12/12/2024**

	Rates	Fringes
LABORERS		
Group GL1		
Air Tool Operator; Common Laborer; Landscape Worker; Flagger; Pilot Car Driver; Trucks under 26,000 GVW; Materials Checker, Special Surface Finish Applicator	**26.93**	**0.00**
Group GL2		
Mechanic Tender; Pipe Layer (except culvert); Form Builder Tender	**26.96**	**0.00**
Group GL3		
Asphalt Plant Tender; Pile Driver Leadsman; Form Setter; Oiler/Greaser	**28.97**	**0.00**
Group GL5		
Carpenter; Form Builder	**31.94**	**0.00**
Group GL6		
Concrete Finisher; Grade Checker	**29.81**	**0.00**
POWER EQUIPMENT OPERATORS		
Group G01		
Tractor (farm type with attachments, including loaders but excluding Backhoe); Self Propelled Broom; Concrete Routing Machine; Paver Feeder; Pugmill; Skid Steer	**30.16**	**0.00**
Group G02		
Concrete Paving Cure Machine; Concrete Paving Joint Sealer; Bull Dozer 80 HP or less; Front End Loader 1.25 CY or less; Self Propelled Roller (except Hot Mix); Sheepsfoot/Pneumatic Roller; Pneumatic Tired Tractor or Crawler (includes Water Wagon and Power Spray units); Wagon Drill (Air Trac – Trac Drill); Truck Type Auger; Concrete Paving Saw; Concrete Grooving	**31.73**	**0.00**
Group G03		
Asphalt Distributor; Bull Dozer over 80 HP; Backhoes/ Excavators 20 tons or less; Crusher (may include internal screening plant); Front End Loader over 1.25 CY; Rough Motor Grader; Self Propelled Hot Mix Roller; Push or Pull Tractor; Off-Highway Haul Trucks; Material Spreader or Placer; Rumble Strip Machine; Pavement Marking Grinding Equipment	**31.56**	**0.00**
Group G04		
Concrete Paving Finishing Machine; Asphalt Paving Machine Screed; Asphalt Paving Machine; Cranes/Derricks/ Draglines/Pile Drivers/Shovels 30 to 50 tons; Backhoes/Excavators 21 to 40 tons; Maintenance Mechanic; Scrapers (wheel or tracks); Concrete Pump Truck	**32.49**	**0.00**
Group G05		
Asphalt Plant; Concrete Batch Plant; Backhoes/Excavators over 40 Tons; Cranes/ Derricks/Draglines/Pile Drivers/Shovels over 50 tons; Heavy Duty Mechanic; Finish Motor Grader; Automatic Fine Grader; Milling Machine; Bridge Welder	**34.96**	**8.36**
TRUCK DRIVERS		
Group GT1		
Tandem Truck without trailer or pup; Single Axle Truck over 26,000 GVW with Trailer	**30.01**	**0.00**
Group GT2		
Semi-Tractor and Trailer; Tandem Truck with Pup or Trailer	**32.07**	**8.42**

Wage and Hour Division
U.S. Department of Labor (DOL)
200 Constitution Avenue, N.W.
Washington, DC 20210

Davis-Bacon Act Wage Decision
State: South Dakota
Construction Types: Heavy and Highway
Counties: South Dakota Statewide

Agency: U.S. DOL
Wage Decision Number: **SD20260001 SD1**
Counties: SD Statewide
Wage Decision Date: **01/30/2026 (Mod-0)**

***SASD2025-001 12/12/2024**

	Rates	Fringes
ELECTRICIANS		
Group E01		
Electrician	**35.43**	**8.69**
IRON WORKERS		
Group I01		
Position and secure steel bars or mesh in concrete for reinforcement, steel tiers, saw. Carrying, placing, tying, reinforcing steel under supervision, cutting. Placing steel or prefabricated reinforcement assembly for placement in concrete forms.	**26.93**	**0.00**
Group I02		
Erect, place and join steel girders, columns, structural framework, air wrenches, spud bars, grinders, drills, sledgehammers, tag lines, plumb bobs, lasers, levels, bolts, wire, welds, shears, rod-bending machines, torches.	**28.97**	**0.00**
PAINTERS		
Group P01		
Line striping machine, paint trucks, epoxy trucks, thermoplastic trucks, cold applied plastic/and preformed thermoplastic pavement marking equipment. Operate pavement marking equipment to include epoxies, paints, primers, sealers, cold applied tapes, thermoplastics used for traffic marking purposes.	**26.96**	**0.00**
Group P02		
Painting or protective coating bridges, apply varnish, anti-rust materials, prepare steel or other surfaces with primer or sandblasting, paints structural framework of bridges, guardrails and cables of bridges and other structures.	**29.81**	**0.00**

WELDERS – Receive rate prescribed for craft performing operation to which welding is incidental.

Unlisted classifications needed for work not included within the scope of the classifications listed may be added after award, pursuant to 29 CFR 5.5(a)(1)(ii); contractors are responsible for requesting SDDOT to secure necessary additional work classifications and rates.

The "SA" identifier indicates that the classifications and prevailing wage rates set by a state (or local) government were adopted under 29 C.F.R. 1.3(g)-(h). Example: SAME2023-007 01/03/2024. SA reflects that the rates are state adopted. ME refers to the State of Maine. 2023 is the year during which the state completed the survey on which the listed classifications and rates are based. The next number, 007 in the example, is an internal number used in producing the wage determination. The date, 01/03/2024 in the example, reflects the date on which the classifications and rates under the "SA" identifier took effect under state law in the state from which the rates were adopted.

For SDDOT Defined Work Classifications, please visit: https://dot.sd.gov/doing-business/contractors/labor-compliance

A COPY OF THIS DOCUMENT, COLORED **GREEN**, **MUST** BE CONSPICUOUSLY POSTED AT THE PROJECT SITE

Wage and Hour Division
U.S. Department of Labor (DOL)
200 Constitution Avenue, N.W.
Washington, DC 20210

Davis-Bacon Act Wage Decision
State: South Dakota
Construction Types: Heavy and Highway
Counties: South Dakota Statewide

SD20260001 SD1 01/30/2026 (Mod-0)

WAGE DETERMINATION APPEALS PROCESS

1) Has there been an initial decision in the matter? This can be:

   a) a survey underlying a wage determination
   b) an existing published wage determination
   c) an initial WHD letter setting forth a position on a wage determination matter
   d) an initial conformance (additional classification and rate) determination

   On survey related matters, initial contact, including requests for summaries of surveys, should be directed to the WHD Branch of Wage Surveys. Requests can be submitted via email to davisbaconinfo@dol.gov or by mail to:

   Branch of Wage Surveys
   Wage and Hour Division
   U.S. Department of Labor
   200 Constitution Avenue, N.W.
   Washington, DC 20210

   Regarding any other wage determination matter such as conformance decisions, requests for initial decisions should be directed to the WHD Branch of Construction Wage Determinations. Requests can be submitted via email to BCWD-Office@dol.gov or by mail to:

   Branch of Construction Wage Determinations
   Wage and Hour Division
   U.S. Department of Labor
   200 Constitution Avenue, N.W.
   Washington, DC 20210

2) If an initial decision has been issued, then any interested party (those affected by the action) that disagrees with the decision can request review and reconsideration from the Wage and Hour Administrator (See 29 CFR Part 1.8 and 29 CFR Part 7). Requests for review and reconsideration can be submitted via email to dba.reconsideration@dol.gov or by mail to:

   Wage and Hour Administrator
   U.S. Department of Labor
   200 Constitution Avenue, N.W.
   Washington, DC 20210

   The request should be accompanied by a full statement of the interested party's position and any information (wage payment data, project description, area practice material, etc.) that the requestor considers relevant to the issue.

3) If the decision of the Administrator is not favorable, an interested party may appeal directly to the Administrative Review Board (formerly the Wage Appeals Board). Write to:

   Administrative Review Board
   U.S. Department of Labor
   200 Constitution Avenue, N.W.
   Washington, DC 20210.

END OF GENERAL DECISION

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
REGARDING
STORMWATER DISCHARGES
TO WATERS OF THE STATE

NOVEMBER 5, 2025

In compliance with the provisions of the South Dakota Water Pollution Control Act and the Administrative Rules of South Dakota (ARSD), Article 74:52, the State of South Dakota has been issued Permit No. SDR10#### "GENERAL PERMIT AUTHORIZING STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES". This permit authorizes the discharge of storm water in accordance with the conditions and requirements set forth in the permit.

The Contractor, by signing the CONTRACTOR AUTHORIZATION FORM and submitting a bid or proposal, certifies the following:

> "I certify under penalty of law that I understand and will comply with the terms and conditions of the Surface Water Discharge General Permit for Stormwater Discharges Associated with Construction Activities for the project identified above."

A copy of the full version of the General Permit Authorizing Stormwater Discharges Associated with Construction Activities, dated 11/01/2023, must be available on the job site. The permit is available for downloading and printing from the SD DANR website:

https://danr.sd.gov/OfficeOfWater/SurfaceWaterQuality/stormwater/StormWaterConstruction.aspx

The Contractor may also obtain a printed copy of the permit from the SDDOT Project Development office or from the SDDOT Area Office assigned to this project.

* * * * *