THE STATE OF THE S

PROJECT

STATE OF SOUTH DAKOTA PLANS FOR PROPOSED

PROJECT P TAPR(03)

HAAKON COUNTY

STANLEY AVENUE SHARED USE PATH

SIDEWALK, CURB & GUTTER, PERMANENT SIGNING, PAVEMENT MARKING PCN 04QF

STORM WATER PERMIT

MAJOR RECEIVING BODY OF WATER: BAD RIVER (NORTH FORK) AREA DISTURBED: 0.28 ACRES TOTAL PROJECT AREA: 0.54 ACRES BEGIN PROJECT: N 44°02'22.13", W 101°40'24.68"

END P TAPR(03)

STA. 7-14 - APPROXIMATELY 595
FEET NORTH OF THE
INTERSECTION OF STANLEY
AVENUE AND PINE STREET
SE \(\frac{1}{4}\) OF SW \(\frac{1}{4}\) SECTION 14, T1N,
R20E, BHM
PHILIP, SD

BEGIN P TAPR(03)

STA. 0+00 - AT SOUTHÈAST CORNER OF THE INTERSECTION OF STANLEY AVENUE AND PINE STREET SE $\frac{1}{4}$ OF SW $\frac{1}{4}$ SECTION 14, T1N, R20E, BHM PHILIP, SD

PHILIP, SD

SCALES

PLAN

1 INCH = 40 FT.

PROFILE , HO

HORIZ. 1 INCH = 40 FT.

VERT. 1 INCH = 6 FT.

GROSS LENGTH .7.15 FEET .0,14 .14 .14 .15 .15 .14 .15 .15 .15 .15 .15 .14 .14 .14 .15 .15 .15 .15 .15 .15 .15 .15 .14 .15 .14 .15</t

INDEX OF SHEETS


- 1 TITLE SHEET
- 2-3 ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS
- 4-9 GENERAL NOTES AND TABLES
- 10-13 SWPPP
- 14 TYPICAL SECTION
- 15 FIXED LOCATION SIGNING
- 16 EROSION AND SEDIMENT CONTROL
- 17 HORIZONTAL ALIGNMENT & SURVEY CONTROL DATA
- 18-19 SYMBOLS & ABBREVIATIONS
- 20-21 PLAN AND PROFILE
- 22 PAVEMENT MARKING PERMANENT &
- PERMANENT SIGNING 23-37 SDDOT STANDARD PLATES
- 38-41 CROSS SECTIONS



330 KNOLLWOOD DRIVE RAPID CITY, SD 57701 PH: 605.721.5553 FAX: 855.288.8055 www.kljeng.com

SURVEY BY: KLJ
RAPID CITY, SOUTH DAKOTA

PLANS BY: KLJ
RAPID CITY, SOUTH DAKOTA



ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH			OTILLIO
DAKOTA	P TAPR(03)	2	41


ESTIMATE OF QUANTITIES

BID ITEM NUMBER	ITEM DESCRIPTION	QUANTITIY	UNIT
009E0010	Mobilization	Lump Sum	LS
009E3200	Construction Staking	Lump Sum	LS
009E3220	Reestablish Property Corner	1	Each
009E3300	Three Man Survey Crew	20	Hour
100E0100	Clearing	Lump Sum	LS
110E0300	Remove Concrete Curb and Gutter	98	Ft
110E0600	Remove Fence	127	Ft
110E0000	Remove Concrete Driveway Pavement	58.6	SqYd
110E1130 110E1140	Remove Concrete Sidewalk	42.5	SqYd
110E1140	Remove Erosion Control Wattle	160	Ft
110E1700	Remove Silt Fence	21	Ft
110E7100	Remove Sign for Reset	2	Each
120E0010	Unclassified Excavation	214	CuYd
120E2000	Undercutting	99	CuYd
230E0100	Remove and Replace Topsoil	Lump Sum	LS
380E3020	6" PCC Driveway Pavement	58.6	SqYd
380E4010	6" PCC Fillet Section	20.1	SY
450E4739	12" CMP 16 Gauge, Furnish	36	Ft
450E4740	12" CMP, Install	36	Ft
450E5203	12" CMP Flared End, Furnish	4	Each
450E5204	12" CMP Flared End, Install	4	Each
450E5509	18" CMP Arch 16 Gauge, Furnish	40	Ft
450E5510	18" CMP Arch, Install	40	Ft
	18" CMP Arch Flared End, Furnish	4	Each
450E5802		4	Each
450E5803	18" CMP Arch Flared End, Install		
620E0040	Type 4 Right-Of-Way Fence	28	Ft
620E1020	2 Post Panel	4	Each
632E1320	2.0"X2.0" Perforated Tube Post	61.2	Ft
632E2520	Type 2 Object Marker	7	Each
632E3205	Flat Aluminum Sign, Nonremovable Copy Super/Very High Intensity	32.8	SqFt
632E3500	Reset Sign	2	Each
633E1430	Pavement Marking Paint, 24" White	60	Ft
634E0010	Flagging	50.0	Hour
634E0110	Traffic Control Signs	145.5	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0280	Type 3 Barricade, 8' Single Sided	5	Each
650E0060	Type B66 Concrete Curb and Gutter	41	Ft
650E4660	Type P6 Concrete Gutter	41	FT
651E0040	4" Concrete Sidewalk	5,222	SqFt
651E0060	6" Concrete Sidewalk	242	SqFt
651E5000	Sidewalk Drain	13.0	FT
651E7000	Type 1 Detectable Warning Panels	79	SqFt
730E0206	Type D Permanent Seed Mixture	27	Lb
730E0200 734E0102	Type 2 Erosion Control Blanket	100	SqYd
734E0151	9" Diameter Erosion Control Wattle	255	Ft
734E0845	Sediment Control at Inlet with Frame and Grate	1	Each
734E0847	Sediment Control at Type S Reinforced Concrete Drop Inlet	13	Ft

SPECIFICATIONS

Standard Specifications for Roads & Bridges, 2015 Edition and Required Provisions, Supplemental Specifications and Special Provisions as included in the Proposal.

REVISED 02/10/2016



ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH	PROJECT	SHEET	TOTAL SHEETS
DAKOTA	P TAPR(03)	3	41

REVISED 12/15/2016

ENVIRONMENTAL COMMITMENTS

An Environmental Commitment is a measure that SDDOT commits to implement in order to avoid, minimize, and/or mitigate a real or potential environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency mentioned below with permitting authority can influence a project if perceived environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office. The environmental commitments associated with this project are as follows:

COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor shall furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the State or City ROW.

The waste disposal site(s) shall be managed and reclaimed in accordance with the following from the General Permit for Highway, Road, and Railway Construction/Demolition Debris Disposal under the South Dakota Waste Management Program issued by the Department of Environment and Natural Resources.

The waste disposal site(s) shall not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements shall apply:

- 1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials shall be buried in a trench completely separate from wood debris. The final cover over the construction and/or demolition debris shall consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the State ROW shall be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor shall control the access to waste disposal sites not within the State ROW through the use of fences, gates, and placement of a sign or signs at the entrance to the site stating "No Dumping Allowed".
- 2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period of time not to exceed the duration of the project. Prior to project completion, the waste shall be removed from view of the ROW or buried and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) shall be incidental to the various contract items.

COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historical Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require review of cultural resources impacts. This work includes, but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.


The Contractor shall arrange and pay for a cultural resource survey and/or records search. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor shall provide ARC with the following: a topographical map or aerial view on which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor shall submit the records search or cultural resources survey report and if the location of the site is within the current geographical or historic boundaries of any South Dakota reservation to SDDOT Environmental Engineer, 700 East Broadway Avenue, Pierre, SD 57501-2586 (605-773-3180). SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

If evidence for cultural resources is uncovered during project construction activities, then such activities shall cease and the Project Engineer shall be immediately notified. The Project Engineer will contact the SDDOT Environmental Engineer in order to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor shall provide the required permits and clearances to the Project Engineer at the preconstruction meeting.



STATE OF	PROJECT NO.	SHEET TOTAL NUMBER SHEETS			
SOUTH DAKOTA	P TAPR (03)	4	41		
GENERAL NOTES, & TABLES					

Total:

GRADING OPERATIONS

No separate payment will be made for the Water for Embankment and all costs associated shall be incidental to the contract unit price per cubic yard of "Unclassified Excavation". Compaction shall be to the satisfaction of the Engineer.

Temporary fence and/or permanent fence shall be placed ahead of the grading operation unless otherwise directed by the Engineer.

UTILITIES

The Contractor shall be aware that the existing utilities shown in the plans were surveyed prior to the design of this project and might have been relocated or replaced by a new utility facility prior to construction of this project, might be relocated or replaced by a new utility facility during the construction of this project, or might not require adjustment and may remain in its current location. The Contractor shall contact each utility owner and confirm the status of all existing and new utility facilities. The utility contact information is provided elsewhere in the plans or bidding documents.

CLEARING

Before clearing activities begin, the Contractor shall contact the Engineer to determine the limits of clearing for the project. If the trees or shrubs that are supposed to remain within the limits of work are damaged or destroyed by the Contractor, the Contractor shall replace them with the same size and type at the Contractor's expense.

TABLE OF UNCLASSIFIED EXCAVATION

		(CuYd)
Excavation		115
Undercutting		99
	Total	214

PROCEDURES FOR DETERMINING UNCLASSIFIED EXCAVATION QUANTITY

When plan quantities are used for payment, the Unclassified Excavation quantity shall be used for final payment

UNDERCUTTING

In all cut sections the earthen subgrade shall be undercut 0.5 feet below the earthen subgrade surface. The undercut material or other suitable material, as directed by the Engineer, shall then be replaced and compacted to the density specified for the section being constructed. Compaction shall be to the satisfaction of the Engineer.

The plan shown quantity will be the basis of payment. However, if there are additional areas of undercut other than what is shown in the plans, the Engineer shall direct removal of these areas and the additional areas will be measured according to the Engineer.

TABLE OF UNDERCUTTING

		Quantity
Station to	Station	(CuYd)
00+58.85	02+31.50	32
02+57.20	02+97.90	8
03+22.00	04+00.00	15
04+00.00	05+89.70	35
06+16.1	06.45.90	9
	Total:	99

TABLE OF CONCRETE CURB AND GUTTER REMOVAL

Station	to	Station	Quantity (Ft)
0+00.0, 7.8' LT	to	0+00.0, 1.2' RT	9
0+49.9, 10.0' LT	to	0+62.1, 5.0' RT	23
0+50.0. 55.8' RT	to	0+60.1, 45.6' LT	16
02+31.5, 13.0' LT	to	02+31.5, 12.0' RT	25
02+57.2, 13.0' LT	to	02+57.2, 12.0' RT	25
		Total:	98

TABLE OF SIDEWALK REMOVAL

				Quantity
Station		Station		(SqYd)
0+00.0, 25.6 LT	to	0+00.0, 12.2' RT		25.6
0+52.4, 49.1 LT	to	0+60.1, 45.6' LT		6.7
0+50.0	to	0+58.8	_	10.2
		-	Total	42.5

CORRUGATED METAL PIPE

Corrugated metal pipes shall have 2 %-inch X %-inch corrugations for 42-inch and smaller round pipe and 48-inch and smaller arch pipe unless otherwise stated in the plans. Corrugated metal pipes shall have 3-inch X 1-inch or 5-inch X 1-inch corrugations for 48-inch and larger round pipe and 54-inch and larger arch pipe unless otherwise stated in the plans.

The gauge of the corrugated metal ends shall match the thickest gauge of corrugated metal pipe it is connected to.

TABLE OF TYPE B66	CONCRETE CLIPR	AND CUTTED
TABLE OF TYPE Bob	CONCRETE CORB	AND GUITER

			Quantity
Station	to	Station	(Ft)
0+49.9, 5.0' RT	to	0+49.9, 0.8' LT	6
0+56.8, 9.5' LT	to	0+62.1, 9.9' LT	5
02+31.5, 5.0' LT	to	02+31.5, 13.0' LT	8
02+31.5, 5.0' RT	to	02+31.5, 12.0' RT	7
02+57.2, 5.0' LT	to	02+57.2, 13.0' LT	8
02+57.2, 5.0' RT	to	02+57.2, 12.0' RT	7

TABLE OF TYPE P6 CONCRETE GUTTER

			Quantity
Station	to	Station	(Ft)
0+00.0, 7.8' LT	to	0+00.0, 1.2' RT	9
0+49.9, 0.8' LT	to	0+56.8, 9.5' LT	12
2+31.5, 5.0' LT	to	2+31.5, 5.0' RT	10
2+57.2, 5.0' LT	to	2+57.2, 5.0' RT	10
		Total:	41

6" PCC FILLET SECTIONS

Payment for "6" PCC Fillet Section" shall be based on plans quantity. If the additions or reductions in to the area of PCC fillet sections are ordered by the Engineer, payment will be made in accordance with the contract unit price per square yard for "6" PCC Fillet Section".

TABLE OF 6" PCC FILLET SECTION

			Quantity
Station	to	Station	(SqYd)
0+47.4, 5.0' RT	То	0+62.1, 12.5' LT	10.8
0+50.0, 55.8' LT	То	0+60.1, 45.6' LT	9.3
		Total:	20.1



	STATE OF	PROJECT NO.	SHEET Number	TOTAL SHEETS
	DAKOTA	P TAPR (03)	5	41
		GENERAL NOTES, & TABI	_ES	

REVISED 12/15/2016

DETECTABLE WARNINGS

Detectable warnings shall be in compliance with the Americans with Disability Act regulations.

The detectable warnings shall be installed according to the manufacturer's installation instructions.

A concrete thickness equal to the adjacent concrete sidewalk thickness and 2 inches of granular cushion material shall be placed below the Type 1 Detectable Warnings. When concrete is placed below the detectable warnings then the concrete thickness shall be transitioned at the rate of 1" per foot to match the adjacent concrete sidewalk thickness.

The detectable warnings shall be a brick red color for application in concrete curb ramps.

When Type 1 Detectable Warnings are specified, the Contractor shall furnish and install only one of the products listed in the Type 1 Detectable Warnings table.

Type 1 Detectable Warnings

<u>Product</u>	<u>Manufacturer</u>		
Detectable Warning Plate Cast Iron Plate	Neenah Foundry Company Neenah, WI 800-558-5075 http://www.neenahfoundry.com/		
Detectable Warning Plate Cast Iron Plate	Deeter Foundry Lincoln, NE 800-234-7466 http://www.deeter.com/		
Detectable Warning Plate Cast Iron Plate(No Coating)	East Jordan Iron Works, Inc. 301 Spring Street East Jordan, MI 49727 800-626-4653 http://www.ejiw.com		

TABLE OF DETECTABLE WARNINGS

Station	L/R	Detectable Warnings (Type)	Quantity (SqFt)	
00+00.00	LT	1	10	
00+55.97	LT	1	8	
00+52.00	LT	1	21	
05+87.70	CL	1	20	
06+18.10	CL	1	20	

Total Type 1 Detectable Warnings: 79

TABLE OF 4" CONCRETE SIDEWALK

Station	to	Station	Quantity (SqFt)
0+00.0, 25.6' LT	to	0+00.0, 7.8' LT	230
0+49.9	to	2+31.5	1868
0+52.4, 49.1' LT	to	0+60.1, 45.6' LT	60
2+57.2	to	2+97.9	419
3+22.0	to	4+00.0	780
4+00.0	to	6+56.4	1565
6+83.8	to	7+14.2	300
		Total	5222

TABLE OF 6" CONCRETE SIDEWALK

Station	to	Station	Quantity (SqFt)
02+97.9		03+22.0	242
		Total	242

TABLE OF SIDEWALK DRAINS


Station	to	Station	(SqFt)
01+97, 5' LT		02+06.5, 5' RT	13
		Total	13

Ougatitu

REMOVE AND REPLACE TOPSOIL

The estimated amount of topsoil to be removed and replaced is 75 CuYd.

All cost associated with removing and replacing the topsoil along shared use path shall be incidental to the lump sum price for "Remove and Replace Topsoil".



	STATE OF	PROJECT NO.	SHEET Number	TOTAL SHEETS
	DAKOTA	P TAPR (03)	6	41
		GENERAL NOTES, & TABI	LES	

MYCORRHIZAL INOCULUM

Mycorrhizal inoculum shall consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier shall provide certification of the fungal species claimed and the live propagule count. The inoculum shall include the following fungal species:

Glomus intraradices	25%
Glomus aggregatu	25%
Glomus mosseae	25%
Glomus etunicatum	25%

All seed shall be inoculated with a minimum of 100,000 live propagules of mycorrhizal fungi per acre. All costs of inoculating the seed shall be incidental to the contract unit price per pound for the corresponding permanent seed

The mycorrhizal inoculum shall be from the list below or an approved equal:

<u>Product</u>	<u>Manufacturer</u>
MycoApply	Mycorrhizal Applications, Inc. Grants Pass, OR Phone: 1-866-476-7800
	http://www.mycorrhizae.com/

FERTILIZING

Application of fertilizer will not be required on this project.

PERMANENT SEEDING

The areas to be seeded consist of all newly graded areas within the project limits except for the top of roadways, driveways and shared use paths, sidewalks and temporary easements under cultivation.

Type D Permanent Seed Mixture shall consist of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/1000 SqFt)
Kentucky Bluegrass	Avalanche, Appalachian, Wildhorse, Blue Bonnet	1.4
Perennial Ryegrass	Turf Type	1.4
Creeping Red Fescue	Epic, Boreal	1.4
Chewings Fescue	Ambrose, K2, VNS, Zodiac	1.4
Alkali Grass	Fults, Fults II, Quill, Salty	1.4
	Total:	7

EROSION CONTROL WATTLE

Erosion control wattles for restraining the flow of runoff and sediment shall be installed at locations noted in the table and at locations determined by the Engineer during construction. Refer to Standard Plate 734.06 for details.

The Contractor shall provide certification that the erosion control wattles do not contain noxious weed seeds.

Erosion control wattles shall remain on the project until vegetation has been established and then they shall be removed in accordance with the Engineer.

The erosion control wattle provided shall be from the approved product list. The approved product list for erosion control wattle may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

TABLE OF EROSION CONTROL WATTLE

		Diameter		Quantity
_Station	LT/RT	(Inch)	Location	(Ft)
00+59 to 01+29	LT	9	East side of Stanley St.	70
01+56	LT	9	Channel bottom	15
02+56	LT	9	Around culvert inlet	25
02+84	RT	9	Channel bottom	15
03+31	RT	9	Channel bottom	15
03+33	LT	9	Around culvert inlet	25
03+69	LT	9	Channel bottom	15
04+75	LT	9	Channel bottom	15
06+40	RT	9	Around culvert inlet	30
07+00	LT/RT	9	Channel bottom	30_
			Total:	255


REVISED 12/15/2016 TABLE OF EROSION CONTROL BLANKET

Station to	Station	LT/RT	Location	Туре	Quantity (SqYd)
05+38	06+40	LT	Ditch Channel (16'W x 56'L)	2	100
		Total	100		

SHAPING FOR EROSION CONTROL BLANKET

The ditches shall be shaped for the erosion control blanket as specified on Standard Plate 734.01.

All costs for shaping the ditches for erosion control blanket including labor and equipment shall be incidental to the contract unit price per square yard for "Erosion Control Blanket".



STATE OF	PROJECT NO.	SHEET Number	TOTAL SHEETS
DAKOTA	SOUTH DAKOTA P TAPR (03)		41
	GENERAL NOTES, & TAB	LES	·

CONTROL AT INLETS WITH FRAMES AND GRATES

This type of sediment control device should be used where there is pavement in the vicinity of the drop inlets and storm water or sediment could possibly enter the frame and grate. Sediment Control at Inlets with Frame and Grates shall be installed prior to working in the vicinity of the drop inlets.

The Contractor shall be responsible for maintaining and repairing the sediment control devices for the duration of the project for which sediment control measures are required. Maintenance shall be scheduled to prevent storm water from backing up into the driving lane.

"Sediment Control at Inlets with Frames and Grates" will be paid for one time at each location, regardless of the number of times the sediment control devices are installed, inspected, cleaned, removed, repaired, or replaced. All costs associated with furnishing, installing, inspecting, maintaining, cleaning, sediment removal, and repairing Sediment Control at Inlets with Frames and Grates shall be incidental to the contract unit price per each for "Sediment Control at Inlet with Frame and Grate".

Sediment collection devices shall be:

A commercial made sediment collection device from the "Sediment Control at Inlet with Frame and Grate" list or an approved equal. The device shall be installed in reinforced concrete drop inlets according to the manufacturer's recommendations.

A sediment control device as shown on Standard Plate 734.10. Filter fabric used for constructing the sediment control at inlets with frames and grates shall be the same type of fabric that is used in high flow silt fence from the approved product list. The approved product list may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

Sediment Control at Inlet with Frame and Grate Approved List:

<u>Product</u>	<u>Manufacturer</u>
InfraSafe Debris Collection Device with filter sock	Royal Environmental Systems, Ind Stacy, MN Phone: 1-800-817-3240 www.royalenterprises.net
Dandy Curb Sack	Dandy Products Inc. Dublin, OH Phone: 1-800-591-2284 www.dandyproducts.com
Silt Trapper	Storm Water Solutions Lakeville, MN Phone: 1-952-461-4376 www.silttrapper.com

DIP Basket Skyview Construction Co., LLC

Waubay, SD

Phone: 1-605-520-0555 www.skyviewconst.com

FLEXSTORM Inlet Filters Inlet and Pipe Protection, Inc.

Naperville, IL

Phone: 1-866-287-8655 www.inletfilters.com

GR-8 Guard ERTEC Environmental Systems LLC

or Alameda, CA

Combo Guard Phone: 1-866-521-0724 www.ertecsystems.com

Sediment Catchers Shaun Jensen

Brookings, SD Phone: 1-605-690-4950

Enviroscape ECM, Ltd.

Oakwood, OH

Phone: 1-419-594-3210 www.strawblanket.com

BX Inlet Sediment Boxes BX Civil and Construction

Dell Rapids, SD

Phone: 1-605-428-5483

<u>bx-cc.com</u>

TABLE OF SEDIMENT CONTROL AT INLETS WITH FRAMES AND GRATES

		Quantity
Station	LT/RT	(Each)
00+62	LT _	1
	Total:	1

Grate FX, Slammer, or VertPro

SEDIMENT CONTROL AT TYPE S REINFORCED CONCRETE DROP INLETS

The sediment control device provided shall be from the list shown below. Refer to Standard Plate 734.11 for details.

<u>Product</u>	<u>Manufacturer</u>
Dandy Curb	Dandy Products Inc. Dublin, OH Phone: 1-800-591-2284 www.dandyproducts.com
Gutterbuddy	ACF Environmental Richmond, VA Phone: 1-800-448-3636 www.acfenvironmental.com
SS-300	Silt-Saver, Inc. Conyers, GA Phone: 1-888-382-7458

www.siltsaver.com

Curb Inlet Guard

ECTEC Environmental Systems LLC

Alameda, CA

Phone: 1-866-521-0724 www.ertecsystems.com

TABLE OF SEDIMENT CONTROL AT TYPE S REINFORCED CONCRETE DROP INLETS


Station	LT/RT	Clear Opening Width (Ft)	Quantity* (Ft)
00+50	RT	11	13
		Total:	13

* Quantity shown is the minimum length required and shall be the basis of payment.

PERMANENT SIGNING

The Contractor shall stake the signs and the Engineer will verify the location prior to installation. The lateral distance from the roadway and the height of the sign shall be established by the contractor in the field according to the standard plates in the plans and the MUTCD.

When signs are vertically mounted in succession, they shall be 1-2 inches apart. Lateral placement of signs shall be determined by the Engineer.



STATE OF	PROJECT NO.	SHEET Number	TOTAL SHEETS		
DAKOTA	P TAPR (03)	8	41		
GENERAL NOTES, & TABLES					

REVISED 12/15/2016

PERFORATED TUBE POST

All perforated tube sign posts shall have a soil stabilizer attached to the base. Soil stabilizers shall be an MPJ Sign Wedge or equivalent as approved by the Engineer.

Sign assemblies mounted in concrete or asphalt surfacing shall use flush mount breakaway post bases. Bases shall be Tapco V-Loc Model 200 style or equivalent.

The Contractor shall use Telespar brand (or equivalent) posts and bases on all new standard highway signs as approved by the engineer. The height of the post shall not exceed the minimum height needed by more than 0.5 feet. Any portion that extends above the sign shall be cut off. No separate payment will be made for cutting the post or for that length cut off. All sign assemblies mounted in concrete surfacing shall utilize a flush mount breakaway post base. All posts and bases shall be accompanied by certificates of compliance.


Payment for new sign posts, hardware, bases, and labor will be made at the contract unit price per foot for "2.0" x 2.0" Perforated Tube Post". Breakaway post details regarding posts, hardware, and bases shall be followed as per the manufacturer's recommendations. The sign post contract items shall include post bases and all hardware. The lengths of the posts in the sign tables are approximate length only. The post lengths shall be verified by the Contractor. The Contractor is urged to cut posts to length on the job site after site by site verification of post length.

Payment for "2.0" x 2.0" Perforated Tube Post" shall include all costs for labor, equipment, and material necessary to complete the following work:

- 1. Furnish all posts, stiffeners, breakaway bases, soil stabilizers, and hardware.
- 2. Assembly and installation of breakaway base sign supports as per details shown in these plans.
- 3. Assembly of sign(s) to sign post as per erection details for highway signs as shown in these plans.
- 4. Installation of sign post and sign(s).

PERMANENT SIGNING TABLE

		SIGN					POST					
Station	n Offset	ation Offset	Width (in)	Height (in)	Number	Square Footage	Sheeting Type	Mounting	Length	Size	#	Description
4+58	30' LT	30	30	W11-15	6.2	Super/Very High Intensity	Post	15.3	2x2	1	Bicycle/Pedestrian	
4+58	30' LT	24	12	W16-9p	2.0	Super/Very High Intensity	Post				Ahead (plaque)	
5+87	8' LT	30	30	W11-15	6.2	Super/Very High Intensity	Post	15.3	2x2	1	Bicycle/Pedestrian	
5+87	8' LT	24	12	W16-7pL	2.0	Super/Very High Intensity	Post				Downward Diagonal Arrow (plaque)	
6+18	8' RT	30	30	W11-15	6.2	Super/Very High Intensity	Post	15.3	2x2	1	Bicycle/Pedestrian	
6+18	8' RT	24	12	W16-7pL	2.0	Super/Very High Intensity	Post				Downward Diagonal Arrow (plaque)	
6+18	108' RT	30	30	W11-15	6.2	Super/Very High Intensity	Post	15.3	2x2	1	Bicycle/Pedestrian	
6+18	108' RT	24	12	W16-9p	2.0	Super/Very High Intensity	Post				Ahead (plaque)	



STATE OF	PROJECT NO.	SHEET Number	TOTAL SHEETS
SOUTH DAKOTA	P TAPR (03)	9	41
	GENERAL NOTES, & TAB	LES	

TRAFFIC CONTROL - GENERAL NOTES

The contractor is required to maintain traffic in accordance with the specifications and as shown in the plans. All traffic control shall conform to the 2009 Edition of the Manual of Uniform Traffic Control Devices for Streets and Highways (MUTCD).

Locations of the signs on the traffic control layouts are diagrammatic. The usage and placement of signs shall be as shown on the Traffic Control Sheets, as detailed in the 2009 Edition of the MUTCD, or as required by the Engineer.

Removing, relocating, covering, salvaging, and resetting traffic control signs shall be the responsibility of the contractor. This includes any existing signs that need to be removed and reset. Cost for this work shall be included in the contract unit prices for the various items. The quantity of signs paid for will be for the most installations per sign in place at any one time regardless of the number of set-ups at this project site. Any delineators and signs damaged or lost shall be replaced by the contractor at no cost to the City or State.

During non-working hours, non-applicable traffic control signs and/or devices shall be covered or removed from view.

Permanent traffic control items (i.e. signing and pavement marking) shall be installed prior to removing temporary traffic control devices.

Flaggers, properly attired and preceded by W20-7a flagger symbol signs shall be required to safely maintain traffic when work activities and/or equipment presents a hazard to workers or traffic, encroaches into a lane open to traffic, or shall be required to safely maintain traffic when work activity is near an intersection.

All equipment and vehicles entering and exiting closed lanes of traffic shall display flashing amber light visible from all directions a minimum distance of $\frac{1}{2}$ mile.


Indiscriminate driving and parking of vehicles within the right-of-way will not be permitted. Any damage to the vegetation, surfacing, embankment, delineators, and existing signs resulting from such indiscriminate use shall be repaired and/or restored by the contractor, at no expense to the City or State, and to the satisfaction of the Engineer.

TABLE OF TRAFFIC CONTROL DEVICES

			CON	VENTIO	NAL F	ROAD	
SIGN CODE	SIGN DESCRIPTION	NUMBER		SIGN SIZE		SQFT PER SIGN	SQFT
R11-2	ROAD CLOSED	2	48"	Х	30"	10.0	20.0
W20-1	ROAD WORK AHEAD	3	48"	X	48"	16.0	48.0
W20-4	ONE LANE ROAD AHEAD	2	48"	X	48"	16.0	32.0
W20-7	FLAGGER (symbol)	2	48"	X	48"	16.0	32.0
G20-2	END ROAD WORK	3	36"	X	18"	4.5	13.5
		CO TRAFFIC		TIONAL ITROL S			145.5

TYPE 3 BARRICADES

ITEM DESCRIPTION	QUANTITY
TYPE 3 BARRICADE, 8' SINGLE SIDED	5 EACH



		STATE OF PROJECT NO.	SHEET Number	TOTAL SHEETS
		SOUTH DAKOTA P TAPR (03)	10	41
		SWPPP		.I
TORM WATER POLLUTION PREVENTION PLAN CHECKLIST	Vegetation Buffer Strips	Hazardous Waste		
The numbers right of the title headings are reference numbers to the	Roughened Surface (e.g. tracking)	All hazardous waste materials will be disposed of in a manr		
ENERAL PERMIT FOR STORM WATER DISCHARGES ASSOCIATED	■ ☐ Dust Control	specified by local or state regulations or by the manufacture		
/ITH CONSTRUCTION ACTIVITIES	■ ☐ Other:	Site personnel will be instructed in these practices, and the		
		individual designated as the Contractor's on-site representa		
SITE DESCRIPTION (4.2 1)	Structural Temporary Erosion and Sediment Controls	will be responsible for seeing that these practices are follow	/ed.	
Project Limits: See Title Sheet (4.2 1.b)	■ ☑ Silt Fence	Sanitary Waste		
Project Description: See Title Sheet (4.2 1.a.)	■ ☐ Floating Silt Curtain	Portable sanitary facilities will be provided on all construction		
Site Map(s): See Title Sheet and Plans (4.2 1.f. (1)-(6))	Straw Bale Check	sites. Sanitary waste will be collected from the portable unit		
Major Soil Disturbing Activities (check all that apply)	■ Temporary Berm	timely manner by a licensed waste management Contractor	r or as	
■ ☑Clearing and grubbing	■ ☐ Temporary Slope Drain	required by any local regulations.		
■ <u></u> Excavation/borrow	■ Straw Wattles or Rolls	·		
■ <u></u> Grading and shaping	■ Turf Reinforcement Mat	MAINTENANCE AND INSPECTION (4.2 3. and 4.2 4.)		
■ ☐Filling	■ ☐ Rip Rap	Maintenance and Inspection Practices		
■	■ ☐ Gabions	 Inspections will be conducted at least one time per week ar 	nd	
■ ☐Other (describe):	■ Rock Check Dams	after a storm event of 0.50 inches or greater.		
> Total Project Area 0.54 Acres (4.2 1.b.)	Sediment Traps/Basins	 All controls will be maintained in good working order. Neces 		
> Total Area To Be Disturbed 0.28 (4.2 1.b.)	■ ☐ Inlet Protection	repairs will be initiated within 24 hours of the site inspection		
Existing Vegetative Cover (%) 50%	■	report.		
Soil Properties: USDA-NRCS Soil Series Classification Nibro Silty	Surface Inlet Protection (Area Drain)	 Silt fence will be inspected for depth of sediment and for tea 		
Clay Loam, Lakoma-Vivian Complex (4.2 1. d.)	■	order to ensure the fabric is securely attached to the posts	and	
Name of Receiving Water Body/Bodies Bad River (North Fork)	 Stabilized Construction Entrances 	that the posts are well anchored. Sediment buildup will be		
(4.2 1.e.)	 Entrance/Exit Equipment Tire Wash 	removed from the silt fence when it reaches 1/3 of the heigh	t of	
	■ Interceptor Ditch	the silt fence.		
ORDER OF CONSTRUCTION ACTIVITIES (4.2 1.c.)	■ Concrete Washout Facility	 Sediment basins and traps will be checked. Sediment will be 		
(Stabilization measures shall be initiated as soon as possible, but in no	■ ☐ Temporary Diversion Channel	removed when depth reaches approximately 50 percent of		
case later than 14 days after the construction activity in that portion of	■ Work Platform	structure's capacity, and at the conclusion of the construction		
the site has temporarily or permanently ceased. Initiation of final or	■ ☐ Temporary Water Barrier	 Check dams will be inspected for stability. Sediment will be 		
temporary stabilization may exceed the 14-day limit if earth disturbing	■ ☐ Temporary Water Crossing	removed when depth reaches ½ the height of the dam.		
activities will be resumed within 21 days.)	■ Other:	 All seeded areas will be checked for bare spots, washouts, 	and	
Install perimeter protection where runoff sheets from the site.	> Wetland Avoidance	vigorous growth free of significant weed infestations.		
Install channel and ditch bottom protection.	Will construction and/or erosion and sediment controls impinge on	 Inspection and maintenance reports will be prepared on for 		
Clearing and grubbing.	regulated wetlands? Yes ☐ No ☒ If yes, the structural and erosion	DOT 298 for each site inspection, this form will also be used	a to	

- > Remove and store topsoil.
- Stabilize disturbed areas.
- > Install storm sewers, curb and gutter.
- > Install inlet and culvert protection after completing storm drainage and other utility installations.
- Complete final grading.
- Complete final paving and sealing of concrete.
- Complete traffic control installation and protection devices.
- Reseed areas disturbed by removal activities.

EROSION AND SEDIMENT CONTROLS (4.2 2.a.(1)(a)-(f))

(Check all that apply)

_	Stabilization	Dracticos	(See Detail Plan Sheets

- ☐ Temporary Seeding (Cover Crop Seeding) □ Permanent Seeding
- ☐ Sodding
- Planting (Woody Vegetation for Soil Stabilization)
- Mulching (Grass Hay or Straw)
- Hydraulic Mulch (Wood Fiber Mulch)
- Soil Stabilizer
- Bonded Fiber Matrix
- Erosion Control Blankets or Mats

and sediment controls have been included in the total project wetland impacts and have been included in the 404 permit process with the USACE.

Storm Water Management (4.2 2.b., (1) and (2))

Storm water management will be handled by temporary controls outlined in "EROSION AND SEDIMENT CONTROLS" above, and any permanent controls needed to meet permanent storm water management needs in the post construction period. Permanent controls will be shown on the plans and noted as permanent.

Other Storm Water Controls (4.2 2.c., (1) and (2))

Waste Disposal

All liquid waste materials will be collected and stored in sealed metal containers approved by the project engineer. All trash and construction debris from the site will be deposited in the approved containers. Containers will be serviced as necessary, and the trash will be hauled to an approved disposal site or licensed landfill. All onsite personnel will be instructed in the proper procedures for waste disposal, and notices stating proper practices will be posted in the field office. The general Contractor's representative responsible for the conduct of work on the site will be responsible for seeing waste disposal procedures are followed.

- document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents.
- The SDDOT Project Engineer and Contractor's Erosion Control Supervisor are responsible for inspections. Maintenance, repair activities are the responsibility of the Contractor. The SDDOT Project Engineer will complete the inspection and maintenance reports and distribute copies per the distribution instructions on DOT 298.



NON-STORM WATER DISCHARGES (3.0) The following non-storm water discharges are anticipated during the
course of this project (check all that apply).
Discharges from water line flushing.
▶ Pavement wash-water, where no spills or leaks of toxic or
hazardous materials have occurred.
➤ ☐ Uncontaminated ground water associated with dewatering
activities.
MATERIALS INVENTORY (4.2. 2.c.(2))
The following materials or substances are expected to be present on the

The following materials or substances are expected to be present on the site during the construction period. These materials will be handled as noted under the headings "EROSION AND SEDIMENT CONTROLS" and "SPILL PREVENTION" (check all that apply).

\triangleright	⊠Concrete and Portland Cement
	□ Detergents
\triangleright	⊠Paints
\triangleright	☐Metals
\triangleright	Bituminous Materials
\triangleright	⊠Petroleum Based Products
\triangleright	Cleaning Solvents
\triangleright	Wood
\triangleright	⊠Cure
\triangleright	Texture
	Chemical Fertilizers
\triangleright	Other:

SPILL PREVENTION (4.2 2.c.(2))

Material Management

- Housekeeping
 - Only needed products will be stored on-site by the Contractor.
 - Except for bulk materials the contractor will store all materials under cover and in appropriate containers.
 - Products must be stored in original containers and labeled.
 - Material mixing will be conducted in accordance with the manufacturer's recommendations.
 - When possible, all products will be completely used before properly disposing of the container off-site.
 - The manufacturer's directions for disposal of materials and containers will be followed.
 - The Contractor's site superintendent will inspect materials storage areas regularly to ensure proper use and disposal.
 - Dust generated will be controlled in an environmentally safe manner
 - Vegetation areas not essential to the construction project will be preserved and maintained as noted on the plans.

Hazardous Materials

- Products will be kept in original containers unless the container is not resealable.
- Original labels and material safety data sheets will be retained in a safe place to relay important product information.

- If surplus product must be disposed of, manufacturer's label directions for disposal will be followed.
- Maintenance and repair of all equipment and vehicles involving oil changes, hydraulic system drain down, degreasing operations, fuel tank drain down and removal, and other activities which may result in the accidental release of contaminants will be conducted on an impervious surface and under cover during wet weather to prevent the release of contaminants onto the ground.
- Wheel wash water will be collected and allowed to settle out suspended solids prior to discharge. Wheel wash water will not be discharged directly into any storm water system or storm water treatment system.
- Potential pH-modifying materials such as: bulk cement, cement kiln dust, fly ash, new concrete washings, concrete pumping, residuals from concrete saw cutting (either wet or dry), and mixer washout waters will be collected on site and managed to prevent contamination of storm water runoff.

Product Specific Practices (6.8)

Petroleum Products

All on-site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

Fertilizers

Fertilizers will be applied only in the amounts specified by the SDDOT. Once applied, fertilizers will be worked into the soil to limit the exposure to storm water. Fertilizers will be stored in an enclosed area. The contents of partially used fertilizer bags will be transferred to sealable containers to avoid spills.

Paints

All containers will be tightly sealed and stored when not required for use. The excess will be disposed of according to the manufacturer's instructions and any applicable state and local regulations.

Concrete Trucks

Contractors will provide designated truck washout facilities on the site. These areas must be self-contained and not connected to any storm water outlet of the site. Upon completion of construction, the area at the washout facility will be properly stabilized.

> Spill Control Practices (4.2 2 c.(2))

In addition to the previous housekeeping and management practices, the following practices will be followed for spill prevention and cleanup if needed.

- For all hazardous materials stored on site, the manufacturer's recommended methods for spill cleanup will be clearly posted. Site personnel will be made aware of the procedures and the locations of the information and cleanup supplies.
- Appropriate cleanup materials and equipment will be maintained by the Contractor in the materials storage area on-site. As appropriate, equipment and materials may include items such as brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand,

	STATE OF	PROJECT NO.	SHEET Number	TOTAL SHEETS
	DAKOTA	P TAPR (03)	11	41
ſ		SWPPP		

REVISED 12/15/2016

sawdust, and plastic and metal trash containers specifically for cleanup purposes.

- All spills will be cleaned immediately after discovery and the materials disposed of properly.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- After a spill a report will be prepared describing the spill, what caused it, and the cleanup measures taken. The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring, as well as clean up instructions in the event of reoccurrences.
- The Contractor's site superintendent, responsible for day-to-day operations, will be the spill prevention and cleanup coordinator. The Contractor is responsible for ensuring that the site superintendent has had appropriate training for hazardous materials handling, spill management, and cleanup.



STATE OF SOUTH	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
DAKOTA	P TAPR (03)	12	41
	SWPPP		

> Spill Response (4.2 2 c.(2))

The primary objective in responding to a spill is to quickly contain the material(s) and prevent or minimize migration into storm water runoff and conveyance systems. If the release has impacted on-site storm water, it is critical to contain the released materials on-site and prevent their release into receiving waters. If a spill of pollutants threatens storm water or surface water at the site, the spill response procedures outlined below must be implemented in a timely manner to prevent the release of pollutants.

- The Contractor's site superintendent will be notified immediately when a spill or the threat of a spill is observed. The superintendent will assess the situation and determine the appropriate response.
- If spills represent an imminent threat of escaping erosion and sediment controls and entering receiving waters, personnel will be directed to respond immediately to contain the release and notify the superintendent after the situation has been stabilized.
- Spill kits containing appropriate materials and equipment for spill response and cleanup will be maintained by the Contractor at the site
- If oil sheen is observed on surface water (e.g. settling ponds, detention ponds, swales), action will be taken immediately to remove the material causing the sheen. The Contractor will use appropriate materials to contain and absorb the spill. The source of the oil sheen will also be identified and removed or repaired as necessary to prevent further releases.
- If a spill occurs the superintendent or the superintendent's designee will be responsible for completing the spill reporting form and for reporting the spill to SD DENR.
- Personnel with primary responsibility for spill response and clean up will receive training by the Contractor's site superintendent or designee. The training must include identifying the location of the spill kits and other spill response equipment and the use of spill response materials.
- Spill response equipment will be inspected and maintained as necessary to replace any materials used in spill response activities.

SPILL NOTIFICATION

In the event of a spill, the Contractor's site superintendent will make the appropriate notification(s), consistent with the following procedures:


- A release or spill of a regulated substance (includes petroleum and petroleum products) must be reported to DENR immediately **if any one of the following** conditions exists:
 - The discharge threatens or is in a position to threaten the waters of the state (surface water or ground water).
 - The discharge causes an immediate danger to human health or safety.
 - The discharge exceeds 25 gallons.
 - The discharge causes a sheen on surface water.
 - The discharge of any substance that exceeds the ground water quality standards of ARSD (Administrative Rules of South Dakota) chapter 74:51:01.
 - The discharge of any substance that exceeds the surface water quality standards of ARSD chapter 74:51:01.

- The discharge of any substance that harms or threatens to harm wildlife or aquatic life.
- The discharge of crude oil in field activities under SDCL (South Dakota Codified Laws) chapter 45-9 is greater than 1 barrel (42 gallons).

To report a release or spill, call DENR at 605-773-3296 during regular office hours (8 a.m. to 5 p.m. Central time). To report the release after hours, on weekends or holidays, call State Radio Communications at 605-773-3231. Reporting the release to DENR does not meet any obligation for reporting to other state, local, or federal agencies. Therefore, the responsible person must also contact local authorities to determine the local reporting requirements for releases. DENR recommends that spills also be reported to the National Response Center at (800) 424-8802.

CONSTRUCTION CHANGES (4.4)

When changes are made to the construction project that will require alterations in the temporary erosion controls of the site, the Storm Water Pollution Prevention Plan (SWPPP) will be amended to provide appropriate protection to disturbed areas, all storm water structures, and adjacent waters. The SDDOT Project Engineer will modify the SWPPP plan (DOT 298) and drawings to reflect the needed changes. Copies of changes will be routed per DOT 298. Copies of forms and the SWPPP will be retained in a designated place for review over the course of the project.



STATE OF	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
DAKOTA	P TAPR (03)	13	41
-	SWPPP		

CERTIFICATIONS

Certification of Compliance with Federal, State, and Local Regulations

The Storm Water Pollution Prevention Plan (SWPPP) for this project reflects the requirements of all local municipal jurisdictions for storm water management and sediment and erosion control as established by ordinance, as well as other state and federal requirements for sediment and erosion control plans, permits, notices or documentation as appropriate.

> South Dakota Department of Transportation

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Tom hall

Authorized Signature (See the General Permit, Section 6.9.1.C.)

> Prime Contractor

This section is to be executed by the General Contractor after the award of the contract. This section may be executed any time there is a change in the Prime Contractor of the project.

I certify under penalty of law that this document and all attachments will be revised or maintained under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Authorized	Signature


CONTACT INFORMATION

Contractor Information:

•	Prime Contractor Name:		
	Contractor Contact Name: _		
	Address:		_
		_,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	_
=	City:	State:	Zip:
	Office Phone:	Field:	
	Cell Phone:	Fax:	
⊳ E	Frosion Control Supervisor		
	Name:		_
	Address:		
•			_
•	City:	State:	Zip:
•	Office Phone:	Field:	
=	Cell Phone:	Fax:	
> 5	SDDOT Project Engineer		
•	Name:		-
	Business Address:	No transport to the state of th	
•	Job Office Location:		***
=	City:	State:	Zip:
×	Office Phone:	Field:	
	Cell Phone:	Fav.	

> SD DENR Contact Spill Reporting

- Business Hours Monday-Friday (605) 773-3296
- Nights and Weekends (605) 773-3231
- > SD DENR Contact for Hazardous Materials.
 - **(605)** 773-3153
- > National Response Center Hotline
 - **(800)** 424-8802.



STATE OF	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
SOUTH DAKOTA	P TAPR(03)	14	41
	TYPICAL SECTION		

CUT SECTION

2'

CONCRETE SIDEWALK, SEE
PLANS FOR THICKNESS

6:1


PROFILE GRADE POINT


2" CUSHION MATERIAL


TYPICAL SECTION

2'

TYPICAL SECTION







HORIZONTAL ALIGNMENT & SURVEY CONTROL DATA

STATE OF SOUTH	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
DAKOTA	P TAPR(03)	17	41
HORIZO	NTAL ALIGNMENT & SURVEY	CONTROL	DATA

					T
TYPE	STATION	DISTANCE	DIRECTION	NORTHING	EASTING
вор	0+00.00			624644.31	1616116.73
		TL = 61.56	N00° 44' 57.71"E		
PC	0+61.56			624705.87	1616117.53
Pl	0+64.69	R = 60.00	Delta = 05° 57' 35.35" R	624708.98	1616117.58
PT	0+67.80			624712.09	1616117.94
		TL = 31.98	N06° 42' 33.06"E		
PC	0+99.78			624743.85	1616121.6
Pl	1+02.80	R = 60.00	Delta = 05° 45' 33.05" L	624746.85	1616122.03
PT	1+05.81			624749.86	1616122.0
		TL = 79.95	N00° 57' 00.01"E		
PC	1+85.76			624829.81	1616123.40
Pl	1+90.69	R = 60.00	Delta = 09° 23' 05.84" R	624834.73	1616123.49
PT	1+95.59			624839.58	1616124.37
		TL = 10.33	N10° 20' 05.85"E		
PC	2+05.92			624849.73	1616126.22
Pl	2+10.95	R = 60.00	Delta = 09° 35' 26.56" L	624854.68	1616127.13
PT	2+15.96			624859.72	1616127.19
		TL = 113.84	N00° 44' 39.29"E		
PC	3+29.80			624973.55	1616128.67
Pl	3+40.70	R = 60.00	Delta = 20° 35' 07.02" R	624984.44	1616128.8°
PT/PC	3+51.36			624994.59	1616132.77
Pl	3+62.22	R = 60.00	Delta = 20° 31' 51.17" L	625004.72	1616136.73
PT	3+72.86			625015.58	1616136.88
		TL = 109.28	N00° 47' 55.80"E		
PC	4+82.14			625124.86	1616138.40
Pl	4+89.25	R = 60.00	Delta = 13° 31' 07.18" R	625131.97	1616138.50
PT	4+96.30			625138.86	1616140.26
		TL = 87.25	N14° 19' 03.04"E		
PC	5+83.55			625223.40	1616161.84
Pl	6+10.07	R = 20.00	Delta = 105° 57' 13.49" L	625249.09	1616168.39
PT	6+20.54			625248.34	1616141.89
		TL = 73.69	S88° 21' 49.55"W		
PC	6+94.23			625246.23	1616068.22
PI	6+97.57	R = 25.00	Delta = 15° 12' 04.14" L	625246.14	1616064.88
PT	7+00.87			625245.17	1616061.69
		TL = 13.32	S73° 09' 45.41"W		
EOP	7+14.19	1		625241.31	1616048.94

	HORIZONTAL AND VERTICAL CONTROL POINTS							
POINT	STATION & OFFSET	NORTHING	EASTING	ELEVATION	DESCRIPTION			
CP1	1	625688.00	1615937.08	2182.99	KLJ ALUMINUM CAP			
CP 2	5+46.01 - 26.90' RT	625201.99	1616168.96	2174.12	KLJ ALUMINUM CAP			
CP3	0+52.15 - 55.21' LT	624697.18	1616062.21	2165.22	KLJ ALUMINUM CAP			

BASIS OF SURVEY

BEARINGS FOR THIS PROJECT ARE BASED ON SOUTH DAKOTA STATE PLANE SOUTH ZONE NAD 83/2011.

VERTICAL DATUM IS NAVD 88 PER RAPID CITY CONTROL.


COMBINED SCALE FACTOR TO CONVERT FROM STATE PLANE DISTANCES (GRID) TO GROUND IS 1.000166.

SURVEY NOTES

THIS SURVEY DOES NOT CONSTITUTE A BOUNDARY SURVEY. THE PROPERTY AND RIGHT-OF- WAY LINES DEPICTED HEREIN ARE FOR PLANNING PURPOSES ONLY. THE LOCATIONS OF LOT AND PROPERTY LINES WERE DETERMINED FROM RECORD DOCUMENTS AND FOUND MONUMENTS.

SNOW COVER WAS ON THE GROUND AT THE TIME OF SURVEY. THE LOCATION OF UTILITIES DEPICTED HEREON WERE DERIVED FROM UTILITY LOCATES FROM SOUTH DAKOTA ONE CALL, UTILITY MAPS AND FOUND APPURTENANCES. CONTACT THE APPROPRIATE UTILITY COMPANIES FOR THE EXACT LOCATION AND NATURE OF UTILITIES.

FIELD SURVEY CONDUCTED IN THE WINTER OF 2013.



CP 3


G


##

PINE STREET

			SYMBOLS AND	ABBREVIATION	S	STATE OF SOUTH DAKOTA	P TAPR(03) SHEET NUMBER 18
Agar	Aggregate	P.P.	Power Pole	400 Watt HPSVL		DANOTA	SYMBOLS & ABBREVIATIONS
Aggr Ahd	Ahead	P.R.C. Pref.	Point of Reverse Curvature Preformed		<u> </u>		
Alt Approx	Alternate Approximate or Approximately	P.S.D.		50 Watt HPSVL		Fire Hydrant (Proposed)	
Appr	Approach	P.T.	Passing Sight Distance Point of Tangency Quantity or Quantities	700 Watt HPSVL	- •	Fiberglass Roving	
Asph Cem or AC Asph Conc	Asphalt Cement Asphaltic Concrete	Quant. R	Radius	70 Watt HPSVL	<u></u>	Flagger	-
Biť	Bituminous or Bitumen Bureau of Land Management	R or Rge	Range Rapid Curing		↔ Ar	Flashing Beacon	⊏
B.L.M. Bk	Back	RC R.C.E.S.	Reinforced Concrete End Section	Access Control Arrow Alignment Data Point	ø.	Flexible Delineator	<u> </u>
BM	Bench Mark	R.C.P.	Reinforced Concrete Pipe	Alignment Point 1	0		<u>-</u>
3ldg 3r	Building Bridge	Rd Rdbd	Road Roadbed	Approach		Feed Point Pole Mounted	abla
C.A.E.S.	Corrugated Aluminum End Section	Rdwy	Roadway	Guy Wire & Anchor	→	Feed Point Pad Mounted	<u>N</u>
C.A.P. C & G	Corrugated Aluminum Pipe Curb and Gutter	Refl. R.R.	Reflectorized Rail Road	Analyzed Sample	2	Fuel Dispenser	
Ch Ch	Channel Change	Rt.	Right	Arrow Panel Caution Mode		·	_
C.I. Cl	Curb Inlet Class	R\W Salv.	Right of Way Salvage	Double Direction Arrow Panel	₩	Fuel Filler Pipe	•
S.S.E.S.	Corrugated Steel End Section	S.C.	Spiral to Curve	Left Direction Arrow Panel	₩	Fuel Leak Sensor	0
C.S.P. Const.	Corrugated Steel Pipe Construction	SC Sc	Slow Curing Spiral Deflection Angle	Right Direction Arrow Panel	Ģ	Gas Vent Pipe	ገ
Conc.	Concrete	S.D.	Sight Distance	Sequencing Arrow Panel	000	GPS Base Station Control Point	\triangle
RS rse	Cationic Rapid Setting Course	S.E. Sec.	Superelevation Section	Truck Mounted Arrow Panel	Ţ	PPSD High Mast Light 3 L	\bigcirc
:.S.	Curve to Spiral	Sec. Line Appr.	Section Line Approach	Artifact Attenuation Device	×	•	
to C .Y.	Center to Center Cubic Yard	Shldr. SP	Shoulder Special Provision	Truck Mounted Attenuator		PPSD High Mast Light 4 L	\mathbb{X}
i. Y .	Degree of Curvature	S.P.P.	Structural Plate Pipe	Type 1 Barricade	T	PPSD High Mast Light 5 L	lacktriangle
)—Load	Dead Load Ditch Block	S.P.P.A. SS	Structural Plate Pipe Arch Slow Setting or Supplement Specification	Type 2 Barricade	π	PPSD High Mast Light 6 L	₩
).B.).G.	Ditch Grade	S.S.D.	Stopping Sight Distance	Type 3 Barricade	Щ	PPSD High Mast Light 7 L	
I. or Elev.	Elevation	S.T. Sec. Line	Spiral to Tangent Section Line	Back to Back Sign	<u> </u>	•	
mb. mul.	Embankment Emulsified	Sec. Line Sta.	Station	Bench Mark	★	PPSD High Mast Light 8 L	\bigoplus
ngr.	Engineer	Std.	Standard	Bench Mark US Gov.		Horizontal Control	\triangle
q .S.	Equation End Section	Std. Specs Struct.	Standard Specifications Structure	Electrical Box	Œ	Horizontal & Vertical Control	◬
ismt.	Easement	Surf.	Surface	Electrical Box (Relocate)	Œ	Hose Hydrant	\\\\\
xc.	Excavation	Surv. S.W.	Survey Sidewalk	Bridges	\square	Inclinometer Tube	E .
xp. ī.D.	Expansion Field Drive	S.Y.	Square Yard	Buildings		Inlet Type 1 (Existing)	
ī.F.	Foundation Fill	T. T or Twp.	Tangent Length (circular curve) Township	Gas Cap or Stub		Inlet Type 1 (Proposed)	Ш
Found. F.P.	Foundation Fence Post	Tel.	Telephone	•		Inlet Type 2 (Existing)	
Ga.	Gage or Gauge	Temp.	Temporary	Catch Basin (Existing)	•	Inlet Type 2 (Proposed)	
Gr. Grd.	Gravel Graded	Tr Trans.	Traffic Transverse or Transition	Catch Basin (Proposed)	00	milet 1966 2 (17666664)	
9.V.	Gate Valve	Trtd.	Treated	Cattle Guard		Inset Ballon	(•)
lyd. M.	Hydrant Iron Monument	Ts TS	Tangent Length(curve with spirals) Tangent to Spiral	Centerline	Ę	Inset Point	•
nst.	Install	T.S. U.S.C. & G.S.	United States Coast and Geodetic Survey	Centerline of Construction	₩44 		
nter.	Intersection	U.S.F.S. U.S.G.S.	U.S. Forest Service U.S. Geological Survey	Clean Out (Existing)	(1)	Inlet Type 2 (Existing)	
าv. t.	Invert Joint	V.C.	Vertical Curve	Clean Out (Proposed)	© ©	Inlet Type 2 (Proposed)	
•	Length of Curve	V.C.P.	Vitrified Clay Pipe	Curb Stop (Existing)	0	Inlet Type 2 Double (Existing)	
.c .evg.	Length of Spiral Leveling	W.M. W.M.V.	Water Main Water Main Valve	Curb Stop (Proposed)	•	, ,	
F	Linear or Lineal Feet	Wrng W.S.V.	Wearing	Concrete Box Culvert (Install)	五 五	Inlet Type 2 Double (Proposed)	
iq. ong.	Liquid Longitudinal	W.S.V. x-sec	Water Service Valve Cross Section	Concrete Curb	=====	Light Pole (Existing)	\$
P.	Light Pole	Xc	Spiral Coordinate	Concrete Curb & Gutter	EEEE	Light Pole (Proposed)	*
t. M"	Left One Thousand	Yc	Spiral Coordinate	Concrete Foundation Lighting	•	Manhole (Existing)	\circ
Natl.	Material			Concrete Split Barrier Sample	<u> </u>		
Max.	Maximum Medium Curing	DESCRIPTION	N SYMBOL	Concrete Walk (Existing) Concrete Walk (Proposed)			PROFESSIONAL
MC M.H.	Manhole		, STINDOL	Culvert (Existing)			PROI LOSIONAL
din.	Minimum Main Line	1000 Watt HPSVL	—	Culvert (Proposéd) Dam or Dike			REG NO 1 CH
И.L. N.F.S.L.	National Forest System Lands	100 Watt HPSVL	- €		\triangleleft		
Off. Loc.	Office Location	150 Watt HPSVL	<u> </u>	Delineator Drum	•		114607 / S
P.V.C. P & P	Polyvinyl Chloride Sewer Pipe Plan and Profile		. ↓	Type A Delineator	Т		PONNED !
P.C.	Point of Curvature	175 Watt HPSVL	<u> </u>		·	i	WILLIAMS
P.C.C. P.D.	Point of Compound Curve Private Drive	200 Watt HPSVL	−\$	Ditch Block	-		
Pen	Penetration	250 Watt HPSVL		Drainage Arrow			THOUTH DAKOTA
Perf. P.I.	Perforated Point of Intersection	30" Riser	o ,	Excavation Unit			10.0
P.O.C.	Point on Curve	310 Watt HPSVL	—(Flight Auger Sample	B		* Count
P.O.T.	Point on Tangent						

			SYME	BOLS AND ABBR	EVIATION	ONS	STATE OF SOUTH DAKOTA	PROJECT NO. P TAPR(03)	SHEET' NUMBER	TOTAL SHEET
		0 Col		Section Corner	•			SYMBOLS & ABBREVI	ATIONS	
Manhole (Proposed)	0	Corner Set Corner Set, Iron Rebar w/Cap		Sod	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	Proposed Cable TV (Buried)				
Federal Mail Box		• •	•	Signal Head With Number	3	Existing Crude Pipeline (Buried)	CDPL	— CDPL——— CDPL—		
Private Mail Box		Corner Found	_	Highway Sign	E	Proposed Crude Pipeline (Buried)				
Marsh or Swamp	, * , *	Corner Calculated	\bigcirc	Sign	•	Existing Easement/RW Line				
Meter Electric	E	Corner Found RLS Remonumented This Survey with USDA Forest Service	$\widehat{oldsymbol{olombol{oldsymbol{olop}}}}}}}$	Street Sign	+	Proposed Easement/RW Line Existing Electric Overhead	E(0)	E(0)		
Meter Gas	G	2 1/2"x30" SSP 3 1/4" Brass Cap		Sprinkler Head	Þ	Proposed Electric Overhead				
Meter Water	W	Corner Found BLM 2 1/2" Aluminum Pipe With 3 1/4" Aluminum Cap 19??		Standard Penetration Test	₿	Existing Electric (Buried)	E	— E ——— Е ——		
Electrical Manhole (Existing)	Ē	Corner Found BLM 2 1/2" Iron Pipe	0	Spot Elevation	× 100.00	Proposed Electric (Buried)	510			
Electrical Manhole (Proposed)	Ē	With 3 1/4" Brass Cap 19??		Stone Circle or Cairn		Existing Electric Signal Heads Proposed Electric Signal Heads	5 G	310		
Manhole Gas (Existing)	©	Original Corner Found		Storie Graid of Gairti	\bigcirc	Existing Fence Barb Wire	x x ·	x x		
Manhole Gas (Existing) Manhole Gas (Proposed)	©	Original Corner Remonumented This Survey With USDA Forest Service	(Tower Windmill	\boxtimes	Proposed Fence Barb Wire	xx	xx		
• • •	o	2 1/2"x30" SSP 3 1/4" Brass Cap		Telephone Pole To Be Lowered		Existing Fence Chain Link		0 0		
Manhole With Inlet (Existing)	(a)	Corner Set This Survey With USDA	٨	Telephone Pole To Be Removed	©	Proposed Fence Chain Link	oo_			
Manhole With Inlet (Proposed)	(1)	Forest Service 5/8"x24" Rebar With 3 1/4" Aluminum Cap		Telephone/Telegraph Pole	-O-	Existing Fence Wood Proposed Fence Wood				
Pipeline Marker (Existing)	<u>(C)</u>	Corner Found USDA Forest Service		Brush or Shrub	ය	Existing Fiberoptic (Buried)	F0	— F0 —— F0 ——		
Pipeline Marker to be Relocated	©	2 1/2"x30" SSP With 3 1/4" Brass Cap 19??		5, 45.1 5. 5.1142	$\widetilde{\mathcal{L}}$	Proposed Fiberoptic (Buried)				
Sanitary FM Manhole (Existing)	€M	Corner Found USDA Forest Service		Tree, Deciduous	C	Proposed Fiber Roll				
Sanitary FM Manhole (Proposed)	₪	2 1/2"x30" Aluminum Pipe 3 1/4" Aluminum Cap 19??			\mathcal{C}	Existing Fuel (Buried)	FUEL-	FUEL	····	
Sanitary Manhole (Existing)	S	Corner Found USDA Forest Service	Δ	Tree, Coniferous		Proposed Fuel (Buried)	***************************************			
Sanitary Manhole (Proposed)	S	5/8"x24" Rebar With 3 1/4" Aluminum Cap		mos, commercus		Existing Guard Rail		* * * * * * * * * * * * * * * * * * * *		
Storm Manhole (Existing)	S	Corner Found GLO 1" Iron Pipe with		Tree Trunk	<u>©</u>	Proposed Guard Rail Existing Line Not Surveyed	**-			
Storm Manhole (Proposed)	<u>©</u>	2" Brass Cap 19??		Traffic Cones	A	Existing Line Not Surveyed Existing Natural Gas Pipeline (Buried)	G	G G		
, , ,	⊚	Corner Found GLO 2" Iron Pipe with		Traffic Signal Pole Mounted		Proposed Natural Gas Pipeline (Buried)				
Sanitary MH With Valve (Existing)	®	2 1/2" Brass Cap 19??		Transformer	A	Existing Property Line				
Sanitary MH With Valve (Proposed)		Corner Found GLO 2 1/2" Iron Pipe w 3 1/4" Brass Cap 19??	≀ ^{ith} 🖾		A	Proposed Property Line				
Telephone Manhole (Existing)	\ominus	Corner Found GLO Cap Remonumented	$\overline{}$	Transformer Pad Mounted		Existing Section Line				
Telephone Manhole (Proposed)	Ū	This Survey With USDA Forest Service		Traffic Signal Control Box with Slab	-	Existing Quarter Line				
Jute Mesh	MANAGE	2 1/2"x30" SSP 3 1/4" Brass Cap		Traffic Signal Control Box Thinwall Tube Sample	0	Existing 1—16 Line				
Electrical Pedestal to be Relocated	(E)	Corner Reestablished This Survey With USDA Forest Service	<u> </u>	Tubular Marker	□ •	Existing 1-32 Line				
Electrical Pedestal	Ē	2 1/2"x30" SSP 3 1/4" Brass Cap		Utility Marker	-	Existing Rail Road Tracks	++++++	 	 	
Pedestrian Head with Number	P1	Corner Set This Survey With USDA		Existing Valve (Gas/Water) Proposed Valve (Gas/Water)	⊗ ⊕	Proposed Rail Road Tracks	++++++	+++++	 	
Pedestrian Push Button Post	_	Forest Service 2 1/2"x30" SSP 3 1/4" Brass Cap	_	Well Or Bore Hole	ⅎ	Existing Sanitary		s s		
	•	Corner Set, Plat	⊳ ⊑₁	Water Observation Well	ōw	Proposed Sanitary	—— »—— »			
Telephone Pedestal	Ш		' Z'	Waterway		Existing Storm Sewer	page year of the second of the	31		
Telephone Pedestal to be Relocated	(Corner Found, Plat	*	Wood Excelsior Fibermat	*******	Proposed Storm Sewer Existing Telephone Overhead				
Television Pedestal	<u> 2</u>	Pug Point	M	Existing Sleeve	\bowtie	Proposed Telephone Overhead				
Television Pedestal to be Relocated	(2)	Pull Box	\otimes	Proposed Sleeve	×	Existing Telephone (Buried)	т	т — т —		
	₩	Quarter Section Corner	•	Existing Tee Proposed Tee	\boxtimes	Proposed Telephone (Buried)			· 	
Pump Storm	_ E D	Reference Marker	0	Existing 11* Bend	\bowtie	Existing Water		— w——— w——		
Pump Sanitary	S			Proposed 11° Bend	×	Proposed Water				
Pump Water	.	Relocate Light Standard	- \(\rightarrow\)	Existing 22° Bend	\bowtie				FESSIONAL	
Pole	0	Railroad Battery Box	\ <u>\</u>	Proposed 22° Bend	•			PRO	FESS/ON	"
Post	0	Railroad Signal With Arm	\P	Existing 45° Bend Proposed 45° Bend				, RED	VA	***
Post Guard	ᢐ	Railroad Cross Buck	Ť	Existing 90° Bend	Ø			SERED PRO	G. NO	SI
Post Guide	•	Railroad Crossing Signal	¥	Proposed 90° Bend	_				146/0///	1, 1/2
Power Pole (Existing)		Right-of-way Marker	(n)	Existing Cross	₩.			7/ (R)Ø1	YNVEKU/	1
Power Pole to be Removed	-	•	⊌	Proposed Cross	*			Viet WHI	LIAMS	
Power Pole To Be Lowered		Right—of—way Monument	0	Existing Reducer Proposed Reducer	×				• — ,	: ,/
	<u> </u>	Riprap	******	Existing Boundary Not Surveyed				OUTH	DAKOTA	טן
Power Pole To Be Moved	•	Road Obliteration		Existing Boundary				Anna Anna Anna Anna Anna Anna Anna Anna	17/9	(stri
Unproductive Probe Productive Probe	o <u>∔</u>	Existing Road (Gravel)	•••••	Existing Cable TV (Buried)	тv	туту		711111	1000	***
Principal Point	0	Split Barrel Sample	3	· · · · · · · · · · · · · · · · · · ·				*****	1111111111	





	STATE OF	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
	SOUTH DAKOTA	P TAPR(03)	21	41
		PLAN & PROFILE		

REMOVE BARBED WIRE FENCE

5+24.4, 21.5' LT TO 6+37.4, 15.8' RT 91 FT 5+47.0, 26.8' LT TO 5+56.7, 7.8' RT 36 FT

INSTALL BARBED WIRE FENCE (TYPE 2) 5+56.7, 7.8' RT TO 6+37.4, 15.8' RT 120 FT

INSTALL 2 POST PANEL

5+59.8, 19.1' RT 2 EACH 6+04.6, 27.8' RT 2 EACH 6+37.4, 15.8' RT 2 EACH

INSTALL 18" CMP ARCH WITH FLARED END SECTIONS 6+36.2, 12.0' RT TO 6+37.4, 12.0' LT 24 FT

6+41.1, 12.0' LT TO 6+42.4, 12.0' LT 24 FT


4" CONCRETE SIDEWALK


 4+00.0 TO 6+56.4
 1565 SQFT

 6+83.8 TO 7+14.2
 300 SQFT


IOTES:


- 1. ALL FENCING MATERIALS REMOVED SHALL BE DISPOSED OF BY CONTRACTOR OFF SITE.
- CMP ARCH BACKFILL MATERIAL SHALL BE FREE OF ROCKS, FROZEN LUMPS AND FOREIGN MATERIAL.
- 3. ALL CMP ARCH BACKFILL MATERIAL SHALL BE PLACED IN A BALANCED FASHION IN THIN LIFTS (6-8" LOOSE TYPICALLY) AND COMPACTED TO 95 PERCENT DENSITY PER SDDOT 104 (AASHTO T-99). SELECT GRANULAR BACKFILL SHALL BE IN ACCORANCE WITH SDDOT SECTION 882 FOR BASE COURSE.
- 4. COMPLETE AND REGULAR MONITORING OF THE ARCH PIPE IS NECESSARY DURING ALL BACKFILLING OF THE PIPES.
- PREVENT EXCESSIVE DISTORTION OF SHAPE AS NECESSARY BY VARYING COMPACTION METHODS AND EQUIPMENT.
- 6. MINIMUM COVER SHALL BE GREATER OF 1' OR MANUFACTURER REQUIRED HEIGHT ABOVE STRUCTURE.






STATE OF	PROJECT NO.	sheet Number	TOTAL SHEETS		
SOUTH DAKOTA	P TAPR(03)	23	41		
SDDOT STANDARD PLATES					





STATE OF SOUTH DAKOTA	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS			
	P TAPR(03)	24	41			
SDDOT STANDARD PLATES						



	23/3" × 1/3	23/3" x 1/2" CORRUGATIONS			3" X I" CORRUGATIONS		
Dia. (in.)	Span (in.)	H Rise (i∩")	Area (Sq. Ft.)	S Span (in,)	H Rise (in.)	Area (Sq. Ft.)	
15	17	13	1.1				
18	21	15	1.6				
21	24	18	2.2				
24	28	20	2.8				
30	35	24	4.4				
36	42	29	6.4	40	31	7.0	
42	49	33	8.7	46	36	9.4	
48	57	38	11.4	53	41	12.3	
54	64	43	14.3	60	46	15.6	
60	71	47	17.6	66	51	19.3	
66	77	52	21.3	73	55	23.2	
72	83	57	25.3	81	59	27.4	
78				87	63	32.1	
84				95	67	37.0	
90				103	71	42.4	
96				112	75	48.0	
102				117	79	54.2	
108				128	83	60.8	
114				137	87	67.4	
120				142	91	74.5	

• Equivalent diameter of circular C.M.P.

GENERAL NOTE:
All dimensions measured from inside crest.

March 31, 2000


PLATE NUMBER

Published Date: 4th Qtr. 2016

CORRUGATED METAL PIPE ARCH CULVERT

450.30 Sheet | of |

Dec 08, 2016 - 9:24am - J:\municipal\10413123\CAD\plan\sheets\10413123-DTL.dwg



All 3 pc. bodies shall have 12 Ga. sides and 10 Ga. center panels. Width of center panels shall be greater than 20% of the pipe periphery. Multiple panel bodies to have lap seams tightly joined by %" Dia. galvanized rivets or bolts.

For 60" through 84" sizes, reinforced edges shall be supplemented with galvanized stiffener angles. The angles will be 2" x 2" x 1/4" for 60" through 72" diameters and 21/2" x 21/2" x1/4" for 78" and 84" diameters. The angles shall be attached by $\frac{1}{2}$ 6" diameter galvanized nuts and bolts.

Rivets and Bolts shall be % Dia, Min. for 10 Ga. and 12 Ga. sheet, and % Dia. Min. for 14 Ga. and 16 Ga. sheets. Tighten nuts with torque wrench to 25 lbs. torque.

March 31, 2000


Published Date: 4th Qtr. 2016


C.M.P. FLARED ENDS


PLATE NUMBER
450. 35


Sheet 1 of 1

STATE OF	PROJECT NO.	sheet Number	TOTAL SHEETS			
SOUTH DAKOTA	P TAPR(03)	25	41			
SDDOT STANDARD PLATES						












STATE OF	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS			
SOUTH DAKOTA	P TAPR(03)	27	41			
SDDOT STANDARD PLATES						







STATE OF	PROJECT NO.	sheet Number	TOTAL SHEETS		
SOUTH DAKOTA	P TAPR(03)	27A	41		
SDDOT STANDARD PLATES					


REVISED 12/15/2016










REVISED 12/15/2016





Dec 15, 2016 - 3:24pm - J:\municipal\10413123\CAD\pian\sheets\10413123-DTL.dwg











The stated radii on the plans and cross sections refer to this line and it shall also be the basis for horizontal linear foot measurement and payment.

Туре	T _i (Inches)	T ₂ (Inches)	Cu, Yd. Per Lin. Ft.	Lin, Ft. Per Cu. Yd.
B66	6	51/16	0.057	17.7
B67	7	6½ ₆	0.065	15.4
B68	8	71/16	0.073	13.7
B68.5	8.5	7%	0.077	13.0
B69	9	81/16	180.0	12.3
B69.5	9.5	8%	0.085	11.7
B610	10	91/16	0.090	11.2
B610.5	10.5	9%	0.094	10.7
B611	11	101/16	0.098	10.2
B611.5	11.5	10%	0.102	9.8
B612	12	111/16	0.106	9.4


GENERAL NOTES:

When concrete curb and gutter longitudinally adjoins new concrete pavement, the method of attachment shall be by one of the methods shown on Standard Plate 380.11.

See Standard Plate 650.90 for expansion and contraction joints in the curb and gutter.

September 6, 2008

	S D D	TYPE B CONCRETE CURB AND GUTTER	PLATE NUMBER 650.0/
Published Date: 4th Qtr. 2016			Sheet I of I



* Joint will not be needed if concrete curb and gutter and type P concrete gutter is placed at the same time. If the ½" Preformed Expansion Joint Filler is provided, then the joint shall be sealed in accordance with Standard Plate 650.90.

GENERAL NOTES:

The concrete for the Type P Concrete Gutter shall comply with the requirements of the Specifications for Class M6 Concrete.

When concrete gutter longitudinally adjoins new concrete pavement, the method of attachment shall be by one of the methods shown on Standard Plate 380.11.

Transverse contraction joints shall be constructed at 10' intervals in the concrete gutter except when concrete gutter is constructed adjacent to mainline PCC pavement. When concrete gutter is constructed adjacent to mainline PCC pavement, a transverse contraction joint shall be constructed in the concrete gutter at each mainline PCC pavement transverse contraction joint location.


When concrete gutter is placed monolithically with mainline PCC pavement, the transverse contraction joints in the concrete gutter shall be sawed and sealed the same as the transverse contraction joints in the mainline PCC pavement.


When concrete gutter is not placed monolithically with the mainline PCC pavement and when the adjacent mainline surfacing is not PCC concrete, the transverse contraction joints in the concrete gutter shall be $1\frac{1}{2}$ inches deep if formed in the fresh concrete using a suitable grooving tool. If a saw is used to cut the contraction joints, then the depth of the joint shall be at least $\frac{1}{4}$ the thickness of the concrete.

June 26, 2015

	S D D O T	TYPE P CONCRETE GUTTER	PLATE HUMBER 650.30
Published Date: 4th Qtr. 2016			Sheet I of I

STATE OF SOUTH DAKOTA	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS		
	P TAPR(03)	30	41		
SDDOT STANDARD PLATES					





* The silicone sealant shall be placed such that it completely seals the joint and is bonded to the sides of the clean joint as approved by the Engineer.

GENERAL NOTES:

For illustrative reason, only the type B curb and gutter is shown.

(Curb and Gutter at 1/2" Preformed

Expansion Joint Filler Location)

- ** A $\frac{1}{2}$ " preformed expansion joint filler shall be placed transversely in the curb and gutter at the following locations:
 - I. At each junction between the radius return of curb and gutter and curb and gutter which is parallel to the project centerline.

 2. At each junction between new curb and gutter and existing curb and gutter.

Transverse contraction joints shall be constructed at 10' Intervals in the concrete curb and gutter except when the concrete curb and gutter is constructed adjacent to mainline PCC pavement. When concrete curb and gutter is constructed adjacent to mainline PCC pavement, a transverse contraction joint shall be constructed in the concrete curb and gutter at each mainline PCC pavement transverse contraction joint location.

When concrete curb and gutter is not placed monolithically with the mainline PCC pavement or when the adjacent mainline surfacing is not PCC concrete, the transverse contraction joints in the concrete curb and gutter shall be $1\frac{1}{2}$ inches deep if formed in the fresh concrete using a suitable grooving tool. If a saw is used to cut the contraction joints, then the depth of the joint shall be at least $\frac{1}{4}$ the thickness of the concrete and the joint shall be sealed in accordance with the details shown above.

September 6, 2013


D D 0 Published Date: 4th Qtr. 2016


JOINTS IN CONCRETE CURB AND GUTTER

PLATE NUMBER 650.90

Sheet 2 of 2

STATE OF SOUTH DAKOTA	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS	
	P TAPR(03)	31	41	
SDDOT STANDARD PLATES				





C KLJ2016

GENERAL NOTES:

For illustrative purpose only, type I detectable warnings are shown in the drawings.

For illustrative purpose only, PCC fillet sections are shown in the drawings. The curb ramp depicted on this standard plate may be used with a PCC fillet section or curb and gutter.

For illustrative purpose only, the curb ramp location is shown at the center of a PCC fillet section. The curb ramp shall be placed at the location stated in the plans.

Sidewalk shall not be placed adjacent to the curb ramp flares when a 2' curb transition is used unless shown otherwise in the plans.

*Care shall be taken to ensure a uniform grade on the curb ramp, free of sags and short grade changes.

Surface texture of the curb ramp shall be obtained by coarse brooming transverse to the slope of the curb ramp.

The normal gutter line profile shall be maintained through the area of the ramp opening.

Joints shall be sawed or tooled into the concrete adjacent to the detectable warnings to alleviate possible corner cracking.

Care shall be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform color.

The detectable warnings shall be cut as necessary to fit the plan specified limits of the detectable warnings. Cost for cutting the detectable warnings shall be incidental to the corresponding detectable warning bid item.

There will be no separate payment for curb ramps. The curb ramp shall be measured and pald for at the contract unit price per square foot for the corresponding concrete sidewalk bid item. The square foot area of the detectable warnings shall be included in the measured and paid for quantity of sidewalk.

If rebar is placed in the Turning Space as depicted in DETAIL E, the cost of the materials, labor, and equipment to furnish and install the rebar shall be incidental to the contract unit price per square foot for the corresponding concrete sidewalk bid item.

The curb transitions and ramp opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and ramp opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid Item when a PCC fillet section is used.


The type I detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type I detectable warnings including labor, equipment, materials, and incidentals shall be paid for at the contract unit price per square foot for "Type I Detectable Warnings".

The type 2 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding shall be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".


September 6, 2015

	S D D	TYPE 1 CURB RAMP	PLATE NUMBER 651.01
Published Date: 4th Otr. 2016	OT	(PERPENDICULAR CURB RAMP)	Sheet 3 of 3

	STATE OF SOUTH DAKOTA	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
		P TAPR(03)	32	41
	SDDOT STANDARD PLATES			



Dec 08, 2016 — 9:28am — J:\municipal\10413123\CAD\plan\sheets\10413123-DTLdwg



STATE OF SOUTH DAKOTA	PROJECT NO.	sheet Number	TOTAL SHEETS	
	P TAPR(03)	33	41	
SDDOT STANDARD PLATES				

GENERAL NOTES:

For illustrative purpose only, type I detectable warnings are shown in the drawings.

The curb ramp depicted on this standard plate may be used with a PCC fillet section or curb and gutter. The curb ramp shall be placed at the location stated in the plans.

Sidewalk shall not be placed adjacent to the curb ramp flares when a 2' curb transition is used unless shown otherwise in the plans.

*Care shall be taken to ensure a uniform grade on the curb ramp, free of sags and short grade changes.

Surface texture of the curb ramp shall be obtained by coarse brooming transverse to the slope of the curb ramp.

The normal gutter line profile shall be maintained through the area of the ramp opening.

Joints shall be sawed or tooled into the concrete adjacent to the detectable warnings to alleviate possible corner cracking.

Care shall be taken to ensure that the surface of the detectable warnings are clean and maintains a uniform color.

The detectable warnings shall be cut as necessary to fit the plan specified limits of the detectable warnings. Cost for cutting the detectable warnings shall be incidental to the corresponding detectable warning bid item.

There will be no separate payment for curb ramps. The curb ramp shall be measured and paid for at the contract unit price per square foot for the corresponding concrete sidewalk bid item. The square foot area of the detectable warnings shall be included in the measured and paid for quantity of sidewalk.

If rebar is placed in the Turning Space as depicted in DETAIL E, the cost of the materials, labor, and equipment to furnish and install the rebar shall be incidental to the contract unit price per square foot for the corresponding concrete sidewalk bid item.

The curb transitions and ramp opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and ramp opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.

All costs for furnishing and installing the transition area at the base of the curb ramp shall be incidental to the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used and shall be incidental to the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used.

The type I detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type I detectable warnings including labor, equipment, materials, and incidentals shall be paid for at the contract unit price per square foot for "Type I Detectable Warnings".

The type 2 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding shall be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings".

September 6, 2015

TYPE 2 CURB RAMP


(DIRECTIONAL CURB RAMP)


PLATE NUMBER


651.02


Sheet 3 of 3


Dec 08, 2016 - 9:28am - J:\municipal\10413123\CAD\plan\sheets\10413123-DTL.dwg















STATE OF SOUTH DAKOTA	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS	
	P TAPR(03)	36	41	
SDDOT STANDARDS PLATES				

REVISED 12/15/2016



GENERAL NOTES:

At cut or fill slope installations, wattles shall be installed along the contour and perpendicular to the water flow.

At ditch installations, point A must be higher than point B to ensure that water flows over the wattle and not around the ends.

The Contractor shall dig a 3" to 5" trench, install the wattle tightly in the trench so that daylight can not be seen under the wattle, and then compact the soil excavated from the trench against the wattle on the uphill side. See Detail B.

The stakes shall be 1"x2" or 2"x2" wood stakes, however, other types of stakes such as rebar may be used only if approved by the Engineer. The stakes shall be placed 6" from the ends of the wattles and the spacing of the stakes along the wattles shall be 3 to 4',

Where installing running lengths of wattles, the Contractor shall butt the second wattle tightly against the first and shall not overlap the ends. See Detail C.

The Contractor and Engineer shall inspect the erosion control wattles once every week and within 24 hours after every rainfall event greater than $\frac{1}{2}$. The Contractor shall remove, dispose, or reshape the accumulated sediment when necessary as determined by the Engineer.

Sediment removal, disposal, or necessary shaping shall be as directed by the Engineer. All costs for removing accumulated sediment, disposal of sediment, and necessary shaping shall be incidental to the contract unit price per cubic yard for "Remove Sediment".

All costs for furnishing and installing the erosion control wattles including labor, equipment, and materials shall be incidental to the contract unit price per foot for the corresponding erosion control wattle bid item.

All costs for removing the erosion control wattle from the project including labor, equipment, and materials shall be incidental to the contract unit price per foot for "Remove Erosion Control Wattle".

December 23, 2004

Published Date: 4th Qtr. 2016

Solution Control Wattle

EROSION CONTROL WATTLE


PLATE NUMBER 734.06

Shoot 2 of 2

	STATE OF	PROJECT NO.	sheet Number	TOTAL SHEETS
	SOUTH DAKOTA	P TAPR(03)	37	41
SDDOT STANDARD PLATES				

Type S Reinforced Concrete Drop Inlet

REVISED 12/15/2016



GENERAL NOTES:

The grate and curb and gutter shown are for illustrative purposes only.

The sediment control at inlet with frame and grate shall be placed at locations stated in the plans or at locations determined by the Engineer.

The filter fabric shall be the type specified in the plans.

The filter fabric shall be placed in the inlet opening prior to placing the grate. Approximately 18 inches of excess filter fabric shall be wrapped around the 2"x4" and stapled securely to the 2"x4" after the grate has been placed.

The Contractor shall inspect and maintain the sediment control device once every week and within 24 hours after every rainfall event. The Contractor shall maintain the sediment control device by removing accumulated sediment and replacing torn filter fabric with new filter fabric.

The removed sediment shall be placed at a location away from the drop inlet where the sediment will not be washed back into the drop inlet or other storm sewer system.

All costs for furnishing, installing, inspecting, maintaining, removing, and replacing the sediment control device at the inlet including labor, equipment, and materials shall be incidental to the contract unit price per each for "Sediment Control at inlet with Frame and Grate".


September 14, 2005

Published Date: 4th Qtr. 2016

SEDIMENT CONTROL AT INLETS
WITH FRAMES AND GRATES

PLATE NUMBER 734.10

Stood | of | Published Date: 4th Qtr. 2016



GENERAL NOTES:

Sediment Control Device-

The type of sediment control device shown is for illustrative purposes only.

The type of sediment control device used shall be one of the types as specified in the plans.

The sediment control device shall be placed at the drop inlets according to the manufacturers' installation instructions.

The sediment control at inlet for type S reinforced concrete drop inlet shall be placed at locations stated in the plans or at locations determined by the Engineer.

The Contractor shall inspect and maintain the sediment control device once every week and within 24 hours after every rainfall event. The Contractor shall maintain the sediment control device by removing the device, removing accumulated sediment, and resetting the device.

The removed sediment shall be placed at a location away from the drop inlet where the sediment will not be washed back into the drop inlet or other storm sewer system.

Payment for the "Sediment Control at Type S Drop Iniet" shall be based on the minimum length required at the drop iniets. Some of the sediment control devices specified in the plans will have to be longer due to available length.


All costs for furnishing, installing, inspecting, maintaining, removing, and resetting the sediment control device at the drop inlet including labor, equipment, and materials shall be incidental to the contract unit price per foot for "Sediment Control at Type S Reinforced Concrete Drop Inlet".


September 14, 2005


D D O T SEDIMENT CONTROL AT INLETS FOR TYPE S REINFORCED CONCRETE DROP INLETS PLATE NUMBER 734.11


Sheet I of I

	STATE OF	PROJECT NO.	sheet Number	TOTAL SHEETS
SOUTH DAKOTA		P TAPR(03)	38	40
	CROSS SECTIONS			













STATE OF	PROJECT NO.	sheet Number	TOTAL SHEETS
SOUTH DAKOTA	P TAPR(03)	39	41
	CROSS SECTIONS		













STATE OF	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
SOUTH DAKOTA	P TAPR(03)	40	41
	CROSS SECTIONS		









	STATE OF SOUTH DAKOTA	PROJECT NO.	SHEET NUMBER	TOTAL SHEETS
		P TAPR(03)	41	41
		CROSS SECTIONS		

