

STATE OF SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION PLANS FOR PROPOSED **PROJECT P TAPU (06) MTI SHARED USE PATH** MITCHELL, DAVISON COUNTY, SOUTH DAKOTA SHARED USE PATH, GRADING, CURB AND GUTTER, CONCRETE SIDEWALK AND SIGNING PCN 04U7

BEGIN P TAPU (06) MTI SHARED USE PATH, MITCHELL DAVISON COUNTY. SD STA. 0+74.62–55.72' R ON P TAPU (06) SOUTH ENTRANCE OF MTI APARTMENTS. N. 503027.1950 E. 2584287.0956

DESIGN DESIGNATION

GROSS LENGTH:	2794.00 FT	0.529 MILES
EXCEPTIONS:	00.00 FT	0.000 MILES
NET LENGTH:	2794.00 FT	0.529 MILES

STORM WATER PERMIT

MAJOR STREAM: DRY RUN CREEK MAJOR WATER BODY: NONE AREA DISTURBED: 2.70 ACRES TOTAL PROJECT AREA: 3.20 ACRES APPROX. BEGIN LAT/LONG: 43.7300/98.0252

103 N F



R 60 W

MTI SHARED USE PATH



	STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL
		P TAPU (06)	1	51

INDEX OF SECTIONS

Sheet	1:	TITLE AND LAYOUT MAP
Sheet	2:	QUANTITIES
Sheet	3-8:	NOTES
Sheet	9-10:	TYPICAL SECTIONS
Sheet	11:	TRAFFIC CONTROL
Sheet	12–18:	EROSION AND SEDIMENT CONTROL
Sheet	19:	HORIZONTAL ALIGNMENT
Sheet	20:	CONTROL DATA
Sheet	21:	LEGEND
Sheet	22–33:	PLAN & PROFILE SHEETS
Sheet	34–37:	CURB RAMP DETAILS
Sheet	38–39:	PERMANENT SIGNING
Sheet	40:	SPECIAL DETAILS
Sheet	41-46:	STANDARD PLATES
Sheet	47-51:	CROSS SECTIONS







103

END P TAPU (06) MTI SHARED USE PATH, MITCHELL, DAVISON COUNTY, SD STA. 28+09.94-11.07' L ON P TAPU (06) WEST SIDE OF EAST ENTRANCE TO MTI UTILITY BUILDING. N. 502497.8272 E. 2585843.7786

ESTIMATE OF QUANTITIES

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
009E3230	Grade Staking	0.532	Mile
009E3250	Miscellaneous Staking	0.532	Mile
009E3330	Three Man Survey Crew	20.0	Hour
100E0100	Clearing	Lump Sum	LS
110E0300	Remove Concrete Curb and Gutter	223	Ft
110E1010	Remove Asphalt Concrete Pavement	174.6	SqYd
110E1100	Remove Concrete Pavement	4.3	SqYd
110E1140	Remove Concrete Sidewalk	26	SqYd
110E1700	Remove Silt Fence	23	Ft
110E7150	Remove Sign for Reset	2	Each
120E0010	Unclassified Excavation	2,015	CuYd
230E0010	Placing Topsoil	815	CuYd
260E1010	Base Course	105.9	Ton
320E1200	Asphalt Concrete Composite	30.1	Ton
451E6080	Adjust Water Valve Box	3	Each
632E1320	2.0"x2.0" Perforated Tube Post	176.0	Ft
632E3203	Flat Aluminum Sign, Nonremovable Copy High Intensity	81.1	SqFt
632E3205	Flat Aluminum Sign, Nonremovable 19.0 Copy Super/Very High Intensity		SqFt
632E3500	Reset Sign	2	Each
633E1430	Pavement Marking Paint, 24" White	330	Ft
634E0100	Traffic Control	1202	Unit
634E0120	Tracffic Control, Miscellaneous	Lump Sum	LS
650E2100	Special Concrete Curb and Gutter	496	Ft
651E0150	5" Reinforced Concrete Sidewalk	25,802	SqFt
651E0180	8" Reinforced Concrete Sidewalk	1,013	SqFt
651E5000	Sidewalk Drain	34.5	Ft
651E7000	Type 1 Dectecable Warnings	262	SqFt
730E0206	Type D Permanent Seed Mixture	288	Lb
731E0100	Fertilizing	1,398	Lb
732E0250	Fiber Mulching	2,832	Lb
734E0604	High Flow Silt Fence	90	Ft
734E0610	Mucking Silt Fence	6	CuYd
734E0620	Repair Silt Fence	23	Ft
735E3010	Salvage, Store, and Replant Tree	4	Each

STATE OF	PROJECT	SHEET	TOTAL
SOUTH DAKOTA	P TAPU (06)	2	51
	RE\	/ 5-29-1	5 NAP
	MUMMOFESS/		
	WIN PHOT 200/	N MA	
	THE REG. NO	\cdot	
	E E // MECHAN	" "	
	The for the for		
	TH DAKS):	1111
	Ally Elacht		
		MILLIN,	
	Q		

Specifications

South Dakota Standard Specifications for Roads and Bridges, 2004 Edition and Required Provisions, Supplemental Specifications and special provisions as included in the proposal.

ENVIRONMENTAL COMMITMENTS

An Environmental Commitment is a measure that SDDOT commits to implement in order to avoid, minimize, and/or mitigate a real or potential environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency mentioned below with permitting authority can influence a project if perceived environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office. The environmental commitments associated with this project are as follows:

COMMITMENT C: WATER SOURCE

Water for compaction is incidental to the project. Water used from City of Mitchell fire hydrants shall be metered and paid for by the Contractor.

The Contractor shall not withdraw water with equipment previously used outside the State of South Dakota without prior approval from the SDDOT Environmental Office. Thoroughly wash all construction equipment before entering South Dakota to reduce the risk of invasive species introduction into the project vicinity.

The Contractor shall not withdraw water directly from streams of the James, Big Sioux, and Vermillion watersheds without prior approval from the SDDOT Environmental Office.

Action Taken/Required:

The Contractor shall obtain the necessary permits from the regulatory agencies such as the Department of Environment and Natural Resources (DENR) and the United States Army Corps of Engineers (COE) prior to executing water extraction activities.

COMMITMENT E: STORM WATER

Construction activities constitute 1 acre or more of earth disturbance.

Action Taken/Required:

The DENR and the US Environmental Protection Agency (EPA) have issued separate general permits for the discharge of storm water runoff. The DENR permit applies to discharges on state land and the EPA permit applies to discharges on federal or reservation land. The Contractor is advised this project is regulated under the Phase II Storm Water Regulations and must receive coverage under the General Permit for Construction Activities. A Notice of Intent (NOI) will be submitted to DENR a minimum of 15 days prior to project start by the DOT Environmental Office. A letter must be received from DENR that acknowledges project coverage under this general permit before project start. The Contractor is advised that permit coverage may also be required by off-site activities, such as borrow and staging areas, which are the responsibility of the Contractor.

The Contractor shall adhere to the "Special Provision Regarding Storm Water Discharges to Waters of the State".

A major component of the storm water construction permits is development and implementation of a Storm Water Pollution Prevention Plan (SWPPP), which is a joint effort and responsibility of the SDDOT and the Contractor. Erosion control measures and best management practices will be implemented in accordance with the SWPPP. The SWPPP is a dynamic document and is to be available on-site at all times.

Information on storm water permits and SWPPPs are available on the following websites:

SDDOT:

http://sddot.com/transportation/highways/environmental/stormwater/Default.as px

DENR: http://www.denr.sd.gov/des/sw/stormwater.aspx

EPA: http://cfpub.epa.gov/npdes/home.cfm?program_id=6

Contractor Certification Form:

The "Department of Environmental and Natural Resources - Contractor Certification Form" (SD EForm - 2110LDV1-ContractorCertification.pdf) shall be completed by the Contractor or their certified Erosion Control Supervisor after the award of the contract. Work may not begin on the project until this form is signed.

The form certifies under penalty of law that the Contractor understands and will comply with the terms and conditions of the Surface Water Discharge General Permit for Storm Water Discharges Associated with Construction Activities for the Project.

The online form can be found at: http://denr.sd.gov/des/sw/eforms/E2110LDV1-ContractorCertification.pdf

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor shall furnish a site(s) for the disposal of construction and/or demolition debris generated by this project. The City of Mitchell will accept clean concrete and asphalt waste at their disposal site located southwest of the Ohlman Street and 8th Avenue Intersection.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the State ROW.

The waste disposal site(s) shall be managed and reclaimed in accordance with the following from the General Permit for Highway, Road, and Railway Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Environment and Natural Resources.

The waste disposal site(s) shall not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation. aesthetic value of an area, or any threatened or endangered species, as approved by the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements shall apply:

- 1. Dumping Allowed".

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) shall be incidental to the various contract items.

COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historical Preservation Office (SHPO or THPO) for all work included within the project limits and all designated option borrow sites provided within the plans.

	STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL
		P TAPU (06)	3	51

Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials shall be buried in a trench

completely separate from wood debris. The final cover over the construction and/or demolition debris shall consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the State ROW shall be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor shall control the access to waste disposal sites not within the State ROW through the use of fences, gates, and placement of a sign or signs at the entrance to the site stating "No

2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period of time not to exceed the duration of the project. Prior to project completion, the waste shall be removed from view of the ROW or buried and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.



COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES (CONTINUED)

Action Taken/Required:

All earth disturbing activities not designated within the plans require review of cultural resources impacts. This work includes, but is not limited to: staging areas, borrow sites, waste disposal sites, and all material processing sites.

The Contractor shall arrange and pay for a cultural resource survey and/or records search. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another gualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review: however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor shall provide ARC with the following: a topographical map or aerial view on which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor shall submit the records search or cultural resources survey report and if the location of the site is within the current geographical or historic boundaries of any South Dakota reservation to SDDOT Environmental Engineer, 700 East Broadway Avenue, Pierre, SD 57501-2586 (605-773-3180). SDDOT will submit the information to the appropriate

SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

If evidence for cultural resources is uncovered during project construction activities, then such activities shall cease and the Project Engineer shall be immediately notified. The Project Engineer will contact the SDDOT Environmental Engineer in order to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for staging areas, borrow sites, waste disposal sites, or material processing sites that affect wetlands, threatened and endangered species, or waterways. The Contractor shall provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

GRADING OPERATIONS

Excavation and construction of Embankments including compaction requirements shall be performed in accordance with Section 120 of the Specifications.

The shared use path shall be completed to the elevations shown in the plans and in accordance with the typical sections. Horizontal and vertical alignments of the path may be altered if necessary at the Engineer's discretion.

All costs for excavation and construction of embankments shall be considered incidental to the contract unit price per cubic yard for Unclassified Excavation. The plans quantity for Unclassified Excavation shall be the basis of payment unless changes are directed by the Engineer.

UTILITIES

Utilities are not planned to be affected on this project. If utilities are identified near the improvement area through the SD one Call process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25, the Contractor shall contact the Project Engineer to determine medications that will be necessary to avoid utility impacts.

The Contractor shall be aware that the existing utilities shown in the plans were surveyed prior to the design of this project and might have been relocated or replaced by a new utility facility prior to construction of this project. It is anticipated that the utilities will not require adjustment and may remain in its current location. The Contractor shall contact each utility owner and confirm the status of all existing and new utility facilities. The following list identifies entities with utilities in the City of Mitchell.

(Name of Company) CENTURYLINK (Mailing Address) (City, State, Zip Code)

125 S. DAKOTA AVENUE SIOUX FALLS SD 57104

Contact Person: JEREMY STUDEMANN Telephone Number: (605) 339-5773

(Name of Company) (Mailing Address) (City, State, Zip Code)

MITCHELL TELECOM 1801 N. MAIN STREET MITCHELL SD 57301

JUSTIN THEISSE Contact Person: Telephone Number: (605) 990-1000

(Name of Company) (Mailing Address) (City, State, Zip Code)

Contact Person: Telephone Number: (800) 888-1300

(Name of Company) (Mailing Address) (City, State, Zip Code)

Contact Person: Telephone Number:

(Name of Company) (Mailing Address) (City, State, Zip Code)

Contact Person: Telephone Number:

(Name of Company) (Mailing Address) (City, State, Zip Code) MIDCONTINENT COMMUNICATIONS

1901 N. MAIN STREET MITCHELL SD 57301

JOHN ADAMS

NORTHWESTERN **514 NORTH MAIN STREET** MITCHELL SD 57301

> JAMIE HAJEK (605) 995-4410

CITY OF MITCHELL WATER 612 NORTH MAIN STREET MITCHELL SD 57301

RICHARD POLLREISZ (605) 995-8449

CITY OF MITCHELL SEWER 612 NORTH MAIN STREET MITCHELL SD 57301

Contact Person Telephone Nun

(Name of Comp (Mailing Addres (City, State, Zip

Contact Person **Telephone Num**

CLEARING

Before clearing activ determine the limits supposed to remain v Contractor, the Contractor shall replace them with the same size and type at the Contractor's expense.

TABLE OF UNCLAS

Excavation Topsoil

Place Topsoil Waste Material

PROCEDURES FOR QUANTITY

The plans quantity for Unclassified Excavation shall be the basis of payment unless changes are directed by the Engineer.

The Topsoil quantity in the Table of Unclassified Excavation is an estimate. The quantity of Topsoil from the cuts will be paid for twice as Unclassified Excavation, as it will be in both the Excavation and Topsoil quantities. This will be full compensation for Excavation, which includes necessary undercutting to provide space for placement of topsoil.

TABLE OF ASPHALT CONCRETE PAVEMENT REMOVAL

Station	to	Station	L/R	Quantity (SqYd)
3+69		6+28	L	172.7
28+10		28+13	L _	1.9
			Total:	174.6

		STATE OF	PROJECT	SHEET	TOTAL SHEETS
		DAKOTA	P TAPU (06)	4	51
			RI	EV 6-5-1	5 JDS
: nber:	JO (60	N VERN)5) 995-8	IEULEN 3446		
oany) ss) Code)	CI 612 MI	TY OF M 2 NORTI TCHELL	ITCHELL STREETS H MAIN STREET SD 57301		
: nber:	RC (60)N OLSC)5) 995-8	DN 3465		
ities begin of clearing within the li	, the for imits	e Contrac the projection of work	tor shall contact the Engi ct. If the trees or shrubs t are damaged or destroyed n with the same size and	neer to hat are by the	

		ALL
SIFIED EXCAV	ATION	PROFESSION A
-	1,200 CuYd 815CuYd	REG. NO.
Total	2,015CuYd	MecoRMICK
	815CuYd	DI TH DAYON T
	385 CuYd	6 5/15 munt
	G UNCLASSIFI	ED EXCAVATION

TABLE OF CONCRETE CURB AND GUTTER REMOVAL

				Quantity	
Station	to	Station	L/R	(Ft)	
0+75		0+85	R	10	
1+31		1+37	R	34	
1+55		1+59	R	29	
11+76		11+77	L/R	14	
12+22		12+24	L/R	14	
14+97		14+99	L/R	14	
15+44		15+46	L/R	14	
21+70		21+73	L/R	14	
22+01		22+03	L/R	14	
24+12		24+14	L/R	14	
24+35		24+37	L/R	14	
27+49		27+64	L/R	30	
28+05		28+05	L _	8	
			Total	223	

TABLE OF SIDEWALK REMOVAL

Station	to	Station	L/R	Quantity (SqYd)
1+57		1+63	L/R	26
			Total:	26

TABLE OF REMOVE CONCRETE PAVEMENT

Station	to	Station	L/R	Quantity (SqYd)
28+05		28+10	L	4.3
			Total:	4.3

SALVAGE, STORE, AND REPLANT TREES

The trees shall be salvaged prior to the start of any unclassified excavation work. Trees to be salvaged, stored and replanted may be replanted the same day that removal occurs. If any damage occurs to the tree during salvaging, transporting or replanting, the Contractor shall replace the tree with the same type and diameter tree which was damaged.

TABLE OF SALVAGE, STORE, AND REPLANT TREES

Salvage Replant				Quantity
Station	L/R	Station	L/R	(Each)
1+18	48' R	1+00	25' R	1
17+77	9' R	17+77	27' R	1
18+00	9' R	18+00	30' R	1
24+76	10' L	24+76	15' L	1
	Total:			4

REMOVE AND RELOCATE SIGN

The signs called out for removal and reset are MTI informational signs. Electrical conduit, wire and boxes will need to be moved with the signs. If the existing footing is damaged during removal the Contractor shall install a new footing for the sign. The sign shall be set level and at the bury depth with which it was removed.

TABLE OF REMOVE SIGN FOR RESET

		Quantity
Station	L/R	(Each)
14+92	10' L	1
22+07	8' L	1
	Total:	2

TABLE OF RESET SIGN

	Quantity		
Product	(Each)	L/R	Station
Detectable Warn	1	18' L	14+92
Cast Iron Pl	1	16' L	22+07
	2	Total:	

SPECIAL TYPE B CONCRETE CURB AND GUTTER

All concrete curb and gutter including P-Gutter shall be considered as Special Type B Concrete Curb and Gutter as shown on the plans.

TABLE OFSPECIALCONCRETE CURB AND GUTTER

Station to	Station	L/R	Quantity (Ft)
0+75.07	0+85.07	R	10.0
1+30.82	1+37.15	R	34.4
1+54.72	1+59.21	R	29.1
3+69.46	3+69.46	L	4.0
3+69.46	6+27.34	L	258.0
6+27.34	6+27.34	L	4.0
11+75.52	11+77.48	L/R	14.0
12+21.99	12+23.99	L/R	14.0
14+97.42	14+99.41	L/R	14.0
15+43.54	15+45.55	L/R	14.0
21+70.47	21+72.69	L/R	14.0
22+01.18	22+03.39	L/R	14.0
24+12.40	24+14.31	L/R	14.0
24+34.79	24+36.61	L/R	14.0
27+48.75	27+64.25	L/R	29.7
28+04.94	28+04.94	L _	15.0
		Total:	496.2

TYPE 1 DETECTABLE WARNINGS

Act regulations.

The detectable warnings shall be installed according to the manufacturer's installation instructions.

A concrete thickness equal to the adjacent concrete sidewalkthicknessand 4 inches of granular cushion material shall be placed below the Type 1Detectable Warnings. When concrete is placed below the detectable warnings then the concrete thickness shall be transitioned at the rate of 1" per foot to match the adjacent concrete sidewalk thickness.Cast iron plates may be a natural patina (weathered steel). When Type 1 Detectable Warnings are specified, the Contractor shall furnish and install only one of the products listed in the Type 1 Detectable Warnings table.

ing Plate late

Detectable Warning Plate Cast Iron Plate

Detectable Warning Plate Cast Iron Plate (No Coating)

> CAST-DWD Cast Iron Plate

STATE OF	PROJECT	SHEET	TOTAL SHEETS
DAKOTA	P TAPU (06)	5	51

Detectable warnings shall be in compliance with the Americans with Disability

Type 1 Detectable Warnings

Manufacturer Neenah Foundry Company Neenah, WI 800-558-5075 http://www.neenahfoundry.com/

Deeter Foundry Lincoln, NE 800-234-7466 http://www.deeter.com/

East Jordan Iron Works, Inc. 301 Spring Street East Jordan, MI 49727 800-626-4653 http://www.ejiw.com

> Key 3 Casting (Northern Foundry) 555 West 25th Street Hibbing, MN55746 218-263-8871 http://key3casting.com



TABLE OF TYPE1 DETECTABLE WARNINGS

		Quantity
Station	L/R	(SqFt)
0+75.91	55.58' R	20
1+33.17	27.91' R	20
1+60.42	27.89' R	20
3+87.47	6.00 L	10
11+74.42	0.00' L/R	20
12+24.96	0.00' L/R	20
14+96.42	0.00' L/R	20
15+46.54	0.00' L/R	20
21+69.59	0.00' L/R	20
22+04.29	0.00' L/R	20
24+11.35	0.00' L/R	20
24+37.73	0.00' L/R	20
27+60.02	0.00' L/R	20
28+09.94	5.07' L	12
	Total:	262

CONCRETE SIDEWALK

Fiber reinforcement shall be used in the M6 concrete sidewalk mix design. Collated fibrillated polypropylene fibers shall meet or exceed ASTM C-1116, ICBO #4151. The length of the fibers shall be 0.75" and have a specific gravity of 0.91. The absorption shall be Nil and have a melting point of 324 degrees Fahrenheit. The fibers shall be applied at a rate of 1.5 pounds per cubic yard and follow the manufacturer's recommendations for mixing.

Collated fibrillated polypropylene fibers shall be from the list below or an approved equal.

<u>Product</u>	<u>Manufacturer</u>
Fibermesh 300	Propex Concrete Systems Chattanooga TN, 37422 Phone: 1-423-892-8080 www.fibermesh.com
Grace Microfiber	Grace Concrete Products Eagan, MN 55121 Phone: 1-651-686-4477 <u>www.grace.com</u>

TABLE OF 5" CONCRETE SIDEWALK – 6 FOOT WIDTH

Station	to	Station	L/R	Quantity (SqFt)
28+06.94	ŀ	28+12.94	L	42.0
			Total:	42.0

TABLE OF 5" CONCRETE SIDEWALK - 10 FOOT WIDTH

				Quantity
Station	to	Station	L/R	(SqFt)
0+74.62		1+29.58	R	883.8
1+57.10		1+69.10	R	421.3
1+59.03		3+11.10	L/R	1509.7
6+52.86		7+50.00	L/R	971.2
7+50.00		9+32.25	L/R	1,844.3
10+00.00)	11+75.42	L/R	1,754.4
12+23.95	5	14+97.42	L/R	2,734.6
15+45.54	1	20+00.00	L/R	4,544.6
20+00.00)	21+70.58	L/R	1,705.8
22+03.29)	24+12.35	L/R	2,090.7
24+36.70)	27+62.36	L/R	3,263.5
			Total:	21,723.9
	F 5" (CONCRETE S	SIDEWALK – 12	2 FOOT WIDTH

				Quantity	
Station	to	Station	L/R	(SqFt)	
3+62.68		6+27.33	L/R	3181.7	
			Total:	3181.7	

TABLE OF 5" CONCRETE SIDEWALK – TRANSITION FROM 10 FOOT WIDTH TO 12 FOOT WIDTH

				Quantity
Station	to	Station	L/R	(SqFt)
3+11.10		3+62.68	L/R	573.9
6+27.33		6+52.86	L/R	280.9
			Total:	854.8

TABLE OF 8" CONCRETE SIDEWALK

Station	to	Station	L/R	Quantity (SqFt)
9+32.25		10+00.00	L/R	1,012.5
			Total:	1,012.5

SIDEWALK DRAINS

At the locations noted in the Table of Sidewalk Drains, the areas draining to the sidewalk will have the drainage carried through the sidewalk drains to the current drainage path. The sidewalk drains shall be constructed in accordance with the details shown on Standard Plate 651.50.

TABLE OF SIDEWALK DRAINS

				Length	
Station	to	Station	L/R	(Ft)	
1+58.71		1+69.21	R	10.5	
4+58.31		4+58.31	L/R	12.5	
9+33.64		9+33.64	L/R	11.5	
			Totals:	34.5	

Mineral aggregate f
requirements for Cla
for Asphalt Concrete
mixture shall be PG

TABLE OF ASPHALT CONCRETE COMPOSITE

Station	to	Station	L/R	Quantity (Ton)
3+69		6+28	L _	30.1
			Total:	30.1

BASE COURSE

TABLE OF BASE COURSE

			Quantity
Station to	Station	L/R	(Ton)
0+75.07	0+85.07	R	0.7
1+30.82	1+37.15	R	3.6
1+54.72	1+59.21	R	3.1
3+69.46	3+69.46	L	0.4
3+69.46	6+27.34	L	81.5
6+27.34	6+27.34	L	0.4
11+75.52	11+77.48	L/R	1.5
12+21.99	12+23.99	L/R	1.5
14+97.42	14+99.41	L/R	1.5
15+43.54	15+45.55	L/R	1.5
21+70.47	21+72.69	L/R	1.5
22+01.18	22+03.39	L/R	1.5
24+12.40	24+14.31	L/R	1.5
24+34.79	24+36.61	L/R	1.5
27+48.75	27+64.25	L/R	3.1
28+04.94	28+04.94	L _	1.1
		Total:	105.9

ADJUST WATER VALVE BOX

Station	L/R
9+42.22	11.80' R
9+47.43	20.04' R
25+22.78	14.38' L

Total

STATE OF	PROJECT	SHEET	TOTAL
SOUTH DAKOTA	P TAPU (06)	6	51

. . . .

ASPHALT CONCRETE COMPOSITE

REV 5-29-15JDS

for the Asphalt Concrete Composite shall conform to the ass E, Type 1. All other requirement in the Specifications te Composite shall apply. The asphalt binder used in the 64-22 Asphalt Binder.

Existing base course under the existing curb and gutter and asphalt surfacing shall remain in place and recompacted prior to placement of new concrete curb and gutter or asphalt concrete composite. If sufficient base course is not present, new base course shall be used. The following quantities have been provided if sufficient base course is not available.

Quantity

(Each)

1

1

1

3

ROFESS/
P. HEG. NO. 7
JEFFRENCE MCCT
COUTH DAK
5/29/15 1000000

PLACING TOPSOIL

The thickness will be approximately 6inches.

The estimated amount of topsoil to be placed is as follows:

				Topsoil
Station	to	Station	L/R	(CuYd)
0+75		1+35	R	18
1+64		3+70	L	30
1+69		7+00	R	66
6+27		7+00	L	15
7+00		11+75	L/R	161
12+24		14+97	L/R	86
15+45		21+70	L/R	246
22+03		24+12	L/R	63
24+36		27+61	L/R	130
			Total:	815

DRILLS

In addition to the drills specified in Section 730 of the Specifications, other types of drills including no-till drills will be allowed as long as they have baffles, partitions, agitators, or augers which keep the seed distributed throughout the seed box and the seed is planted at a depth of $\frac{1}{4}$ " to $\frac{1}{2}$ ".

MYCORRHIZAL INOCULUM

Mycorrhizal inoculum shall consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier shall provide certification of the fungal species claimed and the live propagule count. The inoculum shall include the following fungal species:

Glomus intraradices	25%
Glomus aggregatu	25%
Glomus mosseae	25%
Glomus etunicatum	25%

All seed shall be inoculated by the seed supplier with a minimum of 20,000 live propagules of mycorrhizal fungi per 1,000 square feet. All costs of inoculating the seed shall be incidental to the contract unit price per pound for the corresponding permanent seed mixture.

The mycorrhizal inoculum shall be as shown below or an approved equal:

Product

Manufacturer

MycoApply

Mycorrhizal Applications, Inc. Grants Pass, OR Phone: 1-866-476-7800 http://www.mycorrhizae.com/

PERMANENT SEEDING

The areas to be seeded consistof all newly graded areas within the project limits except for the top of roadways and the shared use path.

All permanent seed shall be planted in the topsoil at a depth of $\frac{1}{4}$ " to $\frac{1}{2}$ ".

All seed broadcast must be raked or dragged in (incorporated) within the top $\frac{1}{4}$ " to $\frac{1}{2}$ " of topsoil when possible. This requirement may be waived by the Engineer during construction when raking or dragging is deemed not feasible by conventional methods.

The varieties listed for the seed mixture are preferred varieties. Native harvest seed will be allowed.

41,118 square feet of newly graded areas are to be seeded.

Type D Permanent Seed Mixture shall consist of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/1000 SqFt)
Kentucky Bluegrass	Avalanche, Appalachian, Wildhorse, Blue Bonnet	1.4
Perennial Ryegrass	Turf Type Varieties	1.4
Creeping Red Fescue	Epic, Boreal	1.4
Chewings Fescue	Ambrose, K2, VNS, Zodiac	1.4
Alkali Grass	Fults, Fults II, Quill, Salty	1.4
	Total:	7

FERTILIZING

The Contractor shall apply an all-natural slow release fertilizer prior to seeding or placing sod. The all-natural fertilizer shall have a minimum guaranteed analysis of 4-6-4 and be USDA Certified BioBased. It should provide a minimum of 4% (N) nitrogen with a minimum water insoluble nitrogen (WIN) fraction of 3.2%, a minimum of 6% (P2O5) available phosphate, a minimum of 4% (K2O) soluble potash, and a maximum carbon to nitrogen ratio (C:N ratio) of 5:1. The all-natural fertilizer shall be free of weed-seed and pathogens accomplished through thermophilic composting, and not mechanical or chemical sterilization, to assure presence of beneficial soil microbiology. The fertilizer shall have a near neutral pH, a low salt index, a low biological oxygen demand, contain organic humic and fulvic acids, and have high aerobic organism counts. The fertilizer shall also be stable, free of bad odors, and be unattractive as a food source for animals. It should also be in a granular form that is easily spread.

The all-natural slow release fertilizer shall be applied according to the manufacturer's application recommendations.

The application rate is 34 pounds per 1,000 square feet.

The all-natural slow release fertilizer shall be from the list below or an approved equal:

<u>Product</u> Sustane

FIBER MULCHING

Fiber mulch shall b seeding.

Fiber mulch shall be applied at the rate of 3000 pounds per acre.

The Contractor shall allow the fiber mulch to cure a minimum of 18 hours prior to watering or any storm event to ensure proper cohesion between the soil and fiber particles.

The fiber mulch provided shall be from the approved product list. The approved product list for fiber mulch may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

TABLE OF FIBER MULCHING

				Quantity
Station	to	Station	L/R	(Lb)
0+75		1+35	R	59.6
1+64		3+70	L	103.0
1+69		7+00	R	50.3
6+27		7+00	L	227.1
7+00		11+75	L/R	566.3
12+24		14+97	L/R	298.4
15+45		21+70	L/R	859.0
22+03		24+12	L/R	217.5
24+36		27+61	L/R	450.7
			Total:	2831.8

	STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL
		P TAPU (06)	7	51

Manufacturer

Sustane Corporate Headquarters Cannon Falls, Minnesota Phone: 1-800-352-9245 http://www.sustane.com/

Fiber mulch shall be applied in a separate operation following permanent



HIGH FLOW SILT FENCE

The high flow silt fence fabric provided shall be from the approved product list. The approved product list for high flow silt fence may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

High flow silt fence shall be placed at the locations noted in the table and at locations that will minimize siltation of adjacent streams, lakes, dams, or drainage areas as determined by the Engineer during construction. Refer to Standard Plate 734.05 for details.

TABLE OF HIGH FLOW SILT FENCE

			Quantity
Station	L/R	Location	(Ft)
9+94	R	Pipe Invert	15
12+44	R	Pipe Invert	15
15+52	R	Pipe Invert	15
21+52	R	Pipe Invert	15
23+96	R	Pipe Invert	15
27+31	R	Pipe Invert	15
		Total	00

Total: 90

MUCKING SILT FENCE

Mucking silt fence shall consist of removing muck trapped by the silt fence and spreading the material evenly over the adjacent area to conform to the existing grade.

REMOVE SILT FENCE

Silt fence shall be removed when vegetation is established. Some or all of the silt fence may be left on the project until vegetation is established.

TABLE OF CONSTRUCTION STAKING

(See Special Provision for Contractor Staking)

						Gra	de Staking		
Roadway and Description	Begin Station	End Station	Number of Lanes	Length (Ft)	Length (Mile)	Lane Factor	*Sets of Stakes	**Grade Staking Quantity (Mile)	Miscellaneous Staking Quantity (Mile)
MTI Shared use Path	00+74.62-55.72' R	28+09.94-11.07' L	1	2811.00	0.532	1.0	1	0.532	0.532
							Totals:	0.532	0.532

* 1 -Blue top Stakes Only

** Grade Staking Quantity- (Length) x (Lane Factor) x (Sets of Stakes)

GENERAL MAINTENANCE OF TRAFFIC

Removing, relocating, covering, salvaging and resetting of existing traffic control devices, including delineation, shall be the responsibility of the Contractor. Cost for this work shall be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost shall be replaced by the Contractor at no cost to the State.

Storage of vehicles and equipment shall be outside the clear zone and as near as possible to the right-of-way line. Contractor's employees should mobilize at a location off the right-of-way and arrive at the work sites in a minimum number of vehicles necessary to perform the work.

Indiscriminate driving and parking of vehicles within the right-of-way will not be permitted. Any damage to the vegetation, surfacing, embankment, delineators and existing signs resulting from such indiscriminate use shall be repaired and/or restored by the Contractor, at no expense to the State, and to the satisfaction of the Engineer.

The Contractor shall provide documentation that all breakaway sign supports comply with NCHRP Report 350 or MASH crash-worthy requirements. The Contractor shall provide installation details at the preconstruction meeting for all breakaway sign support assemblies.

TRAFFIC CONTROL

There are three access points which allow traffic to enter the parking areas for the MTI Housing, Technology Center and the Administration Center. Access must be maintained to the MTI Housing, Technology Center and the Administration Center. The Contractor shall coordinate his work to allow one access point at all times to these facilities. The work directly south of the MTI Housing shall not block access to the parking lot. Traffic Control Drums will be utilized to protect traffic entering and leaving MTI Housing parking lot. Work shall be completed on one side of the street before starting work on the opposite side of the street into the MTI Housing. Traffic Control Drums will also be utilized south of the Utility Building to direct vehicles and pedestrians around the improvements.

PERMANENT PAVEMENT MARKING

All areas to be painted shall be thoroughlybroomed prior to placement of any permanent paint to the satisfaction of the Engineer. Completed sections of permanent pavement markings shall be completed prior to opening to traffic.

PERMANENT SIGNING

The Contractor shall furnish all signs, posts, stiffeners, bases, hardware, and labor for installation of permanent signs in size, type, and quantity as shown in these plans and/or as required by the Engineer.

The Contractor shall provide all labor and equipment necessary to install permanent signing, remove existing signs, and reset existing signs as detailed in these plans and/or as required by the Engineer. Payment for furnishing and installing permanent signs will be paid for at the contract unit price for each type of sign based on sheeting requirements per square foot of sign. All signs shall have Type IV (High Intensity) or Type XI (Super/Very High Intensity). Payment for new signposts, hardware, bases, and labor will be made at the contract unit price per foot for 2.0" x 2.0" perforated tube post. Breakaway post details regarding posts, hardware, and bases shall be followed as per the manufacturer's recommendations. Measurement of post lengths for payment will be for above ground post lengths as field measured. The sign post contract items shall include post bases and all hardware. The lengths of the posts in the sign tables are approximate lengths only. The post lengths shall be verified by the Contractor. The Contractor is urged to cut posts to length on job site after verification of post length.

The Contractor shall use Telespar brand (or equivalent) posts and bases on all new standard highway signs as approved by the Engineer. All post materials shall conform to Section 982 of the Specifications, and be in accordance with 4 foot long base assembly with a shear breakaway base connecting the base to the signpost. The height of the post shall not exceed the minimum height needed by more than 0.5 feet. Any portion that extends above the sign shall be cut off. All posts and bases shall be accompanied by Certificates of Compliance and shall meet all safety standards as set forth in the current edition of the Manual on Uniform Traffic Control Devices (MUTCD).

The Contractor shall stake the signs and Engineer will verify the locations prior to installation. The lateral distance from the pathway and the height of the sign shall be established by the Contractor according to the Permanent Signing Typicals, as well as the Standard Plates in the Plans and MUTCD.

STATE OF	PROJECT	SHEET	TOTAL
SOUTH DAKOTA	P TAPU (06)	8	51

REV 5-29-15 JDS



TYPICAL SECTIONS



Sta. 3+62.68 to 6+27.33

				TOTAL
	STATE OF SOUTH		SHEET	SHEETS
	DAKOTA	F 1APU (00)	9	51
4.1 M	atch			
711				
4:1 N	Match			
ered to				
ile				
en 10' to 12	,			
3+62.68				
0+32,00				
2.0'				
		4:1 Match		
6:1	<			
		4:1 Match		
\backslash				
└─ This poin	t refered	to		
	V PLOTILE		11112	
		ROFESS/C	N	
		REG. NO.	γ	た
				Å
		JERRAN JERRAN	Mille	
		MACORMIC	K	
		He OUTH NAKO		IIII.
			$-\delta^{2}$	
		3/27/15	ANNIN TANK	
		8.44000000	.	

TYPICAL SECTIONS



Sta. 9+32.25 to 10+00.00

	STATE OF	PROJECT	SHEET	TOTAL SHEETS
	SOUTH DAKOTA	P TAPU (06)	10	51
		RE	√ 5-29-1	5 NAP
	atch			
4:1 1				
4:1 N	Match			
d to				
			1111	
		WIND ROFESS/	ON .M.	
		NO SEG. NO		
		8471	1. 1	
		JEFFREME	A int	5
			13 H	
		TH DAK):	
		Ally Elacht	5III	,
		39/11/1 3/27/1 9>11/11/1	mmm.	
		Q	-	

	ITEMIZED LIST FOR TRAFFIC CONTROL											
	SIGN CODE	SIGN SIZE	NUMBER REQUIRED	UNITS PER SIGN	UNITS							
1	W20-1	48"x48"	Road Work Ahead	2	34	68						
2	G20-2	36"x18"	End Road Work	2	17	34						
3	R1-1	30"x30"	Stop Sign	2	21	42						
4/4a	R11-2	48"x30"	Road Closed	6	27	162						
-	_	_	Type III Barricade-8' Double Sided	16	56	896						
					TOTAL	1202						

The itemized list for traffic control bid items reflects two access closures to the MTI Housing, Technology Center and Administration Center. Relocation of signs shall be considered incidental to traffic control, miscellaneous.



NOTE: The direction of stripes on type 3 barricades for each road closure shall be oriented to meet the requirements of the MUTCD latest edition.

BEGIN P TAPU (06)⁻ SHARED USE PATH, GRADING, CURB AND GUTTER, CONCRETE

NOTE: The W20-1, G20-2 and R1-1 signs are fixed location signs and should have ground mounted supports.



STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	P TAPU (06)	11	51

Cones, Drums, Type II Barricades or Fencing Shall be used to block Driveway Entrances, Alleys and Turn lanes as needed during Construction. Miscellaneous Safety devices Shall be Incidental to the contract lump sum price for "Traffic Control, Miscellaneous."

Six (6) traffic control drums shall be utilized to direct traffic around the work into the MTI housing parking lot. The drums shall be spaced no greater then six (6) feet apart.











STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

STORM WATER POLLUTION PREVENTION PLAN CHECKLIST

The numbers right of the title headings are**reference numbers** to the <u>GENERAL</u> PERMIT FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES

- ✤ SITE DESCRIPTION (4.2 1)
- > Project Limits: See Title Sheet (4.2 1.b)
- Project Description: See Title Sheet (4.2 1.a.)
- > Site Map(s): See Title Sheet and Plans (4.2 1.f. (1)-(6))
- > Major Soil Disturbing Activities (check all that apply)
- Clearing and grubbing
- Excavation/borrow
- Grading and shaping
- 🗍 Filling
- Cutting and filling
- Other (describe): > Total Project Area 3.2 Acres (4.2 1.b.)
- > Total Area To Be Disturbed 2.7 Acres (4.2 1.b.)
- > Existing Vegetative Cover (%) 95%
- > Soil Properties: N/A, no soil borings were taken
- Classification N/A (4.2 1. d.)
- > Name of Receiving Water Body/Bodies James River (4.2 1.e.)

✤ ORDER OF CONSTRUCTION ACTIVITIES (4.2 1.c.)

- (Stabilization measures shall be initiated as soon as possible, but in no case later than 14 days after the construction activity in that portion of the site has temporarily or permanently ceased. Initiation of final or temporary stabilization may exceed the 14-day limit if earth disturbing activities will be resumed within 21 days.)
- > Special sequencing requirements (None)
- > Install perimeter protection where runoff sheets from the site.
- > Install channel and ditch bottom protection.
- > Clearing and grubbing.
- > Remove and store topsoil.
- > Stabilize disturbed areas.
- > Complete final grading.
- > Complete shared use path and curb and gutter.
- > Complete traffic control installation and protection devices.
- > Reseed areas disturbed by removal activities.
- * EROSION AND SEDIMENT CONTROLS (4.2 2.a.(1)(a)-(f)) (Check all that apply)
- > Stabilization Practices (See Detail Plan Sheets)
- Temporary Seeding (Cover Crop Seeding)
- X Permanent Seeding
- Soddina
- Planting (Woody Vegetation for Soil Stabilization)
- Mulching (Grass Hay or Straw)
- Hydraulic Mulch (Wood Fiber Mulch)
- Soil Stabilizer
- Bonded Fiber Matrix
- Erosion Control Blankets or Mats
- Uegetation Buffer Strips
- Roughened Surface (e.g. tracking)
- Dust Control
- Other:

- > Structural Temporary Erosion and Sediment Controls
- Silt Fence
- Floating Silt Curtain
- Straw Bale Check
- Temporary Berm
- Temporary Slope Drain
- Straw Wattles or Rolls
- Turf Reinforcement Mat
- Gabions
- Rock Check Dams
- Sediment Traps/Basins
- Inlet Protection
- Outlet Protection
- Surface Inlet Protection (Area Drain)
- Curb Inlet Protection
- Stabilized Construction Entrances
- Entrance/Exit Equipment Tire Wash
- Interceptor Ditch
- Concrete Washout Area
- Temporary Diversion Channel
- Work Platform
- Temporary Water Barrier
- Temporary Water Crossing
- 🗌 Other:
- > Wetland Avoidance

Will construction and/or erosion and sediment controls impinge on regulated wetlands? Yes- No If yes, the structural and erosion and sediment controls have been included in the total project wetland impacts and have been included in the 404 permit process with the USACE.

> Storm Water Management (4.2 2.b., (1) and (2))

Storm water management will be handled by temporary controls outlined in "EROSION AND SEDIMENT CONTROLS" above, and any permanent controls needed to meet permanent storm water management needs in the post construction period. Permanent controls will be shown on the plans and noted as permanent.

- > Other Storm Water Controls (4.2 2.c., (1) and (2))
- Waste Disposal

All liquid waste materials will be collected and stored in sealed metal containers approved by the project engineer. All trash and construction debris from the site will be deposited in the approved containers. Containers will be serviced as necessary, and the trash will be hauled to an approved disposal site or licensed landfill. All onsite personnel will be instructed in the proper procedures for waste disposal, and notices stating proper practices will be posted in the field office. The general contractor's representative responsible for the conduct of work on the site will be responsible for seeing waste disposal procedures are followed.

Hazardous Waste

All hazardous waste materials will be disposed of in a manner specified by local or state regulations or by the manufacturer. Site personnel will be instructed in these practices, and the individual designated as the contractor's on-site representative will be responsible for seeing that these practices are followed.

Sanitary Waste

Portable sanitary facilities will be provided on all construction sites. Sanitary waste will be collected from the portable units in a timely manner by a licensed waste management contractor or as required by any local regulations

- Silt fence will be inspected for depth of sediment and for tears in order to ensure the fabric is securely attached to the posts and that the posts are well anchored.Sediment buildup will be removed from the silt fence when it reaches 1/3of the height of the silt fence.
- Sediment basins and traps will be checked. Sediment will be removed when depth reaches approximately 50 percent of the structure's capacity, and at the conclusion of the construction. Check dams will be inspected for stability. Sediment will be removed
- when depth reaches 1/2 the height of the dam.
- All seeded areas will be checked for bare spots, washouts, and vigorous growth free of significant weed infestations. Inspection and maintenance reports will be prepared on form DOT 298
- for each site inspection, this form will also be used to document changes to the SWPPP. A copy of the completed inspection form will be filed with the SWPPP documents.

* Non-Storm Water Discharges (3.0)

- this project (check all that apply).
- materials have occurred.

Detergents

Paints

> Metals

≻ □ Wood

Texture

> Other:

> 🛛 Cure

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	P TAPU (06)	16	51
		√ 5-29-1	5 NAP

* Maintenance and Inspection (4.2 3. and 4.2 4.)

Maintenance and Inspection Practices

- Inspections will be conducted at least one time per week and after a storm event of 0.50 inches or greater.
- All controls will be maintained in good working order. Necessary repairs will be initiated within 24 hours of the site inspection report.

- The SDDOT Project Engineer and contractor's site superintendent are responsible for inspections. Maintenance, repair activities are the responsibility of the contractor. The SDDOT Project Engineer will
- complete the inspection and maintenance reports and distribute copies per the distribution instructions on DOT 298.

- The following non-storm water discharges are anticipated during the course of
- Discharges from water line flushing.
- > D Pavement wash-water, where no spills or leaks of toxic or hazardous
- Uncontaminated ground water associated with dewatering activities.

* Materials Inventory (4.2. 2.c.(2))

- The following materials or substances are expected to be present on the site during the construction period. These materials will be handled as noted under the headings "EROSION AND SEDIMENT CONTROLS" and "SPILL PREVENTION" (check all that apply). Concrete and Portland Cement
- > X Bituminous Materials Petroleum Based Products Cleaning Solvents
- Chemical Fertilizers



Spill Prevention (4.2 2.c.(2))

> Material Management

- Housekeeping
- Only needed products will be stored on-site by the contractor.
- Except for bulk materials the contractor will store all materials under cover and in appropriate containers.
- Products must be stored in original containers and labeled.
- Material mixing will be conducted in accordance with the manufacturer's recommendations
- When possible, all products will be completely used before properly disposing of the container off site.
- The manufacturer's directions for disposal of materials and containers will be followed
- The contractor's site superintendent will inspect materials storage areas regularly to ensure proper use and disposal.
- Dust generated will be controlled in an environmentally safe manner.
- Vegetation areas not essential to the construction project will be preserved and maintained as noted on the plans.

Hazardous Materials

- Products will be kept in original containers unless the container is not resealable.
- Original labels and material safety data sheets will be retained in a safe place to relay important product information.
- · If surplus product must be disposed of, manufacturer's label directions for disposal will be followed.
- Maintenance and repair of all equipment and vehicles involving oil changes, hydraulic system drain down, de-greasing operations, fuel tank drain down and removal, and other activities which may result in the accidental release of contaminants will be conducted on an impervious surface and under cover during wet weather to prevent the release of contaminants onto the ground.
- Wheel wash water will be collected and allowed to settle out suspended solids prior to discharge. Wheel wash water will not be discharged directly into any storm water system or storm water treatment system.
- Potential pH-modifying materials such as: bulk cement, cement kiln dust, fly ash, new concrete washings, concrete pumping, residuals from concrete saw cutting (either wet or dry), and mixer washout waterswill be collected on site and managed to prevent contamination of storm water runoff

> Product Specific Practices (6.8)

Petroleum Products

All on-site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

Fertilizers

Fertilizers will be applied only in the amounts specified by the SDDOT. Once applied, fertilizers will be worked into the soil to limit the exposure to storm water. Fertilizers will be stored in an enclosed area. The contents of partially used fertilizer bags will be transferred to sealable containers to avoid spills.

Paints

All containers will be tightly sealed and stored when not required for use. The excess will be disposed of according to the manufacturer's instructions and any applicable state and local regulations.

Concrete Trucks

Contractors will provide designated truck washout areas on the site. These areas must be self contained and not connected to any storm water outlet of the site. Upon completion of construction washout areas will be properly stabilized.

> Spill Control Practices (4.2 2 c.(2))

In addition to the previous housekeeping and management practices, the following practices will be followed for spill prevention and cleanup if needed.

- For all hazardous materials stored on site, the manufacturer's recommended methods for spill clean up will be clearly posted. Site personnel will be made aware of the procedures and the locations of the information and cleanup supplies.
- Appropriate cleanup materials and equipment will be maintained by the contractor in the materials storage area on-site. As appropriate, equipment and materials may include items such as brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for clean up purposes.
- All spills will be cleaned immediately after discovery and the materials disposed of properly.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- After a spill a report will be prepared describing the spill, what caused it, and the cleanup measures taken. The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring, as well as clean up instructions in the event of reoccurrences.
- The contractor's site superintendent, responsible for day-to-day operations, will be the spill prevention and cleanup coordinator. The contractor is responsible for ensuring that the site superintendent has had appropriate training for hazardous materials handling, spill management, and cleanup.
- > Spill Response (4.2 2 c.(2))

The primary objective in responding to a spill is to quickly contain the material(s) and prevent or minimize migration into storm water runoff and conveyance systems. If the release has impacted on-site storm water, it is critical to contain the released materials on-site and prevent their release into receiving waters. If a spill of pollutants threatens storm water or surface water at the site, the spill response procedures outlined below must be implemented in a timely manner to prevent the release of pollutants.

- The contractor's site superintendent will be notified immediately when a spill or the threat of a spill is observed. The superintendent will assess the situation and determine the appropriate response.
- If spills represent an imminent threat of escaping erosion and sediment controls and entering receiving waters, personnel will be directed to respond immediately to contain the release and notify the superintendent after the situation has been stabilized.
- Spill kits containing appropriate materials and equipment for spill response and cleanup will be maintained by the contractor at the site.
- If oil sheen is observed on surface water (e.g. settling ponds, detention ponds, swales), action will be taken immediately to

- remove the material causing the sheen. The contractor will use appropriate materials to contain and absorb the spill. The source of the oil sheen will also be identified and removed or repaired as necessary to prevent further releases.
- If a spill occurs the superintendent or the superintendent's designee will be responsible for completing the spill reporting form and for reporting the spill to SD DENR.
- Personnel with primary responsibility for spill response and clean up will receive training by the contractor's site superintendent or designee. The training must include identifying the location of the spill kits and other spill response equipment and the use of spill response materials
- Spill response equipment will be inspected and maintained as necessary to replace any materials used in spill response activities.

* Spill Notification

- In the event of a spill, the contractor's site superintendent will make the appropriate notification(s), consistent with the following procedures: > A release or spill of a regulated substance (includes petroleum and petroleum products) must be reported to DENR immediately if any one of the following conditions exists:
- · The discharge threatens or is in a position to threaten the waters of the state (surface water or ground water).
- The discharge causes an immediate danger to human health or safety.
- The discharge exceeds 25 gallons.
- The discharge causes a sheen on surface water. The discharge of any substance that exceeds the ground water quality
- 74:51:01.
- The discharge of any substance that exceeds the surface water quality standards of ARSD chapter 74:51:01.
- The discharge of any substance that harms or threatens to harm wildlife or aquatic life.
- The discharge of crude oil in field activities under SDCL (South Dakota Codified Laws) chapter 45-9 is greater than 1 barrel (42 gallons).

hours (8 a.m. to 5 p.m. Central time). To report the release after hours, on weekends or holidays, call State Radio Communications at 605-773-3231. Reporting the release to DENR does not meet any obligation for reporting to other state, local, or federal agencies. Therefore, the responsible person must also contact local authorities to determine the local reporting requirements for releases. DENR recommends that spills also be reported to the National Response Center at (800) 424-8802.

Construction Changes (4.4)

When changes are made to the construction project that will require alterations in the temporary erosion controls of the site, the Storm Water Pollution Prevention Plan (SWPPP) will be amended to provide appropriate protection to disturbed areas, all storm water structures, and adjacent waters. The SDDOT Project Engineer will modify the SWPPP plan (DOT 298) and drawings to reflect the needed changes. Copies of changes will be routed per DOT 298. Copies of forms and the SWPPP will be retained in a designated place for review over the course of the project.

	STATE OF	PROJECT	SHEET	TOTAL SHEETS
	DAKOTA	P TAPU (06)	17	51
_				

- standards of ARSD (Administrative Rules of South Dakota) chapter
- To report a release or spill, call DENR at 605-773-3296 during regular office



* CERTIFICATIONS

> Certification of Compliance with Federal, State, and Local Regulations

The Storm Water Pollution Prevention Plan (SWPPP) for this project reflects the requirements of all local municipal jurisdictions for storm water management and sediment and erosion control as established by ordinance, as well as other state and federal requirements for sediment and erosion control plans, permits, notices or documentation as appropriate.

> South Dakota Department of Transportation

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Authorized Signature (See the General Permit, Section 6.7.1.C.)

> Prime Contractor

This section is to be executed by the General Contractor after the award of the contract. This section may be executed any time there is a change in the Prime Contractor of the project.

I certify under penalty of law that this document and all attachments will be revised or maintained under my direction or supervision in accordance with a system designed to assure that gualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Authorized Signature

*** CONTACT INFORMATION**

- > Contractor Information:
- Prime Contractor Name:
- Contractor Contact Name:
- Address:
- Address:
- City: State: Zip:
- Office Phone: Field[.]
- Cell Phone: Fax:
- > Erosion Control Supervisor
- Name:
- Address:
- Address:
- Zip: City: State:
- Office Phone: Field:
- Cell Phone: Fax:
- > SDDOT Project Engineer
- Name:
- Business Address:
- Job Office Location:
- City: State: Zip:
- Office Phone: Field:
- Cell Phone: Fax:
- > SD DENR Contact Spill Reporting
- Business Hours Monday-Friday (605) 773-3296
- Nights and Weekends (605) 773-3231
- > SD DENR Contact for Hazardous Materials.
- (605) 773-3153
- > National Response Center Hotline
- (800) 424-8802.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	P TAPU (06)	18	51
	ATTERNAL CONTRACTOR OF THE OWNER OWNER OF THE OWNER	111.	
	NTROFESS/C	A MARA	
	The second second		
	SAL ANTINA		
	JE FRANK	AMU	
	Adden Macormic	K S	
	TIP Some in		
	H DAKO	• 5	2 ²⁷
	3/27/15		*
	~ >> Manumm	11111.	

										STATE OF	PROJECT	SHEET	TOTAL SHEETS
										DAKOTA	P TAPU (06)	19	51
			HOR	IZON	ГAL A	LIGN	MENT DA	ГА	-				
NO.	BEARING	DELTA	TANGENT	EXTERNAL	LENGTH	RADIUS	P.C.	P.I.	P.T.	7			
1	 S 75°54'02" W								0+74.62-55.72 R	-			
2		88°13'37" Rt	39.16'	11.82'	24.76'	30.0'	1+00.76-54.75 Rt	1+29.82-28.11 Rt	1+29.46-28.11 R	-			
3	S 80°43'02" W							• = • •	1+64.42-27.93 R	-			
4	S 9°47'23" W			+ +					1+64.03	-			
5	S 81°01'13" W			++					1+77.56	-			
6		41°02'15" Rt	29.04'	2.03'	21.49'	30.0'	1+77.56	1+88.55	1+99.33	1			
7	S 39°58'58" W								2+09.05				
8		21°37'17" Lt	14.15'	.54'	11.19'	20.0'	2+09.05	2+14.69	2+20.30	1			
9	S 61°36'15" W								3+11.09	1			
10		122°50'21" Rt	26.61'	8.56'	47.49'	45.0'	3+11.09	3+36.88	3+61.12	1			
11	S 04°04'28" E								8+90.23	1			
12		93°59'16" Lt	3.48'	.12'	4.448'	25.0'	8+90.23	8+91.96	8+93.71				
13	S 10°43'24" E					<u> </u>			9+25.73	1			
14		131°5'18" Rt	30.55'	6.46'	46.03'	35.0'	9+25.73	9+50.85	9+57.97	1			
15	S 87°02'48" E								15+57.76				
16		95°39'16" Lt	2.48'	.12'	4.47'	25.0'	15+57.76	16+60.14	15+57.76				
17	S 81°12'27" E								15+77.96				
18		84°20'44" Rt	2.48'	.12'	4.93'	25.0'	15+77.96	15+80.43	15+82.89	1			
19	N 87°29'00" E								17+00.61	1			
20		81°29'05" Rt	3.74'	.55'	7.4'	25.0'	17+00.61	17+04+38	17+08.09	1			
21	N 70°27'11" E								18+28.65				
22		98°30'55" Lt	3.74'	.28'	7.4'	25.0'	18+28.65	18+32.36	18+36.08	1			
23	N 87°29'00" E								18+84.69	1			
24		84°28'57" Rt	6.03'	.12'	4.81'	25.0'	18+84.69	18+86.92	20+80.41	1			
25	N 81°28'53" E								20+80.41	1			
26		84°28'57" Rt	2.23'	.12'	4.63'	25.0'	20+80.41	20+89.32	20+85.04				
27	N 87°29'00" E								22+25.40	1			
28		80°2'14" Rt	4.13'	.38'	8.65'	25.0'	22+25.40	22+29.75	22+34.09				
29	N 67°33'28" E								22+61.99	1			
30		80°2'14" Lt	5.06'	.38'	8.65'	25.0'	22+61.99	22+66.34	22+70.68	1			
31	N 87°29'00" E								23+40.71				
32		98°55'7" Lt	8.87'	.31'	7.75'	25.0'	23+40.71	23+44.60	23+48.49				
33	S 74°40'46" E								23+81.45	1			
34		81°4'53" Rt	3.47'	.31'	7.57'	25.0'	23+81.45	23+85.34	23.89.05		WIND SEESS	111111111 ····	
35	S 87°29'00" E								24+56.28	1	, PRUFLUU,	ONT	L
36		86°44'19" Rt	4.39'	.63'	11.04'	25.0'	24+56.28	24+61.85	24+67.41	1	A. REG. NO.	••••	唐
37	N 61°58'43" E								25+03.63	1	SA 1 8771	n// t	
38	i	81°12'20" Rt	7.19'	.53'	14.43'	25.0'	25+03.63	25+10.87	25+18.11			PAME	
39	N 78°34'02" E								26+58.97	1	ALLAN MACORMI	CK	
40		85°15'43" Lt	4.02'	.17'	8.14'	25.0'	26+58.97	26+63.10	26+67.12	1	He South and	\mathcal{A}^{T}	
41	N 88°02'36" E								27+32.31	1	A DAG		, xx
42	N 01°57'24" W								28+09.94	1	* 3/27/1	5-111111	
43	S 88°02'37" W								28+09.94-11.07'L		- Manunal		
		<u> </u>		<u> </u>		L							

CONTROL DATA

	CONTROL POINT DATA												
POINT	STATION & OFFSET		NORTHING	EASTING	ELEVATION	DESC.							
BM1	15+10 - 369 L	Top Nut Fire Hydrant SE Tech. Center	502690.101	2584642.018	1352.27	ТВМ							
BM2	27+32 - 46.82 R	Top Nut Fire Hydrant South Admin. Bldg.	502372.767	2585906.834	1353.54	ТВМ							

The coordinates shown on this sheet are based on the South Dakota State Plane Coordinate System. South Zone NAD 83/(1996) SF=0.99990834

The elevations shown on this sheet are based on NGVD/29.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	P TAPU (06)	20	51
		18.	
	MAN OFESS/C	λ_{Λ}	
	ANT PHOTOS	VA/	
	REU. NO		
		allit	が フ
			\tilde{D}
	TH DAKO	• 🔿	
	2/17/15	- ~	
	"SHOW WINNING	111111	

EXISTING TOPOGRAPHY SYMBOLOGY AND LEGEND

Anchor
Antenna
Approach
Approach
Assumed Corner
Azimuth Marker
BBQ Grill/ Fireplace
Bearing Tree
Dearing 1166
Bench Mark
Box Culvert
Bridge
Brush
Buildings
Dullu Tl-
Buik Tank
Cattle Guard
Cemetery
Centerline
Cistorn
Cisterii
Clothes Line
Commercial Sign Double Face
Commercial Sign One Post
Commercial Sign Overhead
Commorcial Sign Two Dect
Commercial Sign Two Post
Concrete Symbol
Creek Edge
Curb/Gutter
Curb
Dam Crade/Dike/Leuree
Dam Grade/Dike/Levee
Deck Edge
Ditch Block
Doorway Threshold
Drainage Profile
Drop Inlet
Edge Of Asphalt
Edge Of Concrete
Edge Of Gravel
Edge Of Other
Edge Of Shoulder
Elec. Trans./Power Jct. Box
Fence Barbwire
Fence Chainlink
Eence Electric
Fence Misc.
Fence Rock
Fence Snow
Fence Wood
Fence Woven
Fire Hydrant
Flag Pole
Flower Bed
Gas Valve Or Meter
Gae Pump Island
Casin Dia
Grain Bin
Guardrail
Guide Sign One Post
Guide Sign Two Post
Gutter
Guy Pole
Havetook

(
Ā.
●
622532
-
Ĕ
*
C
1
þ Janaj
B
Ø
6 P
7777
-
2
5
9

Hedge
Highway R.O.W. Marker
Interstate Close Gate
Iron Pin
Irrigation Ditch
Lake Edge
Lawn Sprinkler
Mailbox
Manhole Electric
Manhole Gas
Manhole Misc
Manhole Sanitary Sewer
Manhole Storm Sewer
Manhole Telephone
Manhole Water
Merry-Go-Round
Microwave Radio Tower
Misc. Line
Misc. Property Corner
Misc. Post
Overhang Or Encroachment
Derking Motor
Parking Meter
Pipe With Headwall
Pipe Without End Section
Playaround Slide
Playaround Swing
Power And Light Pole
Power And Telephone Pole
Power Meter
Power Pole
Power Pole And Transformer
Power Tower Structure
Propane Tank
Property Pipe
Property Pipe With Cap
Property Stone
Public Telephone
Railroad Crossing Signal
Railroad Milepost Marker
Railroad Profile
Railroad R.O.W. Marker
Railroad Signs
Railroad Switch
Railroad Track
Railroad Trestle
Rebar
Rebar With Cap
Reference Mark
Regulatory Sign One Post
Regulatory Sign Two Post
Retaining Wall
Riprap
River Edge
Rock And Wire Baskets
Rockpiles
Satellite Dish
Septic Tank

- OH --~ 0
 0
 0
 0
 0 ¢1 aaaaa

STATE OF	PROJECT	SHEET	ET TOTAL SHEETS 1 51
SOUTH DAKOTA	P TAPU (06)	21	51

Shrub Tree	0
Sidewalk	
Sign Face	
Sign Post	•
Slough Or Marsh	
Spring	a)
Stream Gauge	ø
Street Marker	
Subsurface Utility Exploration Test Ho	
Telephone Fiber Ontics	T/E
Telephone Junction Box	0
Tolophono Dolo	
Tolovision Cable Lat Box	
Television Cable JCt Box	~
Television Tower	4
Test wells/Bore Holes	
	*
Tree Coniferous	*
Tree Deciduous	
Tree Stumps	8
Triangulation Station	▲
Underground Electric Line	— P —
Underground Gas Line	— G —
Underground High Pressure Gas Line	— HG —
Underground Sanitary Sewer	— s —
Underground Storm Sewer	= s =
Underground Tank	-
Underground Telephone Line	— T —
Underground Television Cable	— TV —
Underground Water Line	— w —
Warning Sign One Post	þ
Warning Sign Two Post	E .
Water Fountain	ſ
Water Hydrant	0
Water Meter	
Water Tower	
Water Valve	0
Water Well	۵
Weir Rock	
Windmill	×
Wingwall	
Witness Corper	•
Withess Comer	
State and National Line	
County Line	
Section Line	
Ouarter Line	
Quarter Line	
Sixteentri Line	
Construction Line	
K. U. W. LINE	
New R.O.W. Line	
Control of Access	•••••
New Control of Access	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~
Proposed ROW	
(Alter Property Disposal)	









Furnish and Install Furnish and Install 5" Concrete Sidewalk at the following locations: 8" Concrete Sidewalk at the following location: 10+00.00 to 11+75.42-5.00' L to 5.00' R-1,754.4 SqFt 9+32.25 to 10+00.00-23.38' R to 5.00' L-1,012.5 SqFt

12+23.95 to 14+97.42-5.00' L to 5.00' R-2,734.6 SqFt

Furnish and Install Sidewalk Drain at the following location: 9+33.64-5.71' R to 5.00' L-11.5 Ft

13+00

Adjust Water Valve Box at the following locations: 9+42.22-11.80' R 9+47.43-20.04' R Asphalt Parking Lot Asphalt Drive п ЗМ 12+50 12+00 11+50 11+00 10 ± 00

Spruce Street

Remove

Future Path

Concrete Curb and Gutter at the following locations: 11+76 to 11+77-7' R to 7' L-14 Ft 12+22 to 12+24-7' R to 7' L-14 Ft

Furnish and Install Special Concrete Curb and Gutter 11+75.52 to 11+77.48-7.00' R to 7.00' L-14.0 Ft 12+21.99 to 12+23.99-7.00' R to 7.00' L-14.0 Ft

Furnish and Install Type 1 Detectable Warnings at the following locations: 11+74.42-0.00' R/L-20 SqFt 12+24.96-0.00' R/L-20 SqFt

















CURB RAMP DETAILS



24 1+24.41−28.20' R End Type 3 Curb Ramp Slope

	STATE OF	PROJECT	SHEET	TOTAL SHEETS
	SOUTH DAKOTA	P TAPU (06)	34	51
		RE\	/ 5-29-1	5 NAP
LEGEND:				
* Tur	ning Spa	ce with 2% max. slope		
** Rar	np slopes	with 8.3% max. slope		
Det	ectable W	arning Surface		
\sim		~		
[27)	O TE	w w		
67 [[28] [4	9 1			
T/F	4+00 T/	F T/F		
x _ 3	-30			
	-			
L 54	31	3+89.97–5.50' R TC Elev. 1352.23		
L	6	3+87.47-5.00' R		
1	52	End Type 3 Curb Ramp Slo	pe	
L urb Ramp Slor	. 33	3+84.97–5.50' R TC Elev. 1352.23		
L	(34)	3+78.97-5.50' R		
	0	TC Elev. 1352.23		
L 26		WHUNDOFESS/		
R		NALO SEG. NA	N	
23		8471		
		JEFFRENCE	Mik	5
		Eter Mecomit	X ; 5	
		The Our and		HIN
		H DA		Ň
		757411 5/29/13 9>1110111	MILIUM	
		C	•	





CURB RAMP DETAILS



STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	P TAPU (06)	37	51
	RE	/ 5-29-1	5 NAP

LEGEND:

- Turning Space with 2% max. slope
 Ramp slopes with 8.3% max. slope
 Sidewalk with 5% max. long slope Detectable Warning Surface



28+06.94-4.07'L FL Elev. Match Existing



PERMANENT SIGN TABULATION

	PERMANENT SIGN TABULATION						
	SIGN CODE	SIGN SIZE	SIGN SIZE SF	DESCRIPTION	SHEETING	NUMBER REQUIRED	TOTAL SF
$\langle A \rangle$	D11-1	24" X 18"	3.0	Bike Route	TYPE IV	12	36.0
๎๎฿	R1-1	18"X 18"	1.9	Stop	TYPE XI	10	19.0
\odot	R3-17BP	24" X 8"	1.4	Ends	TYPE IV	2	2.8
\bigcirc	R5-3	24" X 24"	4.0	No Motorized Vehicles	TYPE IV	10	40.0
Ē	W1-1L	18"X 18"	2.3	Left Turn	TYPE IV	1	2.3
							TOTAL
						TYPE IV	81.1
						TYPE XI	19.0



A)−D11−1



⟨B⟩ −R1−1



⟨C⟩ −R3−17BP







(E)−W1−1L



24"x24"

⟨D⟩-R5-3

STATION
1+71
1+71
11+68
11+68
12+31
12+31
14+90
14+90
15+54
15+54
21+63
21+63
22+11
22+11
24+05
24+05
24+44
24+44
27+00
27+50
27+50

	STATE OF	PROJECT		SHEET	TOTAL SHEETS
	SOUTH DAKOTA		P TAPU (06)	38	51
	SIGN P	LACE	MENT		
		2005	2.0" X 2.0" Perforat	ed Tube	
Lt\Rt	SIGN (JODE	Post Length (F	īt)	
9.5'L	.t BA	$\langle C \rangle$	9.0		1
9.5' R	t AD	>	9.0		
9.5'R	t B		8.0		
9.5'L	.t (AXD)	>	9.0		
9.5'L	.t B		8.0		
9.5'R	t (AXD	>	9.0		
9.5'R	t B		8.0		
9.5'L	.t (AXD)	>	9.0		
9.5'L	t B		8.0		
9.5'R	t AXD	>	9.0		
9.5' R	t B		8.0		
9.5'L	t AD	>	9.0		
9.5'L	t B		8.0		
9.5' R	t AXD	>	9.0		
9.5' R	t B		7.0		
9.5'L	t AXD	>	8.0		
9.5' L	t B		8.0		
9.5' R	t AXD	>	9.0		
9.5' R	t E		6.0		1
9.5'R	t BA	\overline{C}	9.0		
9.5'L	t AD	>	9.0		
	TOT	AL	176.0		



PERMANENT SIGN TABULATION BEGIN P TAPU (06) SHARED USE PATH, GRADING, CURB AND GUTTER, CONCRETE SIDEWALK AND NING STA. 0+74.62-55.72' R (A)D) BAC TECH CENTER MTI DRIVE ADMIN CENTER DRIVI AD B B B AD B AD B SPRUCE STREET B (B) 47000 . 11 24"x18" 18"x18" 24"x8" 24"x24" 18"x18" ENDS AD � NO STOP MOTOR BIKE ROU VEHICLES A)−D11−1 ⟨C⟩ −R3−17BP (D)-R5-3 ⟨B⟩ –R1–1 **(E)**−W1−1L

	STATE OF SOUTH		SHEET	TOTAL SHEETS
UTILITY BUILDING	STATE OF SOUTH DAKOTA	PROJECT P TAPU (06)	6) , GRADIN , CONCF NING 1.07' L	SHEETS 51
		JERFRAM MCCORMIC South DAKO JERFRAM JERFRAM MCCORMIC South DAKO 3/27/15	NAVARA	

DETAILS



STATE OF	PROJECT	SHEET	TOTAL SHEETS
DAKOTA	P TAPU (06)	40	51











GENERAL NOTES: For illustrative purpose only, type I detectable warnings are shown in the drawings. For illustrative purpose only, a PCC fillet section is shown in one of the drawings. The curb ramp depicted on this standard plate may be used with a PCC fillet section, with curved curb and gutter, or with straight curb and gutter. The curb ramp shall be placed at the locati Sidewalk adjacent to the curb ramp shall be Care shall be taken to ensure a uniform gr grade changes. Surface texture of the ramp shall be obtain slope of the ramp. The normal gutter line profile shall be maint Joints shall be sawed or tooled into the co to alleviate possible corner cracking (see p Care shall be taken to ensure that the sur and maintains a uniform color. The detectable warnings shall be cut as new of the detectable warnings. Cost for cutti to the corresponding detectable warning bi When curb height is greater than 6" and less than 12", reinforcing steel is required in accordance with the detail on sheet 2 of 3. The reinforcing steel shall conform to ASTM A615, Grade 60. Cost for furnishing and installing the reinforcing steel shall be incidental to the contract unit price per square foot for the corresponding concrete sidewalk bid item. There will be no separate payment for curb ramps. The curb ramp shall be measured and paid for at the contract unit price per square foot for the corresponding concrete sidewalk bid Item. The square foot area of the detectable warnings and the curb along the short radius shall be included in the measured and paid for quantity of sidewalk. The curb transitions and ramp opening shall be measured and paid for at the contract unit price per foot for the corresponding curb and gutter bid item when curb and gutter is used. The curb transitions and ramp opening shall be measured and paid for at the contract unit price per square yard for the corresponding PCC fillet section bid item when a PCC fillet section is used. The type I detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type I detectable warnings including labor, equipment, materials, and incidentals shall be paid for at the contract unit price per square foot for "Type I Detectable Warnings". The type 2 detectable warnings shall be measured to the nearest square foot. All costs for furnishing and installing the type 2 detectable warnings including labor, equipment, and materials, including adhesive, necessary sealant or grout, and necessary grinding shall be paid for at the contract unit price per square foot for "Type 2 Detectable Warnings". September 6, 2013 S PLATE NUMBER D TYPE 3 CURB RAMP 651.03 D (PARALLEL CURB RAMP) 0 Published Date: 1st Otr. 2015

T

STATE OF	PROJECT	SHEET	TOTAL SHEETS
DAKOTA	P TAPU (06)	44	51

ion stated in the plans.
e as shown in the plans.
rade on the ramp,free of sags and short
ined by coarse brooming transverse to the
tained through the area of the ramp.
oncrete adjacent to the detectable warnings plan view for joint location).
rface of the detectable warnings are clean
cessary to fit the plan specified limits ing the detectable warnings shall be incidental id item.
ss than 12", reinforcing steel is required in 5. The reinforcing steel shall conform to ASTM

Sheet 3 of 3

















1355

1355









6+50



6+00

_ + -













20









0

10

1345

20

1345

-20

-10



13+00



12+50





























	SOUTH				SHEET	SHE
	DAKOTA	P TA	PU (06)		51	5
	07.4					
	2/+4	8.75		4745		
	7.19	.00		1345		
	-133	1336		-		
		<u> </u>		1340		
				-		
				1335		
				1330		
-20	-10 0	10	20			
	27+	00				
	8.08	38.27 38.60		1345		
	-133	+ 133				
		-15 F		1340		
				-		
				1335		
20		10	20] ₁₃₃₀		
20	10 0	10	20			