



Department of Transportation

Rapid City Region Office

2300 Eglin Street

P.O. Box 1970

Rapid City, SD 57709-1970

Phone: 605/394-2244

FAX: 605/394-1904

November 4, 2019

ADDENDUM NO. 1

RE: November 5, 2019 Rapid City Region Office Informal Letting
34571S, Pennington County, PCN i5tu
Sand Stockpile – Rapid City Maintenance Yard

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made part of your proposal for the referenced project.

PROPOSAL:

- No change.

PLANS:

- Replace Sheet 4 with attached Sheet 4. Changing the note that the stockpile will be built with a staking conveyor.

Sincerely,

John Rehorst
Region Design Engineer

PENNINGTON COUNTY

SPECIFICATIONS TO BE USED

Standard Specifications for Road and Bridges, 2015 Edition, and Required Provisions, Supplemental Specifications and/or Special Provisions as included in the Proposal.

SCOPE OF WORK

Work on this project shall be to furnish and stockpile sand for deicing at the following locations by the associated completion dates:

Rapid City South Yard – 3,000 ton Sand for Deicing by March 1, 2020.

SAND FOR DEICING

Sand for Deicing shall consist of natural sand or other inert materials with similar characteristics having hard, strong, durable particles and shall conform to the following gradation requirements:

Passing 3/8 inch sieve	100%
Passing No. 4 sieve	80-100%
Passing No. 10 sieve	40-80%
Passing No. 40 sieve	5-35%
Passing No. 200 sieve	0-3%

The Liquid Limit of the material shall not exceed 26 and the Plastic Index shall not exceed 3.

The Contractor shall provide test data showing that the material meets the following:
A durability or hardness as defined in Mohs scale of greater than 6 for 70 percent of the material applied to the streets for deicing or skid control.

No tolerance in the amount passing the largest sieve shall be allowed. 100% shall pass the 3/8 inch sieve.

The stockpile will be built with a staking conveyor. Sand for deicing will be Contractor furnished.