

STATE OF SOUTH DAKOTA

<u>DEPARTMENT OF TRANSPORTATION</u>

PLANS FOR PROPOSED

**PROJECTS** 

090 E-271, 090 W-271,

029 N-271, 029 S-271,

229 N-271 & 229 S-271 INTERSTATES 90, 29 & 229

MINNEHAHA & LINCOLN COUNTIES

GRADING, REPROFING DITCH, SHOULDER SHAPING, CULVERT, GUTTER REPLACEMENT, EROSION CONTROL & RIPRAP PCN I4QA, I4QC, I4QD, I4QE, I4QF & I4QG

STATE OF SOUTH DAKOTA 2017 SF Area Erosion Plans 1 27

Plotting Date: 05/19/201

#### INDEX OF SHEETS


Sheet 1 Layout Map & Index of Sheets Sheets 2 - 3 Estimate of Quantities Environmental Commitments

Sheets 5 - 10 Plan Notes & SWPPP Sheet 11 - 13 Erosion Control Tables

Sheet 14 Typical Section for I90 EB 398.07 to 398.24
Sheet 15 Plan Sheet for I90 EB 398.07 to 398.24
Sheet 16 Cross Sections for I90 EB 398.07 to 398.24

Sheet 17 Median Crossover Layout for I29 MRM 78.87

Sheets 18 - 27 Standard Plates



090W-271 ADT(2016) 9,125 090E-271 ADT(2016) 9,125

029N-271 ADT(2016) 25,475 029S-271 ADT(2016) 22,025

229N-271 ADT(2016) 21,915 229S-271 ADT(2016) 21,915

STORM WATER PERMIT

Receiving Waters: Big Sioux River Area Disturbed: 3.95 Acres Total Project Area: 3.95 Acres Latitude: 43.5446 N (Google Maps) Longitude: -96.7311 W (Google Maps)

#### 090E-271 PCN I4QA

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E0600	Remove Fence	900	Ft
110E7500	Remove Pipe for Reset	16	Ft
110E7510	Remove Pipe End Section for Reset	1	Each
120E0010	Unclassified Excavation	1,000	CuYd
120E0600	Contractor Furnished Borrow Excavation	111	CuYd
120E6300	Water for Vegetation	31.3	MGal
230E0020	Contractor Furnished Topsoil	17	CuYd
230E0100	Remove and Replace Topsoil	Lump Sum	LS
450E9000	Reset Pipe	16	Ft
450E9001	Reset Pipe End Section	1	Each
620E0030	Type 3 Right-of-Way Fence	900	Ft
620E1020	2 Post Panel	2	Each
634E0010	Flagging	5.0	Hour
634E0110	Traffic Control Signs	382.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0285	Type 3 Barricade, 8' Double Sided	1	Each
634E0420	Type C Advance Warning Arrow Board	1	Each
700E0210	Class B Riprap	48.0	Ton
730E0251	Special Permanent Seed Mixture 1	30	Lb
732E0200	Fiber Mulching	0.4	Ton
734E0042	Soil Stabilizer	3,472.3	SqYd
734E0103	Type 3 Erosion Control Blanket	2,547	SqYd
734E0133	Type 3 Turf Reinforcement Mat	237.3	SqYd
734E0154	12" Diameter Erosion Control Wattle	120	Ft
734E0510	Shaping for Erosion Control Blanket	1,265	Ft
831E0110	Type B Drainage Fabric	82	SqYd

#### 090W-271 PCN I4QC

NUMBER         Lump Sum         LS           120E0600         Contractor Furnished Borrow Excavation         28         CuY           120E4100         Reprofiling Ditch         5.0         Sta           120E6300         Water for Vegetation         8.9         MGa           230E0020         Contractor Furnished Topsoil         6         CuY           634E0010         Flagging         5.0         Hou           634E0110         Traffic Control Signs         382.0         SqF           634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Eacl           634E0420         Type C Advance Warning Arrow Board         1         Eacl           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	09044-271	PCN 14QC		
120E0600         Contractor Furnished Borrow Excavation         28         CuY           120E4100         Reprofiling Ditch         5.0         Sta           120E6300         Water for Vegetation         8.9         MGa           230E0020         Contractor Furnished Topsoil         6         CuY           634E0010         Flagging         5.0         Hou           634E0110         Traffic Control Signs         382.0         SqF           634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Eacl           634E0420         Type C Advance Warning Arrow Board         1         Eacl           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft		ITEM	QUANTITY	UNIT
120E4100         Reprofiling Ditch         5.0         Sta           120E6300         Water for Vegetation         8.9         MGa           230E0020         Contractor Furnished Topsoil         6         CuY           634E0010         Flagging         5.0         Hou           634E0110         Traffic Control Signs         382.0         SqF           634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Eacl           634E0420         Type C Advance Warning Arrow Board         1         Eacl           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	009E0010	Mobilization	Lump Sum	LS
120E6300         Water for Vegetation         8.9         MGa           230E0020         Contractor Furnished Topsoil         6         CuY           634E0010         Flagging         5.0         Hou           634E0110         Traffic Control Signs         382.0         SqF           634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Each           634E0420         Type C Advance Warning Arrow Board         1         Each           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	120E0600	Contractor Furnished Borrow Excavation	28	CuYd
230E0020         Contractor Furnished Topsoil         6         CuY           634E0010         Flagging         5.0         Hou           634E0110         Traffic Control Signs         382.0         SqF           634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Eacl           634E0420         Type C Advance Warning Arrow Board         1         Eacl           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	120E4100	Reprofiling Ditch	5.0	Sta
634E0010         Flagging         5.0         Hou           634E0110         Traffic Control Signs         382.0         SqF           634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Eacl           634E0420         Type C Advance Warning Arrow Board         1         Eacl           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	120E6300	Water for Vegetation	8.9	MGal
634E0110         Traffic Control Signs         382.0         SqF           634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Eacl           634E0420         Type C Advance Warning Arrow Board         1         Eacl           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	230E0020	Contractor Furnished Topsoil	6	CuYd
634E0120         Traffic Control, Miscellaneous         Lump Sum         LS           634E0285         Type 3 Barricade, 8' Double Sided         1         Eacl           634E0420         Type C Advance Warning Arrow Board         1         Eacl           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	634E0010	Flagging	5.0	Hour
634E0285         Type 3 Barricade, 8' Double Sided         1         Each           634E0420         Type C Advance Warning Arrow Board         1         Each           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqYr           734E0103         Type 3 Erosion Control Blanket         444         SqYr           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqYr           734E0154         12" Diameter Erosion Control Wattle         70         Ft	634E0110	Traffic Control Signs	382.0	SqFt
634E0420         Type C Advance Warning Arrow Board         1         Each           730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqYo           734E0103         Type 3 Erosion Control Blanket         444         SqYo           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqYo           734E0154         12" Diameter Erosion Control Wattle         70         Ft	634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
730E0251         Special Permanent Seed Mixture 1         9         Lb           732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	634E0285	Type 3 Barricade, 8' Double Sided	1	Each
732E0200         Fiber Mulching         0.1         Ton           734E0042         Soil Stabilizer         1,002.1         SqYo           734E0103         Type 3 Erosion Control Blanket         444         SqYo           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqYo           734E0154         12" Diameter Erosion Control Wattle         70         Ft	634E0420	Type C Advance Warning Arrow Board	1	Each
734E0042         Soil Stabilizer         1,002.1         SqY           734E0103         Type 3 Erosion Control Blanket         444         SqY           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqY           734E0154         12" Diameter Erosion Control Wattle         70         Ft	730E0251	Special Permanent Seed Mixture 1	9	Lb
734E0103         Type 3 Erosion Control Blanket         444         SqYo           734E0133         Type 3 Turf Reinforcement Mat         102.2         SqYo           734E0154         12" Diameter Erosion Control Wattle         70         Ft	732E0200	Fiber Mulching	0.1	Ton
734E0133 Type 3 Turf Reinforcement Mat 102.2 SqY/ 734E0154 12" Diameter Erosion Control Wattle 70 Ft	734E0042	Soil Stabilizer	1,002.1	SqYd
734E0154 12" Diameter Erosion Control Wattle 70 Ft	734E0103	Type 3 Erosion Control Blanket	444	SqYd
	734E0133	Type 3 Turf Reinforcement Mat	102.2	SqYd
	734E0154	12" Diameter Erosion Control Wattle	70	Ft
734E0510   Shaping for Erosion Control Blanket 500   Ft	734E0510	Shaping for Erosion Control Blanket	500	Ft

## **ESTIMATE OF QUANTITIES**

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	2017 SF Area Erosion Plans	2	27

#### 029N-271 PCN I4QD

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
120E0010	Unclassified Excavation	144	CuYd
120E0600	Contractor Furnished Borrow Excavation	225	CuYd
120E6300	Water for Vegetation	35.0	MGal
230E0020	Contractor Furnished Topsoil	141	CuYd
230E0100	Remove and Replace Topsoil	Lump Sum	LS
250E0020	Incidental Work, Grading	Lump Sum	LS
450E4759	18" CMP 16 Gauge, Furnish	50	Ft
450E4760	18" CMP, Install	50	Ft
450E5406	18" CMP Safety End, Furnish	2	Each
450E5407	18" CMP Safety End, Install	2	Each
634E0010	Flagging	5.0	Hour
634E0110	Traffic Control Signs	382.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0285	Type 3 Barricade, 8' Double Sided	1	Each
634E0420	Type C Advance Warning Arrow Board	1	Each
730E0251	Special Permanent Seed Mixture 1	34	Lb
732E0200	Fiber Mulching	1.0	Ton
734E0042	Soil Stabilizer	3,880.0	SqYd
734E0103	Type 3 Erosion Control Blanket	2,075	SqYd
734E0133	Type 3 Turf Reinforcement Mat	302.2	SqYd
734E0154	12" Diameter Erosion Control Wattle	220	Ft
831E0110	Type B Drainage Fabric	867	SqYd

### 029S-271 PCN I4QE

7293-2711			
BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
120E0600	Contractor Furnished Borrow Excavation	17	CuYd
120E4100	Reprofiling Ditch	1.5	Sta
120E6300	Water for Vegetation	5.0	MGal
230E0020	Contractor Furnished Topsoil	41	CuYd
634E0010	Flagging	5.0	Hour
634E0110	Traffic Control Signs	382.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0285	Type 3 Barricade, 8' Double Sided	1	Each
634E0420	Type C Advance Warning Arrow Board	1	Each
730E0251	Special Permanent Seed Mixture 1	5	Lb
732E0200	Fiber Mulching	0.2	Ton
734E0042	Soil Stabilizer	560.0	SqYd
734E0103	Type 3 Erosion Control Blanket	289	SqYd
734E0133	Type 3 Turf Reinforcement Mat	244.4	SqYd
734E0154	12" Diameter Erosion Control Wattle	70	Ft
734E0510	Shaping for Erosion Control Blanket	345	Ft

#### 229N-271 PCN I4QF

<u>ZZ314-Z7 1</u>	<u></u>		
BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E0300	Remove Concrete Curb and/or Gutter	66	Ft
120E0010	Unclassified Excavation	25	CuYd
120E0600	Contractor Furnished Borrow Excavation	11	CuYd
120E6300	Water for Vegetation	80.6	MGal
230E0020	Contractor Furnished Topsoil	38	CuYd
230E0100	Remove and Replace Topsoil	Lump Sum	LS
380E6110	Insert Steel Bar in PCC Pavement	25	Each
634E0010	Flagging	5.0	Hour
634E0110	Traffic Control Signs	382.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0285	Type 3 Barricade, 8' Double Sided	1	Each
634E0420	Type C Advance Warning Arrow Board	1	Each
650E4695	Type P9.5 Concrete Gutter	66	Ft
700E0210	Class B Riprap	12.0	Ton
730E0251	Special Permanent Seed Mixture 1	78	Lb
732E0200	Fiber Mulching	0.8	Ton
734E0042	Soil Stabilizer	9,012.3	SqYd
734E0103	Type 3 Erosion Control Blanket	2,803	SqYd
734E0154	12" Diameter Erosion Control Wattle	30	Ft
734E0510	Shaping for Erosion Control Blanket	3,153	Ft
831E0110	Type B Drainage Fabric	22	SqYd

#### 229S-271 PCN I4QG

BID ITEM			
NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
120E0010	Unclassified Excavation	53	CuYd
120E4100	Reprofiling Ditch	2.0	Sta
120E6300	Water for Vegetation	3.5	MGal
230E0020	Contractor Furnished Topsoil	17	CuYd
634E0010	Flagging	5.0	Hour
634E0110	Traffic Control Signs	382.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0285	Type 3 Barricade, 8' Double Sided	1	Each
634E0420	Type C Advance Warning Arrow Board	1	Each
700E0210	Class B Riprap	75.0	Ton
730E0251	Special Permanent Seed Mixture 1	3	Lb
732E0200	Fiber Mulching	0.1	Ton
734E0042	Soil Stabilizer	387.7	SqYd
734E0103	Type 3 Erosion Control Blanket	258	SqYd
734E0154	12" Diameter Erosion Control Wattle	100	Ft
734E0510	Shaping for Erosion Control Blanket	290	Ft
831E0110	Type B Drainage Fabric	120	SqYd

# | STATE OF | SOUTH | DAKOTA | 2017 SF Area Erosion Plans | 3 | 27 |

## ESTIMATE OF QUANTITIES (CONTINUED) (FOR INFORMATION ONLY)

BID ITEM		090 E- 271 PCN I4QA	090 W- 271 PCN I4QC	029 N - 271 PCN I4QD	029 S - 271 PCN I4QE	229 N - 271 PCN I4QF Lincoln &	229 S - 271 PCN I4QG Lincoln &	TOTAL
NUMBER	ITEM	Minnehaha	Minnehaha	Minnehaha	Minnehaha	Minnehaha	Minnehaha	QUANTITY
009E0010	Mobilization	◀		LUMF 1	SUM		▶	Lump Sum
110E0300	Remove Concrete Gutter					66		66 Ft
110E0600	Remove Fence	900						900 Ft
110E7500	Remove Pipe for Reset	16						16 Ft
110E7510	Remove Pipe End Section for Reset	1						1 Each
120E0010	Unclassified Excavation	1000		144		25	53	1,222 CuYd
120E0600	Contractor Furnished Borrow Excavation	111	28	225	17	11		392 CuYd
120E4100	Reprofile Ditch		5.0		1.5		2.0	8.5 Sta
120E6300	Water for Vegetation	31.3	8.9	35.0	5.0	80.6	3.5	164.3 Mgal
230E0020	Contractor Furnished Topsoil	17	6	141	41	38	17	260 CuYd
230E0100	Remove and Replace Topsoil	Lump Sum		Lump Sum		Lump Sum		Lump Sum
250E0020	Incidental Work, Grading			Lump Sum				Lump Sum
380E6110	Install Steel Bar in PCC Pavement					25		25 Each
450E4759	18" CMP 16 Gauge, Furnish			50				50 Ft
450E4760	18" CMP, Install			50				50 Ft
450E5406	18" CMP Safety End, Furnish			2				2 Each
450E5407	18" CMP Safety End, Install			2				2 Each
450E9000	Reset Pipe	16						16 Ft
450E9001	Reset Pipe End Section	1						1 Each
620E0030	Type 3 Right-of-Way Fence	900						900 Ft
620E1020	2 Post Panel	2						2 Each
634E0010	Flagging	5	5	5	5	5	5	30 Hour
634E0110	Traffic Control Signs	382	382	382	382	382	382	2,292.0 SqFt
634E0120	Traffic Control, Miscellaneous	◀		Ll	JMP SUM		▶	Lump Sum
634E0285	Type 3 Barricade, 8' Double Sided	1	1	1	1	1	1	6 Each
634E0420	Type C Advance Warning Board	1	1	1	1	1	1	6 Each
650E4695	Type P9.5 Gutter					66		66 Ft
700E0210	Class B Riprap	48.0				12.0	75.0	135.0 Ton
730E00251	Special Permanent Seed Mixture 1	30	9	34	5	78	3	159 Lb
732E0200	Fiber Mulching	0.4	0.1	1.0	0.2	0.8	0.1	2.6 Ton
734E0042	Soil Stabilizer	3472.3	1002.1	3880.0	560.0	9012.3	387.7	18,314.4 SqYd
734E0103	Type 3 Erosion Control Blanket	2547	444	2075	289	2803	258	8,416 SqYd
734E0133	Type 3 Turf Reinforcement Mat	237.3	102.2	302.2	244.4			886.1 SqYd
734E0154	12" Diameter Erosion Control Wattle	120	70	220	70	30	100	610 Ft
734E0510	Shaping for Erosion Control Blanket	1265	500		345	3153	290	5,553 Ft
831E0110	Type B Drainage Fabric	82		867		22	120	1,091 SqYd

#### **ENVIRONMENTAL COMMITMENTS**

An Environmental Commitment is a measure that SDDOT commits to implement in order to avoid, minimize, and/or mitigate a real or potential environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency mentioned below with permitting authority can influence a project if perceived environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office. The environmental commitments associated with this project are as follows:

#### **COMMITMENT C: WATER SOURCE**

The Contractor shall not withdraw water with equipment previously used outside the State of South Dakota without prior approval from the SDDOT Environmental Office. Thoroughly wash all construction equipment before entering South Dakota to reduce the risk of invasive species introduction into the project vicinity.

The Contractor shall not withdraw water directly from streams of the James, Big Sioux, and Vermillion watersheds without prior approval from the SDDOT Environmental Office.

#### Action Taken/Required:

The Contractor shall obtain the necessary permits from the regulatory agencies such as the Department of Environment and Natural Resources (DENR) and the United States Army Corps of Engineers (COE) prior to executing water extraction activities.

#### **COMMITMENT E: STORM WATER**

Construction activities constitute 1 acre or more of earth disturbance.

#### **Action Taken/Required:**

The DENR and the US Environmental Protection Agency (EPA) have issued separate general permits for the discharge of storm water runoff. The DENR permit applies to discharges on state land and the EPA permit applies to discharges on federal or reservation land. The Contractor is advised this project is regulated under the Phase II Storm Water Regulations and must receive coverage under the General Permit for Construction Activities. A Notice of Intent (NOI) will be submitted to DENR a minimum of 15 days prior to project start by the DOT Environmental Office. A letter must be received from DENR that acknowledges project coverage under this general permit before project start. The Contractor is advised that permit coverage may also be required by off-site activities, such as borrow and staging areas, which are the responsibility of the Contractor.

The Contractor shall adhere to the "Special Provision Regarding Storm Water Discharges to Waters of the State".

A major component of the storm water construction permits is development and implementation of a Storm Water Pollution Prevention Plan (SWPPP), which is a joint effort and responsibility of the SDDOT and the Contractor. Erosion control measures and best management practices will be implemented in accordance with the SWPPP. The SWPPP is a dynamic document and is to be available onsite at all times.

Information on storm water permits and SWPPPs are available on the following websites:

#### SDDOT:

http://www.sddot.com/business/environmental/stormwater/Default.aspx

DENR: http://www.denr.sd.gov/des/sw/stormwater.aspx

EPA: <a href="http://cfpub.epa.gov/npdes/home.cfm?program">http://cfpub.epa.gov/npdes/home.cfm?program</a> id=6

#### **Contractor Certification Form:**

The "Department of Environmental and Natural Resources – Contractor Certification Form" (SD EForm – 2110LDV1-ContractorCertification.pdf) shall be completed by the Contractor or their certified Erosion Control Supervisor after the award of the contract. Work may not begin on the project until this form is signed.

The form certifies under penalty of law that the Contractor understands and will comply with the terms and conditions of the Surface Water Discharge General Permit for Storm Water Discharges Associated with Construction Activities for the Project.

The online form can be found at:

http://denr.sd.gov/des/sw/eforms/E2110LDV1-ContractorCertification.pdf

#### **COMMITMENT H: WASTE DISPOSAL SITE**

The Contractor shall furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

#### Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) shall be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Environment and Natural Resources.

The waste disposal site(s) shall not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements shall apply:

- 1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials shall be buried in a trench completely separate from wood debris. The final cover over the construction and/or demolition debris shall consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW shall be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor shall control the access to waste disposal sites not within the Public ROW through the use of fences, gates, and placement of a sign or signs at the entrance to the site stating "No Dumping Allowed".
- 2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period of time not to exceed the duration of the project. Prior to project completion, the waste shall be removed from view of the ROW or buried and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	2017 SF Area Erosion Plans	4	27

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) shall be incidental to the various contract items.

#### **COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES**

The SDDOT has obtained concurrence with the State Historical Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

#### Action Taken/Required:

All earth disturbing activities not designated within the plans require review of cultural resources impacts. This work includes, but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor shall arrange and pay for a cultural resource survey and/or records search. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor shall provide ARC with the following: a topographical map or aerial view on which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor shall submit the records search or cultural resources survey report and if the location of the site is within the current geographical or historic boundaries of any South Dakota reservation to SDDOT Environmental Engineer, 700 East Broadway Avenue, Pierre, SD 57501-2586 (605-773-3180). SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

If evidence for cultural resources is uncovered during project construction activities, then such activities shall cease and the Project Engineer shall be immediately notified. The Project Engineer will contact the SDDOT Environmental Engineer in order to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor shall provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

#### **SPECIFICATIONS**

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

#### **SCOPE OF WORK**

This project consists of reprofiling ditches, reshaping shoulders, construction of maintenance crossover, pipe repair, fence replacement, and erosion control.

#### **SEQUENCE OF OPERATIONS**

Lane closures and/or narrowing of lanes will **NOT** be allowed as follows:

- 6:30 a.m. to 8:30 a.m.
- 4:00 p.m. to 7:00 p.m.

Traffic shall be returned to the normal driving lanes during nonworking hours. Approval from the Engineer will be required to complete work at night.

#### UTILITIES

The Contractor shall contact the involved utility companies through South Dakota One Call (1-800-781-7474) prior to starting work. It shall be the responsibility of the Contractor to coordinate work with the utility owners to avoid damage to existing facilities.

Utilities are not planned to be affected on this project. If utilities are identified near the improvement area through the SD One Call Process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25, the Contractor shall contact the Project Engineer to determine modifications that will be necessary to avoid utility impacts.

#### **COORDINATION BETWEEN CONTRACTORS**

A separate contract for Project No. 000I-271, PCN I4K9 has been awarded to another Contractor for Mowing of the Interstate ROW of this project.

A separate contract for Project No. IM 0293(108)78, PCN 05NQ has been awarded to another Contractor for Pavement Restoration on Interstate 29 from MRM 78 to MRM 86.

The Contractor shall schedule his work so as not to interfere with or hinder the progress of the work performed by other Contractors on these projects.

#### TIE BOLTS FOR RCP CULVERTS

Tie Bolts shall be installed at the inlet and outlet on all sections of reset culvert and on reset culvert ends. Connection shall be made from the first section left in place to the first reset section and to all reset sections.

For informational purposes:

Field drilling will be required to install the tie bolts on reset culvert, on reset culvert ends.

Cost for removing tie bolts for reuse, drilling tie bolt holes and providing, installing and reinstalling tie bolts shall be incidental to the contract unit prices for resetting RCP Culverts and End Sections.

#### REPROFILING DITCH

The following ditches shall be cleaned out to allow drainage through the ditch.

- West side of the 29 S-271 MRM 76.640
- West side of 229 S 271 MRM 0.95
- North side of 90 W- 271 MRM 399.31 to 399.36 On Ramp

The total estimated length of ditch cleanout is 850 feet (8.5 stations).

These locations shall be restored to the existing typical ditch section.

Areas to be cleaned out will be staked by the Engineer prior to cleanout.

Disturbed areas will be restored to the satisfaction of the Engineer. Disturbed areas will be seeded by the Contractor.

Cost for this work, including labor and equipment necessary to remove and dispose of the silt and vegetation and reshape the ditch shall be included in the contract unit price per station for Reprofiling Ditch.

Cost for seeding and mulching shall be included in the contract unit prices for the respective items.

#### **MAINTENANCE CROSSOVERS**

Maintenance crossovers shall be constructed as shown in the plans. The maintenance crossovers noted with "Retain" are maintenance crossovers at the same location and approximately the same elevation as the existing crossovers; therefore small quantities of excavation or embankment are required at these locations. The maintenance crossover subgrade shall be constructed to conform to the details on Standard Plate 120.04.

Excavation quantities for the maintenance crossovers are included in the earthwork balance notes on the profile sheets.

The Engineer will establish the exact location of the new maintenance cross over for the contractor.

#### **CONTRACTOR FURNISHED BORROW EXCAVATION**

The Contractor shall provide a suitable site for Contractor furnished borrow excavation material. The Contractor is responsible for obtaining all required permits and clearances for the borrow site. The plans quantity for "Contractor Furnished Borrow Excavation" as shown in the Estimate of Quantities will be the basis of payment for this item.

Restoration of the Contractor furnished borrow excavation site shall be the responsibility of the Contractor.

#### **INCIDENTAL WORK, GRADING**

On I-29 MRM 82.251 under Russell Street structure the contractor shall perform the following work:

- Grade and area of 52' wide by 150' long x 6" of depth, the excavation for this will be paid for under unclassified excavation.
- Install drainage fabric, paid under Type B drainage fabric.
- Place and shape state furnished asphalt millings in the area that was excavated. Provide engineer 3 day notice to coordinate work with state forces.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	2017 SF Area Erosion Plans	5	27

#### **REMOVE AND RESET TYPE 2 OBJECT MARKERS**

The Contractor will be required to remove prior to work and reset after the work any Type 2 object markers delineating the pipe ends. Cost for this work shall be incidental to the contract unit prices for the various items.

#### REMOVE AND RESET DELINEATORS

The Contractor will be required to remove prior to shoulder shaping work and reset after the work any delineators that are delineating the roadway. Cost for this work shall be incidental to the contract unit prices for the various items.

#### **REMOVE FENCE**

The Contractor shall remove the existing right-of-way fence that is to be replaced as designated in the plans and/or as ordered by the Engineer.

Limited Access Security - All fence removed during any one working day is to be replaced during the same day if livestock are being restrained.

#### **FENCE ALIGNMENT**

Where fence is being removed and replaced, fence shall be installed on the same alignment as existing. It shall be the Contractor's responsibility to preserve the fence alignment.

#### **TYPE 3 RIGHT-OF-WAY FENCE**

The Contractor shall furnish new posts. Install alternate wood and steel posts at 16'-6" spacing for Type 3 Right-of-Way Fence.

#### **NEW POST PANELS**

Existing post panels shall be replaced. Existing 5 Post and 4 Post Panels shall be replaced with a combination of 2 Post and 3 Post Panels as determined by the Engineer.

The number of 2 Post and 3 Post Panels will be the actual number installed and will be paid for at the contract unit price per each.

#### **TABLE OF FENCING QUANTITIES** TYPE 3 **INTERSTATE 90** REMOVE R/W **POST** LANE PSEUDO MRM to PSEUDO MRM FENCE FENCE PANEL **EACH** FT (DMI) FT EB 398.07 to 398.24 900 900 190E TOTALS: 900 900

#### TABLE OF CONCRETE GUTTER REMOVAL

Location	Quantity	Description
1229 – Louise	66'	Remove from SF 5' Drop Inlet to
NB		the North

#### **CONTRACTOR FURNISHED TOPSOIL**

It is anticipated that a larger volume of topsoil will be needed for the new grade than can be salvaged from the existing grade. The Contractor will be required to furnish and place 4 inches of topsoil on roadway inslopes and areas as determined by the Engineer during construction.

Contractor furnished topsoil shall be free from clay lumps, stones, coarse gravel, or similar objects larger than 1/2 inch in diameter. Brush, stumps, roots, wood, objectionable weeds, litter, or any other material which may be harmful to plant growth will not be allowed. Organic material shall be decomposed.

All costs to furnish and place the Contractor furnished topsoil shall be incidental to the contract unit price per cubic yard for "Contractor Furnished Topsoil".

#### **REMOVE AND REPLACE TOPSOIL**

Special conditions for the following shoulders:

- East side of the 29 N-271 MRM 81.8 to MRM 82.04
- East side of 229 N 271 MRM 3.213 Ramp
- East side of 229 N 271 MRM 5.95 to 6.30
- East side of 229 N 271 MRM 8.61 to MRM 8.70
- East side of 229 N 271 MRM 8.86 to MRM 9.00

These locations shall have topsoil stripped and shaped for approximately 16 feet.

After topsoil is stripped the top 6 feet needs to be re-shaped at a 10:1 slope to allow drainage to shed from roadway.

Areas to be shaped will be staked by the Engineer.

Cost for this work, including labor and equipment necessary to remove and replace topsoil and reshape the shoulder shall be included in the contract unit price per mile for shoulder shaping.

Cost for seeding, mulching, soil stabilizer, water for vegetation and blanket shall be included in the contract unit prices for the respective items.

#### **PERMANENT SEEDING**

The areas to be seeded consist of all newly graded areas within the project limits.

Special Permanent Seed Mixture 1 shall consist of the following:

Special Permanent Seed Mixture 1 shall consist of the following:				
Grass Species	Variety	Pure Live Seed (PLS) (Pounds/Acre)		
Western Wheatgrass	Arriba, Flintlock, Rodan, Rosana	14		
Switchgrass	Dacotah, Forestburg, Nebraska 28, Pathfinder, Summer, Sunburst, Trailblazer	6		
Indiangrass	Holt, Tomahawk	6		
Big Bluestem	Bison, Bonilla, Champ, Pawnee, Sunnyview	6		
Oats or Spring Wheat: April through May;		10		
Winter Wheat: August through November				
	Total:	42		

#### WATER FOR VEGETATION

Water for vegetation consists of applying water to seeded areas to enhance germination and/or root growth. When watering, use the following guidelines:

Immediately after seeding:

- Keep the topsoil moist but not excessively wet until the seed has germinated.
- Water a minimum of 3 days a week for 2 weeks preferably watering 2 or 3 times a day in small quantities.
- Use fine spray and low pressure to avoid topsoil wash and to prevent uncovering buried seeds.

#### After emergence:

- Topsoil shall be kept thoroughly moistened by sprinkling, as necessary, for 6 weeks. After the 6 week period, an inspection shall be made to determine if grass is established enough to suspend watering. Continue watering until grass has been thoroughly established.
- Never apply water at a rate faster than the topsoil can absorb.
- Water during early morning hours or early evening hours.
- Do not water when rain is forecasted for the area.
- If rainfall occurs, suspend watering according to rainfall amount.

An estimated 9 Gallons of water per square yard of seeding area was used to compute the quantity for the bid item "Water for Vegetation".

All costs for furnishing and applying the water including hauling, materials, equipment, labor, and incidentals necessary shall be paid for at the contract unit price per MGal for "Water for Vegetation".

#### FIBER MULCHING

Fiber mulch shall be applied in a separate operation following permanent seeding.

An additional 2% by weight of tackifier shall be added to the fiber mulch product selected from the approved product list. If the product selected has guar gum tackifier included, then the additional 2% of tackifier shall be guar gum. If the product selected has synthetic tackifier included, then the additional 2% of tackifier shall be synthetic.

Fiber mulch shall be applied at the rate of 3,000 pounds per acre.

The Contractor shall allow the fiber mulch to cure a minimum of 18 hours prior to watering or any storm event to ensure proper cohesion between the soil and fiber particles.

All costs for the additional tackifier added to the fiber mulch including labor, equipment, and materials shall be incidental to the contract unit price per ton for "Fiber Mulching".

The fiber mulch provided shall be from the approved product list. The approved product list for fiber mulch may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

Fiber mulch is included for every location for areas outside of erosion control blanket and erosion control mat. Plans quantity will be basis of payment.

#### SOIL STABILIZER

Soil stabilizer shall be applied on the areas listed in the table and any other areas deemed necessary by the Engineer. The soil stabilizer limits shall be adjusted as necessary by the Engineer during construction.

STATE OF

PROJECT

2017 SF Area Erosion Plans

SHEET

6

The Contractor shall apply soil stabilizer according to the manufacturer's application instructions and at the rate specified in the list of approved soil stabilizers.

Wood fiber mulch that contains a green dye shall be mixed with the soil stabilizer to be used as a tracer when the soil stabilizer is applied hydraulically. Wood fiber mulch shall be added at a rate of 300 pounds per acre to all of the approved soil stabilizers listed in the table except for the Pam-12 Plus product. The wood fiber mulch shall be a 100% wood fiber product and does not need to contain a tackifier.

All costs for furnishing and applying the soil stabilizer including wood fiber mulch, hauling, materials, equipment, labor, and incidentals necessary shall be paid for at the contract unit price per Square Yard for "Soil Stabilizer".

The soil stabilizer shall be from the list below or an approved equal:

Product Manufacturer

StarTak 600 Chemstar Products Company
Applied at a rate of 150 Lb/Acre Minneapolis, MN
Phone: 1-800-328-5037

www.chemstar.com

Pam-12 Plus
Applied at a rate of:
Slope
Slope
None to 4:1
1000 Lb/Acre
4:1 to 3:1
1000 to 2000 Lb/Acre
ENCAP, LLC
Green Bay, WI
Phone: 1-877-405-5050
http://professional.encap.net/

M-Binder Ecology Controls
Applied at a rate of 150 Lb/Acre Carpinteria, CA
Phone: 1-805-684-0436
www.ssseeds.com

FiberRX
Applied at a rate of:
Slope
None to 4:1
50 Lb/Acre
3:1
60 Lb/Acre
2:1
70 Lb/Acre
1:1 or steeper

Hydrostraw, LLC
Manteno, IL
Phone: 1-800-545-1755
hydrostraw.com

Enviropam Innovative Turf Solutions, LLC
Applied at a rate of 9 Lb/Acre Cincinnati, OH
Phone: 1-513-317-8311
www.innovativeturfsolutions.com

HydraTack, Tack Plus, Tack-P, or Tack-P Plus Applied at a rate of 30 Lb/Acre

3:1 to 2:1 2000 to 3000 Lb/Acre

Innovative Turf Solutions, LLC Cincinnati, OH

Phone: 1-513-317-8311 www.innovativeturfsolutions.com

## SOIL STABILIZER (CONTINUED)

FI-1045 Hydrobond or FI-1046 Hydrobond Applied at a rate of 15 Lb/Acre JRM Chemical, Inc. Cleveland, OH Phone: 1-216-475-8

Phone: 1-216-475-8488 www.soilmoist.com

HF5000 Tack Applied at a rate of 60 Lb/Acre Rantec Corporation Ranchester, WY Phone: 1-307-655-9565 www.ranteccorp.com

R-Tack Applied at a rate of 150 Lb/Acre Rantec Corporation Ranchester, WY Phone: 1-307-655-9565 www.ranteccorp.com

Rantec Corporation Ranchester, WY

www.ranteccorp.com

Phone: 1-307-655-9565

SpecTac
Applied at a rate of:
Slope

None 30 to 80 Lb/Acre 4:1 50 to 100 Lb/Acre 3:1 80 to 120 Lb/Acre

Super Tack Applied at a rate of 60 Lb/Acre Rantec Corporation Ranchester, WY Phone: 1-307-655-9565 www.ranteccorp.com

EarthGuard SFM Applied at a rate of 60 LB/Acre (approx. 6 Gallons/Acre)

Terra Novo Inc. Bakersfield, CA Phone: 1-661-747-5956

www.terranovo.com

#### **EROSION CONTROL WATTLE**

Erosion control wattles for restraining the flow of runoff and sediment shall be installed at locations noted in the table and at locations determined by the Engineer during construction. Refer to Standard Plate 734.06 for details.

The Contractor shall provide certification that the erosion control wattles do not contain noxious weed seeds.

Erosion control wattles shall remain on the project to decompose.

The erosion control wattle provided shall be from the approved product list. The approved product list for erosion control wattle may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

#### **EROSION CONTROL BLANKET**

Erosion control blanket shall be installed 8 feet wide at the locations noted and at locations determined by the Engineer during construction.

The erosion control blanket provided shall be from the approved product list. The approved product list for erosion control blanket may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

#### SHAPING FOR EROSION CONTROL BLANKET

The ditches shall be shaped for the erosion control blanket as specified on Standard Plate 734.01.

#### TURF REINFORCEMENT MAT

Turf Reinforcement Mat shall be installed at locations shown in the attached table at an 8 foot width, and at locations determined by the Engineer during construction. The Contractor shall use a turf reinforcement mat from the approved products list. The approved product list for turf reinforcement mat may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

#### STEEL BAR INSERTION

Steel bars shall conform to Section 1010.

Locations and quantity of concrete gutter repair are subject to change in the field at the discretion of the Engineer. The Contractor will be responsible for ordering the actual quantity of steel bars necessary to complete the work.

The Contractor shall insert the steel bars No.  $5 \times 24$ " epoxy coated deformed tie bars for longitudinal joints) into drilled holes in the existing concrete pavement. An epoxy resin adhesive must be used to anchor the steel bar in the drilled hole as per Section 380.3 C.1.

Steel bars shall be inserted in the longitudinal joint on 30" centers and shall be a minimum of 15" from either transverse joint. It will be necessary to laterally adjust the location of some of the inserted steel bars when the dimensions above interfere with existing steel bar locations.

A rigid frame or mechanical device will be required to guide the drill to ensure proper horizontal and vertical alignment of the steel bars in the drilled holes.

#### **SAW AND SEAL JOINTS**

All longitudinal and transverse joints at concrete repair areas shall be sawed and sealed.

Joint sealing shall conform to Section 380.3 P.

Longitudinal joints in urban sections shall be sealed with Hot Poured Elastic Joint Sealer.

Acceptance of the Hot Poured Elastic Joint Sealer will be based on visual inspection by the Engineer.

Cost for sawing and sealing of the longitudinal construction joint shall be incidental to the contract unit price Type P9.5 Gutter.

#### **REPLACING GUTTER**

Damaged gutter around the following drop inlets shall be sawed full depth and removed and replaced with concrete gutter at the following location:

Location	Quantity	Description
I229 – Louise	66'	Remove from SF 5' Drop Inlet to
SB		the North

Lengths of gutter removal shall be as directed by the Engineer.

New concrete gutter shall be tied to adjacent PCC Pavement and existing concrete curb and gutter with deformed tie bars.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	2017 SF Area Erosion Plans	7	27

#### **GENERAL MAINTENANCE OF TRAFFIC**

Sufficient traffic control devices have been included in these plans to sign one workspace on each route. If the Contractor elects to work on additional sites simultaneously, the cost for additional traffic control devices shall be incidental to the contract unit price per square foot for Traffic Control Signs.

#### ITEMIZED LIST FOR TRAFFIC CONTROL SIGNS

	EXPRESSWAY / INT								
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT				
R2-1	SPEED LIMIT 65	1	36" x 48"	12.0	12.0				
R2-1	SPEED LIMIT 45	7	36" x 48"	12.0	84.0				
R2-6aP	FINES DOUBLE (plaque)	1	36" x 24"	6.0	6.0				
W3-5	SPEED REDUCTION AHEAD (45 MPH)	5	48" x 48"	16.0	80.0				
W4-2	LEFT or RIGHT LANE ENDS (symbol)	2	48" x 48"	16.0	32.0				
W5-4	RAMP NARROWS	1	48" x 48"	16.0	16.0				
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0				
W20-5	LEFT or RIGHT LANE CLOSED AHEAD	2	48" x 48"	16.0	32.0				
W20-7	FLAGGER (symbol)	1	48" x 48"	16.0	16.0				
W21-5a	LEFT or RIGHT SHOULDER CLOSED	2	48" x 48"	16.0	32.0				
W21-5b	LEFT or RIGHT SHOULDER CLOSED AHEAD	2	48" x 48"	16.0	32.0				
G20-2	END ROAD WORK	1	48" x 24"	8.0	8.0				
			SWAY / IN IC CONTRO SQFT	TERSTATE OL SIGNS	382.0				

#### **TYPE 3 BARRICADES**

ITEM DESCRIPTION	QUANTITY
Type 3 Barricade, 8' Double Sided	1 Each

#### **ARROW BOARDS**

ITEM DESCRIPTION	QUANTITY
Type C Advance Warning Arrow Board	1 Each

			STATE OF	PROJECT	SHEET	T(
STORM WATER POLLUTION PREVENTION PLAN CHECKLIST			SOUTH DAKOTA	2017 SF Area Erosion Plans	8	<u> </u>
(The numbers right of the title headings are reference numbers to the	Structural Temporary Erosion and Sediment Controls			2011 01 7 11 00 21 00 10 11 10 110		丄
GENERAL PERMIT FOR STORM WATER DISCHARGES ASSOCIATED	■ Silt Fence					
WITH CONSTRUCTION ACTIVITIES	■ ☐ Floating Silt Curtain					
	Straw Bale Check	MAINTENANCE AND INSPECT	ION (4.2	3. and 4.2 4.)		
SITE DESCRIPTION (4.2 1)	Temporary Berm	<ul> <li>Maintenance and Inspecti</li> </ul>				
> Project Limits: See Title Sheet (4.2 1.b)	Temporary Slope Drain	<ul> <li>Inspections will be cond</li> </ul>			nd	
<ul> <li>Project Description: See Title Sheet (4.2 1.a.)</li> </ul>	Straw Wattles or Rolls				iu	
		after a storm event of 0				
> Site Map(s): See Title Sheet and Plans (4.2 1.f. (1)-(6))	■ ☐ Turf Reinforcement Mat	All controls will be main				
Major Soil Disturbing Activities (check all that apply)	■ ⊠ Rip Rap	•	within 24	hours of the site inspection	ו	
■ ☐Clearing and grubbing	■ Gabions	report.				
■   ⊠Excavation/borrow	■ Rock Check Dams	<ul> <li>Silt fence will be inspect</li> </ul>				
■   Grading and shaping	<ul> <li>Sediment Traps/Basins</li> </ul>	order to ensure the fabi	ic is secu	rely attached to the posts	and	
■ ☐Filling	■ Inlet Protection	that the posts are well a	anchored.	Sediment buildup will be		
■ Cutting and filling	<ul> <li>Outlet Protection</li> </ul>	removed from the silt fe	nce wher	$^{1}$ it reaches $^{1}$ / $_{3}$ of the heigh	nt of	
■ Other (describe):	<ul> <li>Surface Inlet Protection (Area Drain)</li> </ul>	the silt fence.		•		
> Total Project Area 3.95 Acres (4.2 1.b.)	■ Curb Inlet Protection	<ul> <li>Sediment basins and tr</li> </ul>	ans will h	e checked. Sediment will b	ne.	
> Total Area To Be Disturbed 172,200 SqFt - 3.95 Acres (4.2 1.b.)	Stabilized Construction Entrances			proximately 50 percent of		
Existing Vegetative Cover (%) 75	■ ☐ Entrance/Exit Equipment Tire Wash			onclusion of the construction		
Soil Properties: AASHTO Soil or USDA-NRCS Soil Series	■ Interceptor Ditch			r stability. Sediment will be		
•	Concrete Washout Facility				•	
Classification AASHTO A-7-6 & USDA: Silty clay loam, silt loam (4.2		removed when depth re			ا م م ما	
1. d.)	■ ☐ Temporary Diversion Channel			for bare spots, washouts,	and	
Name of Receiving Water Body/Bodies Big Sioux River (4.2 1.e.)	■ Work Platform	vigorous growth free of				
	<ul> <li>Temporary Water Barrier</li> </ul>			orts will be prepared on for		
ORDER OF CONSTRUCTION ACTIVITIES (4.2 1.c.)	<ul> <li>Temporary Water Crossing</li> </ul>			i, this form will also be use		
(Stabilization measures shall be initiated as soon as possible, but in no	■ Other:			P. A copy of the completed	d	
case later than 14 days after the construction activity in that portion of	Wetland Avoidance			the SWPPP documents.		
the site has temporarily or permanently ceased. Initiation of final or	Will construction and/or erosion and sediment controls impinge on	<ul> <li>The SDDOT Project En</li> </ul>	gineer ar	nd Contractor's Erosion Con	ntrol	
temporary stabilization may exceed the 14-day limit if earth disturbing	regulated wetlands? Yes 🗌 No 🔯 If yes, the structural and erosion	Supervisor are respons	ible for in	spections. Maintenance, re	epair	
activities will be resumed within 21 days.)	and sediment controls have been included in the total project wetland	activities are the respor	sibility of	the Contractor. The SDDC	ΤĊ	
Remove and restore topsoil.	impacts and have been included in the 404 permit process with the	Project Engineer will co	mplete th	e inspection and maintena	ance	
Fix Culverts or Erosion Areas	USACE.			the distribution instructions		
Grading where necessary	Storm Water Management (4.2 2.b., (1) and (2))	DOT 298.				
> Install Rip Rap where necessary.	Storm water management will be handled by temporary controls					
> Seed disturbed areas.	outlined in "EROSION AND SEDIMENT CONTROLS" above, and any	NON-STORM WATER DISCHA	RGES (3.	0)		
> Install blanket or turf matt.	permanent controls needed to meet permanent storm water	The following non-storm water			na the	د
Fiber mulch areas outside of blanket and turf matt.	management needs in the post construction period. Permanent	course of this project (check all				
> Water Vegetation.	controls will be shown on the plans and noted as permanent.	➤ ☐ Discharges from water li				
/ Water Vogetation.	> Other Storm Water Controls (4.2 2.c., (1) and (2))	Pavement wash-water, v				
EROSION AND SEDIMENT CONTROLS (4.2 2.a.(1)(a)-(f))	■ Waste Disposal	hazardous materials have o		spills of leaks of toxic of		
(Check all that apply)	All liquid waste materials will be collected and stored in sealed			assisted with dowstoring		
	· ·	Uncontaminated ground	water as	sociated with dewatering		
> Stabilization Practices (See Detail Plan Sheets)	metal containers approved by the project engineer. All trash and	activities.				
■ ☐ Temporary Seeding (Cover Crop Seeding)	construction debris from the site will be deposited in the approved	MATERIAL C INVENTORY (4.0	0 - (0))			
■ ☑ Permanent Seeding	containers. Containers will be serviced as necessary, and the	MATERIALS INVENTORY (4.2.			41	
■ Sodding	trash will be hauled to an approved disposal site or licensed	The following materials or subs				
Planting (Woody Vegetation for Soil Stabilization)	landfill. All onsite personnel will be instructed in the proper	site during the construction peri				
■ ☐ Mulching (Grass Hay or Straw)	procedures for waste disposal, and notices stating proper	noted under the headings "ERC			S" and	
■ ☐ Hydraulic Mulch (Wood Fiber Mulch)	practices will be posted in the field office. The general	"SPILL PREVENTION" (check a		ply).		
■ Soil Stabilizer	Contractor's representative responsible for the conduct of work		ement			
■ ☐ Bonded Fiber Matrix	on the site will be responsible for seeing waste disposal	Detergents				
■	procedures are followed.	➤ □Paints				
<ul> <li>Uegetation Buffer Strips</li> </ul>	<ul> <li>Hazardous Waste</li> </ul>	Metals				
■ Roughened Surface (e.g. tracking)	All hazardous waste materials will be disposed of in a manner	Bituminous Materials				
■ Dust Control	specified by local or state regulations or by the manufacturer.	Petroleum Based Produc	ts			
Other:	Site personnel will be instructed in these practices, and the	➢ ☐Cleaning Solvents				
_	individual designated as the Contractor's on-site representative	➤ ☐Wood				
	will be responsible for seeing that these practices are followed.	➤ ☐Cure				
	Sanitary Waste	➤ ☐Texture				
	Portable sanitary facilities will be provided on all construction	➤ □Chemical Fertilizers				
	sites. Sanitary waste will be collected from the portable units in a	> Other:				
	timely manner by a licensed waste management Contractor or as					
	required by any local regulations.					
	4					

#### SPILL PREVENTION (4.2 2.c.(2))

#### Material Management

- Housekeeping
  - Only needed products will be stored on-site by the Contractor.
  - Except for bulk materials the contractor will store all materials under cover and in appropriate containers.
  - Products must be stored in original containers and labeled.
  - Material mixing will be conducted in accordance with the manufacturer's recommendations.
  - When possible, all products will be completely used before properly disposing of the container off-site.
  - The manufacturer's directions for disposal of materials and containers will be followed.
  - The Contractor's site superintendent will inspect materials storage areas regularly to ensure proper use and disposal.
  - Dust generated will be controlled in an environmentally safe
    manner.
  - Vegetation areas not essential to the construction project will be preserved and maintained as noted on the plans.

#### Hazardous Materials

- Products will be kept in original containers unless the container is not resealable.
- Original labels and material safety data sheets will be retained in a safe place to relay important product information.
- If surplus product must be disposed of, manufacturer's label directions for disposal will be followed.
- Maintenance and repair of all equipment and vehicles involving oil changes, hydraulic system drain down, degreasing operations, fuel tank drain down and removal, and other activities which may result in the accidental release of contaminants will be conducted on an impervious surface and under cover during wet weather to prevent the release of contaminants onto the ground.
- Wheel wash water will be collected and allowed to settle out suspended solids prior to discharge. Wheel wash water will not be discharged directly into any storm water system or storm water treatment system.
- Potential pH-modifying materials such as: bulk cement, cement kiln dust, fly ash, new concrete washings, concrete pumping, residuals from concrete saw cutting (either wet or dry), and mixer washout waters will be collected on site and managed to prevent contamination of storm water runoff.

#### Product Specific Practices (6.8)

#### Petroleum Products

All on-site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

#### Fertilizers

Fertilizers will be applied only in the amounts specified by the SDDOT. Once applied, fertilizers will be worked into the soil to limit the exposure to storm water. Fertilizers will be stored in an enclosed area. The contents of partially used fertilizer bags will be transferred to sealable containers to avoid spills.

#### Paints

All containers will be tightly sealed and stored when not required for use. The excess will be disposed of according to the

manufacturer's instructions and any applicable state and local regulations.

#### Concrete Trucks

Contractors will provide designated truck washout facilities on the site. These areas must be self-contained and not connected to any storm water outlet of the site. Upon completion of construction, the area at the washout facility will be properly stabilized.

#### > Spill Control Practices (4.2 2 c.(2))

In addition to the previous housekeeping and management practices, the following practices will be followed for spill prevention and cleanup if needed.

- For all hazardous materials stored on site, the manufacturer's recommended methods for spill cleanup will be clearly posted. Site personnel will be made aware of the procedures and the locations of the information and cleanup supplies.
- Appropriate cleanup materials and equipment will be maintained by the Contractor in the materials storage area on-site. As appropriate, equipment and materials may include items such as brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for cleanup purposes.
- All spills will be cleaned immediately after discovery and the materials disposed of properly.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- After a spill a report will be prepared describing the spill, what caused it, and the cleanup measures taken. The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring, as well as clean up instructions in the event of reoccurrences.
- The Contractor's site superintendent, responsible for day-to-day operations, will be the spill prevention and cleanup coordinator. The Contractor is responsible for ensuring that the site superintendent has had appropriate training for hazardous materials handling, spill management, and cleanup.

#### > Spill Response (4.2 2 c.(2))

The primary objective in responding to a spill is to quickly contain the material(s) and prevent or minimize migration into storm water runoff and conveyance systems. If the release has impacted on-site storm water, it is critical to contain the released materials on-site and prevent their release into receiving waters. If a spill of pollutants threatens storm water or surface water at the site, the spill response procedures outlined below must be implemented in a timely manner to prevent the release of pollutants.

- The Contractor's site superintendent will be notified immediately when a spill or the threat of a spill is observed. The superintendent will assess the situation and determine the appropriate response.
- If spills represent an imminent threat of escaping erosion and sediment controls and entering receiving waters, personnel will be directed to respond immediately to contain the release and notify the superintendent after the situation has been stabilized.
- Spill kits containing appropriate materials and equipment for spill response and cleanup will be maintained by the Contractor at the site.
- If oil sheen is observed on surface water (e.g. settling ponds, detention ponds, swales), action will be taken immediately to remove the material causing the sheen. The Contractor will use appropriate materials to contain and absorb the spill. The source of the oil sheen will also be identified and removed or repaired as necessary to prevent further releases.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	2017 SF Area Erosion Plans	9	27

- If a spill occurs the superintendent or the superintendent's designee will be responsible for completing the spill reporting form and for reporting the spill to SD DENR.
- Personnel with primary responsibility for spill response and clean up will receive training by the Contractor's site superintendent or designee. The training must include identifying the location of the spill kits and other spill response equipment and the use of spill response materials.
- Spill response equipment will be inspected and maintained as necessary to replace any materials used in spill response activities.

#### SPILL NOTIFICATION

In the event of a spill, the Contractor's site superintendent will make the appropriate notification(s), consistent with the following procedures:

- A release or spill of a regulated substance (includes petroleum and petroleum products) must be reported to DENR immediately **if any one of the following** conditions exists:
  - The discharge threatens or is in a position to threaten the waters of the state (surface water or ground water).
  - The discharge causes an immediate danger to human health or safety.
  - The discharge exceeds 25 gallons.
  - The discharge causes a sheen on surface water.
  - The discharge of any substance that exceeds the ground water quality standards of ARSD (Administrative Rules of South Dakota) chapter 74:51:01.
  - The discharge of any substance that exceeds the surface water quality standards of ARSD chapter 74:51:01.
  - The discharge of any substance that harms or threatens to harm wildlife or aquatic life.
  - The discharge of crude oil in field activities under SDCL (South Dakota Codified Laws) chapter 45-9 is greater than 1 barrel (42 gallons).

To report a release or spill, call DENR at 605-773-3296 during regular office hours (8 a.m. to 5 p.m. Central time). To report the release after hours, on weekends or holidays, call State Radio Communications at 605-773-3231. Reporting the release to DENR does not meet any obligation for reporting to other state, local, or federal agencies. Therefore, the responsible person must also contact local authorities to determine the local reporting requirements for releases. DENR recommends that spills also be reported to the National Response Center at (800) 424-8802.

#### **CONSTRUCTION CHANGES (4.4)**

When changes are made to the construction project that will require alterations in the temporary erosion controls of the site, the Storm Water Pollution Prevention Plan (SWPPP) will be amended to provide appropriate protection to disturbed areas, all storm water structures, and adjacent waters. The SDDOT Project Engineer will modify the SWPPP plan (DOT 298) and drawings to reflect the needed changes. Copies of changes will be routed per DOT 298. Copies of forms and the SWPPP will be retained in a designated place for review over the course of the project.

#### **CERTIFICATIONS**

#### > Certification of Compliance with Federal, State, and Local Regulations

The Storm Water Pollution Prevention Plan (SWPPP) for this project reflects the requirements of all local municipal jurisdictions for storm water management and sediment and erosion control as established by ordinance, as well as other state and federal requirements for sediment and erosion control plans, permits, notices or documentation as appropriate.

#### > South Dakota Department of Transportation

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Ton hall

Authorized Signature (See the General Permit, Section 6.9.1.C.)

#### Prime Contractor

This section is to be executed by the General Contractor after the award of the contract. This section may be executed any time there is a change in the Prime Contractor of the project.

I certify under penalty of law that this document and all attachments will be revised or maintained under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Authorized Signature	· · · · · · · · · · · · · · · · · · ·

#### **CONTACT INFORMATION**

#### Contractor Information:

	Prime Contractor Name:		
	Contractor Contact Name: _		
	Address:		_
	City:	State:	Zip:
•	Office Phone:	Field:	
•	Cell Phone:	Fax:	
Er	osion Control Supervisor		
•	Name:		
•	Address:		_
			_
	City:	State:	Zip:
•	Office Phone:	Field:	
•	Cell Phone:	Fax:	
SE	DOT Project Engineer		
•	Name:		
•	Business Address:		<del></del>
•	Job Office Location:		
•	City:	State:	Zip:
•	Office Phone:	Field:	
•	Cell Phone:	Fax:	
SE			

- Business Hours Monday-Friday (605) 773-3296
- Nights and Weekends (605) 773-3231
- > SD DENR Contact for Hazardous Materials.
  - **(605)** 773-3153
- > National Response Center Hotline
  - **(800)** 424-8802.

STATE OF	PROJECT	SHEET	TOTAL
SOUTH DAKOTA	2017 SF Area Erosion Plans	10	27

1	STATE OF	PROJECT	SHEET	TOTAL SHEETS
ı	SOUTH			SHEETS
ı	DAKOTA	2017 SF Area Erosion Plans	11	27

## TABLE FOR EROSION CONTROL FOR 090 E-271 PCN I4QA

		110E0600	110E7500	110E7510	120E0100	120E0600	120E6300	230E0020	230E0100	450E9000	450E9001	620E0030	620E1020	700E0210	730E0251	732E0200	734E0042	734E0103	734E0133	734E0154	734E0510	831E0110
			REMOVE	REMOVE		CONTRACTOR	WATER		REMOVE		RESET				SPECIAL			TYPE 3	TYPE 3 TURF	12" DIAMETER	SHAPING	
	090 E-271		PIPE	PIPE		FURNISHED	FOR	CONTRACTOR	AND		PIPE	TYPE 3			PERMANENT			EROSION	TURF	EROSION	FOR EROSION	TYPE B
	PCN I4QA	REMOVE	FOR	<b>END FOR</b>	UNCLASSIFIED	BORROW	VEGET-	FURNISHED	REPLACE	RESET	END	ROW	2 POST	CLASS B	SEED	FIBER	SOIL	CONTROL	REINFOR-	CONTROL	CONTROL	DRAINAGE
	SQUARE	FENCE	RESET	RESET	EXCAVATION	EXCAVATION	ATION	TOPSOIL	TOPSOIL	PIPE	SECTION	FENCE	PANEL	RIPRAP	MIXTURE (1)	MULCHING	STABILIZER	BLANKET	CEMENT MAT	WATTLE	BLANKET	FABRIC
	FOOTAGE	FT	FT	EACH	CUYD	CUYD	MGAL	CUYD	LS	FT	EACH	FT	EACH	TON	LB	TON	SQYD	SQYD	SQYD	FT	FT	SQYD
LOCATION	WORK AREA																					
396.719	680				0	2	0.7	1							0.66	0.02	75.6	75.6	0	10	85	0
	85 x 8																	85 x 8				
397.170	2800				0	17	2.8	9							2.70	0.1	311.1	311.1	0	20	350	0
	350 x 8																	350 x 8				
397.300	1880				0	29	1.9	6							1.81	0.06	208.9	0	208.9	20	0	0
	235 x 8																		235 x 8			
398.090	25600	900			1000		25.6		LS			900	2		24.68	0.21	2844.4	2133.3		70	800	
	800x32																	800x24				
398.201	240		16	1						16	1				0.23			26.7			30	
	8 x 30																	30 x 8				
400.934	256				0	63	0.3	1						48.0	0.25	0.01	28.4	0	28.4	0	0	82
	32 x 8																		32 x 8			<u>1</u>
	TOTALS:	900	16	1	1000	111	31.3	17	LS	16	1	900	2	48.0	30	0.4	3472.3	2547	237.3	120	1265	82

## TABLE FOR EROSION CONTROL FOR 090 W-271 PCN I4QC

		120E0600	120E4100	120E6300	230E0020	730E0251	732E0200	734E0042	734E0103	734E0133	734E0154	734E0510
		CONTRACTOR				SPECIAL			TYPE 3	TYPE 3	12" DIAMETER	SHAPING
	090 W-271	FURNISHED		WATER	CONTRACTOR	PERMANENT			EROSION	TURF	EROSION	FOR EROSION
	PCN I4QC	BORROW	REPROFILE	FOR	FURNISHED	SEED	FIBER	SOIL	CONTROL	REINFORCEMENT	CONTROL	CONTROL
	SQUARE	EXCAVATION	DITCH	VEGETATION	TOPSOIL	MIXTURE (1)	MULCHING	STABILIZER	BLANKET	MAT	WATTLE	BLANKET
	FOOTAGE	CUYD	STA.	MGAL	CUYD	LB	TON	SqYd	SQYD	SQYD	FT	FT
LOCATION	WORK AREA											
397.494	920	28	0	0.9	6	0.89	0.01	102.2	0	102.2	20	0
	115 x 8									115 x 8		
399.31 to 399.36 Ramp	8000	0	5.0	8	0	7.71	0.09	888.9	444.4	0	50	500
	500 x 16								500 x 8			
	TOTALS:	28	5.0	8.9	6	9	0.1	1002.1	444	102.2	70	500

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH			SHEETS
DAKOTA	2017 SF Area Erosion Plans	12	27

## TABLE FOR EROSION CONTROL FOR 029 N-271 PCN I4QD

		120E0100	120E0600 CONTRACTOR	120E6300	230E0100 REMOVE	230E0020	450E4759	450E760	450E5406	450E5407	730E0251 SPECIAL	732E0200	734E0042	734E0103 TYPE 3	734E0133 TYPE 3 TURF	734E0154 12" DIAMETER	831E0110 TYPE
	029 N-271		FURNISHED	WATER	AND	CONTRACTOR	18" CMP		18" CMP	18" CMP	PERMANENT			EROSION	REINFOR-	EROSION	В
	PCN I4QD	UNCLASSIFIED	BORROW	FOR	REPLACE	FURNISHED	16 GAUGE	18" CMP	SAFETY END	SAFETY END	SEED	FIBER	SOIL	CONTROL	CEMENT	CONTROL	DRAINAGE
	SQUARE	EXCAVATION	EXCAVATION	VEGETATION	TOPSOIL	TOPSOIL	FURNISH	INSTALL	FURNISH	INSTALL	MIXTURE (1)	MULCHING	STABILIZER	BLANKET	MAT	WATTLE	FABRIC
	FOOTAGE	CUYD	CUYD	MGAL	LS	CUYD	FT	FT	EACH	EACH	LB	TON	SQYD	SQYD	SQYD	FT	SqYd
LOCATION	WORK AREA																
78.87 MEDIAN	3680	0	225	3.7	0	0	50	50	2	2	3.55	0.14	408.9	404	0	20	0
	80 x 46													Various			
79.72	1800	0	0	1.8	0	22	0	0	0	0	1.74	0.07	200.0	0	200	50	
	75 x 24														75 x 24		
80.76	2800	0	0	2.8	0	52	0	0	0	0	2.70	0.11	311.1	311.1	0	0	0
	175 x 16													175 x 16			
80.86 RAMP	880	0	0	0.9	0	16	0	0	0	0	0.85	0.03	97.8	97.8	0	0	0
	110 x 8													110 x 8			
80.893 RAMP	1200	0	0	1.2	0	15	0	0	0	0	1.16	0.04	133.3	133.3	0	80	0
	75 x 16													75 x 16			
81.1 RAMP	2960	0	0	3	0	36	0	0	0	0	2.85	0.11	328.9	328.9	0	50	0
	185 x 16													185 x 16			
82.251 MEDIAN	7800	144	0	0	0	0	0	0	0	0	0.00	0	0.0	0	0	0	867
	52 x 150																
81.8 TO 82.04	21600	0	0	21.6	LS	0	0	0	0	0	20.83	0.5	2400.0	800	102.2	20	0
	900 x 24													900 x 8	115 x 8		1
	TOTALS:	144	225	35.0	LS	141	50	50	2	2	34	1.0	3880.0	2075	302.2	220	867

## TABLE FOR EROSION CONTROL FOR 029 S-271 PCN I4QE

	029 S-271 PCN I4QE SQUARE FOOTAGE	120E0600 CONTRACTOR FURNISHED BORROW EXCAVATION CUYD	120E4100  REPROFILE  DITCH  STA.	120E6300  WATER FOR  VEGETATION  MGAL	230E0020  CONTRACTOR FURNISHED TOPSOIL CUYD	730E0251 SPECIAL PERMANENT SEED MIXTURE (1) LB	732E0200  FIBER  MULCHING  TON	734E0042  SOIL  STABILIZER  SQYD	734E0103 TYPE 3 EROSION CONTROL BLANKET SQYD	734E0133 TYPE 3 TURF REINFORCEMENT MAT SQYD	734E0154 12" DIAMETER EROSION CONTROL WATTLE FT	734E0510 SHAPING FOR EROSION CONTROL BLANKET FT
LOCATION	<b>WORK AREA</b>											
82.773	560	0	0	0.6	3	0.54	0.02	62.2	62.2	0	10	70
	70 x 8								70 x 8			
81.865	2400	0	0	2.4	29	2.31	0.1	266.7	200	66.7	30	75
	75 x 32								75 x 24	75 x 8		
81.720	240	0	0	0.2	4	0.23	0.01	26.7	0	0	10	0
	30 x 8											
81.717	400	17	0	0.4	2	0.39	0.01	44.4	0	44.4	10	50
	50 x 8									50 x 8		
81.716	240	0	0	0.2	3	0.23	0.01	26.7	26.7	0	10	0
	30 x 8								30 x 8			
76.640	1200	0	1.5	1.2	0	1.16	0.05	133.3	0	133.3	0	150
	150 x 8									150 x 8		
	TOTALS:	17	1.5	5	41	5	0.2	560.0	289	244.4	70	345

1	STATE OF	PROJECT	SHEET	TOTAL SHEETS
ı	SOUTH DAKOTA	2017 SF Area Erosion Plans	12	27
•	DAROTA	2017 OF AIRA EIUSIUII FIAIIS	13	21

## TABLE FOR EROSION CONTROL FOR 229 N-271 PCN I4QF

						- 1 OIX E		_									
		110E0300	120E0100	120E0600	120E6300	230E0100	230E0020	380E6110	650E4695	700E0210	730E0251	732E0200	734E0042	734E0103	734E0154	734E0510	831E0110
				CONTRACTOR		REMOVE		INSTALL	TYPE		SPECIAL			TYPE 3	12" DIAMETER	SHAPING FOR	
	229 N-271	REMOVE		FURNISHED	WATER	AND	CONTRACTOR	STEEL BAR	P9.5		PERMANENT			EROSION	EROSION	EROSION	TYPE B
	PCN I4QF	CONCRETE	LINCL ASSISIED		FOR	REPLACE	FURNISHED	IN PCC	CONCRETE	CLASS B	SEED	FIBER	SOIL	CONTROL	CONTROL	CONTROL	DRAINAGE
		_	UNCLASSIFIED		_						_						
	SQUARE	GUTTER	EXCAVATION	EXCAVATION	VEGETATION	TOPSOIL	TOPSOIL	PAVEMENT	GUTTER	RIPRAP	. , ,		STABILIZER	BLANKET	WATTLE	BLANKET	FABRIC
	FOOTAGE	FT	CUYD	CUYD	MGAL	LS	CUYD	EACH	FT	TON	LB	TON	SQYD	SQYD	FT	FT	SQYD
LOCATION	WORK AREA																
8.86 TO 9	16320	0	17	0	16.3	LS	0	0	0		15.74	0.16	1813.3	604.4	0	680	0
	680 x 24													680 x 8			
8.800	112	0	8	0	0.1	0	0	0	0	12.0	0.11	0	12.4	0	0	0	22
	8 x 14																
8.61 TO 8.7	11760	0	0	0	11.8	LS	0	0	0		11.34	0.17	1306.7	0	0	0	0
	490 x 24																
5.95 TO 6.30	41592	0	0	0	41.6	LS	0	0	0		40.10	0.4	4621.3	1540.4	0	1733	0
	1733 x 24													1733 x 8			
3.213 RAMP	9760	0	0	0	9.8	LS	22	0	0		9.41	0.07	1084.4	542.2	0	610	0
	610 x 16													610 x 8			
0.906 BRIDGE	800	66	0	11	0.8	0	10	25	66		0.77	0	88.9	88.9	30	100	0
	100 x 8													100 x 8			
0.905	240	0	0	0	0.2	0	6	0	0		0.23	0	26.7	26.7	0	30	0
	30 x 8													30 x 8			
	TOTALS:	66	25	11	80.6	LS	38	25	66	12.0	78	0.8	9012.3	2803	30	3153	22

## TABLE FOR EROSION CONTROL FOR 229 S-271 PCN I4QG


PCN I4QG   SQUARE   FOR   FURNISHED   CLASS B   SEED   FIBER   SOIL   CONTROL   CONTROL   CONTROL   CONTROL   FABRICATION   FOR   FURNISHED   TOPSOIL   FURNISHED   TOPSOIL   FURNISHED   TOPSOIL   FURNISHED   TOPSOIL   TOPSOI			120E0100	120E4100	120E6300	230E0020	700E0210	730E0251	732E0200	734E0042	734E0103	734E0154	734E0510	831E0110
PCN								SPECIAL			TYPE 3	12" DIAMETER	SHAPING	
SQUARE FOOTAGE   FOOTAGE		229 S-271			WATER	CONTRACTOR		PERMANENT			EROSION	EROSION	FOR EROSION	TYPE B
COLOM   FOOTAGE   CUYD   STA.   MGAL   CUYD   TON   LB   TON   SQYD   SQYD   FT   FT   SQYD		PCN I4QG	UNCLASSIFIED	REPROFILE	FOR	FURNISHED	CLASS B	SEED	FIBER	SOIL	CONTROL	CONTROL	CONTROL	DRAINAGE
LOCATION         WORK AREA         WORK AREA <th< th=""><th></th><th>SQUARE</th><th>EXCAVATION</th><th>DITCH</th><th>VEGETATION</th><th>TOPSOIL</th><th>RIPRAP</th><th>MIXTURE (1)</th><th>MULCHING</th><th>STABILIZER</th><th>BLANKET</th><th>WATTLE</th><th>BLANKET</th><th>FABRIC</th></th<>		SQUARE	EXCAVATION	DITCH	VEGETATION	TOPSOIL	RIPRAP	MIXTURE (1)	MULCHING	STABILIZER	BLANKET	WATTLE	BLANKET	FABRIC
9.96       360       53       0       0.4       0       75.0       0.35       0.01       40.0       0       0       0       0       120         9.96       720       0       0       0.7       13       0.69       0.02       80.0       80       90       90       9       0         90 x 8       90 x 8       90 x 8       90 x 8       90       90       0		FOOTAGE	CUYD	STA.	MGAL	CUYD	TON	LB	TON	SQYD	SQYD	FT	FT	SQYD
90 x 4	LOCATION	WORK AREA												
9.96       720       0       0       0.7       13       0.69       0.02       80.0       80       90       90       0         90 x 8	9.96	360	53	0	0.4	0	75.0	0.35	0.01	40.0	0	0	0	120
90 x 8 0.95 2400 0 2.0 2.4 4 2 2.31 0.07 266.7 177.8 10 200 0 200 x 12 200 x 8		90 x 4												
0.95     2400     0     2.0     2.4     4     2.31     0.07     266.7     177.8     10     200     0       200 x 12     200 x 8     200 x 8     200 x 8     200 x 8     0	9.96	720	0	0	0.7	13		0.69	0.02	80.0	80	90	90	0
200 x 12 200 x 8		90 x 8									90 x 8			
	0.95	2400	0	2.0	2.4	4		2.31	0.07	266.7	177.8	10	200	0
		200 x 12				·					200 x 8			
TOTALS: 53 2.0 3.5 1/ /5.0 3 0.1 387.7 258 100 290 120		TOTALS:	53	2.0	3.5	17	75.0	3	0.1	387.7	258	100	290	120


STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH			SHEETS
DAKOTA	2017 SF Area Erosion Plans	14	27


Plotting Date: 05/01/2017


# TYPICAL SECTION 090 E-271 MRM 398.07 TO 398.24


158+00 to 166+00












STATE OF SOUTH DAKOTA 2017 SF Area Erosion Plans 18 27

Plotting Date: 05/18/2017

Wall "†"	Rod Dia.	Pipe Sleeve Dia.		GENERAL NOTES:
≤ 3 <sup>1</sup> / <sub>4</sub> 3 <sup>1</sup> / <sub>2</sub> -6 <sup>1</sup> / <sub>2</sub> ≥ 7	5/8 3/4 I	3/4 I I <sup>1</sup> / <sub>4</sub>		Tie bolts shall conform to ASTM F1554 Grade 36 or ASTM A36. Nuts shall be heavy hex conforming to ASTM A563. Washers shall conform to ASTM F436.
			tside Edge	Pipe Sleeve shall conform to ASTM A500 or A53, Grade B.
		GHOIE	F Joint E Hole 16" _1	Galvanize adjustible eye bolt tie assembly in accordance with ASTM AI53.
Pipe Sle Welded (			+	—ASTM F1554 Grade 36 or ASTM A36 Tie Bolt with 2 Heavy Hex Nuts and 2 Washers
ASTM F155 36 or AST Rod with I Hex Nut a	M A36	32" (±1½"		



ADJUSTABLE EYE BOLT TIE


#### GENERAL NOTES:

Angles shall conform to ASTM A36.

Bolts shall conform to ASTM A307. Nuts shall be heavy hex conforming to ASTM A563. Washers shall conform to ASTM F436.

Galvanize angles, bolts, nuts, and washers in accordance with ASTM A153.

#### GENERAL NOTES:



In lieu of the tie bolts detailed above other types of tie bolt connections may be installed as approved by the Office of Bridge Design.

All pipe sections of R.C.P. and R.C.P. Arch shall be tied with tie bolts except for pipe located between drop inlets, manholes, and junction boxes. All pipe sections of pipes that only enter or exit drop inlets, manhole, and junction boxes shall be tied with tie bolts.

There will be no separate measurement or payment for the tie bolts. The cost for furnishing and installing the tie bolts shall be incidental to the contract unit price per foot for the corresponding bid item for R.C.P. or R.C.P. Arch.

February 28, 2013

TIE BOLTS FOR R.C.P. AND R.C.P. ARCH

PLATE NUMBER
450.18

Sheet I of I


Published Date: 2nd Qtr. 2017

"CIRCULAR"

D D

S

"ARCH"



STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	2017 SF Area Erosion Plans	19	27

Plotting Date: 05/18/2017

		Δ	RCH	C.M.I	P. S	SAF	<u>ETY</u>	ENDS		
Equv.	(Incl	nes)	Min.	Thick.	Dim	ens	ions	(Inches)	L Dim	ensions
Dia. (Inch)	Span	Rise	Inch	Gage	Α	Н	W	Overall Width	Slope	Length (Inch)
18	21	15	.064	16	8	6	27	43	6 <b>:</b> I	30
21	24	18	.064	16	8	6	30	46	6 <b>:</b> I	48
24	28	20	.064	16	8	ဖ	34	50	6 <b>:</b> I	60
30	35	24	.079	14	12	9	41	65	6 <b>:</b> I	84
36	42	29	.109	12	12	9	48	72	6 <b>:</b> I	114
42	49	33	.109	12	16	12	55	87	6:1	138
48	57	38	.109	12	16	12	63	95	6 <b>:</b> I	168
54	64	43	.109	12	16	12	70	102	6 <b>:</b> I	198
60	71	47	.109	12	16	12	77	109	6 <b>:</b> I	222
72	83	57	.109	12	16	12	89	121	6 <b>:</b> I	282

	CIRCULAR C.M.P. SAFETY ENDS										
Pipe	Min.	Thick.	Dim	ensi	ions	(Inches)	L Dime	ensions			
Dia. (Inch)	Inch	Gage	Α	Н	w	Overall Width	Slope	Length (Inch)			
15	.064	16	8	6	21	37	6 <b>:</b> I	30			
18	.064	16	8	6	24	40	6 <b>:</b> I	48			
21	.064	16	8	6	27	43	6 <b>:</b> I	66			
24	.064	16	8	6	30	46	6 <b>:</b> I	84			
30	.109	12	12	9	36	60	6:1	120			
36	.109	12	12	9	42	66	6:1	156			
42	.109	12	16	12	48	80	6 <b>:</b> I	192			
48	.109	12	16	12	54	86	6:1	228			
54	.109	12	16	12	60	92	6 <b>:</b> I	264			
60	.109	12	16	12	66	98	6:1	300			

#### GENERAL NOTES:

Safety ends shall be fabricated from galvanized steel conforming to the requirements of the Specifications.

Safety bars shall be fabricated from steel schedule 40 pipe in conformance with ASTM A53, grade B or HSS 3.5X.216 in conformance with ASTM A500, grade B.

Slotted holes for safety bar attachment shall be provided for all end sections.

Attachment to circular pipes 15" through 24" diameter shall be made with Type #1 straps. All other sizes shall be attached with Type #2 rods and lugs.


When stated in the plans, optional toe plate extension shall be punched and bolted to end section apron lip with  $\frac{3}{8}$ " diameter galvanized bolts. Steel for toe plate extension shall be same gauge as end section. Dimensions shall be overall width less 6" by 8" high.

Installation shall be performed in accordance with the Specifications.

Cost of all work and materials required for fabrication and installation of safety ends shall be incidental to the bid items for the various sizes of safety ends.

June 26, 2015

	C. M. P. SAFETY END	C. M. P. SAFETY ENDS	PLATE NUMBER 450.38	
Published Date: 2nd Qtr. 2017			Sheet 2 of 2	



BARBED WIRE

NUMBER AND

SHAPE OF

BARBS

14'-0" or 16'-6"

14'-0" or 16'-6"

-121/2ga. Barbed

Rd. Barbs

TYPE

3 BARBED WIRES

TYPE 4

26" WOVEN WIRE

WITH 2 BARBED WIRES

TYPE OF FENCE

TYPE DESCRIPTION

I 3 Barbed Wires 2 4 Barbed Wires

3 5 Barbed Wires

26" Woven Wire

Wire with 2 Pt.

-12½ga. Barbed Wire with 2 Pt.

726-6-121/2

Woven Wire

WIRE

Rd. Barbs

14'-0" or 16'-6"

14'-0" or 16'-6"

Wood Post

└─121/2ga. Barbed

7Rd.Barbs

Wire with 2 Pt.

121/2ga. Barbed

Wire with 2 Pt.

726-6-121/2

Woven Wire

¹-12½ga. Barbed

Rd. Barbs

Wire with 4 Pt.

Rd. Barbs

(Typ.)

31/2" Dia. x 6'-6"

ALL WOOD POSTS

ALTERNATE WOOD AND STEEL POSTS

TYPE 2

4 BARBED WIRES

TYPE 5

26" WOVEN WIRE

WITH 4 BARBED WIRES

 $3\frac{1}{2}$ " Dia. x 6'-6" Wood Post (Typ.)

5'-6" long Steel Post

anchor plate iš 7.99

·121/2ga. Barbed Wire with 2 Pt.

121∕₂ga. Barbed

Wire with 2 Pt.

Rd. Barbs

*−*832-6-12<sup>1</sup>/<sub>2</sub>

Woven Wire

└─12½ga.Barbed

Rd. Barbs

Wire with 4 Pt.


Rd. Barbs

Weight including

pounds ±5% (Typ.)

PROJECT TOTAL SHEETS STATE OF SHEET 2017 SF Area Erosion Plans 20 27 DAKOTA

Plotting Date: 05/18/2017



#### STAPLE INSTALLATION

#### GENERAL NOTES:

The Right-of-Way fence shall consist of barbed wire or a combination of woven wire and barbed wire. The barbed wire and/or woven wire shall be fastened to all wood posts or fastened to alternating wood and steel posts. Only wood posts shall be used for brace panels. Gates shall be of the type designated in the plans or as otherwise directed by the Engineer. Fence shall be constructed conforming to the details on the standard plates and in the plans unless otherwise directed by the Engineer.

Right-of-Way fence on Interstate Projects shall be constructed one foot within the Interstate Right-of-Way lines except at bridge openings, cattle passes, and as otherwise directed by the Engineer.

Right-of-Way fence other than on Interstate Projects shall be constructed within one foot of the Right-of-Way on the Landowner's side except at bridge openings, cattle passes, and as otherwise directed by the Engineer.

Barbs shall be fabricated from zinc coated 14 ga. wire. Two point barbs shall be wrapped twice around one main strand at 4" spacings and the four point barbs shall be interlocked and wrapped around both main strands at 5" spacings.

The gages of wire and wood post lengths and sizes are the minimum acceptable unless otherwise specified in the plans. The tolerances for steel posts shall be as stated in AASHTO M281. Woven wire shall conform to design and specifications of ASTM All6 and barbed wire shall conform to ASTM Al21.

PLATE NUMBER STAPLE INSTALLATION AND GENERAL 620.02 RIGHT-OF-WAY FENCE NOTES Sheet I of I

Published Date: 2nd Otr. 2017

D D 0

December 23, 2004

Sheet | of |

PLATE NUMBER

2 Point Round 2 Point Round

WOVEN WIRE

STYLE OR

DESIGN NO.

letter S shall have smooth (barbless) wires.

TYPE 6

32" WOVEN WIRE

WITH 3 BARBED WIRES

Fence types designated on the

plans that are followed by the

GENERAL NOTES:

TYPE 3

5 BARBED WIRES

When type 5S or 6S is designated

the bottom wire may be barbed, smooth or left off.

All degrees of curvature stated for fence are at centerline of roadway. September 14, 2009

620.01

Horizontal Wood-

Brace

5" Dia. x 8'-0

Wood Posts

Horizontal Wood-

∕5" Dia.× 8'-0"

GENERAL NOTES:

(Typ.)

Diagonal -

Brace Wires

Wood Posts ELEVATION VIEW

3 POST PANEL

(Typ.)

Brace

Published Date: 2nd Qtr. 2017

directed by the Engineer.






PLATE NUMBER Sheet I of 3

Place diagonal brace wire

Direction of

Fence Pull

3 loops of II Ga. wire -7 tightly wrapped, tied,

and stapled around

DETAIL B

of fence pull.

DETAIL A

posts

4" to 6" Space -Between Posts

that corresponds to direction

Place ½"Dia. x 4"steel

dowel at center of end

of horizontal wood brace

Drill 1/2" Dia. hole in post

and in horizontal brace for steel dowel placement

Staple (Typ.)

2 turns of II Ga. wire —

to stop splitting

Diagonal — Brace Wires

**ELEVATION VIEW** 

2 POST PANEL

or 3 turns of 121/2Ga. wire

2 turns of II Ga. wire

to stop splitting

Two Post Panels shall be installed at least every 1320' between corners.

Two Post Panels shall be installed at any sharp vertical angle crest points and as

Horizontal wood braces shall consist of 4" dia. x 8' wood posts or rough 4" x 4" x 8' timbers.

tight. The diagonal brace wires shall be installed in accordance with the direction of the

Diagonal brace wires shall be fabricated with 4 strands of 9 Ga. galvanized wire twisted

fence pull. Two diagonal brace wires are required if fence pull is in both directions.

or 3 turns of 121/2Ga. wire


See Detail A

Provide shallow notch-


horizontal wood brace.

in brace post to accept

-See Detail A




Plotting Date: 05/18/2017



PROJECT TOTAL SHEETS SHEET STATE OF 2017 SF Area Erosion Plans 22 27 DAKOTA

Plotting Date: 05/18/2017



or cable crossing.

Ground rods shall be located on the post side of the fence and shall be as close as possible to the post and fence.

The cost of furnishing and placing all materials for grounding shall be incidental to the contract unit price per Ft for the respective Right-of-Way fence or chain link fence bid item.

The approximate quantites of materials per each installation of a ground are:

- ground rod clamp.
- $\frac{5}{8}$ " dia. X 8' long copper clad ground rod
- #6 AWG bare copper wire; 7' long for Right-of-Way fence or 10' long for chain link fence.

Compression type or other type of connectors: 26" woven wire shall have a total of two connectors.

one secured to the top and one secured to the bottom. GROUND ROD DETAIL 32" woven wire shall have a total of three connectors, one secured to the top, one secured to the middle, and one secured to the bottom. One connector shall be used for each strand of barbed wire.

A minimum of 3 connectors shall be installed on chain link fence, the connectors shall be placed vertically at every two foot increment and connectors shall be placed on the top and bottom tension wires or top rail.

March 31, 2000

#6 AWG Bare

Ground Rod Clamp

Copper Wire

PLATE NUMBER D 620.11  $\overline{D}$ FENCE GROUNDING 0 Published Date: 2nd Qtr. 2017 Sheet I of I

Spacing of Spacing of Posted Speed Advance Warning Taper Channelizing Prior to Signs .ength Devices ○ Reflectorized Drum Work (Feet) (Feet) (Feet) (M.P.H.) (A) (B) (C) (G) ■ Channelizing Device 0 - 30 200 180 25 350 500 500 750 1000 320 600 25 25 50 \* ☐ Movable Concrete Barrier 45 50 \*\* For distances  $\frac{1}{2}$  mile or greater. 600 50 **\*** 660 780 60 - 65 (A) (B) 70 - 80 1000 1500 1125 50 \* 42" cones may be used in place \* Spacing is 40' for 42" cones. of the drums shown in the taper if setup will not be used during night time hours. ROAD WORK This standard plate shows one G20-2 (Optional) method which may be used to close a shoulder of a roadway for a long term project. The Highway Authority will determine if the use of barriers is -Delineation required. If barriers are required, the layout details will be included elsewhere in the plans. Type 3 Barricade RIGHT SHOULDER CLOSED / NO RIGHT SHOULDER CLOSED AHEAD ROAD WORK AHEAD June 3, 2016 S D D O T PLATE NUMBER **GUIDES FOR TRAFFIC CONTROL DEVICES** 634.61 SHOULDER CLOSED Published Date: 2nd Qtr. 2017 Sheet I of I

STATE OF	PROJECT	SHEET	TOTAL SHEETS	
SOUTH			SHEETS	
DAKOTA	2017 SF Area Erosion Plans	23	27	

Plotting Date: 05/18/2017

ā

VSTANDABDD ATES DGN

Spacing of Advance Warning

Signs (Fee†) (A) (B) (C)

350 500 750

(A) (B) (C) 70 - 80 1000 1500 2640

\*\* Speed appropriate for location.

ROAD WORK AHEAD sign is only required in advance of the first lane closure.

High speed is defined as having a posted speed limit greater than 45 mph.

Posted Speed Prior to

Work (M.P.H.)

0 - 30 35 - 40 45 - 50 55

60 - 65

 Reflectorized Drum ■ Channelizing Device

Published Date: 2nd Qtr. 2017

S D D O T WORK ZONE SPEED REDUCTION FOR INTERSTATE AND HIGH SPEED MULTI-LANE HIGHWAYS

В <

8 2

0 ~

0/2

PLATE NUMBER *634.63* 

June 3, 2016

-SEE DETAIL A

on Sheet 2 of 2

SPEED LIMIT 65

RIGHT LANE CLOSED AHEAD

ROAD WORK AHEAD

Sheet I of 2

Posted Spacing of Speed Channelizing Tape Prior to Devices Lengt Work (Feet) (Feet) (Feet) (M.P.H.) (G) (L) 0 - 30 25 180 35 - 40 25 320 45 25 600 50 50 8 660 60 - 65 50 8 780 70 - 80 50 8 960 8 Spacing is 40' for 42" cones.  **Speed appropriate for locat the condition when workers present in the work space. Signs shall be covered or removed when workers are not present.  Flagger (As Necessary)  Reflectorized Drum Channelizing Device The Work Space shall be a minimum of 500' from the end of the taper.  The FLAGGER sign shall be used whenever there is a Flagger present.  The channelizing devices shall be 42" cones or drums.  4" white temporary pavement arking left lane closures, or temp markers at 5' spacing shall to the taper when the lane overnight, and along the tar where the skip lines do not lane is closed for more the	th)	rking "yellow pe for y road nstalled closed t section st and the days.	SPEED **  R2-1  SPEED **  SPEED **  SPEED **  LIMIT 65  R2-1  **  FINES DOUBLE R2-6aP  (As Necessary)  W Board
			w Board Fial Chevron
		DETAIL A	June 3, 2016
	S D D	WORK ZONE SPEED REDUCTION FOR INTERSTATE AND HIGH	PLATE NUMBER 634.63
Published Date: 2nd Qtr. 2017	O T	SPEED MULTI-LANE HIGHWAYS	Sheet 2 of 2

PROJECT

2017 SF Area Erosion Plans

SHEET

24

TOTAL SHEETS

27

STATE OF


DAKOTA

Plotting Date: 05/18/2017

Temporary pavement markings shall be used if traffic control must remain overnight.  The channelizing devices shall be drums or 42" cones if traffic control must remain overnight.  Truck off-tracking should be considered when determining whether the IO-foot minimum lane width is adequate.	SDD	GUIDES FOR TRAFFIC CONTROL DEVICES	June 3, 2016  PLATE NUMBER 634.69
Channelizing Device  4" White Temporary Pavement Marking  ** Need and safe speed to be determined by the Highway Authority.		RAMINARRO  *** Wi3-li (Option	ws /
Posted Spacing of Channelizing Prior to Work (Feet) (G) 0 - 30 25 35 - 45 25 50 \$50 \$55 50 \$\$\$ 60 - 80 50 \$*\$\$  * Spacing is 40' for 42" cones.		WORK SPACE	ROBA WORK
Posted   Spacing of   Speed   Advance Warning   L		IO' (Min.)	

PROJECT TOTAL SHEETS STATE OF SHEET 2017 SF Area Erosion Plans 25 27 DAKOTA

Plotting Date: 05/18/2017



\* Joint will not be needed if concrete curb and gutter and type P concrete gutter is placed at the same time. If the  $\frac{1}{2}$  Preformed Expansion Joint Filler is provided, then the joint shall be sealed in accordance with Standard Plate 650.90.

The concrete for the Type P Concrete Gutter shall comply with the requirements of the Specifications for Class M6 Concrete.

When concrete gutter longitudinally adjoins new concrete pavement, the method of attachment shall be by one of the methods shown on Standard Plate 380.11.

Transverse contraction joints shall be constructed at 10' intervals in the concrete gutter except when concrete gutter is constructed adjacent to mainline PCC pavement. When concrete gutter is constructed adjacent to mainline PCC pavement, a transverse contraction joint shall be constructed in the concrete gutter at each mainline PCC pavement transverse contraction joint location.


When concrete gutter is placed monolithically with mainline PCC pavement, the transverse contraction joints in the concrete gutter shall be sawed and sealed the same as the transverse contraction joints in the mainline PCC pavement.

When concrete gutter is not placed monolithically with the mainline PCC pavement and when the adjacent mainline surfacing is not PCC concrete, the transverse contraction joints in the concrete gutter shall be  $1\frac{1}{2}$  inches deep if formed in the fresh concrete using a suitable grooving tool. If a saw is used to cut the contraction joints, then the depth of the joint shall be at least  $\frac{1}{4}$  the thickness of the concrete.

June 26, 2015


PLATE NUMBER D *650.30* D TYPE P CONCRETE GUTTER 0 Published Date: 2nd Qtr. 2017 Sheet I of I





PROJECT TOTAL SHEETS STATE OF SHEET 2017 SF Area Erosion Plans 26 27 DAKOTA

Plotting Date: 05/18/2017



#### GENERAL NOTES:

Prior to placement of the erosion control blanket, the areas shall be properly prepared, shaped, seeded, and fertilized.

Erosion control blanket shall be unrolled in the direction of the flow of water when placed in ditches and on slopes. The upslope end of the erosion control blanket shall be buried in a trench 6" wide by 6" deep. There shall be at least a 6" overlap wherever one roll of erosion control blanket ends and another begins, with the upslope erosion control blanket placed on top of the downslope erosion control blanket.

The erosion control blanket shall be pinned to the ground according to the manufacturer's installation recommendations.

After the placement of the erosion control blanket, the Contractor shall fine grade along all edges of the blanket to maintain a uniform slope adjacent to the blanket and level any low spots which might prevent uniform and unrestricted flow of side drainage directly onto the erosion control blanket.

All ditch sections shall be shaped when installing the erosion control blanket. All costs for shaping the ditches shall be incidental to the contract unit price per foot for "Shaping for Erosion Control Blanket".

December 23, 2004

PLATE NUMBER D 734.01 **EROSION CONTROL BLANKET** D 0 Published Date: 2nd Qtr. 2017 Sheet I of I

2%


3%

4%

5%

Excavated Material

from Trench




Spacing Varies (See Table)


See Detail B-


**ELEVATION VIEW** 

CUT OR FILL SLOPE INSTALLATION

#### CUT OR FILL SLOPE INSTALLATION Spacing Slope 10 1:1 2:1 20 3**:**I 30







← Point A Point A Point B-Wood Stake SECTION A-A

December 23, 2004

	S D D	EROSION CONTROL WATTLE	PLATE NUMBER 734.06
Published Date: 2nd Qtr. 2017	<b>O T</b>		Sheet Lof 2

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH			SHEETS
DAKOTA	2017 SF Area Erosion Plans	27	27

Plotting Date: 05/18/2017

#### GENERAL NOTES:

At cut or fill slope installations, wattles shall be installed along the contour and perpendicular to the water flow.

At ditch installations, point A must be higher than point B to ensure that water flows over the wattle and not around the ends.

The Contractor shall dig a 3" to 5" trench, install the wattle tightly in the trench so that daylight can not be seen under the wattle, and then compact the soil excavated from the trench against the wattle on the uphill side. See Detail B.

The stakes shall be I"x2" or 2"x2" wood stakes, however, other types of stakes such as rebar may be used only if approved by the Engineer. The stakes shall be placed 6" from the ends of the wattles and the spacing of the stakes along the wattles shall be 3' to 4'.

Where installing running lengths of wattles, the Contractor shall butt the second wattle tightly against the first and shall not overlap the ends. See Detail C.

The Contractor and Engineer shall inspect the erosion control wattles once every week and within 24 hours after every rainfall event greater than  $\frac{1}{2}$ . The Contractor shall remove, dispose, or reshape the accumulated sediment when necessary as determined by the Engineer.

Sediment removal, disposal, or necessary shaping shall be as directed by the Engineer. All costs for removing accumulated sediment, disposal of sediment, and necessary shaping shall be incidental to the contract unit price per cubic yard for "Remove Sediment".

All costs for furnishing and installing the erosion control wattles including labor, equipment, and materials shall be incidental to the contract unit price per foot for the corresponding erosion control wattle bid item.

All costs for removing the erosion control wattle from the project including labor, equipment, and materials shall be incidental to the contract unit price per foot for "Remove Erosion Control Wattle".

December 23, 2004

PLATE NUMBER D *734.06* **EROSION CONTROL WATTLE**  $\bar{D}$ 0 Published Date: 2nd Qtr. 2017 Sheet 2 of 2