

# **ESTIMATE OF QUANTITIES**

#### I-90 (PCN I7X8)

	. 66 (. 6.1 7.6)		
BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
120E0600	Contractor Furnished Borrow Excavation	101	CuYd
210E1010	Site Preparation	Lump Sum	LS
230E0020	Contractor Furnished Topsoil	34	CuYd
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
734E0010	Erosion Control	Lump Sum	LS
734E0102	Type 2 Erosion Control Blanket	71	SqYd

## I-229 (PCN I7X9)

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
120E0600	Contractor Furnished Borrow Excavation	168	CuYd
210E1010	Site Preparation	Lump Sum	LS
230E0020	Contractor Furnished Topsoil	13	CuYd
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
734E0010	Erosion Control	Lump Sum	LS
734E0102	Type 2 Erosion Control Blanket	36	SqYd

## I-29 (PCN I7X7)

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
120E0600	Contractor Furnished Borrow Excavation	240	CuYd
210E1010	Site Preparation	Lump Sum	LS
230E0020	Contractor Furnished Topsoil	20	CuYd
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
734E0010	Erosion Control	Lump Sum	LS
734E0102	Type 2 Erosion Control Blanket	55	SqYd

## I-29 (PCN I7X6)

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
120E0600	Contractor Furnished Borrow Excavation	100	CuYd
210E1010	Site Preparation	Lump Sum	LS
230E0020	Contractor Furnished Topsoil	14	CuYd
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
734E0010	Erosion Control	Lump Sum	LS
734E0102	Type 2 Erosion Control Blanket	38	SqYd

### **SPECIFICATIONS**

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications and Special Provisions as included in the Proposal.

#### **ENVIRONMENTAL COMMITMENTS**

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: <a href="https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf">https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf</a> >

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

# **COMMITMENT C: WATER SOURCE**

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species (AIS) positive waters within South Dakota without prior approval from the SDDOT Environmental Office. To prevent and control the introduction and spread of invasive species into the project vicinity, all equipment will be power washed with hot water (≥140 °F) and completely dried for a minimum of 7 days prior to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the possession and transport of AIS; therefore, all attached dirt, mud, debris and vegetation must be removed and all compartments and tanks capable of holding standing water must be drained. This includes, but is not limited to, all equipment, pumps, lines, hoses and holding tanks.

The Contractor will not withdraw water directly from streams of the James, Big Sioux, and Vermillion watersheds without prior approval from the SDDOT Environmental Office.

# **Action Taken/Required:**

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Agriculture and Natural Resources (DANR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of water sources impacted by Aquatic Invasive Species in South Dakota can be accessed at:

< https://sdleastwanted.sd.gov/maps/default.aspx>

< South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species: https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04 >

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029-272, 029-271	2	7
DAROTA	090-271, 229-271	-	l '

### COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

## Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

#### COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

### Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

- 1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, "No Dumping Allowed".
- 2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

### **COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES**

State Historic Preservation Office (SHPO or THPO) concurrence has not been obtained for this project.

## **Action Taken/Required:**

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 100 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

The Contractor is responsible for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

## **UTILITIES**

The Contractor will contact the involved utility companies through South Dakota One Call (1-800-781-7474) prior to starting work. It will be the responsibility of the Contractor to coordinate work with the utility owners to avoid damage to existing facilities.

If utilities are identified near the improvement area through the SD One Call Process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25, the Contractor will contact the Engineer to determine modifications that will be necessary to avoid utility impacts.

## **SITE PREPARATION**

The Contractor will prepare the sites to allow for borrow to be placed to the satisfaction of the Engineer. All site preparation will be incidental to the contract lump sum price for "Site Preparation".

### **CONTRACTOR FURNISHED BORROW EXCAVATION**

The Contractor will provide a suitable site for Contractor furnished borrow excavation material. The Contractor is responsible for obtaining all required permits and clearances for the borrow site. The borrow material will be approved by the Engineer. The plans quantity for "Contractor Furnished Borrow Excavation" as shown in the Estimate of Quantities will be the basis of payment for this item.

Restoration of the Contractor furnished borrow excavation site will be the responsibility of the Contractor.

## **CONTRACTOR FURNISHED TOPSOIL**

The Contractor will be required to furnish and place 4 inches of topsoil on areas where borrow is placed and areas as determined by the Engineer during construction.

Contractor furnished topsoil will be free from stones, coarse gravel, or similar objects larger than 3/4 inch in diameter. Brush, stumps, roots, wood, objectionable weeds, liter, or any other material which may be harmful to plant growth will not be allowed. Organic material will be decomposed.

All costs to furnish and place the Contractor furnished topsoil will be incidental to the contract unit price per cubic yard for "Contractor Furnished Topsoil". The plans quantity for "Contractor Furnished Topsoil" as shown in the Estimate of Quantities will be the basis of payment for this item.

## **EROSION CONTROL**

The estimated area requiring erosion control is 6550 square feet. All costs for the erosion control work for furnishing, placing, and maintaining erosion control including equipment, labor, seeding, and mulching will be incidental to the contract lump sum price for "Erosion Control".

The limits of erosion control work will be determined by the Engineer during construction.

# Permanent Seeding

The areas to be seeded consist of all newly graded areas within the project limits except for the top of roadways and temporary easements under cultivation.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029-272, 029-271 090-271, 229-271	3	7

Type G Permanent Seed Mixture will consist of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/Acre)
Western Wheatgrass	Arriba, Flintlock, Rodan, Rosana, Walsh	7
	Dacotah, Forestburg,	3
Switchgrass	Nebraska 28, Pathfinder, Summer, Sunburst, Trailblazer	
Indiangrass	Holt, Tomahawk, Chief, Nebraska 54	3
Big Bluestem	Bison, Bonilla, Champ, Sunnyview, Rountree, Bonanza	3
Oats or Spring Wheat: April through May;		10
Winter Wheat: August through November		
	Total:	26

# Mycorrhizal Inoculum

Mycorrhizal inoculum will consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier will provide certification of the fungal species claimed and the live propagule count. The inoculum will include a minimum 25% the fungal species *Rhizophagus intraradices*. The remaining 75% may include other endomycorrhizal fungal species.

All seed will be inoculated by the seed supplier with a minimum of 100,000 live propagules of mycorrhizal fungi per acre. All costs of inoculating the seed will be incidental to the contract unit price per pound for the corresponding permanent seed mixture.

The Mycorrhizal Inoculum provided will be from the approved product list. The approved product list may be viewed at the following internet site:

https://apps.sd.gov/HC60ApprovedProducts/main.aspx

# Mulching (Grass Hay or Straw) for Temporary Stabilization

Grass Hay or Straw Mulch for temporary stabilization is to be used on this project at locations noted in the table and at locations determined by the Engineer during construction. Two applications of Grass Hay or Straw Mulch on areas that receive temporary Grass Hay or Straw Mulch will not be required if the Engineer determines that there is sufficient Mulch remaining at the time permanent seeding takes place.

If the Contractor uses a no-till drill, mulch may be applied prior to seeding and the mulch can then be punched into the soil by the no-till drill. If the Contractor uses this process, the no-till drill seeding will be completed immediately following the mulch application and the mulch will be punched into the soil at a 3-inch depth.

# **EROSION CONTROL BLANKET**

Erosion control blanket will be installed 16 feet wide at locations determined by the Engineer during construction. A quantity of 200 square yards has been included.

The erosion control blanket provided will be from the approved product list. The approved product list for erosion control blanket may be viewed at the following internet site:

https://apps.sd.gov/HC60ApprovedProducts/main.aspx

# **MAINTENANCE OF TRAFFIC**

Unless otherwise stated in these plans, no work will be allowed during hours of darkness.

Shoulder closures will exist only when required for manned workspaces or haul of materials into the work areas. The shoulders will be opened when manned workspaces or haul of materials is not in progress. Any damage to the shoulder due to Contractor's equipment will be repaired at no additional cost to the State.

During construction all vehicles, equipment, and materials being used must be located within the workspace.

All haul trucks will be equipped with an additional flashing amber light that is visible from the backside of the haul truck. The costs for the flashing amber lights will be incidental to the various related contract items.

# TRAFFIC CONTROL, MISCELLANEOUS

All costs for traffic control, including signs, will be incidental to the contract lump sum price for "Traffic Control, Miscellaneous".

STATE OF	PROJECT	SHEET	TOTAL SHEETS	ı
SOUTH	029-272, 029-271		SHEETS	
	029-212, 029-211		-	
DAKOTA	090-271 229-271	4	/	

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029-272, 029-271	5	7
DAROTA	090-271, 229-271	5	1

	Borrow Excavation (CY)	Contractor Furnished Topsoil (CY)	N.A.B.I. Mulching (Lb)	Type G Permanent Seed Mixture (Lb)
-90 (PCN 17X8)				
MRM 395 EB	32	4	13.8	0.18
Marion Road on ramp				
MRM 390.28 WB	34	2	7.3	0.10
under bridge				
MRM 398.39 WB	35	28	103.3	1.34
30' x 75' total disturbed area				
PCN I7X8 Total:	: 101	34	124.4	1.62
-229 (PCN I7X9)				
MRM 5.6 NB	24	3	10.3	0.13
down steep slope			20.0	0.20
MRM 7.5 SB	52	3	11.5	0.15
MRM 8.16 NB	17	1	5.0	0.06
undermining shoulder	1/	·	5.0	0.00
MRM 8.3 SB	75	6	22.0	0.29
PONUTYO Takal	100	40	40.0	0.00
PCN I7X9 Total:	168	13	48.8	0.63
-29 (PCN I7X7)				
MRM 83 SB	10	2	8.3	0.11
60th Street off ramp				
MRM 81 SB	17	1	3.7	0.05
on ramp				
MRM 79 SB	32	2	9.2	0.12
on ramp				
MRM 81 NB (2 locations)	104	6	23.0	0.30
clover on ramp				
MRM 82 NB (6 locations)	63	7	27.5	0.36
just before off ramp				
MRM 98 NB	14	1	4.1	0.05
just before off ramp				
PCN I7X7 Total:	240	20	75.8	0.98
-29 (PCN I7X6)				
MRM 114.83 NB & SB	100	14	51.9	0.68
all four corners of bridge				
PCN I7X6 Total:	100	14	51.9	0.68
Grand Totals:	609	81	300.9	3.91

SD	PRO
DOT	029-272,
וטען	090-271,
Plotting Date: 5/16	/2025


TOTAL SHEETS SHEET 029-271 6 229-271

Spacing of Advance Warning The signs illustrated are not required Posted if the work space is behind a barrier, Speed more than 2 feet behind the curb, or 15 Prior to Signs feet or more from the edge of any (Feet) Work (M.P.H.) (A) roadway. 0 - 30 200 The signs illustrated will be used where there are distracting situations; such as: 35 - 40 350 45 - 50 500 vehicles parked on shoulder, vehicles 55 750 accessing the work site via the highway, and equipment traveling on or crossing 60 - 80 1000 the roadway to perform work operations. The ROAD WORK AHEAD sign may be replaced with other appropriate signs, such as the SHOULDER WORK sign. The SHOULDER WORK sign may be used for work adjacent to the shoulder. \* If the work space is on a divided WORK SPACE highway, an advance warning sign should also be placed on the left side of the directional roadway. For short term, short duration, or mobile operations, all signs and channelizing devices may be eliminated if a vehicle with an activated flashing or revolving yellow light is used. January 22, 2021 S D D O T PLATE NUMBER 634.01 WORK BEYOND THE SHOULDER

Sheet I of I

WORK AND WATER DESCRIPTION OF THE ADDRESS OF THE AD		Prior to Work (M.P.H.)  0 - 30  35 - 40  45  50  55  60 - 65  Chann The chan cones if t	200 350 500 500 750 1000 nelizing Device END ROAD WORK G20-2 nelizing devices wireffic control must in	(Feet) (L) 180 320 600 600 660 780	Channelizing Devices (Feet) (G)  25  25  50  50  50  ums or 42" overnight.
SHOULDER NORK SH	500	channeliz with an a used.  Worker s instead o  A SHOUL left side o left shoul  The SHO roadway roadway sign befo	duration operation ing devices may be ctivated flashing or igns (W21-1 or W2 f SHOULDER WOILDER WORK sign of a divided or oneder is affected.  ULDER WORK sign is not required if drawill encounter another they reach a work SPACE	e elimin revolvii 1-1a) m RK sign should I way roa in on an ivers en her adv	ated if a vehicle and yellow light is ay be used s. De placed on the dway only if the intersecting anerging from that ance warning
WORK SPACE  S-02-0-2  BOND MOBK  END		A A	SHOUL DER WORK ROAD WORK AHE AD	> >	
Published Date: 2026	'	NORK ON S	HOULDERS		January 22, 2021  PLATE NUMBER 634.03  Sheet I of I

Published Date: 2026



Prior to placement of the erosion control blanket, the areas will be properly prepared, shaped, seeded, and

Erosion control blanket will be unrolled in the direction of the flow of water when placed in ditches and on slopes. The upslope end of the erosion control blanket will be buried in a trench 6" wide by 6" deep. There will be at least a 6" overlap wherever one roll of erosion control blanket ends and another begins, with the upslope erosion control blanket placed on top of the downslope erosion control blanket.

The erosion control blanket will be pinned to the ground according to the manufacturer's installation recommendations.

D D

O

After the placement of the erosion control blanket, the Contractor will fine grade along all edges of the blanket to maintain a uniform slope adjacent to the blanket and level any low spots which might prevent uniform and unrestricted flow of side drainage directly onto the erosion control blanket.

All ditch sections will be shaped when installing the erosion control blanket. All costs for shaping the ditches will be incidental to the contract unit price per foot for "Shaping for Erosion Control Blanket".

February 14, 2020

PLATE NUMBER 734.01

Published Date: 2026

EROSION CONTROL BLANKET

Sheet I of I

PROJECT SHEET TOTAL SHEETS 029-272, 029-271 **D01** 7 7 090-271, 229-271 Plotting Date: 5/16/202