

3934G & 3973G
Mellette & Tripp Counties

PILE	STOCKPILE#	PCN	COUNTY	LOCATION
1	3934G	i4jc	Mellette	SW1/4 S35 T40N R29W 1/2mi N of MELLETE/TODD CO LINE
2	3973G	i4jd	Tripp	SW1/2 S34 T98N R75W 1/4mi SE OF COLOME on US18

3934G & 3973G
Mellette & Tripp Counties

INDEX OF PLAN SHEETS

SHEET NO. 1	LAYOUT MAP & LOCATION
SHEET NO. 2	DESCRIPTION FOR GRAVEL SURFACING STOCKPILES
SHEET NO. 3	INDEX OF PLAN SHEETS AND ESTIMATE OF QUANTITIES
SHEET NOS. 3 AND 4	SPECIFICATIONS & NOTES

ESTIMATE OF QUANTITIES

BID ITEM NUMBER	ITEM	TOTAL QUANTITY
009E0010	Mobilization	LUMP SUM
740E0300	Gravel Surfacing, (US83 Mellette CO – 3934G)	5, 000 TONS
740E0300	Gravel Surfacing, (US18 Colome – 3973G)	5, 000 TONS

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications and/or Special Provisions as included in the Proposal.

PRIOR TO STOCKPILE CONSTRUCTION

The Contractor is responsible for contacting the following person prior to stockpile construction:

Stockpile # 3934G – Winner
Gregg Ulmer, Maintenance Supervisor, at (605) 842-0810

Stockpile # 3973G – Winner
Gregg Ulmer, Maintenance Supervisor, at (605) 842-0810

PRIOR TO STOCKPILE CONSTRUCTION (CONTINUED)

The Contractor shall find out the exact location to place the stockpile at each site and also the desired shape of the finished stockpile. If the shape and location are not done properly as per the Maintenance Supervisor's instructions, the contractor will be held accountable to correct the stockpile before any payment of materials is made.

GRAVEL SURFACING

Gravel Surfacing shall be furnished by the contractor, and shall have a PI requirement of 1 - 8. All other requirements of Section 882 shall apply.

MAINTENANCE OF TRAFFIC

The Contractor shall furnish and install 48" x 48" TRUCK CROSSING signs, W8-6, to be placed on State or County highways or other well-traveled roadways. The signs shall be located a minimum of 550' in advance of intersections and approaches to the highway where the haul route crosses or turns onto/from the highway. The TRUCK CROSSING signs shall be installed for both directions of traffic travel. The exact number and location of the signs will be determined based on the pit location and haul road approved for use.

The TRUCK CROSSING signs shall be displayed at all times when the haul vehicles are hauling material from the pit to the stockpile site. During non-working hours, the fixed signs shall be covered and the portable signs shall be removed from view. Hinged signs may be used.

There will be no direct payment for the TRUCK CROSSING signs. All costs for furnishing, installing, maintaining and removing the signs shall be incidental to other contract items.