

SOUTH DAKOTA 029 S - 171 1 30	STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS
			1	

Plotting Date: 04/19/2017

INDEX OF SHEETS

SHEET NO. 1 **TITLE SHEET**

SHEET NO. 2 **ESTIMATE OF QUANTITIES &**

> **ENVIRONMENTAL COMMITMENTS ENVIRONMENTAL COMMITMENTS**

SHEET NOS. 4 THRU 7 **PLAN NOTES**

SHEET NO. 3

SHEET NOS. 8 THRU 10 STORM WATER POLLUTION

PREVENTION PLAN

SITE LAYOUTS SHEET NOS. 11 THRU 14

SHEET NOS. 15 AND 16 **IMAGES ORIGINAL CONSTRUCTION PLANS** SHEET NOS. 17 THRU 27

SHEET NOS, 28 THRU 30 STANDARD PLATES

ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS

STATE OF SOUTH DAKOTA PROJECT SHEET TOTAL SHEETS 029 S - 171 & 029 N - 171 2 30

Estimate of Quantities – i4LX (SB Rest Area)

	illiate of Qualitates — ITEX (OD INC	3t Alca	<u> </u>
BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E0210	Remove Building(s)	Lump Sum	LS
110E0300	Remove Concrete Curb and/or Gutter	920	Ft
110E1950	Remove Contaminated Water	145.0	MGal
120E0600	Contractor Furnished Borrow Excavation	453	CuYd
120E0900	Contaminated Material Excavation	65	CuYd
230E0020	Contractor Furnished Topsoil	469	CuYd
250E0010	Incidental Work	Lump Sum	LS
250E0020	Incidental Work, Grading	Lump Sum	LS
634E0110	Traffic Control Signs	40.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
730E0204	Type C Permanent Seed Mixture	41	Lb
731E0100	Fertilizing	2,302	Lb
734E0154	12" Diameter Erosion Control Wattle	75	Ft

Estimate of Quantities – i4LY (NB Rest Area)

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E0210	Remove Building(s)	Lump Sum	LS
110E0300	Remove Concrete Curb and/or Gutter	410	Ft
110E1950	Remove Contaminated Water	130.0	MGal
120E0600	Contractor Furnished Borrow Excavation	422	CuYd
120E0900	Contaminated Material Excavation	65	CuYd
230E0020	Contractor Furnished Topsoil	405	CuYd
250E0010	Incidental Work	Lump Sum	LS
250E0020	Incidental Work, Grading	Lump Sum	LS
634E0110	Traffic Control Signs	40.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
730E0204	Type C Permanent Seed Mixture	41	Lb
731E0100	Fertilizing	2,274	Lb
734E0154	12" Diameter Erosion Control Wattle	75	Ft

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

ENVIRONMENTAL COMMITMENTS

An Environmental Commitment is a measure that SDDOT commits to implement in order to avoid, minimize, and/or mitigate a real or potential environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency mentioned below with permitting authority can influence a project if perceived environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office. The environmental commitments associated with this project are as follows:

COMMITMENT E: STORM WATER

Construction activities constitute 1 acre or more of earth disturbance.

Action Taken/Required:

The DENR and the US Environmental Protection Agency (EPA) have issued separate general permits for the discharge of storm water runoff. The DENR permit applies to discharges on state land and the EPA permit applies to discharges on federal or reservation land. The Contractor is advised this project is regulated under the Phase II Storm Water Regulations and must receive coverage under the General Permit for Construction Activities. A Notice of Intent (NOI) will be submitted to DENR a minimum of 15 days prior to project start by the DOT Environmental Office. A letter must be received from DENR that acknowledges project coverage under this general permit before project start. The Contractor is advised that permit coverage may also be required by off-site activities, such as borrow and staging areas, which are the responsibility of the Contractor.

The Contractor shall adhere to the "Special Provision Regarding Storm Water Discharges to Waters of the State".

A major component of the storm water construction permits is development and implementation of a Storm Water Pollution Prevention Plan (SWPPP), which is a joint effort and responsibility of the SDDOT and the Contractor. Erosion control measures and best management practices will be implemented in accordance with the SWPPP. The SWPPP is a dynamic document and is to be available on-site at all times.

Information on storm water permits and SWPPPs are available on the following websites:

SDDOT:

http://www.sddot.com/business/environmental/stormwater/Default.aspx

DENR: http://www.denr.sd.gov/des/sw/stormwater.aspx

EPA: http://cfpub.epa.gov/npdes/home.cfm?program_id=6

Contractor Certification Form:

The "Department of Environmental and Natural Resources – Contractor Certification Form" (SD EForm – 2110LDV1-ContractorCertification.pdf) shall be completed by the Contractor or their certified Erosion Control Supervisor

Revised: 6/6/17 MD

The form certifies under penalty of law that the Contractor understands and will comply with the terms and conditions of the Surface Water Discharge General Permit for Storm Water Discharges Associated with Construction Activities for the Project.

after the award of the contract. Work may not begin on the project until this

The online form can be found at:

form is signed.

http://denr.sd.gov/des/sw/eforms/E2110LDV1-ContractorCertification.pdf

ENVIRONMENTAL COMMITMENTS

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor shall furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) shall be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Environment and Natural Resources.

The waste disposal site(s) shall not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements shall apply:

- 1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials shall be buried in a trench completely separate from wood debris. The final cover over the construction and/or demolition debris shall consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW shall be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor shall control the access to waste disposal sites not within the Public ROW through the use of fences, gates, and placement of a sign or signs at the entrance to the site stating "No Dumping Allowed".
- 2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period of time not to exceed the duration of the project. Prior to project completion, the waste shall be removed from view of the ROW or buried and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) shall be incidental to the various contract items.

COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES

The SDDOT has obtained concurrence with the State Historical Preservation Office (SHPO or THPO) for all work included within the project limits and all department designated sources and designated option material sources, stockpile sites, storage areas, and waste sites provided within the plans.

Action Taken/Required:

All earth disturbing activities not designated within the plans require review of cultural resources impacts. This work includes, but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor shall arrange and pay for a cultural resource survey and/or records search. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor shall provide ARC with the following: a topographical map or aerial view on which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor shall submit the records search or cultural resources survey report and if the location of the site is within the current geographical or historic boundaries of any South Dakota reservation to SDDOT Environmental Engineer, 700 East Broadway Avenue, Pierre, SD 57501-2586 (605-773-3180). SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

If evidence for cultural resources is uncovered during project construction activities, then such activities shall cease and the Project Engineer shall be immediately notified. The Project Engineer will contact the SDDOT Environmental Engineer in order to determine an appropriate course of action.

SHPO/THPO review does not relieve the Contractor of the responsibility for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor shall provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

Ī	STATE OF	PROJECT	SHEET	TOTAL SHEETS
	SOUTH DAKOTA	029 S – 171 & 029 N – 171	3	30

UTILITIES

The Contractor shall be aware that the existing utilities shown in the plans were surveyed prior to the design of this project and might have been relocated or replaced by a new utility facility prior to construction of this project. The Contractor shall contact the utility companies in sufficient time to allow the company to terminate services and disconnect/remove utility lines from the rest area site.

Utility Company	Address	Phone Number	Contact
H D Electric	PO Box 1007 Clear	(605) 874-2171	Troy
Coop Inc.	Lake, SD 57226	(003) 074-2171	Kwasniewski
Sioux Rural	45703 176th St.	(COE) 004 CO24	Todd
Water Inc.	Watertown, SD 57201	(605) 881-6021	Goodfellow
Interstate Telecom Coop Assoc.	312 4 th St. West Clear Lake, SD 57226	(605) 874-8324	Terry Pederson

PERMITS AND LICENSES

The Contractor shall obtain all necessary State and/or County Permits and/or Licenses in accordance with Section 7.2 of the Standard Specifications

CONTRACTOR FURNISHED BORROW EXCAVATION

The Contractor shall provide a suitable site for Contractor furnished borrow excavation material. The Contractor is responsible for obtaining all required permits and clearances for the borrow site. The borrow material shall be approved by the Engineer. The quantity for "CONTRACTOR FURNISHED BORROW EXCAVATION" as shown in the Estimate of Quantities has been included for bidding purposes only. The quantity used per cubic yard on site will be the basis of pay for this bid item.

Restoration of the Contractor furnished borrow excavation site shall be the responsibility of the Contractor.

REMOVAL OF BUILDINGS

Included in these plans is the removal and disposal of several buildings. The locations and types of buildings are as follows:

Station	Туре
Southbound Hidewood Rest Area	1 rest area building & 4 picnic shelters
Northbound Hidewood Rest Area	1 rest area building & 4 picnic shelters

These buildings shall be removed in accordance with Section 110 of the Specifications and all local codes with the exception of the building footings. All building footings must be removed to a minimum depth of 4' below finished ground elevation. The buildings have been inspected for asbestos and asbestos has been removed when required or asbestos was not found. It is the responsibility of the Contractor to visit the site to determine the extent of work required to complete the project. All costs associated with this work shall be incidental contract lump sum price for REMOVE BUILDING(S).

Both the northbound and southbound rest area sites have four picnic shelter buildings that shall be removed. All footings and concrete associated with these buildings shall be removed as well. See "Original Construction Plans" sheets for details on these buildings.

All furniture remaining within the building shall become property of the Contractor.

INCIDENTAL WORK, GRADING

All work items below shall be incidental to the contract lump sum price for INCIDENTAL WORK, GRADING. Everything removed per bid item, INCIDENTAL WORK, GRADING shall become property of the Contractor for his/her disposal, unless otherwise indicated.

Sealing Water and Sewer Mains

The Contractor shall seal all open ends of water and sewer mains to be abandoned with a concrete plug having a length equal to the diameter of the pipe being plugged.

Remove Sprinkler System

All sprinkler heads, valve boxes and irrigation pipe associated with the underground sprinkler system for both northbound and southbound rest areas shall be removed. See "Original Construction Plans" sheets for details on sprinkler head and valve box locations.

Remove Electrical Conduit and Wiring

All electrical wiring, conduit and junction boxes associated with the luminaries shall be removed.

Remove Underground Potable Water Storage Tank

12'x19.5' Fiberglass water storage tanks and all hardware at both the northbound and southbound rest areas shall be removed.

Remove Manholes

All existing manholes shall have the top 4' collapsed within themselves or removed, then filled to maintain even earth contours. See "Original Construction Plans" sheets for details and locations of manholes.

Remove Trees

Only trees that interfere with demolition work shall be removed from the work sites at both the northbound and southbound rest areas. The number of trees removed may differ from the quantity provided in the table as deemed necessary by the Contractor and approved by the Engineer.

Remove Luminaires, Poles and Pole Footings

All luminaires, poles and pole footings associated with the luminaires shall be removed from both the northbound and southbound rest areas. The detail of the footings can be found in the "Original Construction Plans" sheets.

High Mast Light Towers & Footings

Each rest area includes a high mast light tower. The detail of the footings for these towers can be found in the "Original Construction Plans" sheets. All material associated with the high mast tower shall be removed; including luminaires, poles, and footings.

Remove Underground Propane Tanks

Each rest area has two 1000 gallon underground propane tanks that shall be removed. Each tank is approximately 16' long with a 41" diameter.

	STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029 S – 171 & 029 N - 171	4	30	

INCIDENTAL WORK

All work items below shall be incidental to the contract lump sum price for INCIDENTAL WORK. Everything removed per bid item, INCIDENTAL WORK shall become property of the Contractor for his/her disposal, unless otherwise indicated.

Remove Concrete Sidewalk

All concrete sidewalk at both the northbound and southbound rest areas shall be removed.

Remove Flagpole

Flagpoles, concrete foundations and lighting at both northbound and southbound rest areas shall be removed.

Remove Picnic Tables

Concrete picnic tables shall be removed.

Remove Dump Station Facilities

All surface facilities associated with the sewage dump stations for both northbound and southbound rest areas shall be removed to a depth of 2' below finished ground elevation.

Salvage Historical Marker

The Historical Markers plaques located at both the northbound and southbound rest areas shall be removed and salvaged. The remaining brick foundations shall be removed.

Remove Chain Link Fence & Swing Gate

The chain link fence that surrounds both northbound and southbound wastewater lagoons shall be removed. This removal shall include the gate and any footings for posts.

Remove Traffic Control Signs

All traffic control signs shall be removed from the rest area sites. Only signs that direct the existing truck parking traffic shall remain in place.

REMOVE CONCRETE CURB AND/OR GUTTER

Only the southbound rest area site will require curb and gutter removal. As part of this removal, a full depth saw cut is required prior to removing. All costs associated with this work, including the saw cut, are incidental to the contract unit price per foot for REMOVE CONCRETE CURB AND/OR GUTTER.

WASTEWATER LAGOON CLEANOUT

The Contractor shall be responsible for removal and disposal of both liquid and sludge (biosolid) residue in the wastewater stabilization ponds at both rest areas. Sludge and water sampling to determine the Biosolid Concentration Analysis and other elements is a Contractor obligation. City of Brookings Landfill does accept the sludge. All landfill fees, including sampling and testing charges, are the responsibilities of the Contractor.

Sludge quantities will be determined by the truck haul method and the Engineer and Contractor shall agree on the haul amount in each truck prior to hauling sludge material. All costs for the excavation, hauling and disposal of sludge material shall be incidental to the contract unit price per cubic yard for CONTAMINATED MATERIAL EXCAVATION. A quantity of 65 cubic yards is included in the Estimate of Quantities for both the northbound and southbound rest areas for bidding purposes.

If water is present in wastewater lagoons dewatering is required. The contaminated water shall be pumped into calibrated storage containers or tanks and disposed of at a SDDENR permitted facility or landfill for disposal. Discharge of contaminated water to the ground will not be allowed.

Contaminated water quantities will be measured by the MGal and pumped to a storage container or tank and hauled to and disposed of at a SDDENR permitted facility. The Contractor and Engineer shall agree on the amount of water pumped into the truck prior to hauling. Payment for removing, hauling, and disposing of the contaminated water shall be incidental to the contract unit price per MGal for REMOVE CONTAMINATED WATER. A quantity of 275 MGal has been included in the Estimate of Quantities for both the Northbound and Southbound Rest areas for bidding purposes.

Location of the disposal sites shall be provided to the Area Engineer at the Preconstruction meeting. It is the Contractors responsibility to arrange for disposal site locations and pay any fees associated with disposal of sludge/water.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029 S – 171 & 029 N - 171	5	30

Revised: 6/6/17 MD

Breakdown of Contractor Furnished Borrow Excavation (Information Only)									
	Rest Area Building	Picnic Shelters	Water Storage Tank	Light Pole Footings	Manholes	Drinking Fountain Foundation	Concrete Sidewalk	Underground Propane Tanks	
	Cu. Yd.								<u>TOTAL</u>
Southbound Rest Area	48	20	155	83	67	1	45	34	453
Northbound Rest Area	48	20	155	78	42	1	44	34	422
Totals	96	41	310	161	109	2	89	68	875

Table of Incidental Work, Grading (Information Only)									
	Remove Sanitary Manhole	Remove Sprinkler System	Remove Underground Water Storage Tank	Remove Luminaire Pole Footing	Remove High Mast Light Tower & Footing	Remove Trees			
	Each	Each	Each	Each	Each	Each			
Southbound Rest Area	8	1	1	11	1	7			
Northbound Rest Area	5	1	1	8	1	6			
Totals	13	2	2	19	2	13			

Table of Incidental Work (Information Only)									
	Remove Concrete Sidewalk	Remove Flagpole & Light	Remove Lagoon Chain Link Fence	Remove Lagoon Chain Link Swing Gate	Remove Concrete Picnic Tables	Remove Trailer Waste Station	Remove Historical Marker Foundation		
	Sq. Yd.	Each	Ft	Each	Each	Each	Each		
Southbound Rest Area	1,010	1	848	1	8	1	1		
Northbound Rest Area	951	1	828	1	8	1	1		
Totals	1,961	2	1,676	2	16	2	2		

SALVAGED ITEMS

All salvaged items noted in the following table shall be salvaged for future highway use and hauled to the Department of Transportation's Aberdeen Yard as directed by the Engineer. The SDDOT Aberdeen Yard is located 0.9 miles west of the US12 & US281 junction. Care shall be taken not to damage the structural properties of the items during dismantling and transporting. All broken concrete and materials not salvaged shall be disposed of in accordance with the Specifications. All costs for salvaging and transporting the items shall be incidental to the contract lump sum price for INCIDENTAL WORK, GRADING. All items that are to be salvaged shall be protected from the elements after they have been removed and before transporting. Before preparing his/her bid, the Contractor shall make a visual inspection of the project to verify the extent of the work and material involved.

Prior to delivery of the salvaged items, the Contractor shall contact

Brian Wacholz, Office (605) 626-7888 Cell (605) 228-7618

to schedule a time of delivery for all salvaged materials.

TRAFFIC CONTROL - GENERAL NOTES

Unless otherwise stated in these plans, no work will be allowed during the hours of darkness.

Storage of vehicles and equipment shall be as near the right-of-way as possible. Contractor's employees should mobilize at a location off the right-of-way and arrive at the worksites in a minimum number of vehicles necessary to perform the work. Indiscriminate driving and parking of vehicles within the right-of-way will not be permitted. Any damage of the vegetation, surfacing, embankment, delineators and existing signs or barricades resulting from such indiscriminate use shall be repaired and/or restored by the Contractor, at no expense to the State, and to the satisfaction of the Engineer.

All materials and equipment shall be stored a minimum distance of 30' from the traveled way during nonworking hours.

Traffic Control Devices shall be installed per Standard Plate 634.01 starting at the off ramp for each rest area.

The Contractor shall be responsible for maintaining the present roadway closure within the rest area and shall cause as minimal disturbance to the existing truck parking as possible. Parking of equipment within the truck parking area will not be permitted.

INVENTORY OF TRAFFIC CONTROL DEVICES

I-29 SB - i4LX

		Ελ	TE		
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT
W20-1 G20-2	ROAD WORK AHEAD END ROAD WORK	2	48" x 48" 48" x 24"	16.0 8.0	32.0 8.0
EXPRESSWAY / INTERSTATE TRAFFIC CONTROL SIGNS SQFT 40					40.0

 STATE OF SOUTH DAKOTA
 PROJECT
 SHEET
 TOTAL SHEETS

 029 S - 171 & 029 N - 171
 6
 30

Table of Salvaged Materials												
	Chain Link Swing Gate from Building	Building	Lobby Bulletin Boards	Computer Monitor & Steel Enclosure in Building Lobby	Irrigation Pumps	Hanging Heaters & Thermostat	Surveillance System Hardware in Mechanical Room	Surveillance Cameras	Furnaces & Thermostat	Garbage	Historical Marker Plaque	3 Unit Outdoor Tourism Panels & Hardware
	Each	Ft	Each	Each	Each	Each	Each	Each	Each	Each	Each	Each
Southbound Rest Area	1	330	1	1	1	1	1	7	2	9	1	3
Northbound Rest Area	1	330	1	1	1	1	1	7	2	9	1	3
Totals	2	660	2	2	2	2	2	14	4	18	2	6

I-29 NB - i4LY

		E	(PRESSWAY	/ INTERSTA	TE
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT
W20-1 G20-2	ROAD WORK AHEAD END ROAD WORK	2	48" x 48" 48" x 24"	16.0 8.0	32.0 8.0
			SSWAY / INTI CONTROL S		40.0

CONTRACTOR FURNISHED TOPSOIL

It is anticipated that a larger volume of topsoil will be needed for the new grade than can be salvaged from the existing grade. The Contractor will be required to furnish and place 4 inches of topsoil on areas as determined by the Engineer during construction.

Contractor furnished topsoil shall be free from clay lumps, stones, coarse gravel, or similar objects larger than 1/2 inch in diameter. Brush, stumps, roots, wood, objectionable weeds, litter, or any other material which may be harmful to plant growth will not be allowed. Organic material shall be decomposed.

All costs to furnish and place the Contractor furnished topsoil shall be incidental to the contract unit price per cubic yard for CONTRACTOR FURNISHED TOPSOIL.

MYCORRHIZAL INOCULUM

Mycorrhizal inoculum shall consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier shall provide certification of the fungal species claimed and the live propagule count. The inoculum shall include the following fungal species:

Glomus intraradices 25% Glomus aggregatu 25% Glomus mosseae 25% Glomus etunicatum 25%

All seed shall be inoculated by the seed supplier with a minimum of 100,000 live propagules of mycorrhizal fungi per acre. All costs of inoculating the seed shall be incidental to the contract unit price per pound for the corresponding permanent seed mixture.

The mycorrhizal inoculum shall be as shown below or an approved equal:

Product MycoApply Manufacturer

Mycorrhizal Applications, Inc. Grants Pass, OR Phone: 1-866-476-7800 www.mycorrhizae.com

FERTILIZING

The Contractor shall apply an all-natural slow release fertilizer prior to seeding or placing sod. The all-natural fertilizer shall have a minimum guaranteed analysis of 4-6-4 and be USDA Certified BioBased. It should provide a minimum of 4% (N) nitrogen with a minimum water insoluble nitrogen (WIN) fraction of 3.2%, a minimum of 6% (P₂O5) available phosphate, a minimum of 4% (K2O) soluble potash, and a maximum carbon to nitrogen ratio (C:N ratio) of 5:1. The all-natural fertilizer shall be free of weed-seed and pathogens accomplished through thermophilic composting, and not mechanical or chemical sterilization, to assure presence of beneficial soil microbiology. The fertilizer shall have a near neutral pH, a low salt index, a low biological oxygen demand, contain organic humic and fulvic acids, and have high aerobic organism counts. The fertilizer shall also be stable, free of bad odors, and be unattractive as a food source for animals. It should also be in a granular form that is easily spread.

The fertilizer shall be applied at a rate of 1,000 pounds per acre in accordance with the manufacturer's recommended method of application.

The quantity of fertilizer provided in the Estimate of Quantities accounts for the use of fertilizer on the wastewater lagoons located at each rest area. These areas are to be closed by SDDOT personnel; placement of fertilizer shall wait until the lagoons are completely closed.

The all-natural slow release fertilizer shall be as shown below or an approved equal:

Product Manufacturer

Sustane Sustane Corporate Headquarters
Cannon Falls, Minnesota

Phone: 1-800-352-9245 www.sustane.com

PERMANENT SEEDING

The areas to be seeded consist of all newly graded areas within the project limits except for the top of roadways, temporary easements under cultivation, and areas designated to be sod.

The quantity of Permanent Seeding provided in the Estimate of Quantities accounts for the use of seed on the wastewater lagoons located at each rest area. These areas are to be closed by SDDOT personnel; placement of the permanent seeding shall wait until the lagoons are completely closed.

STATE OF SOUTH DAKOTA 029 S - 171 & 029 N - 171 7 30

Type C Permanent Seed Mixture shall consist of the following:

Grass Species	Variety		Pure Live Seed (PLS) (Pounds/Acre)
Western Wheatgrass	Arriba, Flintlock, Rodan, Rosana		16
Canada Wildrye	Mandan		2
		Total:	18

EROSION CONTROL WATTLE

Erosion control wattles for restraining the flow of runoff and sediment shall be installed at locations noted in the table and at locations determined by the Engineer during construction. Refer to Standard Plate 734.06 for details.

The Contractor shall provide certification that the erosion control wattles do not contain noxious weed seeds.

Erosion control wattles shall remain on the project to decompose.

The erosion control wattle provided shall be from the approved product list. The approved product list for erosion control wattle may be viewed at the following internet site:

http://sddot.com/business/certification/products/Default.aspx

TABLE OF EROSION CONTROL WATTLE

Location	Diameter (Inch)	Quantity (Ft)
Southbound Rest Area	12	50
Northbound Rest Area	12	50
	Additional Quantity:	50
	Total:	150

Table of Erosion Control Items										
	Main Rest Area Demolition					Closing of	Lagoons			
	Area		Contractor Furnished Topsoil	Fertilizer	Type C Permanent Seed Mixture	Erosion Control Wattle	Lagoon Area		Fertilizer for Lagoons	Type C Permanent Seed Mixture for Lagoons
	Sq. Ft.	Acres	Cu. Yd.	Lb	Lb	Ft	Sq. Ft. Acres		Lb	Lb
Southbound Rest Area	37,967	0.87	469	872	16	75	62,488	1.43	1,430	26
Northbound Rest Area	32,842	0.75	405	754	14	75	66,413	1.52	1,520	27
Totals	70,810	1.63	874	1,626	29	150	128,901	2.96	2,950	53

		STATE OF PROJECT SHEET TOTAL SHEET SHEET SHEET
STORM WATER POLLUTION PREVENTION PLAN CHECKLIST	 Inlet Protection 	SOUTH DAKOTA 029 S - 171 & 029 N - 171 8 30
(The numbers right of the title headings are reference numbers to the	Outlet Protection	DAROTA 029 5 - 171 & 029 N - 171 8 30
GENERAL PERMIT FOR STORM WATER DISCHARGES ASSOCIATED	■ Surface Inlet Protection (Area Drain)	MAINTENANCE AND INSPECTION (4.2 3. and 4.2 4.)
WITH CONSTRUCTION ACTIVITIES	Curb Inlet Protection	Maintenance and Inspection Practices
	 Stabilized Construction Entrances 	 Inspections will be conducted at least one time per week and
SITE DESCRIPTION (4.2 1)	 Entrance/Exit Equipment Tire Wash 	after a storm event of 0.50 inches or greater.
> Project Limits: See Title Sheet (4.2 1.b)	■ ☐ Interceptor Ditch	 All controls will be maintained in good working order. Necessary
	Concrete Washout Facility	
Project Description: See Title Sheet (4.2 1.a.)		repairs will be initiated within 24 hours of the site inspection
Site Map(s): See Title Sheet and Plans (4.2 1.f. (1)-(6))	 Temporary Diversion Channel 	report.
Major Soil Disturbing Activities (check all that apply)	■	 Silt fence will be inspected for depth of sediment and for tears in
■ Clearing and grubbing	 Temporary Water Barrier 	order to ensure the fabric is securely attached to the posts and
■ □Excavation/borrow	■ ☐ Temporary Water Crossing	that the posts are well anchored. Sediment buildup will be
_	Other:	
■ ⊠Grading and shaping		removed from the silt fence when it reaches 1/3 of the height of
■ <u></u> Filling	Wetland Avoidance	the silt fence.
■ Cutting and filling	Will construction and/or erosion and sediment controls impinge on	 Sediment basins and traps will be checked. Sediment will be
■ Other (describe): Rest Area Demolition	regulated wetlands? Yes No If yes, the structural and erosion	removed when depth reaches approximately 50 percent of the
> Total Project Area: 48.72 Acres (4.2 1.b.)	and sediment controls have been included in the total project wetland	structure's capacity, and at the conclusion of the construction.
> Total Area To Be Disturbed: 4.57 Acres (4.2 1.b.)	impacts and have been included in the 404 permit process with the	 Check dams will be inspected for stability. Sediment will be
Existing Vegetative Cover (%) 90%	USACE.	removed when depth reaches $\frac{1}{2}$ the height of the dam.
Soil Properties: USDA-NRCS Soil Series Classification: Kranzburg-	Storm Water Management (4.2 2.b., (1) and (2))	 All seeded areas will be checked for bare spots, washouts, and
Brookings silty clay loams (4.2 1. d.)	Storm water management will be handled by temporary controls	vigorous growth free of significant weed infestations.
Name of Receiving Water Body/Bodies: Hidewood Creek (4.2 1.e.)	outlined in "EROSION AND SEDIMENT CONTROLS" above, and any	 Inspection and maintenance reports will be prepared on form
Name of Necesting Water Body/Bodies. Flacewood Oreck (4.2 1.6.)	·	
	permanent controls needed to meet permanent storm water	DOT 298 for each site inspection, this form will also be used to
ORDER OF CONSTRUCTION ACTIVITIES (4.2 1.c.)	management needs in the post construction period. Permanent	document changes to the SWPPP. A copy of the completed
(Stabilization measures shall be initiated as soon as possible, but in no	controls will be shown on the plans and noted as permanent.	inspection form will be filed with the SWPPP documents.
case later than 14 days after the construction activity in that portion of	Other Storm Water Controls (4.2 2.c., (1) and (2))	 The SDDOT Project Engineer and Contractor's Erosion Control
the site has temporarily or permanently ceased. Initiation of final or	■ Waste Disposal	Supervisor are responsible for inspections. Maintenance, repair
temporary stabilization may exceed the 14-day limit if earth disturbing	All liquid waste materials will be collected and stored in sealed	activities are the responsibility of the Contractor. The SDDOT
activities will be resumed within 21 days.)	metal containers approved by the project engineer. All trash and	Project Engineer will complete the inspection and maintenance
Install perimeter protection where runoff sheets from the site.	construction debris from the site will be deposited in the approved	reports and distribute copies per the distribution instructions on
Install channel and ditch bottom protection.	containers. Containers will be serviced as necessary, and the	DOT 298.
 Clearing and grubbing. 	trash will be hauled to an approved disposal site or licensed	23. 233.
		NON OTORIA WATER RIGOUAROES (O.O.)
Remove and store topsoil.	landfill. All onsite personnel will be instructed in the proper	NON-STORM WATER DISCHARGES (3.0)
Stabilize disturbed areas.	procedures for waste disposal, and notices stating proper	The following non-storm water discharges are anticipated during the
Complete final grading.	practices will be posted in the field office. The general	course of this project (check all that apply).
Reseed areas disturbed by removal activities.	Contractor's representative responsible for the conduct of work	Discharges from water line flushing.
Accord arous distarsed by removal delivines.	on the site will be responsible for seeing waste disposal	Pavement wash-water, where no spills or leaks of toxic or
EROSION AND SEDIMENT CONTROLS (4.2 2.a.(1)(a)-(f))	procedures are followed.	hazardous materials have occurred.
Stabilization Practices (See Detail Plan Sheets)	 Hazardous Waste 	Uncontaminated ground water associated with dewatering
 Temporary Seeding (Cover Crop Seeding) 	All hazardous waste materials will be disposed of in a manner	activities.
■ ⊠ Permanent Seeding	specified by local or state regulations or by the manufacturer.	
	Site personnel will be instructed in these practices, and the	MATERIALS INVENTORY (4.2. 2.6.(2))
■ Sodding		MATERIALS INVENTORY (4.2. 2.c.(2))
 Planting (Woody Vegetation for Soil Stabilization) 	individual designated as the Contractor's on-site representative	The following materials or substances are expected to be present on the
 Mulching (Grass Hay or Straw) 	will be responsible for seeing that these practices are followed.	site during the construction period. These materials will be handled as
 Hydraulic Mulch (Wood Fiber Mulch) 	Sanitary Waste	noted under the headings "EROSION AND SEDIMENT CONTROLS" and
■ Soil Stabilizer	Portable sanitary facilities will be provided on all construction	"SPILL PREVENTION" (check all that apply).
■ ☐ Bonded Fiber Matrix	sites. Sanitary waste will be collected from the portable units in a	➤ ⊠Concrete and Portland Cement
	, i	
 Erosion Control Blankets or Mats 	timely manner by a licensed waste management Contractor or as	Detergents
 Uegetation Buffer Strips 	required by any local regulations.	➤ □Paints
■ Roughened Surface (e.g. tracking)		➤ Metals
Other:		➤ ☐Bituminous Materials
> Structural Temporary Erosion and Sediment Controls		➤ ⊠Petroleum Based Products
■ Silt Fence		➢ ☐Cleaning Solvents
■ ☐ Floating Silt Curtain		➤ ⊠Wood
Straw Bale Check		➤ ☐Cure
Temporary Berm		➤ ☐Texture
■ Temporary Slope Drain		➢ ☐ Chemical Fertilizers
■ ⊠ Straw Wattles or Rolls		➤ ☐Other:
 Turf Reinforcement Mat 		
■ Rip Rap		
■ Gabions		
■ Rock Check Dams		
 Sediment Traps/Basins 		

SPILL PREVENTION (4.2 2.c.(2))

Material Management

- Housekeeping
 - Only needed products will be stored on-site by the Contractor.
 - Except for bulk materials the contractor will store all materials under cover and in appropriate containers.
 - Products must be stored in original containers and labeled.
 - Material mixing will be conducted in accordance with the manufacturer's recommendations.
 - When possible, all products will be completely used before properly disposing of the container off-site.
 - The manufacturer's directions for disposal of materials and containers will be followed.
 - The Contractor's site superintendent will inspect materials storage areas regularly to ensure proper use and disposal.
 - Dust generated will be controlled in an environmentally safe manner
 - Vegetation areas not essential to the construction project will be preserved and maintained as noted on the plans.

Hazardous Materials

- Products will be kept in original containers unless the container is not resealable.
- Original labels and material safety data sheets will be retained in a safe place to relay important product information.
- If surplus product must be disposed of, manufacturer's label directions for disposal will be followed.
- Maintenance and repair of all equipment and vehicles involving oil changes, hydraulic system drain down, degreasing operations, fuel tank drain down and removal, and other activities which may result in the accidental release of contaminants will be conducted on an impervious surface and under cover during wet weather to prevent the release of contaminants onto the ground.
- Wheel wash water will be collected and allowed to settle out suspended solids prior to discharge. Wheel wash water will not be discharged directly into any storm water system or storm water treatment system.
- Potential pH-modifying materials such as: bulk cement, cement kiln dust, fly ash, new concrete washings, concrete pumping, residuals from concrete saw cutting (either wet or dry), and mixer washout waters will be collected on site and managed to prevent contamination of storm water runoff.

Product Specific Practices (6.8)

Petroleum Products

All on-site vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

Fertilizers

Fertilizers will be applied only in the amounts specified by the SDDOT. Once applied, fertilizers will be worked into the soil to limit the exposure to storm water. Fertilizers will be stored in an enclosed area. The contents of partially used fertilizer bags will be transferred to sealable containers to avoid spills.

Paints

All containers will be tightly sealed and stored when not required for use. The excess will be disposed of according to the

manufacturer's instructions and any applicable state and local regulations.

Concrete Trucks

Contractors will provide designated truck washout facilities on the site. These areas must be self-contained and not connected to any storm water outlet of the site. Upon completion of construction, the area at the washout facility will be properly stabilized.

> Spill Control Practices (4.2 2 c.(2))

In addition to the previous housekeeping and management practices, the following practices will be followed for spill prevention and cleanup if needed.

- For all hazardous materials stored on site, the manufacturer's recommended methods for spill cleanup will be clearly posted. Site personnel will be made aware of the procedures and the locations of the information and cleanup supplies.
- Appropriate cleanup materials and equipment will be maintained by the Contractor in the materials storage area on-site. As appropriate, equipment and materials may include items such as brooms, dust pans, mops, rags, gloves, goggles, kitty litter, sand, sawdust, and plastic and metal trash containers specifically for cleanup purposes.
- All spills will be cleaned immediately after discovery and the materials disposed of properly.
- The spill area will be kept well ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with a hazardous substance.
- After a spill a report will be prepared describing the spill, what caused it, and the cleanup measures taken. The spill prevention plan will be adjusted to include measures to prevent this type of spill from reoccurring, as well as clean up instructions in the event of reoccurrences.
- The Contractor's site superintendent, responsible for day-to-day operations, will be the spill prevention and cleanup coordinator. The Contractor is responsible for ensuring that the site superintendent has had appropriate training for hazardous materials handling, spill management, and cleanup.

> Spill Response (4.2 2 c.(2))

The primary objective in responding to a spill is to quickly contain the material(s) and prevent or minimize migration into storm water runoff and conveyance systems. If the release has impacted on-site storm water, it is critical to contain the released materials on-site and prevent their release into receiving waters. If a spill of pollutants threatens storm water or surface water at the site, the spill response procedures outlined below must be implemented in a timely manner to prevent the release of pollutants.

- The Contractor's site superintendent will be notified immediately when a spill or the threat of a spill is observed. The superintendent will assess the situation and determine the appropriate response.
- If spills represent an imminent threat of escaping erosion and sediment controls and entering receiving waters, personnel will be directed to respond immediately to contain the release and notify the superintendent after the situation has been stabilized.
- Spill kits containing appropriate materials and equipment for spill response and cleanup will be maintained by the Contractor at the site.
- If oil sheen is observed on surface water (e.g. settling ponds, detention ponds, swales), action will be taken immediately to remove the material causing the sheen. The Contractor will use appropriate materials to contain and absorb the spill. The source of the oil sheen will also be identified and removed or repaired as necessary to prevent further releases.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029 S – 171 & 029 N - 171	9	30

- If a spill occurs the superintendent or the superintendent's designee will be responsible for completing the spill reporting form and for reporting the spill to SD DENR.
- Personnel with primary responsibility for spill response and clean up will receive training by the Contractor's site superintendent or designee. The training must include identifying the location of the spill kits and other spill response equipment and the use of spill response materials.
- Spill response equipment will be inspected and maintained as necessary to replace any materials used in spill response activities.

SPILL NOTIFICATION

In the event of a spill, the Contractor's site superintendent will make the appropriate notification(s), consistent with the following procedures:

- A release or spill of a regulated substance (includes petroleum and petroleum products) must be reported to DENR immediately **if any one of the following** conditions exists:
 - The discharge threatens or is in a position to threaten the waters of the state (surface water or ground water).
 - The discharge causes an immediate danger to human health or safety.
 - The discharge exceeds 25 gallons.
 - The discharge causes a sheen on surface water.
 - The discharge of any substance that exceeds the ground water quality standards of ARSD (Administrative Rules of South Dakota) chapter 74:51:01.
 - The discharge of any substance that exceeds the surface water quality standards of ARSD chapter 74:51:01.
 - The discharge of any substance that harms or threatens to harm wildlife or aquatic life.
 - The discharge of crude oil in field activities under SDCL (South Dakota Codified Laws) chapter 45-9 is greater than 1 barrel (42 gallons).

To report a release or spill, call DENR at 605-773-3296 during regular office hours (8 a.m. to 5 p.m. Central time). To report the release after hours, on weekends or holidays, call State Radio Communications at 605-773-3231. Reporting the release to DENR does not meet any obligation for reporting to other state, local, or federal agencies. Therefore, the responsible person must also contact local authorities to determine the local reporting requirements for releases. DENR recommends that spills also be reported to the National Response Center at (800) 424-8802.

CONSTRUCTION CHANGES (4.4)

When changes are made to the construction project that will require alterations in the temporary erosion controls of the site, the Storm Water Pollution Prevention Plan (SWPPP) will be amended to provide appropriate protection to disturbed areas, all storm water structures, and adjacent waters. The SDDOT Project Engineer will modify the SWPPP plan (DOT 298) and drawings to reflect the needed changes. Copies of changes will be routed per DOT 298. Copies of forms and the SWPPP will be retained in a designated place for review over the course of the project.

CERTIFICATIONS

> Certification of Compliance with Federal, State, and Local Regulations

The Storm Water Pollution Prevention Plan (SWPPP) for this project reflects the requirements of all local municipal jurisdictions for storm water management and sediment and erosion control as established by ordinance, as well as other state and federal requirements for sediment and erosion control plans, permits, notices or documentation as appropriate.

> South Dakota Department of Transportation

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

Tom hall

Authorized Signature (See the General Permit, Section 6.9.1.C.)

Prime Contractor

This section is to be executed by the General Contractor after the award of the contract. This section may be executed any time there is a change in the Prime Contractor of the project.

I certify under penalty of law that this document and all attachments will be revised or maintained under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.

	Authorized Signature	

CONTACT INFORMATION

Contractor Information:

Prime Contractor Name: _		
Contractor Contact Name:		
Address:		_
•		_
• City:	State:	Zip:
Office Phone:	Field:	
Cell Phone:	Fax:	
Erosion Control Supervisor		
• Name:		-
Address:		
•		_
• City:	State:	Zip:
Office Phone:	Field:	
Cell Phone:	Fax:	
SDDOT Project Engineer		
• Name:		-
Business Address:		
Job Office Location:		
• City:	State:	Zip:
Office Phone:	Field:	
Cell Phone:	Fax:	
SD DENR Contact Spill Repo Business Hours Monday-F		296

- Nights and Weekends (605) 773-3231
- > SD DENR Contact for Hazardous Materials.
 - **(605)** 773-3153
- > National Response Center Hotline
 - **•** (800) 424-8802.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029 S – 171 & 029 N - 171	10	30

REST AREA LAYOUT - I-29 SB

STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS
SOUTH DAKOTA	029 S - 171 029 N - 171	11	30


Plotting Date: 04/19/2017

480+00	485+00	490+00	495+00	500+00
RL		Remove Curb & Gutter RL PS DS Remove All Sidewalk	Remove Flagpole PS UT	
HM - Remove High Mas	et Light Tower RL RL Et Light Tower RL Et Light Tower		PT	re Chain Link Fence
PS - Remove Picnic Sh		(RL)	Do NOT Disturb Tree B	elts
DS - Remove Dump Sta				

PLOTTED FROM - TRABIA2AA


(TB) - Salvage Tourist Information Boards


 (UT) - Remove Underground Propane Tanks



SOUTHBOUND SITE LAYOUT


Plotting Date: 04/19/2017

















BURKUN SITE The borrow mite will be developed in the general area shown. The material to be removed, in the amount of 1365+ cu. yds., is to be used to develop the overlook site. Following excavation the site is to be graded to provide smooth contours, with slopes 6:1 or flatter. Topsoil is to be replaced and the borrow site seeded, fertilized and mulched. OVERLOOK SITE BORROW The overlook site shall be graded to the approximate contours shown. The cost of excavating hauling and placing site borrow material at the overlook site shall be included in the Bid Item "Unclassified Excavation". EXISTING CHAN LINK FENCE. B" DRAW DOWN CIF WITH HEADWALLS. DASHED CONTOURS Denote existing ground line. SEE XSECTION S BASE LINE SOLID CONTOURS Denote proposed construction. to the overlook 1425 Contours 33 thru 25 are not tied to bench mark shown. They are based on assumed existing contours from previous site construction and are provided as guide for developing the borrow area. +_1041E 1400 (2) SEE 1 SEETON BORROW SITE NOTTO ENGONCH ON TREE GELT AREAS. DVERLOOK SITE FOWER TRAUSFORMER. ion. Remove or DISTORN damage. See Sheet 10412 3 SEE X SECTION EXILTING & CIP WATER STORAGE TANK EXISTING M.H Put in 6 gate valve-1 Ea line PUT IN NEW & PVC SEWER LINE. WS - NEW SEWER CHE) WITH CURB STOPS. HISTORICAL MARKER BRICK TRASH CONTAINER REST AREA INFORMATION PANELS (3 PANEL UNIT) CONCRETE BENCH PLAG POLE LICHT POLE Location of Sanitary SEE CROSS SECTIONS FOR Manholes DIRT BALANCES FOR SYER-LOOK AND LAGOON. EXISTING IN WATER LINE TO EXISTING TROLLER WATE SEE DETAIL 6.8 SHT. 8 BENCH MARK " X" IN CONCRETE BASE OF FLAG POLE BOOK


TOTAL SHEETS ORIGINAL CONSTRUCTION PLANS PROJECT STATE OF SOUTH 029 S - 171 029 N - 171 21 30 DAKOTA CONTRACTORS TO VERIFY LOCATION & DEPTH OF ALL EXISTING UTILITIES. EXISTING TRANSFORMER EXISTING RURAL WATER PIPE SIZE REMOVE EXISTING 6000 GAL WATER STORAGE TANK & CONCRETE SLAB-INSTALL NEW TANK IN SAME LOCATION M.C. TO VERIFY. SEE SCHEDULE FOR SPRINKLER PIPE SIZING TYPE OF HEADS Valve Boxes for F SEE SAT. 10 Respective Zone Valve Boxes for Respective Zone ZONE #4 2" PVC MAIN 2" WASTE FROM DRINKING FOUNTAIN TO MANHOLE BUILDING SPRINKLER SYSTEM PLAN - NORTHBOUND PROVIDE PVC SLEEVES FOR SPRINKLER SYSTEM PIPING UNDER ALL SIDEWALKS (TYP) SCALE : 1" - 20'-0 NOTE: SPRINKLER CONTRACTOR TO REMOVE ALL EXISTING SPRINKLER HEADS & QUICK COUPLING VALVES. EXISTING PIPING TO BE ABANDONED. SITE PLAN & SPRINKLER SYSTEM LAYOUT-NORTHBOUND SPRINKLER SXSTEM SCHEDULE SPRINKLER SYSTEM NOTES PRESSURE HFG. NO. RADIUS STAKE ALL HEAD AND SPRINKLER LINE LOCATIONS FOR FUTURE REFERENCE. ADJUST HEAD LOCATIONS AS NECESSARY TO CONFORM TO FINAL FACILITY LOCATIONS AND TO PROVIDE ADEQUATE COVERAGE. SEE SHEET M-3 FOR CONTINUATION OF SPRINKLER SYSTEM SUPPLY PIPING. CONTRACTOR TO VERIFY SIDEWALK LQCATION AND SIZE. TI Valve Boxes for Respective Zone 2" WASTE FROM DRINKING FOUNTAIN TO MANHOLE -QUICK COUPLING VALVE (TYP) 2" PVC MAIN REST AREA 2" PVC MAIN BUILDING NOTE: PROVIDE PVC SLEEVES FOR SPRINKER SYSTEM PIPING UNDER ALL SIDEWALKS (TYP) ONNECT, TO CAPPED AT 24 BELOW GRADE 10'-0" FROM BUILDING BUILDING SPRINKLER SYSTEM PLAN - SOUTHBOUND Engineering Services ZONE #9 -GRADE Consulting Engineers ZONE #5 Charles H neller REMOVE EXISTING GOOD GAL WATER STORAGE TANK & CONCRETE SLAB-INSTALL NEW TANK IN SAME LOCATION M.C. TO YERIFY -POP-UP SPRINKLER HEAD OR QUICK COUPLING VALVE YE' LPS SERVICE -- 1/2 OR 3/4 FLEXIBLE CONNECTION AS REQUIR 18" (TYP) SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION 11-4-91 C EXISTING TRANSFORMER MECHANICAL PLAN & SPRINKLER SYSTEM LAYOUT - SOUTHBOUND

SPRINKLER SWING JOINT

SCALE: 1" - 30'-0"

DEUEL COUNTY REST AREA BUILDING SOUTH DAKOTA PROJECT #1R 29-6 (18) 160

ARCHITECTURE AUTOMATED, INC.



KEYED NOTES

- 1) HAND SPLIT CEDAR SHAKE SHINGLES ON 30# FELT.
- (2)2 LAYERS OF 3/4" RIGID INSULATION.
- (3) TREATED 2x4 NAILER.
- (4)1x6 ROUGH SAWN CEDAR FASCIA.
- (5)LAMINATED WOOD DECKING.
- (6)BREAK BOND W/ 15# FELT.
- (7) FACE BRICK STRETCHER.
- (8)2" RIGID INSULATION.
- (9) FACE BRICK SOLDIERS.
- (10) EXPANSION JOINT.
- (11) SIDEWALK AND DRAINAGE FILL, SEE DETAIL.
- (12)4" SLOTTED A.D.S. TUBING SURROUNDED W/ DRAINAGE FILL, 2'-0" HIGH AND 2'-0" WIDE.
- (13)12" CONCRETE FOUNDATION WALL.
- (14)#4'S VERTICAL & HORIZONTAL @ 15" O.C. EACH WAY.
- 15)4" CONCRETE SLAB W/ 6x6-10/10 W.W.F. ON VAPOR BARRIER ON 6" DRAINAGE FILL.
- (16)4" CONCRETE BLOCK.
- (17)5"x10 1/2" LAMINATED WOOD BEAM.
- (18)1" PROJECTION
- 19 ENGINEERED FILL"TO BOTTOM OF CONCRETE AND AT PERIMETER AROUND BUILDING.
- (20) REMOVE EXISTING DOOR AND THRESHOLD, FRAME TO REMAIN.
- (21)1/2" THICK QUARRY TILE ON 1" SETTING BED.
- (22) EXISTING CONCRETE FOUNDATION WALL.
- (23)1/2" NAIL BASE PLYWOOD.
- (24)30 MIL FLASHING.
- (25) WEEP HOLES @ 2'-8" O.C.

11-4-1

SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION DEUEL COUNTY FREST AREA BUILDING


ARCHITECTURE AUTOMATED, INC.




SHEET A-5

TEABLESON - TEABLESON

TATE OF PROJECT SHEET TOTAL NO. SHEETS DAKOTA 029 N - 171 23 30





KEYED NOTES


- (1) 3 1/2" x 10 1/2" LAMINATED WOOD BEAM.
- (2) CEDAR SHAKES ON 1 LAYER OF 30# FELT ON 3" LAMINATED WOOD DECK.
- 3) FACE BRICK STRETCHER.
- 4) FACE BRICK SOLDIERS.
- (5) 1x4 ROUGH SAWN CEDAR FASCIA.
- (6) MASONRY TIES Ø 16" O.C.
- (7) 5" CONCRETE SIDEWALK.
- (8) CONCRETE PIER
- 9 4" CONCRETE SLAB W/ 6x6-10/10 W.W.M. ON 6 MIL VAPOR BARRIER.
- (10) #5 VERTICAL.
- (11) #5 HORIZONTAL.
- (12) #4 REBAR.
- (13) 1 3/8" EXPANSION JOINT.
- (14) 6" DRAINAGE FILL.
- (15) 2" POLYSTYRENE.
- (16) 2" SAND.
- (17) 5" CONCRETE SLAB.
- (18) 1 3/4"x4" ALUMINUM TUBE.
- (19) ∠-8" x 4" x 7/16" W/ 7/16" BEARING PLATE
 WELDED BETWEEN TO ACCEPT LAM. WOOD BEAM.
 BEAM SOCKET IS ANCHORED TO WALL W/ 4-3/8"


 STUDS ② EACH JOIST (TYP.).
- (20) 1×2 ROUGH SAWN CEDAR TRIM 6 ALL MASONRY AND LAMINATED WOOD DECK JUNCTIONS.
- (21) 1'-6" x 1'-6" x 1'-0" DEEP PAD (TYP.).
- (22) BRICK BEYOND.
- (23) CONCRETE FOUNDATION WALL AND PAD BEYOND.
- (24) HISTORICAL MARKER
- 25) 3"x5"x3/16" THICK x 5" LONG STEEL SLEEVE W/ CLOSED BOTTOM, SEE DETAIL THIS SHEET.
- (26) WELD.
- (27) #5ø x 12" LONG.
- (28) 1/4" ALUMINUM / X 12" LONG. INSTALL PL. 8"
 FROM THE TOP OF THE RAIL W/ 3 S. S. SCREWS
- (29) NEW FOUNDATION CONTINIOUS TO EXISTING PICAIC SHELTER FOUNDATION.
- (3) PROUICE "L" AS SHOWN IN DETAIL (3) MO KEYED NOTE II GOTH ON SHEET IT.

SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION
DEUEL COUNTY REST AREA BUILDIN SOUTH DAKOTA PROJECT #IR 29-6 (18) 10

ARCHITECTURE AUTOMATED, INC.








S LOAD S G IPARM IPARM

DATE

AN CONCORD IN N. C.

RAWN BY:

PROJECT SOUTH 029 S - 171 029 N - 171 26 30 DAKOTA



6"

6'-0" before low ground elevation at each facting location, Maintain minimum 4'-0" cover over facting.

CONDUIT PLACEMENT DETAIL (Condult shall be located in the faciling as directed by the Engineer,)

SPECIFICATION NOTE-

Use South Dakota Standard Specifications for Roads and Bridges, 1990 Edition and Required Provisions, Supplemental Specifications and/or Special Provisions as Included in the Proposal.

GENERAL NOTES-

- I All exposed edges shall be chamfered %" except as shown.
- 2 All reinforcing steel shall conform to ASJ.N.: A6IS Grade 60.
- 3 Unit Stressese Concrete fo = 1800 p.s.l.

Reinforcing Steel fa = 24000 p.s.l.

- 4 Design Specifications: A.A.S. H.T.O. Specifications for Highway Bridges, 1990 Edition with 1991 Interlines and A.A.S. H.T.O. Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 1985 Edition with 1986 1991 Interlines.
- 5 The cost of Furnishing and installing the Condults embedded in the Footings shall be obsorbed in the Unit Price Bid for Class A45 Concrete, Miscellaneous
- 6 Prior to fobrication, details of the Tower Anchorage Assembly (Including anchorage) shall be submitted to the Office of Bridge Design for approval. Any modifications of the Footings shown to accommodate the Tower Anchorage Assembly must be submitted to and approved by the Office of Bridge Design, Additional quantities of materials resulting from modifications to accommodal the Towar Anchorage Assembly with not be measured for payment.
- 7 Structure Excordion, Light Tower shall be in accordance with the applicable sections of Section 420 of the Standard Specification. The Light Tower Fooling shall be bookfilled to existing groundline. Care shall be taken during backfilling to ensure that drainage will be away from the Tower Pedestal.
- 8 After excavation and backfill, excess material shall be disposed of an after obtained by the Contractor and approved by the Engineer.

DESIGN MIX OF CONCRETE-

- 1 Mix shall be designed to produce a concrete having a minimum compressive strength of 4500 p.s.l. at 28 days.
- 2 Type II Coment is required.

			REINI	ORCI.	NG SCHEDULE Tooling)	
Mk.	Na.	Size	Length	Type	Bending Details	B.
H	12	8	8.8"	17A		
][-6	4	15' - 5"	71	TI T	
ki	26	8	11'-6"	Str.	i 6	
12	24	5	11'-6"	Str.	1 6	
					E 7000 474	3-6" /1
All di	All dimensions are out to out of bars. Type ITA					

ESTIMATED O	UANTITIES	
ITEN	UNIT	QUANTITY
Class A45 Concrete, Misc.	Cu.Yd.	14.2
Reinforcing Steel	LA	1426
Structure Excavation, Light Tower	Cu, Yd.	64.6

DETAILS FOR 120' LIGHT TOWER FOOTINGS

> I-29 AT HIDEWOOD REST AREA IR 29-6(18)160 PCEMS NO. 2767

DEUEL COUNTY S. D. DEPT. OF TRANSPORTATION


NOVEMBER 1991

(I) OF (I) DESIGNED BY DRAWN BY CHECKED BY APPROVED


OC./HE

OC./HE

OC./HE




N- 12 Sp@11"=11-0"





(Bottom Steel)


12-0


PLANS BY a OFFICE OF BRIDGE DESIGN, SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION















Note: Use "White" cement concrete or a concrete mixture that matches the color of the information panels for parties of center fooling placed above construction joint,

REMOVE FOOTINGS-BOLTS AND WASHERS
MY BE REUSED IF APPROVED BY THE
ENGINEER. PROVIDE NEW FOOTINGS
AND REINFORCEMENT.
FXERCISE CARE IN CENTER RISER

EXERCISE CARE IN CENTER RISER REMOVAL.



1	REIN	FOR	CING	SCH	EDL	ILE
		1 -				/lates

M	No	Size	Length	Type	Bending Delaits .
Ai	12	4	3-3"	Str	
AZ	6	4	2'-0"	511.	
Az	4	4	5'-4"	Sic	• •
*,,	3	3	21-2"	Spiral	
¥,,	7	3	30'-5"	Spiral	();4
				1	1 / 1
				· ·	Carret 6

May be replaced with ¹z* \$ End Welded Deformed Bar Anchor Studs.

*Hoops with 12" minimum taps and 6 2" spacing may be substituded for spirals at no additional cost to the state

Spirats — Use 6" pitch and une extra turn at each end. Spirats may be smooth bars.

All dimension are out of out bars.


QUANTIES FOR FOOTINGS AND CONECTING HARDWA

LOKE IN	TIONING	1017		
EST	IMATI	ED	QUAN	ITITIES

ITEM ·	UNIT	QUANTITY
CLASS 'MS" CONCRETE	C4.408.	0.5
REINFORCEMENT FOR CONC. MASONE		82
STRUCTURAL STEEL	1.88	WPLACE
STRUCTURE EXCAVATION	Cu, 405,	0.4

- 1
0
0
\bigcirc
0
~
뛰
2
\vdash
-11
Σ
α
ш
ы
H
\vdash
=

The signs illustrated are not rif the work space is behind a more than 2 feet behind the cafeet or more from the edge or roadway. The signs illustrated shall be ustined a more are distracting situation vehicles parked on shoulder, velocessing the work site via the and equipment traveling on or the roadway to perform work. The ROAD WORK AHEAD sign may be with other appropriate signs, so the SHOULDER WORK sign. The SHO sign may be used for work adjusted shoulder. * If the work space is on a distribution highway, an advance warning so should also be placed on the of the directional roadway. For short term, short duration, operations, all signs and channel devices may be eliminated if a an activated flashing or revolvilight is used.	barrier, urb, or f any sed whe s; such hicles e highwo crossing operatio be repla uch as DULDER W acent to vided sign left sign or mob lizing vehicle	Speed Adv. Work (M.P.H.) 0 - 30 35 - 40 45 - 50 55 60 - 80 WORK SPACE Weth	pacing of ance Warning Signs (Feet) (A) 200 350 500 750 1000
	mig yen	ROAD WORK AHEAD	A
	S D D	GUIDES FOR TRAFFIC CONTROL DEVICES	April 15, 2015 PLATE NUMBER 634.01
Published Date: 1st Qtr. 2017	<i>O T</i>	WORK BEYOND THE SHOULDER	Sheet I Of I



Examples of-60"Chord Line Clearance Checks

S D D O T

Published Date: 1st Qtr. 2017

BREAKAWAY SUPPORT STUB CLEARANCE

-Anchor Post or Slip Base


PLATE NUMBER 634.99

Sheet I of I

Plotting Date: 04/19/2017

TLE - ...\STD PLATES_(3),[





CUT OR FILL SLOPE INSTALLATION

Slope

Spacing

Spacing Varies (See Table)

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	029 S - 171 029 N - 171	NO. SHEE	30

Plotting Date: 04/19/2017

GENERAL NOTES:

Published Date: 1st Qtr. 2017

At cut or fill slope installations, wattles shall be installed along the contour and perpendicular to the water flow.

At ditch installations, point A must be higher than point B to ensure that water flows over the wattle and not around the ends.

The Contractor shall dig a 3" to 5" trench, install the wattle tightly in the trench so that daylight can not be seen under the wattle, and then compact the soil excavated from the trench against the wattle on the uphill side. See Detail B.

The stakes shall be I"x2" or 2"x2" wood stakes, however, other types of stakes such as rebar may be used only if approved by the Engineer. The stakes shall be placed 6" from the ends of the wattles and the spacing of the stakes along the wattles shall be 3' to 4'.

Where installing running lengths of wattles, the Contractor shall butt the second wattle tightly against the first and shall not overlap the ends. See Detail C.

The Contractor and Engineer shall inspect the erosion control wattles once every week and within 24 hours after every rainfall event greater than $\frac{1}{2}$. The Contractor shall remove, dispose, or reshape the accumulated sediment when necessary as determined by the Engineer.

Sediment removal, disposal, or necessary shaping shall be as directed by the Engineer. All costs for removing accumulated sediment, disposal of sediment, and necessary shaping shall be incidental to the contract unit price per cubic yard for "Remove Sediment".

All costs for furnishing and installing the erosion control wattles including labor, equipment, and materials shall be incidental to the contract unit price per foot for the corresponding erosion control wattle bid item.

All costs for removing the erosion control wattle from the project including labor, equipment, and materials shall be incidental to the contract unit price per foot for "Remove Erosion Control Wattle".

December 23, 2004

EROSION CONTROL WATTLE

PLATE NUMBER 734.06

Sheet 2 of 2