
SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION

RAPID CITY REGION YARD - PHASE 1

PROJECT NUMBER 410394



PROJECT LOCATION MAP NOT TO SCALE

EXISTING LEGEND

•	BOREHOLE	Ø	POWER POLE	
R	CABLE TV OR TELEPHONE RISER		TYPE "E" INLET	
E	ELECTRICAL JUNCTION BOX		TYPE "B" INLET	
	FIBER OPTIC VAULT	M	MAILBOX	
BHF	BLACK HILLS FIBER	*	DELINEATOR	
	DECIDUOUS TREE			
	CONIFEROUS TREE			= EXISTING CURB AND GUTTER
	DECIDUOUS HEDGE/TREE LINE		5	SANITARY SEWER LINE
WWW.	CONIFEROUS HEDGE/TREE LINE		44	_
	DECIDUOUS BUSH		18" RCP	_ STORM SEWER LINE
₩ ₩	CONIFEROUS BUSH		- W W W W	WATER LINE
M	STUMP	wsws_		WATER SERVICE LINE
• •	2 POLE SIGN			
	1 POLE SIGN			TELEPHONE LINE
0	POST / BOLLARD	OH	OH← OH← OH← OH←	 OVERHEAD LINES (POWER, CABLE, ETC)
	FIRE HYDRANT	PP	PPP	– POWER LINE
→ MW	MONITORING WELL			— GAS LINE
	CURB STOP	F0 F0	F0	- FIBEROPTIC LINE
⊗ICV	IRRIGATION CONTROL VALVE			- CABLE TV LINE
WTR	GATE VALVE			- BARBED WIRE FENCE
	WATER MANHOLE			DUIL DING LINE
	TELEPHONE MANHOLE			PROPERTY LINE
	STORM SEWER MANHOLE			
	SANITARY SEWER MANHOLE			- SECTION LINE
(00)	CLEAN OUT			LASLIMENT LINE
G	GAS METER		100	
Δ	CONTROL POINT			MINOR CONTOUR

RIGHT-OF-WAY MARKER

ELECTRICAL MANHOLE

LUMINAIRE

N.T.S.

INDEX OF SHEETS

1.1	TITLE SHEET
1.2	PROJECT OVERVIEW
1.3	ESTIMATE OF QUANTITIES AND GENERAL NOTES
1.4	REMOVALS & TABLE OF EXCAVATION
2.1	EROSION & SEDIMENT CONTROL NOTES
2.2	STORM WATER POLLUTION PREVENTION PLAN
2.3	EROSION & SEDIMENT CONTROL LAYOUT
3.1	SITE LAYOUT
3.2-3.4	SITE GRADING
4.1-4.2	PROJECT SPECIFIC DETAILS


STORM WATER PERMIT

5.1-5.6

Major Receiving Body of Water: Box Elder Creek Area Disturbed: 5.6 Acres Total Project Area: 8.9 Acres Approx. Begin Lat/Long 44.0553/103.1030

STANDARD DETAILS

PROPOSED LEGEND



----- STEEL BAR INSTALLATION

100 — PROPOSED MAJOR CONTOUR PROPOSED MINOR CONTOUR STORM SEWER LINE


> STORM SEWER INLET STORM SEWER JUNCTION BOX





BEFORE DIGGING 1 - 800 - 781 - 7474 TRANSPORTATION PHASE 1

ARTMEN REGION Y



NOTES:

SPECIFICATIONS

STANDARD SPECIFICATIONS FOR ROADS AND BRIDGES, 2015 EDITION AND REQUIRED PROVISIONS, SUPPLEMENTAL SPECIFICATIONS, AND SPECIAL PROVISIONS AS INCLUDED IN THE PROPOSAL.

<u>UTILITIES</u>

THE CONTRACTOR SHALL BE AWARE THAT THE EXISTING UTILITIES SHOWN IN THE PLANS WERE SURVEYED PRIOR TO THE DESIGN OF THIS PROJECT AND MIGHT HAVE BEEN RELOCATED OR REPLACED BY A NEW UTILITY FACILITY PRIOR TO CONSTRUCTION OF THIS PROJECT, MIGHT BE RELOCATED OR REPLACED BY A NEW UTILITY FACILITY DURING THE CONSTRUCTION OF THIS PROJECT, OR MIGHT NOT REQUIRE ADJUSTMENT AND MAY REMAIN IN ITS CURRENT LOCATION. THE CONTRACTOR SHALL CONTACT EACH UTILITY OWNER AND CONFIRM THE STATUS OF ALL EXISTING AND NEW UTILITY FACILITIES. THE UTILITY CONTACT INFORMATION IS PROVIDED ELSEWHERE IN THE PLANS OR BIDDING DOCUMENTS.

SEQUENCE OF OPERATIONS

ALL PAVING OUTSIDE OF SEAMAN BOULEVARD SHALL BE COMPLETED AND OPEN TO TRAFFIC NO LATER THAN SEPTEMBER 15, 2017. ALL REMAINING WORK, INCLUDING CLEANUP, SHALL BE COMPLETED NO LATER THAN NOVEMBER 3, 2017.

CONSTRUCTION EQUIPMENT SHALL NOT ACCESS THE WORK AREA FROM THE INTERSTATE

CONSTRUCTION STAKING

CONSTRUCTION STAKING SHALL BE DONE BY THE SDDOT OR A REPRESENTATIVE OF THE SDDOT. THE CONTRACTOR WILL NOT BE RESPONSIBLE FOR CONSTRUCTION

TRAFFIC CONTROL

ROAD CONSTRUCTION AHEAD SIGNS SHALL BE INSTALLED ALONG THE EAST BOUND I-90 MAINLINE AND ON RAMP.

TRAFFIC CONTROL DEVICES SUCH AS CONES OR DELINEATORS SHALL BE INSTALLED TO SEPARATE STATE VEHICLE TRAFFIC FROM THE WORK AREA. ALL TRAFFIC CONTROL RELATED ITEMS SHALL BE INCIDENTAL TO THE PROJECT.

CONDUIT INSTALLATION

EACH END OF EACH CONDUIT SHALL BE MARKED WITH A 1/2-INCH DIA. X 12-INCH LONG REINFORCING BAR DRIVEN FLUSH WITH THE FINISHED GRADE, EXCEPT WHEN THE CONDUIT END TERMINATES INSIDE A JUNCTION BOX. THE ENDS OF EACH CONDUIT RUN SHALL BE CAPPED TO PREVENT WATER AND SOIL FROM ENTERING THIS WORK SHALL BE DONE BY THE LIGHTING CONTRACTOR AND SHALL NOT BE DISTURBED BY THE GRADING CONTRACTOR.

REMOVE AND RESET EXISTING LIGHT POLE

ALL WORK AND MATERIALS INCLUDING BUT NOT LIMITED TO CONDUIT, WIRING, FLOWABLE FILL ETC. NEEDED TO RESET THE EXISTING POLE AND FOOTINGS AT THE ISLAND LEFT OF STATION 6+00 SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE FOR "INSTALL LUMINAIRE POLE"

<u>UNDERCUTTING</u>

IN ALL CUT SECTIONS THE EARTHEN SUBGRADE SHALL BE UNDERCUT 1 FEET BELOW THE EARTHEN SUBGRADE SURFACE. THE UNDERCUT MATERIAL OR OTHER SUITABLE MATERIAL, AS DIRECTED BY THE ENGINEER, SHALL THEN BE REPLACED AND COMPACTED TO THE DENSITY SPECIFIED FOR THE SECTION BEING CONSTRUCTED.

AN EXCEPTION TO THE UNDERCUT REQUIREMENTS SHALL BE MADE IN SECTIONS THAT ENCOUNTER IN PLACE ROCK. CUT SECTIONS MADE THROUGH IN PLACE ROCK SHALL BE EXCAVATED TO THE TOP OF THE SUBGRADE SURFACE ONLY. SHALLOW EMBANKMENT SECTIONS (AS DESCRIBED ABOVE) PLACED OVER IN PLACE ROCK WITH LESS THAN 2 FEET OF SOIL COVER SHALL BE EXCAVATED TO THE SURFACE OF THE ROCK PRIOR TO PLACING ANY FILL.

THE PLAN SHOWN QUANTITY WILL BE THE BASIS OF PAYMENT. HOWEVER, IF THERE ARE ADDITIONAL AREAS OF UNDERCUT OTHER THAN WHAT IS SHOWN IN THE PLANS, THE ENGINEER SHALL DIRECT REMOVAL OF THESE AREAS AND THE ADDITIONAL AREAS WILL BE MEASURED ACCORDING TO THE ENGINEER.

EXCAVATION

CuYd

EXCAVATION MATERIAL SHALL BE SPLIT INTO TWO CATEGORIES, UNCLASSIFIED EXCAVATION AND CONTAMINATED MATERIAL EXCAVATION. THE CATEGORY OF EXCAVATION SHALL BE DETERMINED DURING CONSTRUCTION BY THE ENGINEER. IF THE EXCAVATED MATERIAL IS DETERMINED TO BE USABLE BY THE ENGINEER IT SHALL BE CONSIDERED UNCLASSIFIED EXCAVATION, AND STOCKPILED ON SITE AT A LOCATION DETERMINED BY THE ENGINEER. IF THE EXCAVATED MATERIAL IS DETERMINED TO BE UNUSABLE BY THE ENGINEER IT SHALL BE CONSIDERED CONTAMINATED MATERIAL EXCAVATION AND SHALL BE HAULED OFF-SITE AND DISPOSED OF PROPERLY BY THE CONTRACTOR. THE CONTAMINATED MATERIAL EXCAVATION IS NOT CONTAMINATED WITH PETROLEUM BASED CHEMICALS AND WILL NOT REQUIRE SPECIAL MATERIAL HANDLING, IT IS WASTE MATERIAL.

FOR BIDDING PURPOSES IT IS ASSUMED THAT THE TOTAL EXCAVATION QUANTITY WILL BE SPLIT EQUALLY BETWEEN UNCLASSIFIED AND CONTAMINATED MATERIAL EXCAVATION.

THE STOCKPILED UNCLASSIFIED EXCAVATION SHALL BE MEASURED AFTER GRADING OPERATIONS TO DETERMINE QUANTITY FOR PAYMENT. UNCLASSIFIED EXCAVATION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR "UNCLASSIFIED EXCAVATION".

THE DIFFERENCE BETWEEN THE TOTAL EXCAVATION QUANTITY (1713 CY) AND THE MEASURED UNCLASSIFIED EXCAVATION QUANTITY WILL BE THE BASIS OF PAYMENT FOR THE WASTE MATERIAL . THE WASTE MATERIAL SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR "CONTAMINATED MATERIAL EXCAVATION".

TABLE OF EXCAVATION IS LOCATED ON SHEET 1.4.

MUCK EXCAVATION

THE AREAS OF MUCK EXCAVATION ARE SHOWN ON THE PLANS WITHIN THE INTERSTATE 90 DITCH RIGHT OF WAY. THE ESTIMATED QUANTITY OF 1012 CUBIC YARDS OF MUCK EXCAVATION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR "MUCK EXCAVATION".

MUCK EXCAVATION CONSISTS OF THE REMOVAL OF HIGHLY ORGANIC AND/OR HIGHLY SATURATED MATERIAL FROM THE DESIGNATED AREAS SHOWN ON THE PLANS. HIGHLY ORGANIC MUCK MATERIAL SHALL NOT BE USED IN THE EMBANKMENT BUT MAY BE USED AS TOPSOIL. NON-ORGANIC MUCK MATERIAL MAY BE USED AS EMBANKMENT OUTSIDE OF THE FILL SUBGRADE SHOULDER IF IT IS PROPERLY HANDLED AND DRIED PRIOR TO PLACEMENT IN THE EMBANKMENT.

FIELD MEASUREMENT OF MUCK EXCAVATION WILL NOT BE MADE UNLESS THE ENGINEER ORDERS ADDITIONAL EXCAVATION, OR WHEN THE ENGINEER DETERMINES, IN ACCORDANCE WITH SECTION 120.3 A.1. OF THE SPECIFICATIONS, THAT THE CLASSIFICATION OF EXCAVATION BE CHANGED.

MUCK EXCAVATION SHALL NOT BE USED AS BACKFILL, EMBANKMENT OR TOPSOIL. IT SHALL BE DISPOSED OF PROPERLY AND SHALL BE CONSIDERED WASTE

PIPE CULVERT UNDERCUT

PIPE CULVERT UNDERCUT MAY BE REQUIRED FOR THIS PROJECT. A QUANTITY OF 100 CY HAS BEEN INCLUDED IN THE ESTIMATE OF QUANTITIES. THE ENGINEER WILL DETERMINE WHICH PIPE SHALL BE UNDERCUT IN ACCORDANCE WITH SECTION 421 OF THE SPECIFICATIONS.

REINFORCED CONCRETE PIPE

HIGH SULFATE LEVELS ARE LIKELY TO BE ENCOUNTERED ON THIS PROJECT. THE TYPE OF CEMENT USED FOR THE REINFORCED CONCRETE PIPES SHALL BE EITHER A TYPE II WITH 25% CLASS F MODIFIED FLY ASH SUBSTITUTED FOR CEMENT IN ACCORDANCE WITH SPECIFICATIONS SECTION 605 OR A TYPE V. THE WATER/CEMENTITIOUS MATERIAL RATIO SHALL NOT EXCEED 0.45 AS DEFINED IN SPECIFICATIONS SECTION 460.3 A. THE MIX SHALL BE AS PER THE FABRICATOR'S DESIGN; HOWEVER, MINIMUM COMPRESSIVE STRENGTH SHALL NOT BE LESS THAN 4500 PSI AT 28 DAYS. THE PIPE MUST BE MARKED IN AN ACCEPTABLE WAY TO DESIGNATE MEETING REQUIREMENTS FOR SULFATE RESISTANCE.

STORM SEWER

REINFORCED CONCRETE PIPE MAY BE BELL AND SPIGOT. THE PIPE SECTIONS SHALL BE ADJOINED SUCH THAT THE ENDS ARE FULLY ENTERED AND THE INNER SURFACES ARE REASONABLY FLUSH AND EVEN.

LIFT HOLES IN THE REINFORCED CONCRETE PIPE SHALL BE PLUGGED WITH GROUT.

DROP INLETS

THE CONTRACTOR SHALL COVER THE INSTALLED DROP INLETS TO PROVIDE SAFE TRAVEL FOR MOTORISTS AND TO PREVENT SURFACING MATERIALS FROM ENTERING THE STORM SEWER SYSTEM. THE METHOD AND TYPE OF COVER SHALL BE APPROVED BY THE ENGINEER. ALL COSTS INVOLVED WITH THE COVERINGS AND SHAPING OF THE INTERIM SURFACING SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICES FOR THE COMPONENTS OF THE DROP INLETS.

WHERE DROP INLETS ARE CONSTRUCTED WITHIN AREAS OF CURB AND GUTTER, THE CONTRACTOR SHALL CONSTRUCT WEEP HOLES OF AT LEAST 3 INCHES IN DIAMETER IN THE DROP INLET WALLS. THE WEEP HOLES SHALL BE CONSTRUCTED AT THE SAME ELEVATION AS THE ADJACENT TOP OF THE EARTHEN SUBGRADE AND SHALL BE MAINTAINED CLEAN AND OPEN AT ALL TIMES UNTIL THE PERMANENT SURFACING IS PLACED. THE DROP INLETS SHALL BE COVERED THROUGHOUT CONSTRUCTION OPERATIONS AS NECESSARY WITH AN ENGINEER APPROVED COVER TO PROVIDE SAFE TRAVEL FOR MOTORISTS AND TO PREVENT MATERIALS FROM ENTERING THE STORM SEWER SYSTEM. AFTER THE PERMANENT SURFACING HAS BEEN PLACED THE CONTRACTOR SHALL SEAL THE WEEP HOLES WITH GROUT AND REMOVE ALL DEBRIS FROM THE DROP INLET. ALL COSTS INVOLVED WITH THE COVERINGS, WEEP HOLES, AND REMOVING DEBRIS FROM THE DROP INLETS SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICES FOR THE COMPONENTS OF THE DROP INLETS.

THE PLAN SHOWN QUANTITIES OF THE DROP INLETS, TYPE B FRAME AND GRATE ASSEMBLY, TYPE C FRAME AND GRATE, PRECAST DROP INLET COLLAR, AND PRECAST CONCRETE TYPE S DROP INLET LID WILL BE THE BASIS OF PAYMENT FOR THESE ITEMS.

SPECIAL MANHOLE

THERE ARE FIVE SPECIAL MANHOLE/INLETS THAT SERVE AS STORM WATER QUALITY OUTLET STRUCTURES. THE OUTLET STRUCTURES SHALL BE BUILT ACCORDING TO THE DETAILS IN THE PLANS. EACH INLET WILL SLIGHTLY VARY DEPENDING ON THE LOCATION AND INTENT OF EACH STRUCTURE. FOR DETAILED INFORMATION REFER TO

THE STORM WATER QUALITY STRUCTURES SHALL BE PAID FOR UNDER THE CONTRACT UNIT PRICE PER EACH FOR "SPECIAL MANHOLE". PAYMENT INCLUDES BUT IS NOT LIMITED TO ALL LABOR, CONCRETE, REINFORCEMENT, GRATES AND TRASH SCREENS NECESSARY TO PROPERLY CONSTRUCT EACH STRUCTURE.

LOCATION OF CONCRETE PAVEMENT JOINTS

THE LOCATION OF JOINTS, AS SHOWN ON THE "SITE GRADING" SHEETS, ARE ONLY APPROXIMATE LOCATIONS TO BE USED AS A GUIDE IN THE FINAL LOCATION OF JOINTS AND TO AFFORD BIDDERS A BASIS FOR ESTIMATING THE CONSTRUCTION COSTS OF THE JOINTS. THE FINAL LOCATIONS OF THE JOINTS ARE TO BE DESIGNATED BY THE ENGINEER DURING CONSTRUCTION.

8" NONREINFORCED CONCRETE PAVEMENT

THE FINE AGGREGATE SHALL BE SCREENED OVER A 1-INCH SQUARE OPENING SCREEN JUST PRIOR TO INTRODUCTION INTO THE CONCRETE PAVING MIX. THE CONTRACTOR WILL SCREEN ALL OF THE AGGREGATE TO PREVENT THE INCORPORATION OF FOREIGN MATERIALS (IE: MUD BALLS) INTO THE CONCRETE MIX.

A CONSTRUCTION JOINT WILL BE SAWED WHENEVER NEW CONCRETE PAVEMENT IS PLACED ADJACENT TO EXISTING CONCRETE PAVEMENT.

THE TRANSVERSE CONTRACTION JOINTS SHALL BE PERPENDICULAR TO THE CENTERLINE AS DETAILED IN THE STANDARD PLATES 380.01 AND 380.08. IN MULTILANE AREAS THE TRANSVERSE CONTRACTION JOINTS SHALL BE PERPENDICULAR THE CENTERLINE AND BE IN A STRAIGHT LINE ACROSS THE WIDTH OF THE PAVEMENT. IN SPECIAL SITUATIONS THE ENGINEER MAY PRE-APPROVE TRANSVERSE CONTRACTION JOINTS THAT DO NET MEET THESE REQUIREMENTS. ALL NONCONFORMING TRANSVERSE CONTRACTION JOINTS THAT ARE NOT PRE-APPROVED SHALL BE REMOVED AT THE CONTRACTOR'S EXPENSE. ANY METHOD OF PLACEMENT THAT CANNOT PRODUCE THESE REQUIREMENTS SHALL BE ALLOWED TO

CONCRETE JOINT SEALING MAY ALL BE HOT POURED JOINT SEALANT.

EXPANSION MATERIAL SHALL BE USED IN ALL INSTANCES WHERE NEW CONCRETE IS BEING PLACED AROUND EXISTING STRUCTURES INCLUDING FOUNDATIONS, FOOTINGS, BUILDINGS ETC.

LANDSCAPE ROCK

LANDSCAPE ROCK PLACED SHALL BE THREE TO SIX INCH RIVER ROCK PLACED AT A NOMINAL DEPTH OF SIX INCHES. THE ROCK SHALL BE PLACED ON TOP OF DRAINAGE FABRIC. THE DRAINAGE FABRIC SHALL BE INCIDENTAL TO THE INSTALLATION OF THE RIVER ROCK, LANDSCAPE ROCK SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR LANDSCAPE ROCK.

CHAIN LINK FENCE

CHAIN LINK FENCE SHALL BE 6' CHAIN LINK FENCE WITH TENSION WIRED TOP AND BARBED WIRE TOP, MEASUREMENT AND PAYMENT SHALL BE MADE PER LINEAL FOOT FOR "6' CHAIN LINK FENCE WITH TENSION WIRED TOP" ACCORDING TO THE STANDARD SPECIFICATIONS AND PLATES.

SPECIAL 4' CHAIN LINK FENCE

SPECIAL CHAIN LINK FENCE SHALL BE INSTALLED ON THE TOP OF THE SPECIAL TYPE C RETAINING WALL AS SHOWN ON THE PLANS. THE RAILING SHALL BE CONSTRUCTED ACCORDING THE THE DETAILS IN SECTION 4. PAYMENT SHALL BE MADE PER LINEAL FOOT FOR "SPECIAL 4' CHAIN LINK FENCE" AND INCLUDES ALL NECESSARY LABOR, MATERIALS, PAINT, FASTENERS ETC TO PROPERLY CONSTRUCT THE HAND RAILING.

SPECIAL TYPE C RETAINING WALL

THE CONCRETE STORM WATER QUALITY FACILITIES LOCATED ON THE NORTH SIDE OF THE PROPERTY ADJACENT TO THE INTERSTATE 90 RIGHT-OF-WAY SHALL BE CONSTRUCTED ACCORDING TO THE PLANS AND DETAILS IN SECTION 4. THE ENTIRE STRUCTURE, INCLUDING WALLS AND FOUNDATION SHALL BE PAID FOR UNDER THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR "SPECIAL TYPE C RETAINING WALL" FOR DETAILED INFORMATION REFER TO SHEET 4.1.

TYPE C RETAINING WALL


TYPE C WALLS WILL BE CONSTRUCTED AROUND THE EXISTING TANKS AS SHOWN IN THE PLANS. THE WALLS SHALL BE 3.5' HIGH. EXPANSION SHALL BE PLACED BETWEEN THE EXISTING TANK FOUNDATIONS AND THE PROPOSED TYPE C WALLS. THE CONCRETE PAVEMENT SURROUNDING THE TYPE C WALLS WILL SERVE AS THE "SIDEWALK" FOR REINFORCEMENT.

INCIDENTAL WORK

THIS WORK INCLUDES ALL MISCELLANEOUS ITEMS NOT INCLUDED UNDER THE REGULAR ITEMS COVERED BY UNIT PRICES AS LISTED IN THE PROPOSAL, BUT WHICH MUST ME PERFORMED IN ORDER TO COMPLETE THE CONTRACT. SPECIFIC INCIDENTAL ITEMS ARE SHOWN ON THE DRAWINGS AND WILL BE PAID FOR AT THE CONTRACT LUMP SUM PRICE FRO "INCIDENTAL WORK." INCIDENTAL WORK INCLUDES. BUT IS NOT LIMITED TO THE FOLLOWING:

- 1. STORM SEWER REMOVALS, INCLUDING RCP, PVC, HDPE ETC.
 - ASPHALT SAW CUTTING OPERATIONS
- SWEEPING
- 4. TRAFFIC CONTROL 5. EXCAVATION FOR RIPRAP
- 6. MISCELLANEOUS GRADING AROUND INLETS, OUTLETS AND RIPRAP.
- DEWATERING
- 8. WASTE DISPOSAL SITE 9. DUST CONTROL
- 10. ADJUST PRIVATE UTILITIES
- 11. PROTECTION OF EXISTING FEATURES/UTILITIES 12. EXISTING UTILITY LOCATION AND VERIFICATION;







0

0

Ш

1


0

REGI APID

١۵

Sheet Title:

ESTIMATE OF **QUANTITIES AND GENERAL NOTES**



ALL COSTS TO FURNISH AND PLACE THE CONTRACTOR FURNISHED TOPSOIL SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER CUBIC YARD FOR "CONTRACTOR FURNISHED TOPSOIL".

THE ESTIMATED AMOUNT OF TOPSOIL TO BE FURNSHED IS AS FOLLOWS:

STATION TO	STATION		TOPSOIL (CUYD)	
3+39	8+86		845	(I-90 ROW)
3+88	5+94		201	(SWQ POND)
		TOTAL -	1046	

MYCORRHIZAL INOCULUM

MYCORRHIZAL INOCULUM SHALL CONSIST OF MYCORRHIZAL FUNGI SPORES AND MYCORRHIZAL FUNGI-INFECTED ROOT FRAGMENTS IN A SOLID CARRIER. THE CARRIER MAY INCLUDE ORGANIC MATERIALS, CALCINATED CLAY, OR OTHER MATERIALS CONSISTENT WITH APPLICATION AND GOOD PLANT GROWTH. THE SUPPLIER SHALL PROVIDE CERTIFICATION OF THE FUNGAL SPECIES CLAIMED AND THE LIVE PROPAGULE COUNT. THE INOCULUM SHALL INCLUDE THE FOLLOWING FUNGAL SPECIES:

LOMUS INTRARADICES	25%
LOMUS AGGREGATU	25%
LOMUS MOSSEAE	25%
LOMUS ETUNICATUM	25%

ALL SEED SHALL BE INOCULATED BY THE SEED SUPPLIER WITH A MINIMUM OF 100.000 LIVE PROPAGULES OF MYCORRHIZAL FUNGI PER ACRE. ALL COSTS OF INOCULATING THE SEED SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER POUND FOR THE CORRESPONDING PERMANENT SEED MIXTURE.

THE MYCORRHIZAL INOCULUM SHALL BE AS SHOWN BELOW OR AN APPROVED EQUAL

PRODUCT	MANUFACTURER
MYCOAPPLY	MYCORRHIZAL APPLICATIONS, INC. GRANTS PASS, OR PHONE: 1-866-476-7800
	www.mycorrhizae.com

FERTILIZING

THE CONTRACTOR SHALL APPLY AN ALL-NATURAL SLOW RELEASE FERTILIZER PRIOR TO SEEDING OR PLACING SOD. THE ALL-NATURAL FERTILIZER SHALL HAVE A MINIMUM GUARANTEED ANALYSIS OF 4-6-4 AND BE USDA CERTIFIED BIOBASED. IT SHOULD PROVIDE A MINIMUM OF 4% (N) NITROGEN WITH A MINIMUM WATER INSOLUBLE NITROGEN (WIN) FRACTION OF 3.2%, A MINIMUM OF 6% (P2O5) AVAILABLE PHOSPHATE. A MINIMUM OF 4% (K2O) SOLUBLE POTASH, AND A MAXIMUM CARBON TO NITROGEN RATIO (C:N RATIO) OF 5:1. THE ALL-NATURAL FERTILIZER SHALL BE FREE OF WEED-SEED AND PATHOGENS ACCOMPLISHED THROUGH THERMOPHILIC COMPOSTING, AND NOT MECHANICAL OR CHEMICAL STERILIZATION, TO ASSURE PRESENCE OF BENEFICIAL SOIL MICROBIOLOGY. THE FERTILIZER SHALL HAVE A NEAR NEUTRAL PH, A LOW SALT INDEX, A LOW BIOLOGICAL OXYGEN DEMAND, CONTAIN ORGANIC HUMIC AND FULVIC ACIDS, AND HAVE HIGH AEROBIC ORGANISM COUNTS, THE FERTILIZER SHALL ALSO BE STABLE, FREE OF BAD ODORS, AND BE UNATTRACTIVE AS A FOOD SOURCE FOR ANIMALS. IT SHOULD ALSO BE IN A GRANULAR FORM THAT IS EASILY SPREAD.

THE FERTILIZER SHALL BE APPLIED AT A RATE OF 1,500 POUNDS PER ACRE IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDED METHOD OF APPLICATION.

THE ALL-NATURAL SLOW RELEASE FERTILIZER SHALL BE AS SHOWN BELOW OR AN APPROVED EQUAL:

PRODUCT	MANUFACTURER
SUSTANE	SUSTANE CORPORATE HEADQUARTERS CANNON FALLS, MINNESOTA PHONE: 1-800-352-9245

www.sustane.com

PERMANENT SEEDING

THE AREAS TO BE SEEDED CONSIST OF ALL NEWLY GRADED AREAS WITHIN THE PROJECT LIMITS EXCEPT FOR THE TOP OF ROADWAYS, GRAVELED AREAS, AND OTHER AREAS AS DIRECTED BY THE ENGINEER.

TYPE F PERMANENT SEED MIXTURE SHALL CONSIST OF THE FOLLOWING:

GRASS SPECIES	VARIETY	PURE LIVE SEED (PLS) (POUNDS/ACRE)
WESTERN WHEATGRASS	ARRIBA, FLINTLOCK, RODAN, ROSANA	7
SIDEOATS GRAMA	BUTTE, KILLDEER, PIERRE, TRAILWAY	3
GREEN NEEDLEGRASS	LODORM	4
BLUE GRAMA	BAD RIVER, WILLIS	2
OATS OR SPRING WHEAT: APRIL THROUGH MAY; WINTER WHEAT: AUGUST THROUGH NOVEMBER		10
	TOTAL:	26

WATER FOR VEGETATION

WATER FOR VEGETATION CONSISTS OF APPLYING WATER TO SEEDED AREAS TO ENHANCE GERMINATION AND/OR ROOT GROWTH. WHEN WATERING, USE THE FOLLOWING GUIDELINES:

IMMEDIATELY AFTER SEEDING:

- KEEP THE TOPSOIL MOIST BUT NOT EXCESSIVELY WET UNTIL THE SEED HAS GERMINATED.
- WATER A MINIMUM OF 3 DAYS A WEEK FOR 2 WEEKS PREFERABLY WATERING 2 OR 3 TIMES A DAY IN SMALL QUANTITIES
- USE FINE SPRAY AND LOW PRESSURE TO AVOID TOPSOIL WASH AND TO PREVENT UNCOVERING BURIED SEEDS.

AFTER EMERGENCE:

 TOPSOIL SHALL BE KEPT THOROUGHLY MOISTENED BY SPRINKLING, AS NECESSARY, FOR 6 WEEKS. AFTER THE 6 WEEK PERIOD, AN INSPECTION SHALL BE MADE TO DETERMINE IF GRASS IS ESTABLISHED ENOUGH TO SUSPEND WATERING. CONTINUE WATERING UNTIL GRASS HAS BEEN THOROUGHLY ESTABLISHED.

- NEVER APPLY WATER AT A RATE FASTER THAN THE TOPSOIL CAN ABSORB.
- WATER DURING EARLY MORNING HOURS OR EARLY EVENING HOURS.
- DO NOT WATER WHEN RAIN IS FORECASTED FOR THE AREA. IF RAINFALL OCCURS, SUSPEND WATERING ACCORDING TO

AN ESTIMATED 18 GALLONS OF WATER PER SQUARE YARD OF SEEDING AREA WAS USED TO COMPUTE THE QUANTITY FOR THE BID

ALL COSTS FOR FURNISHING AND APPLYING THE WATER INCLUDING HAULING, MATERIALS, EQUIPMENT, LABOR, AND INCIDENTALS NECESSARY SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER MGAL FOR "WATER FOR VEGETATION".

HIGH FLOW SILT FENCE

ITEM "WATER FOR VEGETATION".

THE HIGH FLOW SILT FENCE FABRIC PROVIDED SHALL BE FROM THE APPROVED PRODUCT LIST. THE APPROVED PRODUCT LIST FOR HIGH FLOW SILT FENCE MAY BE VIEWED AT THE FOLLOWING INTERNET SITE:

http://sddot.com/business/certification/products/default.aspx

HIGH FLOW SILT FENCE SHALL BE PLACED AT THE LOCATIONS NOTED IN THE TABLE AND AT LOCATIONS THAT WILL MINIMIZE SILTATION OF ADJACENT STREAMS, LAKES, DAMS, OR DRAINAGE AREAS AS DETERMINED BY THE ENGINEER DURING CONSTRUCTION. REFER TO STANDARD PLATE 734.05 FOR DETAILS.

FIBER MULCHING

FIBER MULCH SHALL BE APPLIED IN A SEPARATE OPERATION FOLLOWING PERMANENT SEEDING.

AN ADDITIONAL 1% BY WEIGHT OF TACKIFIER SHALL BE ADDED TO THE FIBER MULCH PRODUCT SELECTED FROM THE APPROVED PRODUCT LIST. IF THE PRODUCT SELECTED HAS GUAR GUM TACKIFIER INCLUDED, THEN THE ADDITIONAL 1% OF TACKIFIER SHALL BE GUAR GUM. IF THE PRODUCT SELECTED HAS SYNTHETIC TACKIFIER INCLUDED, THEN THE ADDITIONAL 1% OF TACKIFIER SHALL BE SYNTHETIC.

FIBER MULCH SHALL BE APPLIED AT THE RATE OF 2,000 POUNDS PER

THE CONTRACTOR SHALL ALLOW THE FIBER MULCH TO CURE A MINIMUM OF 18 HOURS PRIOR TO WATERING OR ANY STORM EVENT TO ENSURE PROPER COHESION BETWEEN THE SOIL AND FIBER PARTICLES.

ALL COSTS FOR THE ADDITIONAL TACKIFIER ADDED TO THE FIBER MULCH INCLUDING LABOR, EQUIPMENT, AND MATERIALS SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER POUND FOR "FIBER MULCHING".

THE FIBER MULCH PROVIDED SHALL BE FROM THE APPROVED PRODUCT LIST. THE APPROVED PRODUCT LIST FOR FIBER MULCH MAY BE VIEWED AT THE FOLLOWING INTERNET SITE:

http://sddot.com/business/certification/products/Default.aspx

EROSION CONTROL BLANKET

EROSION CONTROL BLANKET SHALL BE INSTALLED 16 FEET WIDE AT THE LOCATIONS NOTED IN THE TABLE AND AT LOCATIONS DETERMINED BY THE ENGINEER DURING CONSTRUCTION.

THE EROSION CONTROL BLANKET PROVIDED SHALL BE FROM THE APPROVED PRODUCT LIST. THE APPROVED PRODUCT LIST FOR EROSION CONTROL BLANKET MAY BE VIEWED AT THE FOLLOWING INTERNET SITE:

http://sddot.com/business/certification/products/default.aspx

SHAPING FOR EROSION CONTROL BLANKET

THE DITCHES SHALL BE SHAPED FOR THE EROSION CONTROL BLANKET AS SPECIFIED ON STANDARD PLATE 734.01.

INTERIM SEDIMENT CONTROL AT INLETS, MANHOLES, AND JUNCTION BOXES AFTER SURFACING REMOVAL AND BEFORE PLACEMENT OF SURFACING

REFER TO STANDARD PLATE 734.05 FOR DETAILS OF INSTALLATION OF HIGH FLOW SILT FENCE AT DROP INLETS, MANHOLES, AND JUNCTION BOXES.

THE HIGH FLOW SILT FENCE FABRIC PROVIDED SHALL BE FROM THE APPROVED PRODUCT LIST. THE APPROVED PRODUCT LIST FOR HIGH FLOW SILT FENCE MAY BE VIEWED AT THE FOLLOWING INTERNET

http://sddot.com/business/certification/products/default.aspx

IN ADDITION, THE CONTRACTOR SHALL DO THE FOLLOWING FOR THIS INSTALLATION:

- A SPACE OF AT LEAST 1' SHALL BE PROVIDED BETWEEN THE SILT FENCE INSTALLATION AND THE INLET. THIS SPACE SHALL BE FILLED COMPLETELY WITH A 2" DEPTH OF AGGREGATE, 2" MINUS OR SMALLER.
- THE TOP ELEVATION OF THE SILT FENCE SHALL BE SUCH THAT A 12" HORIZONTAL FLAP OF SILT FENCE WILL REMAIN AT THE
- . THE BASE OF THE SILT FENCE SHALL CONFORM TO THE NATURAL GROUND PROFILE BUT DOES NOT NEED TO BE
- TRENCHED IN AT THE BOTTOM. THE EXTRA 12" OF THE SILT FENCE MATERIAL MAY BE CUT SO
- THAT THE MATERIAL WILL LAY FLAT UPON THE SUBGRADE. SEDIMENT FILTER BAGS SHALL BE PLACED ON THE 12" FLAP AROUND THE PERIMETER OF THE SILT FENCE INSTALLATION. THE SEDIMENT FILTER BAGS SHALL OVERLAP 6" AT THE ENDS AND BE PLACED TIGHTLY TOGETHER.
- THE SEDIMENT FILTER BAGS SHALL BE FILLED WITH CLEAN AGGREGATE 2" MINUS OR SMALLER.

SEDIMENT FILTER BAG

PRODUCT	MANUFACTURER
SNAKE BAG	SACRAMENTO BAG
	MANUFACTURING CO.
	SACRAMENTO, CA
	PHONE: 1-800-287-2247

THE SEDIMENT FILTER BAG SHALL BE THE SNAKE BAG FROM SACRAMENTO BAG MANUFACTURING COMPANY OR AN APPROVED

www.sacbag.com

ALL COSTS FOR FURNISHING AND INSTALLING THE SEDIMENT FILTER BAGS SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER FOOT

FOR "SEDIMENT FILTER BAG."

ALL COSTS FOR REMOVING THE SEDIMENT FILTER BAGS SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER FOOT FOR "REMOVE SEDIMENT FILTER BAG".

PAYMENT FOR HIGH FLOW SILT FENCE SHALL BE AS STATED IN SECTION 734.5 OF THE SPECIFICATIONS.

ALL COSTS FOR FURNISHING, INSTALLING, AND REMOVING THE 2" DEPTH OF AGGREGATE SHALL BE INCIDENTAL TO OTHER EROSION AND SEDIMENT CONTROL BID ITEMS.

ALL COSTS FOR REMOVING AND DISPOSING OF SEDIMENT COLLECTED BY THE SEDIMENT CONTROL DEVICE SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER CUBIC YARD FOR "REMOVE SEDIMENT".

THE REMOVED SEDIMENT SHALL BE PLACED AT A LOCATION AWAY FROM THE DROP INLET WHERE THE SEDIMENT WILL NOT BE WASHED BACK INTO THE DROP INLET OR OTHER STORM SEWER SYSTEM.

THE CONTRACTOR AND ENGINEER SHALL INSPECT AND MAINTAIN THE SEDIMENT CONTROL DEVICE ONCE EVERY WEEK AND WITHIN 24 HOURS AFTER EVERY RAINFALL EVENT GREATER THAN 1/2'

SEDIMENT CONTROL AT INLETS WITH FRAMES AND GRATES

THIS TYPE OF SEDIMENT CONTROL DEVICE SHOULD BE USED WHERE THERE IS PAVEMENT IN THE VICINITY OF THE DROP INLETS AND STORM WATER OR SEDIMENT COULD POSSIBLY ENTER THE FRAME AND GRATE. SEDIMENT CONTROL AT INLET WITH FRAME AND GRATE SHALL BE INSTALLED PRIOR TO WORKING IN THE VICINITY OF THE DROP INLETS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING AND REPAIRING THE SEDIMENT CONTROL DEVICES FOR THE DURATION OF THE PROJECT FOR WHICH SEDIMENT CONTROL MEASURES ARE REQUIRED. MAINTENANCE SHALL BE SCHEDULED TO PREVENT STORM WATER FROM BACKING UP INTO THE DRIVING LANE.

"SEDIMENT CONTROL AT INLET WITH FRAME AND GRATE" WILL BE PAID FOR ONE TIME AT EACH LOCATION, REGARDLESS OF THE NUMBER OF TIMES THE SEDIMENT CONTROL DEVICES ARE INSTALLED, INSPECTED, CLEANED, REMOVED, REPAIRED, OR REPLACED. ALL COSTS ASSOCIATED WITH FURNISHING, INSTALLING, INSPECTING, MAINTAINING, CLEANING, SEDIMENT REMOVAL, AND REPAIRING SEDIMENT CONTROL AT INLET WITH FRAME AND GRATE SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER EACH FOR "SEDIMENT CONTROL AT INLET WITH FRAME AND GRATE".

SEDIMENT COLLECTION DEVICES SHALL BE:

RECOMMENDATIONS.

A COMMERCIAL MADE SEDIMENT COLLECTION DEVICE FROM THE "SEDIMENT CONTROL AT INLET WITH FRAME AND GRATE" LIST OR AN APPROVED EQUAL. THE DEVICE SHALL BE INSTALLED IN REINFORCED CONCRETE DROP INLETS ACCORDING TO THE MANUFACTURER'S

SEDIMENT CONTROL AT INLET WITH FRAME AND GRATE APPROVED

ST:	
PRODUCT	MANUFACTURER
INFRASAFE DEBRIS COLLECTION DEVICE WITH FILTER SOCK	ROYAL ENVIRONMENTAL SYSTEMS, INC. STACY, MN PHONE: 1-800-817-3240 www.royalenterprises.net
DANDY CURB SACK	DANDY PRODUCTS INC. DUBLIN, OH PHONE: 1-800-591-2284 www.dandyproducts.com
SILT TRAPPER	STORM WATER SOLUTIONS LAKEVILLE, MN PHONE: 1-952-461-4376 www.silttrapper.com
DIP BASKET	SKYVIEW CONSTRUCTION CO., LLC WAUBAY, SD PHONE: 1-605-520-0555 www.skyviewconst.com
LEXSTORM INLET FILTERS	INLET AND PIPE PROTECTION, INC. NAPERVILLE, IL PHONE: 1-866-287-8655 www.inletfilters.com
GR-8 GUARD OR COMBO GUARD	ERTEC ENVIRONMENTAL SYSTEMS LLC ALAMEDA, CA PHONE: 1-866-521-0724 www.ertecsystems.com
SEDIMENT CATCHERS	SHAUN JENSEN

BROOKINGS, SD

www.strawblanket.com

bx-cc.com

PHONE: 1-605-690-4950 GRATE FX, SLAMMER, OR ENVIROSCAPE ECM, LTD. **VERTPRO** OAKWOOD, OH PHONE: 1-419-594-3210

BX INLET SEDIMENT BOXES BX CIVIL AND CONSTRUCTION DELL RAPIDS, SD PHONE: 1-605-428-5483

TABLE OF SEDIMENT CONTROL AT INLETS WITH FRAMES AND

SEE EROSION CONTROL LAYOUT SHEET IN PLANS FOR LOCATIONS, TYPES AND QUANTITIES OF SEDIMENT CONTROL AT INLETS.

SEDIMENT CONTROL AT TYPE S REINFORCED CONCRETE DROP

THE SEDIMENT CONTROL DEVICE PROVIDED SHALL BE FROM THE LIST SHOWN BELOW. REFER TO STANDARD PLATE 734.11 FOR DETAILS.

PRODUCT	MANUFACTURER
DANDY CURB	DANDY PRODUCTS INC. DUBLIN, OH PHONE: 1-800-591-2284 www.dandyproducts.com
GUTTERBUDDY	ACF ENVIRONMENTAL RICHMOND, VA PHONE: 1-800-448-3636 www.acfenvironmental.com
SS-300	SILT-SAVER, INC. CONYERS, GA PHONE: 1-888-382-7458 www.siltsaver.com
CURB INLET GUARD	ECTEC ENVIRONMENTAL SYSTEMS LLC ALAMEDA, CA PHONE: 1-866-521-0724 www.ertecsystems.com

TABLE OF SEDIMENT CONTROL AT TYPE S REINFORCED CONCRETE DROP INLETS

SEE EROSION CONTROL LAYOUT SHEET IN PLANS FOR LOCATIONS, TYPES AND QUANTITIES OF SEDIMENT CONTROL AT INLETS.

STREET SWEEPING

VEHICLE TRACKING OF SEDIMENT FROM THE CONSTRUCTION SITE SHALL BE MINIMIZED. STREET SWEEPING SHALL BE USED IF EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES ARE NOT ADEQUATE TO PREVENT SEDIMENT FROM BEING TRACKED ONTO THE

THE CONTRACTOR SHALL USE A PICKUP BROOM HAVING INTEGRAL SELF-CONTAINED STORAGE TO CLEAN THE ROADWAY. THE PICKUP BROOM USED SHALL BE A MINIMUM OF 6 FEET WIDE AND HAVE WORKING GUTTER BROOMS.

AT A MINIMUM, SWEEPING WILL BE REQUIRED AS DIRECTED BY THE

ALL COSTS FOR CLEANING THE ROADWAY WITH A PICKUP BROOM SHALL BE INCIDENTAL TO THE PROJECT.

SDDOT CONSTRUCTION ENTRANCE

IF THE SDDOT CONSTRUCTION ENTRANCE IS UTILIZED, THEN THE CONTRACTOR SHALL INSTALL THE SDDOT CONSTRUCTION ENTRANCE IN ACCORDANCE WITH THESE NOTES AND THE DETAIL

PIT RUN MATERIAL SHALL BE OBTAINED FROM A GRANULAR SOURCE AND SHALL CONFORM TO THE FOLLOWING GRADATION:

IEVE SIZE	PERCEN'	
	PASSING	
6"	100%	
#4	0-60%	
#200	0-20%	

THE PIT RUN MATERIAL SHALL BE COMPACTED TO THE SATISFACTION OF THE ENGINEER.

THE AGGREGATE FOR THE GRANULAR MATERIAL SHALL CONFORM TO THE FOLLOWING GRADATION REQUIREMENTS:

SIEVE SIZE	PERCEN
3 7	PASSIN
3"	100%
2 1/2"	90-1009
1 1/2"	25-60%
3/4"	0-10%
1/2"	0-5%

THE GRANULAR MATERIAL SHALL BE PLACED IN 6" MAXIMUM LIFTS.

IT IS ANTICIPATED THAT THE GRANULAR MATERIAL WILL NEED TO BE PERIODICALLY REMOVED AND REPLACED AS IT BECOMES INUNDATED WITH MUD AND SEDIMENT.

THE REINFORCEMENT FABRIC (MSE) SHALL CONFORM TO SECTION 831 OF THE SPECIFICATIONS. THE MSE GEOTEXTILE SHALL BE ON THE APPROVED PRODUCTS LIST FOR THIS MATERIAL OR WILL BE CERTIFIED BY THE SUPPLIER TO MEET THIS SPECIFICATION PRIOR TO INSTALLATION.

THE REINFORCEMENT FABRIC (MSE) SHOULD BE KEPT AS TAUT AS POSSIBLE PRIOR TO PLACING.

EQUIPMENT SHALL NOT BE ALLOWED ON THE REINFORCEMENT FABRIC (MSE) UNTIL THE FIRST LIFT OF GRANULAR MATERIAL IS IN

ALL SEAMS IN THE REINFORCEMENT FABRIC (MSE) SHALL BE OVERLAPPED AT LEAST 2' AND SHINGLED.

TREE REPLACEMENT

TREES SHALL BE PLANTED AT A 20' SPACING BETWEEN TREES AND IN A RANDOM PATTERN TO MIMIC NATURE.

PLANTING LOCATIONS FOR EACH INDIVIDUAL TREE SHALL BE IDENTIFIED PRIOR TO PLANTING AND APPROVED BY THE ENGINEER.

ALL TREES SHALL BE PURCHASED FROM COUNTY CONSERVATION DISTRICTS, A LANDSCAPE NURSERY, OR OTHER APPROVED SOURCE. TREES FURNISHED SHALL BE OF THE SAME GENUS, SPECIES, CULTIVAR, AND HEIGHT AS SPECIFIED IN THE PLANS. EACH TREE SHALL HAVE AN IDENTIFICATION LABEL.

AFTER BEING PLANTED, EACH TREE SHALL RECEIVE 10 GALLONS OF WATER TO THOROUGHLY SATURATE THE BACKFILL SOIL AS THIS PROVIDES SETTLEMENT AND FILLING OF VOIDS IN THE BACKFILL. AS SOON AS THE INITIAL PLANTING IS COMPLETED. THE ENGINEER SHALL VISUALLY INSPECT THE TREES FOR HEALTH, VIGOR, AND CONDITION, AND SHALL AT THAT TIME ACCEPT OR REJECT THEM.

WOOD CHIP MULCH SHALL BE APPLIED AT THE BASE OF EACH TREE AT A 4 INCH DEPTH AND IN A 3 FOOT DIAMETER FOR WEED SUPPRESSION. THE WOOD CHIP MULCH SHALL BE PULLED BACK FROM THE BASE OF THE TREE TRUNK 2 INCHES TO EXPOSE THE

THE CONTRACTOR SHALL PROVIDE A ONE YEAR WARRANTY FOR ALL TREES. AFTER ONE YEAR FROM INITIAL PLANTING, THE ENGINEER SHALL MAKE AN INSPECTION AND DEAD, UNHEALTHY, OR OTHERWISE NOT ACCEPTABLE PLANTS SHALL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE STATE.

ALL COSTS FOR FURNISHING, HANDLING, STORING, AND PLANTING THE TREES INCLUDING THE MATERIALS, EQUIPMENT, LABOR, PREPARATION OF THE GROUND, INITIAL WATERING, CLEANUP OF THE PLANTED AREAS, TREE SHELTERS, WOOD CHIP MULCH, AND THE WARRANTY SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER EACH FOR THE CORRESPONDING "6" TO 8" TREE, FURNISH AND PLANT" BID ITEM.

TABLE OF TREE REPLACEMENT

DMMON NAME	BOTANICAL NAME	HEIGHT	QUANTITY
UE SPRUCE	PICEA PUNGENS	6' TO 8'	6





0

0

RTM **a** Ш 1

Sheet Title:

0 S

> **EROSION AND** SEDIMENT **CONTROL NOTES**

SITE DESCRIPTION (4.2 1)

> PROJECT LIMITS: SEE TITLE SHEET (4.2 1.B) > PROJECT DESCRIPTION: SEE TITLE SHEET (4.2 1.A.)

- > SITE MAP(S): SEE TITLE SHEET AND PLANS (4.2 1.F. (1)-(6)) > MAJOR SOIL DISTURBING ACTIVITIES (CHECK ALL THAT
- TEXCAVATION/BORROW
- GRADING AND SHAPING
- FILLING CUTTING AND FILLING
- OTHER (DESCRIBE): > TOTAL PROJECT AREA 8.9 AC (4.2 1.B.)
- > TOTAL AREA TO BE DISTURBED 5.6 AC (4.2 1.B.)
- > EXISTING VEGETATIVE COVER (%) 15 SOIL PROPERTIES: UNK
- > CLASSIFICATION (4.2 1. D.) > NAME OF RECEIVING WATER BODY/BODIES TRIBUTARY TO

BOXELDER CREEK (4.2 1.E.)

ORDER OF CONSTRUCTION ACTIVITIES (4.2 1.C.)

- (STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS POSSIBLE, BUT IN NO CASE LATER THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. INITIATION OF FINAL OR TEMPORARY STABILIZATION MAY EXCEED THE 14-DAY LIMIT IF EARTH DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 21 DAYS.)
- INSTALL STABILIZED CONSTRUCTION ENTRANCE(S). > INSTALL PERIMETER PROTECTION WHERE RUNOFF SHEETS
- FROM THE SITE.
- > INSTALL CHANNEL AND DITCH BOTTOM PROTECTION.
- CLEARING AND GRUBBING.
- REMOVE AND STORE TOPSOIL STABILIZE DISTURBED AREAS.
- > INSTALL UTILITIES, STORM SEWERS, CURB AND GUTTER. > INSTALL INLET AND CULVERT PROTECTION AFTER COMPLETING STORM DRAINAGE AND OTHER UTILITY
- INSTALLATIONS. > COMPLETE FINAL GRADING.
- > COMPLETE FINAL PAVING AND SEALING OF CONCRETE. > COMPLETE TRAFFIC CONTROL INSTALLATION AND PROTECTION DEVICES.
- RESEED AREAS DISTURBED BY REMOVAL ACTIVITIES.

EROSION AND SEDIMENT CONTROLS (4.2 2.A.(1)(A)-(F))

- (CHECK ALL THAT APPLY) > STABILIZATION PRACTICES (SEE DETAIL PLAN SHEETS) ☐ TEMPORARY SEEDING (COVER CROP SEEDING)
- □ PERMANENT SEEDING SODDING
- □ PLANTING (WOODY VEGETATION FOR SOIL
- STABILIZATION) ☐ MULCHING (GRASS HAY OR STRAW)
-] HYDRAULIC MULCH (WOOD FIBER MULCH)
- SOIL STABILIZER
- BONDED FIBER MATRIX
- TEROSION CONTROL BLANKETS OR MATS
- VEGETATION BUFFER STRIPS
- ROUGHENED SURFACE (E.G. TRACKING) DUST CONTROL
- □ OTHER:

> STRUCTURAL TEMPORARY EROSION AND SEDIMENT CONTROLS

- SILT FENCE
- FLOATING SILT CURTAIN
- STRAW BALE CHECK TEMPORARY BERM
- TEMPORARY SLOPE DRAIN
- ☐ STRAW WATTLES OR ROLLS TURF REINFORCEMENT MAT
- ⊠ RIP RAP
- GABIONS
- ROCK CHECK DAMS SEDIMENT TRAPS/BASINS
- INLET PROTECTION **OUTLET PROTECTION**
- SURFACE INLET PROTECTION (AREA DRAIN) CURB INLET PROTECTION
- STABILIZED CONSTRUCTION ENTRANCES] ENTRANCE/EXIT EQUIPMENT TIRE WASH
- INTERCEPTOR DITCH
- CONCRETE WASHOUT FACILITY TEMPORARY DIVERSION CHANNEL
- WORK PLATFORM
- TEMPORARY WATER BARRIER
- ☐ TEMPORARY WATER CROSSING

OTHER: WETLAND AVOIDANCE

- WILL CONSTRUCTION AND/OR EROSION AND SEDIMENT CONTROLS IMPINGE ON REGULATED WETLANDS? YES ☐ NO ☑ IF YES, THE STRUCTURAL AND EROSION AND SEDIMENT CONTROLS HAVE BEEN INCLUDED IN THE TOTAL PROJECT WETLAND IMPACTS AND HAVE BEEN INCLUDED IN THE 404
- PERMIT PROCESS WITH THE USACE. ➤ STORM WATER MANAGEMENT (4.2 2.B., (1) AND (2)) STORM WATER MANAGEMENT WILL BE HANDLED BY TEMPORARY CONTROLS OUTLINED IN "EROSION AND SEDIMENT CONTROLS" ABOVE, AND ANY PERMANENT CONTROLS NEEDED TO MEET PERMANENT STORM WATER MANAGEMENT NEEDS IN THE POST CONSTRUCTION PERIOD. PERMANENT CONTROLS WILL BE SHOWN ON THE PLANS AND NOTED AS PERMANENT.

> OTHER STORM WATER CONTROLS (4.2 2.C., (1) AND (2)) WASTE DISPOSAL

- ALL LIQUID WASTE MATERIALS WILL BE COLLECTED AND STORED IN SEALED METAL CONTAINERS APPROVED BY THE PROJECT ENGINEER. ALL TRASH AND CONSTRUCTION DEBRIS FROM THE SITE WILL BE DEPOSITED IN THE APPROVED CONTAINERS. CONTAINERS WILL BE SERVICED AS NECESSARY, AND THE TRASH WILL BE HAULED TO AN APPROVED DISPOSAL SITE OR LICENSED LANDFILL. ALL ONSITE PERSONNEL WILL BE INSTRUCTED IN THE PROPER PROCEDURES FOR WASTE DISPOSAL, AND NOTICES STATING PROPER PRACTICES WILL BE POSTED IN THE FIELD OFFICE. THE GENERAL CONTRACTOR'S REPRESENTATIVE RESPONSIBLE FOR THE CONDUCT OF WORK ON THE SITE WILL BE RESPONSIBLE FOR SEEING WASTE DISPOSAL
- PROCEDURES ARE FOLLOWED. HAZARDOUS WASTE ALL HAZARDOUS WASTE MATERIALS WILL BE DISPOSED OF IN A MANNER SPECIFIED BY LOCAL OR STATE REGULATIONS OR BY THE MANUFACTURER. SITE PERSONNEL WILL BE INSTRUCTED IN THESE PRACTICES. AND THE INDIVIDUAL DESIGNATED AS THE CONTRACTOR'S ON-SITE REPRESENTATIVE WILL BE RESPONSIBLE FOR SEEING THAT THESE PRACTICES ARE
- FOLLOWED SANITARY WASTE
- PORTABLE SANITARY FACILITIES WILL BE PROVIDED ON ALL CONSTRUCTION SITES. SANITARY WASTE WILL BE COLLECTED FROM THE PORTABLE UNITS IN A TIMELY MANNER BY A LICENSED WASTE MANAGEMENT CONTRACTOR OR AS REQUIRED BY ANY LOCAL REGULATIONS.

MAINTENANCE AND INSPECTION (4.2 3. AND 4.2 4.)

- > MAINTENANCE AND INSPECTION PRACTICES INSPECTIONS WILL BE CONDUCTED AT LEAST ONE TIME PER WEEK AND AFTER A STORM EVENT OF 0.50 INCHES
- ALL CONTROLS WILL BE MAINTAINED IN GOOD WORKING ORDER. NECESSARY REPAIRS WILL BE INITIATED WITHIN 24 HOURS OF THE SITE INSPECTION REPORT
- SILT FENCE WILL BE INSPECTED FOR DEPTH OF SEDIMENT AND FOR TEARS IN ORDER TO ENSURE THE FABRIC IS SECURELY ATTACHED TO THE POSTS AND THAT THE POSTS ARE WELL ANCHORED. SEDIMENT BUILDUP WILL BE REMOVED FROM THE SILT FENCE WHEN IT REACHES 1/3 OF THE HEIGHT OF THE SILT FENCE.
- SEDIMENT BASINS AND TRAPS WILL BE CHECKED. SEDIMENT WILL BE REMOVED WHEN DEPTH REACHES APPROXIMATELY 50 PERCENT OF THE STRUCTURE'S CAPACITY, AND AT THE CONCLUSION OF THE CONSTRUCTION.
- CHECK DAMS WILL BE INSPECTED FOR STABILITY. SEDIMENT WILL BE REMOVED WHEN DEPTH REACHES ½ THE HEIGHT OF THE DAM. ALL SEEDED AREAS WILL BE CHECKED FOR BARE SPOTS,
- WASHOUTS, AND VIGOROUS GROWTH FREE OF SIGNIFICANT WEED INFESTATIONS. INSPECTION AND MAINTENANCE REPORTS WILL BE PREPARED ON FORM DOT 298 FOR EACH SITE
- INSPECTION, THIS FORM WILL ALSO BE USED TO DOCUMENT CHANGES TO THE SWPPP. A COPY OF THE COMPLETED INSPECTION FORM WILL BE FILED WITH THE SWPPP DOCUMENTS.
- THE SDDOT PROJECT ENGINEER AND CONTRACTOR'S EROSION CONTROL SUPERVISOR ARE RESPONSIBLE FOR INSPECTIONS. MAINTENANCE, REPAIR ACTIVITIES ARE THE RESPONSIBILITY OF THE CONTRACTOR. THE SDDOT PROJECT ENGINEER WILL COMPLETE THE INSPECTION AND MAINTENANCE REPORTS AND DISTRIBUTE COPIES PER THE DISTRIBUTION INSTRUCTIONS ON DOT 298.

NON-STORM WATER DISCHARGES (3.0)

- THE FOLLOWING NON-STORM WATER DISCHARGES ARE ANTICIPATED DURING THE COURSE OF THIS PROJECT (CHECK ALL THAT APPLY).
- DISCHARGES FROM WATER LINE FLUSHING:
- PAVEMENT WASH-WATER, WHERE NO SPILLS OR LEAKS OF TOXIC OR HAZARDOUS MATERIALS HAVE OCCURRED. ➤ ☐ UNCONTAMINATED GROUND WATER ASSOCIATED WITH

DEWATERING ACTIVITIES.

- MATERIALS INVENTORY (4.2. 2.C.(2))
 THE FOLLOWING MATERIALS OR SUBSTANCES ARE EXPECTED TO BE PRESENT ON THE SITE DURING THE CONSTRUCTION PERIOD. THESE MATERIALS WILL BE HANDLED AS NOTED UNDER THE HEADINGS "EROSION AND SEDIMENT CONTROLS" AND "SPILL"
- PREVENTION" (CHECK ALL THAT APPLY). ➤ ⊠CONCRETE AND PORTLAND CEMENT
- DETERGENTS
- PAINTS METALS
- BITUMINOUS MATERIALS

→ □OTHER:

- PETROLEUM BASED PRODUCTS
- CLEANING SOLVENTS
- ➤ □CURE
- TWOOD
- ➤ □TEXTURE ☐CHEMICAL FERTILIZERS

- MATERIAL MANAGEMENT
 - HOUSEKEEPING ONLY NEEDED PRODUCTS WILL BE STORED ON-SITE
 - BY THE CONTRACTOR EXCEPT FOR BULK MATERIALS THE CONTRACTOR WILL STORE ALL MATERIALS UNDER COVER AND IN APPROPRIATE CONTAINERS
 - PRODUCTS MUST BE STORED IN ORIGINAL CONTAINERS AND LABELED.
 - MATERIAL MIXING WILL BE CONDUCTED IN ACCORDANCE WITH THE MANUFACTURER'S **RECOMMENDATIONS**
 - WHEN POSSIBLE, ALL PRODUCTS WILL BE COMPLETELY USED BEFORE PROPERLY DISPOSING
 - OF THE CONTAINER OFF-SITE. THE MANUFACTURER'S DIRECTIONS FOR DISPOSAL OF MATERIALS AND CONTAINERS WILL BE FOLLOWED
 - THE CONTRACTOR'S SITE SUPERINTENDENT WILL INSPECT MATERIALS STORAGE AREAS REGULARLY TO ENSURE PROPER USE AND DISPOSAL.

CONSTRUCTION PROJECT WILL BE PRESERVED AND

 DUST GENERATED WILL BE CONTROLLED IN AN ENVIRONMENTALLY SAFE MANNER.

VEGETATION AREAS NOT ESSENTIAL TO THE

MAINTAINED AS NOTED ON THE PLANS.

SPILL PREVENTION (4.2 2.C.(2))

- HAZARDOUS MATERIALS PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS
- UNLESS THE CONTAINER IS NOT RESEALABLE. ORIGINAL LABELS AND MATERIAL SAFETY DATA SHEETS WILL BE RETAINED IN A SAFE PLACE TO RELAY IMPORTANT PRODUCT INFORMATION.
- IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURER'S LABEL DIRECTIONS FOR DISPOSAL WILL BE FOLLOWED.
- MAINTENANCE AND REPAIR OF ALL EQUIPMENT AND VEHICLES INVOLVING OIL CHANGES, HYDRAULIC SYSTEM DRAIN DOWN, DE-GREASING OPERATIONS, FUEL TANK DRAIN DOWN AND REMOVAL, AND OTHER ACTIVITIES WHICH MAY RESULT IN THE ACCIDENTAL RELEASE OF CONTAMINANTS WILL BE CONDUCTED ON AN IMPERVIOUS SURFACE AND UNDER COVER DURING WET WEATHER TO PREVENT THE RELEASE OF CONTAMINANTS ONTO THE GROUND.
- WHEEL WASH WATER WILL BE COLLECTED AND ALLOWED TO SETTLE OUT SUSPENDED SOLIDS PRIOR TO DISCHARGE. WHEEL WASH WATER WILL NOT BE DISCHARGED DIRECTLY INTO ANY STORM WATER SYSTEM OR STORM WATER TREATMENT SYSTEM.
- POTENTIAL PH-MODIFYING MATERIALS SUCH AS: BULK CEMENT, CEMENT KILN DUST, FLY ASH, NEW CONCRETE WASHINGS, CONCRETE PUMPING, RESIDUALS FROM CONCRETE SAW CUTTING (EITHER WET OR DRY), AND MIXER WASHOUT WATERS WILL BE COLLECTED ON SITE AND MANAGED TO PREVENT CONTAMINATION OF STORM WATER RUNOFF.

> PRODUCT SPECIFIC PRACTICES (6.8)

- PETROLEUM PRODUCTS ALL ON-SITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTIVE MAINTENANCE TO
- REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED.
- FERTILIZERS FERTILIZERS WILL BE APPLIED ONLY IN THE AMOUNTS SPECIFIED BY THE SDDOT. ONCE APPLIED, FERTILIZERS WILL BE WORKED INTO THE SOIL TO LIMIT THE EXPOSURE TO STORM WATER. FERTILIZERS WILL BE STORED IN AN
- ENCLOSED AREA. THE CONTENTS OF PARTIALLY USED FERTILIZER BAGS WILL BE TRANSFERRED TO SEALABLE CONTAINERS TO AVOID SPILLS. ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. THE EXCESS WILL BE DISPOSED OF ACCORDING TO THE MANUFACTURER'S
- INSTRUCTIONS AND ANY APPLICABLE STATE AND LOCAL REGULATIONS. CONCRETE TRUCKS CONTRACTORS WILL PROVIDE DESIGNATED TRUCK WASHOUT FACILITIES ON THE SITE. THESE AREAS MUST BE SELF-CONTAINED AND NOT CONNECTED TO ANY
- OF CONSTRUCTION, THE AREA AT THE WASHOUT FACILITY WILL BE PROPERLY STABILIZED. > SPILL CONTROL PRACTICES (4.2 2 C.(2)) IN ADDITION TO THE PREVIOUS HOUSEKEEPING AND MANAGEMENT PRACTICES. THE FOLLOWING PRACTICES WILL

STORM WATER OUTLET OF THE SITE. UPON COMPLETION

- BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP IF NEEDED. FOR ALL HAZARDOUS MATERIALS STORED ON SITE. THE MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED. SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATIONS OF THE INFORMATION AND CLEANUP
- SUPPLIES. APPROPRIATE CLEANUP MATERIALS AND EQUIPMENT WILL BE MAINTAINED BY THE CONTRACTOR IN THE MATERIALS STORAGE AREA ON-SITE. AS APPROPRIATE, EQUIPMENT AND MATERIALS MAY INCLUDE ITEMS SUCH AS BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST, AND PLASTIC AND METAL TRASH CONTAINERS SPECIFICALLY FOR CLEANUP PURPOSES.
- DISCOVERY AND THE MATERIALS DISPOSED OF THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE

CLOTHING TO PREVENT INJURY FROM CONTACT WITH A

ALL SPILLS WILL BE CLEANED IMMEDIATELY AFTER

- HAZARDOUS SUBSTANCE. AFTER A SPILL A REPORT WILL BE PREPARED DESCRIBING THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES TAKEN. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING, AS WELL AS CLEAN UP INSTRUCTIONS IN THE EVENT OF
- REOCCURRENCES. THE CONTRACTOR'S SITE SUPERINTENDENT, RESPONSIBLE FOR DAY-TO-DAY OPERATIONS, WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT THE SITE SUPERINTENDENT HAS HAD APPROPRIATE TRAINING FOR HAZARDOUS MATERIALS HANDLING, SPILL MANAGEMENT, AND CLEANUP.

> SPILL RESPONSE (4.2 2 C.(2))

SITE STORM WATER, IT IS CRITICAL TO CONTAIN THE

RELEASED MATERIALS ON-SITE AND PREVENT THEIR

POLLUTANTS THREATENS STORM WATER OR SURFACE

OUTLINED BELOW MUST BE IMPLEMENTED IN A TIMELY

■ THE CONTRACTOR'S SITE SUPERINTENDENT WILL BE

A SPILL IS OBSERVED. THE SUPERINTENDENT WILL

ESCAPING EROSION AND SEDIMENT CONTROLS AND

ENTERING RECEIVING WATERS, PERSONNEL WILL BE

SPILL KITS CONTAINING APPROPRIATE MATERIALS AND

MAINTAINED BY THE CONTRACTOR AT THE SITE.

IF OIL SHEEN IS OBSERVED ON SURFACE WATER (E.G.

CAUSING THE SHEEN. THE CONTRACTOR WILL USE

IF A SPILL OCCURS THE SUPERINTENDENT OR THE

SPILL. THE SOURCE OF THE OIL SHEEN WILL ALSO BE

SUPERINTENDENT'S DESIGNEE WILL BE RESPONSIBLE

PERSONNEL WITH PRIMARY RESPONSIBILITY FOR SPILL

THE CONTRACTOR'S SITE SUPERINTENDENT OR

RESPONSE EQUIPMENT AND THE USE OF SPILL

MAINTAINED AS NECESSARY TO REPLACE ANY

IN THE EVENT OF A SPILL, THE CONTRACTOR'S SITE

NOTIFICATION(S), CONSISTENT WITH THE FOLLOWING

> A RELEASE OR SPILL OF A REGULATED SUBSTANCE

SUPERINTENDENT WILL MAKE THE APPROPRIATE

FOLLOWING CONDITIONS EXISTS:

HUMAN HEALTH OR SAFETY.

THE DISCHARGE EXCEEDS 25 GALLONS.

OR GROUND WATER).

CHAPTER 74:51:01.

MATERIALS USED IN SPILL RESPONSE ACTIVITIES.

RESPONSE AND CLEAN UP WILL RECEIVE TRAINING BY

DESIGNEE. THE TRAINING MUST INCLUDE IDENTIFYING

THE LOCATION OF THE SPILL KITS AND OTHER SPILL

SPILL RESPONSE EQUIPMENT WILL BE INSPECTED AND

(INCLUDES PETROLEUM AND PETROLEUM PRODUCTS) MUST

THREATEN THE WATERS OF THE STATE (SURFACE WATER

BE REPORTED TO DENR IMMEDIATELY **IF ANY ONE OF THE**

THE DISCHARGE THREATENS OR IS IN A POSITION TO

THE DISCHARGE CAUSES AN IMMEDIATE DANGER TO

GROUND WATER QUALITY STANDARDS OF ARSD

SURFACE WATER QUALITY STANDARDS OF ARSD

THREATENS TO HARM WILDLIFE OR AQUATIC LIFE.

THE DISCHARGE OF CRUDE OIL IN FIELD ACTIVITIES

THE DISCHARGE CAUSES A SHEEN ON SURFACE WATER.

THE DISCHARGE OF ANY SUBSTANCE THAT EXCEEDS THE

(ADMINISTRATIVE RULES OF SOUTH DAKOTA) CHAPTER

THE DISCHARGE OF ANY SUBSTANCE THAT EXCEEDS THE

DIRECTED TO RESPOND IMMEDIATELY TO CONTAIN THE

RELEASE AND NOTIFY THE SUPERINTENDENT AFTER THE

EQUIPMENT FOR SPILL RESPONSE AND CLEANUP WILL BE

SETTLING PONDS, DETENTION PONDS, SWALES), ACTION

WILL BE TAKEN IMMEDIATELY TO REMOVE THE MATERIAL

APPROPRIATE MATERIALS TO CONTAIN AND ABSORB THE

IDENTIFIED AND REMOVED OR REPAIRED AS NECESSARY

FOR COMPLETING THE SPILL REPORTING FORM AND FOR

NOTIFIED IMMEDIATELY WHEN A SPILL OR THE THREAT OF

MANNER TO PREVENT THE RELEASE OF POLLUTANTS.

ASSESS THE SITUATION AND DETERMINE THE

IF SPILLS REPRESENT AN IMMINENT THREAT OF

APPROPRIATE RESPONSE.

SITUATION HAS BEEN STABILIZED.

TO PREVENT FURTHER RELEASES.

REPORTING THE SPILL TO SD DENR.

RESPONSE MATERIALS

WATER AT THE SITE, THE SPILL RESPONSE PROCEDURES

RELEASE INTO RECEIVING WATERS. IF A SPILL OF

- > CERTIFICATION OF COMPLIANCE WITH FEDERAL, STATE, AND THE PRIMARY OBJECTIVE IN RESPONDING TO A SPILL IS TO QUICKLY CONTAIN THE MATERIAL(S) AND PREVENT OR MINIMIZE MIGRATION INTO STORM WATER RUNOFF AND CONVEYANCE SYSTEMS. IF THE RELEASE HAS IMPACTED ON-
 - THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) FOR THIS PROJECT REFLECTS THE REQUIREMENTS OF ALL LOCAL MUNICIPAL JURISDICTIONS FOR STORM WATER MANAGEMENT AND SEDIMENT AND EROSION CONTROL AS ESTABLISHED BY ORDINANCE, AS WELL AS OTHER STATE AND FEDERAL REQUIREMENTS FOR SEDIMENT AND EROSION CONTROL PLANS PERMITS, NOTICES OR DOCUMENTATION AS APPROPRIATE.

> SOUTH DAKOTA DEPARTMENT OF TRANSPORTATION

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.



> PRIME CONTRACTOR

SECTION 6.9.1.C.)

THIS SECTION IS TO BE EXECUTED BY THE GENERAL CONTRACTOR AFTER THE AWARD OF THE CONTRACT. THIS SECTION MAY BE EXECUTED ANY TIME THERE IS A CHANGE IN THE PRIME CONTRACTOR OF THE PROJECT

AUTHORIZED SIGNATURE (SEE THE GENERAL PERMIT,

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WILL BE REVISED OR MAINTAINED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHER AND EVALUATE THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON OR PERSONS WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR GATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE, AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.

AUTHORIZED SIGNATURE

CONTACT INFORMATION

THE DISCHARGE OF ANY SUBSTANCE THAT HARMS OR

CELL PHONE: _____

UNDER SDCL (SOUTH DAKOTA CODIFIED LAWS) CHAPTER 45-9 IS GREATER THAN 1 BARREL (42 GALLONS). TO REPORT A RELEASE OR SPILL, CALL DENR AT 605-773-3296 DURING REGULAR OFFICE HOURS (8 A.M. TO 5 P.M. CENTRAL TIME). TO REPORT THE RELEASE AFTER HOURS, ON WEEKENDS OR HOLIDAYS, CALL STATE RADIO COMMUNICATIONS AT 605-773-3231. REPORTING THE RELEASE TO DENR DOES NOT MEET ANY OBLIGATION FOR REPORTING TO OTHER STATE, LOCAL, OR FEDERAL AGENCIES. THEREFORE, THE RESPONSIBLE PERSON MUST ALSO CONTACT LOCAL AUTHORITIES TO DETERMINE THE LOCAL

THAT SPILLS ALSO BE REPORTED TO THE NATIONAL RESPONSE

CENTER AT (800) 424-8802.

CONSTRUCTION CHANGES (4.4)
WHEN CHANGES ARE MADE TO THE CONSTRUCTION PROJECT THAT WILL REQUIRE ALTERATIONS IN THE TEMPORARY EROSION CONTROLS OF THE SITE, THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) WILL BE AMENDED TO PROVIDE APPROPRIATE PROTECTION TO DISTURBED AREAS, ALL STORM WATER STRUCTURES, AND ADJACENT WATERS. THE SDDOT PROJECT ENGINEER WILL MODIFY THE SWPPP PLAN (DOT 298) AND DRAWINGS TO REFLECT THE NEEDED CHANGES. COPIES OF CHANGES WILL BE ROUTED PER DOT 298. COPIES OF FORMS AND THE SWPPP WILL BE RETAINED IN A DESIGNATED PLACE FOR REVIEW OVER THE COURSE OF THE PROJECT.

> CONTRACTOR INFORMATION:

ADDRESS:

EROSION CONTROL SUPERVISOR

■ PRIME CONTRACTOR NAME: _____ CONTRACTOR CONTACT NAME: _______

.

CITY: _____STATE: ___ZIP: ____
 OFFICE PHONE: ____FIELD: _____

ADDRESS:

• • CITY: _____STATE: ____ZIP: ____ REPORTING REQUIREMENTS FOR RELEASES. DENR RECOMMENDS

OFFICE PHONE: ______FIELD: ______

> SDDOT PROJECT ENGINEER

NAME: ______ BUSINESS ADDRESS:

OFFICE PHONE: ______FIELD: _____


JOB OFFICE LOCATION: • CITY: _____STATE: ____ZIP: ____

 CELL PHONE: _____FAX: _____ > SD DENR CONTACT SPILL REPORTING BUSINESS HOURS MONDAY-FRIDAY (605) 773-3296

 NIGHTS AND WEEKENDS (605) 773-3231 > SD DENR CONTACT FOR HAZARDOUS MATERIALS. **(605)** 773-3153

> NATIONAL RESPONSE CENTER HOTLINE (800) 424-8802.





ORTA

OF


回


Ш


S


Sheet Title:


STORM WATER POLLUTION PREVENTION PLAN












NORTH SIDE SEDIMENT BASINS WNSB & MNSB TYPICAL SECTION /1




#4 @ 18" OC BOTH WAYS (TYP) **VARIES** 8" AGGREGATE / BASE COURSE

END WALL TYPICAL SECTION


BASIN TYPICAL SECTION 4.1

MEASUREMENT FOR SPECIAL TYPE C RETAINING WALL SHALL BE MADE TO THE NEAREST SQUARE FOOT FOR THE FLOOR, FOOTINGS, AND WALLS. THE FLOOR IS MEASURED FROM THE OUTSIDE WALL TO OUTSIDE WALL IN BOTH DIRECTIONS. THE WALLS ARE MEASURED FROM FINISHED FLOOR OR TOP OF FOOTING TO THE TOP OF WALL ALONG THE ENTIRE LENGTH. THE 2-FOOT WIDE SPREAD FOOTING FOR THE END WALLS SHALL ALSO BE MEASURED TO THE NEAREST SQUARE FOOT. ALL COSTS FOR EXCAVATION, FURNISHING AND PLACING BACKFILL AND CUSHION MATERIAL, LABOR, EQUIPMENT, PREFORMED EXPANSION JOINT FILLER, ALL REINFORCING STEEL, AND ALL CONCRETE SHALL BE INCIDENTAL TO THE CONTRACT UNIT PRICE PER SQUARE FOOT FOR "SPECIAL TYPE C RETAINING WALL" PLANS QUANTITY SHALL BE THE BASIS OF PAYMENT UNLESS CHANGES ARE MADE DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER.


SPECIAL TYPE C WALL QUANTITIES					
FLOOR	3946	SqFt			
APPROACH PAD	695	SqFt			
END WALL FOOTINGS	46	SqFt			
END WALLS	104	SqFt			
NORTH WALLS (1' HIGH)	249	SqFt			
SOUTH WALLS (VARYING HEIGHT)	1661	SqFt			
WEST WALL (7' HIGH)	70	SqFt			
EAST WALL (6' HIGH)	60	SqFt			
TOTAL	6831	SqFt			



SPECIAL 4' CHAINLINK FENCE INSTALLATION (6)



NORTH SIDE BASIN OUTLET WORKS



SEDIMENT BASIN ENSB - TYPICAL SECTION (5)








ANSPORTATION

DEPARTMENT OF

Sheet Title:

PROJECT SPECIFIC **DETAILS**







ANSPORTATION DEPARTMENT OF
PROJECT NUMBER 410394

SOUTH DAKOTA

CITY REGION YARD RAPID CITY, SD

Sheet Title:

PROJECT SPECIFIC **DETIALS**

Spacing shown for 12 foot lane

-0.177" (Min.) spacer wires.

and bend spacer wires

-4 Anchor

transverse contraction joint.

Published Date: 2nd Qtr. 2017

wires per unit.

_Anchor Pins-

Direction of Paving

oproved Coating-

A minimum of 4 spacer

9 anchor pins per unit (Min.) II Spoces @ I'-0" = II'-0"

ELEVATION

Dowel Bar Size

VIEW A-A

5 Anchor —

-Gravel Cushion

Longitudinal joint tie bars shall be placed a minimum of 15 inches from the

roadway and the dowel bars shall be centered on the sawed joint ±1 inch.

and to all other dowel bars in the assembly $\pm 1/16$ inch in 18 inches.

Centerline of individual dowel bars shall be parallel to top of subgrade ±1/8 inch in 18 inches

The transverse contraction joints shall be sawed perpendicular to the centerline of the

Supporting devices as shown on this sheet, or equivalent as approved by the Engineer, shall be used to maintain proper horizontal and vertical alignment of the dowel bars.

PCC PAVEMENT DOWEL BAR ASSEMBLY

FOR TRANSVERSE CONTRACTION JOINTS

12 Bar Assembly on Granular Base Material

Centerline of individual dowel bars shall be parallel to the centerline of the roadway

Outside Edge-

TYPICAL ANCHOR

PLATE NUMBER

380.01

Sheet I of I

PAVEMENT EPOXY COATED HEIGHT TO THICKNESS DOWEL BAR SIZE CENTER

7" to $7^{1}/_{2}$ " | 1" x 18" | 3.0"

8" to 10" 11/4" x 18" 4.0"

10½" to 12" 1½" x 18" 5.0"


____0.243" Wire (Min.) ___


Loops may be installed on either


inside or outside of rails


SIDE RAIL DETAIL OPTIONS


0.306" Wire (Min.)

















Spacing shown for 12 foot lane

-Anchor Pins

PLAN

ELEVATION

Outside Edge-

TYPICAL ANCHOR

PLATE NUMBER

380.03

Sheet | of |

Sheet I of 2

PAVEMENT EPOXY COATED HEIGHT THICKNESS DOWEL BAR SIZE CENTER

-0.243" Wire (Min.)-

Loops may be installed on either

inside or outside of rails

SIDE RAIL DETAIL OPTIONS

0.306" Wire (Min.)

1" × 18"

∠0.177" (Min.) spacer wires.

wires per unit.

after staking.

Edge

Lane

Direction of Paving

proved Coating-

GENERAL NOTES:

1/2 inch in 18 inches.

Published Date: 2nd Qtr. 2017

A minimum of 4 spacer

Contractor option to cut

Dowel Bar Size -4 Anchor 5 Anchor-

VIEW A-A

-Gravel Cushion

Longitudinal joint tie bars shall be placed a minimum of 15 inches from the transverse contraction joint.

oadway and the dowel bars shall be centered on the sawed joint ± 1 inch.

be used to maintain proper horizontal and vertical alignment of the dowel bars.

and to all other dowel bars in the assembly $\pm 1/16$ inch in 18 inches.

Centerline of individual dowel bars shall be parallel to top of subgrade +1/8 inch in 18 inches

Centerline of individual dowel bars shall be parallel to the centerline of the roadway


The transverse contraction joints shall be sawed perpendicular to the centerline of the


supportina devices as shown on this sheet,or equivalent as approved by the Engineer, shall

PCC PAVEMENT DOWEL BAR ASSEMBLY

FOR TRANSVERSE CONTRACTION JOINTS

9 Bar Assembly on Granular Base Material





CONCRETE CURB AND GUTTER

Sheet | of |

Published Date: 2nd Qtr. 2017



ш

N

ARI SD REGION APID CITY

Sheet Title: SDDOT STANDARD **DETIALS**





PLATE NUMBER

621.02

Sheet I of I



1/4" R.

DETAIL B

PCC Approach Pavement Limits


Concrete Curb

PLATE NUMBER


380.40


Sheet I of I

and Gutter





Published Date: 2nd Qtr. 2017





Published Date: 1st Qtr. 2017





LONGITUDINAL CONSTRUCTION JOINT WITHOUT TIE BARS

T = Pavement Thickness

When concrete pavement is formed and a keyway is provided, a metal recess strip shall be used. When concrete pavement is slip formed, a metal recess strip is not

The term "In Place PCC Pavement" in the above drawing indicates that the in place PCC pavement was placed on the current project.

LONGITUDINAL CONSTRUCTION JOINT WITHOUT TIE BARS

T = Pavement Thickness

The term "In Place PCC Pavement" in the above drawing indicates that the in place

PCC PAVEMENT LONGITUDINAL

JOINTS WITHOUT TIE BARS

New PCC Pavement

-Metal Recess Strip

Full Depth Saw Cut

PLATE NUMBER

380.12

Sheet I of 2

Sawed Joint filled with Hot-Poured Elastic Joint Sealer

Sawed Joint filled with Hot-


GENERAL NOTE:


Published Date: 2nd Qtr. 2017

In Place PCC Pavement

PCC pavement was placed on a previous project.

In Place PCC Pavement








ARI SD REGION PID CITY

SDDOT STANDARD **DETIALS**

Sheet Title:

Sheet I of I

GENERAL NOTES:



** A $\frac{1}{2}$ " preformed expansion joint filler shall be placed transversely in the curb and


Transverse contraction joints shall be constructed at 10' intervals in the concrete curb and gutter except when the concrete curb and gutter is constructed adjacent to

mainline PCC pavement. When concrete curb and gutter is constructed adjacent to mainline PCC pavement, a transverse contraction joint shall be constructed in the concrete

I. At each junction between the radius return of curb and gutter and curb and

2. At each junction between new curb and gutter and existing curb and gutter.

√2"Preformed Expansion**-Joint Filler




Cow Modulus *
Silicone Sealant


SECTION D-D


* The silicone sealant shall be placed such


as approved by the Engineer.


that it completely seals the joint and is bonded to the sides of the clean joint

















-Low Modulus * Silicone Sealant


SECTIONAL VIEW

For illustrative reason, only the type B curb and gutter is shown.

gutter which is parallel to the project centerline.

gutter at the following locations:

(Curb and Gutter at 1/2" Preformed Expansion Joint Filler Location)





Top of Curb

PLATE NUMBER

650.35

Sheet I of I







ARI SD REGION PID CITY

Sheet Title: SDDOT STANDARD **DETIALS**

0

Top of wall elevation as referred to in the plans.

Floor elevation as referred to in the plans.

REINFORCING SCHEDULE

2' X 3' TYPE B

REINFORCED CONCRETE DROP INLET

4' - 0"

SEC. A - A

NOTE: All dimensions are out to out of bars.

Published Date: 1st Qtr. 2017

★ Maximum "H" is 10' - 0"

Drop Inlet

7" 4 Spcs @ 5 ½" 7"


3'-0"

SEC. B - B

PLATE NUMBER

670.01

Sheet 2 of 2



6 Spaces @ 8" = 4' - 0"

+++++

• • • • • • •

BOTTOM SECTION

PIPE DISPLACEMENT

REDUCTIONS

December 16, 201

PLATE NUMBER

PLAN VIEW

Design Specifications: AASHTO LRFD Bridge Design Specifications, 2012 Edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

Reinforcing steel shall conform to ASTM A615 grade 60. The d bars shall be lapped 12 inches with the b and c bars. Cut and bend reinforcing steel as required to place pipe(s) through the drop inlet wall.

Drop inlet may be precast. If precast drop inlet details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Office of Bridge Design for approval.

Reduce total quantities of concrete by the amount of concrete displaced by the pipe(s). The total quantity of concrete shall be computed to the nearest hundredth of a cubic yard. The total quantity of reinforcing steel shall be computed to the nearest pound.

Drop inlet shown may be modified by the addition or omission of connecting

pipes as noted elsewhere in the plans. All pipes entering drop inlet must fit between the inside face of walls and shall not enter through the corners.

The dimension of H is in feet. Maximum H is 10 feet

Maximum R.C.P. diameter shall not exceed 24 inches (24 inches for R. C. arch) on the 3-foot wide side and shall not exceed 36 inches (30 inches for R.C. arch) on the 4-foot wide side of the drop inlet.

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

SPECIFICATIONS


GENERAL NOTES:


ESTIMATED QUANTITIES


DROP INLETS FOR 12" TO 36" DIAMETER PIPE


Cu. Yd. 0.72 Lb. 130.93 embly Each 1


UNIT CONSTANT VARIABLE QUANTITY QUANTITY











H DAKOTA DEPARTMENT OF TRANSPC
PROJECT NUMBER 410394

RAPID CITY REGION YARD PH RAPID CITY, SD

Sheet Title:

SDDOT STANDARD

DETIALS

0

5.4

Drog inlet

| Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten and offset as referred to in plans | Sisten a

REINFORCING SCHEDULE

Type 17

(17 · 10 · 10 · 1

3" b - 9 Spaces @ 6" = 4'- 6" 3" 5'- 0" SEC. B-B

★ Maximum H is 8' - 0"

PLATE NUMBER

670.32

Sheet 2 of 2

PIPE DISPLACEMENT

REDUCTIONS

ESTIMATED QUANTITIES

a - 23 Spaces @ 6" = 11' - 6"


SEC. A - A


4'X 11'TYPE S DROP INLET BASE

ITEM UNIT


Published Date: 1st Qtr. 2017


GENERAL NOTE:







Published Date: 1st Qtr. 2017












CITY REGION YARD F RAPID CITY, SD


Sheet Title: SDDOT STANDARD **DETIALS**

670.86


Sheet I of I

5.5





Published Date: 1st Qtr. 2017



TYPE S DROP INLET

Precast Concrete Type S
 Drop Inlet Lid

type of shims provided sha be approved by the SDDO Office of Bridge Design prio to installation.

Grout gap with same type of material as that used to conne the pipes to the drop inlet.

PLATE NUMBER

670.45

Sheet I of 2

GROUTING DETAIL (Sides and Back, Adjacent to Sidewall

INSTALLATION DETAILS FOR

SPECIFICATIONS

Design Specifications: AASHTO LRFD Bridge Design Specifications, 2012 Edition.

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, Current Edition and required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

GENERAL NOTES

Design Live Load: HL-93. No construction loading in excess of legal load was considered.

Drop inlet covers may be precast. If precast diop inlet cover details differ from this standard plate, submit a checked design done by a SD registered P.E. and shop plans to the Office of Bridge Design for approval. If precast, top side of lid shall be marked. Use 1 ½ inch clear cover on all reinforcing steel except as shown.

All exposed edges shall be chamfered ¾ inch.

Maximum fill over drop inlet cover shall be 3 feet, including surfacing.

Contractor shall break out drop inlet walls as necessary for the drop inlet cover to fit below roadway surfacing. Apply a thin layer of grout between drop inlet and cover to ensure uniform bearing. Grout shall conform to Section 460.2 K.

All costs involved in furnishing and installing the drop inlet cover including the epoxy resin and dowels shall be incidental to the contract unit price per Each for "4" x 11" Drop Inlet Cover", "5.5" x 11" Drop Inlet Cover, or "7" x 11" Drop Inlet Cover".

INSTALLING DOWELS IN CONCRETE

Holes drilled in the existing concrete shall be true and normal or as shown in the plans. Care shall be taken not to damage the existing reinforcing steel. It is very likely that some of the existing reinforcing steel shown in the original construction plans may have been placed out of position during original construction. Therefore, prior to drilling holes in the concrete, an effort will be made by the Department forces to mark locations of the in place reinforcing steel on the concrete surface. In spite of this precaution, the Contractor can still expect to encounter and have to drill through reinforcing steel or shift the dowel spacing as approved by the Engineer to miss the existing reinforcing steel.

The epoxy resin mixture shall be of a type for bonding steel to hardened concrete and shall conform to AASHTO M235 Type IV, Grade 3 (Equivalent to ASTM C881, Type IV, Grade 3).


The diameter of the drilled holes shall not be less than V_6 inch greater, nor more than \hat{Y}_6 inch greater than the diameter of the dowels or as per the Manufacturer's recommendations. Use compressed air or other techniques to ensure that the hole is free of any loose material before epoxy


Mix epoxy resin as recommended by the Manufacturer and apply by an injection method as approved by the Engineer. Beginning at the bottom of the drilled holes, fill the holes ½ to ½ full of epoxy resin. Rotate the steel bar during installation to eliminate voids and ensure complete bonding of the bar. Insertion of the bars by the dipping method will not be allowed.


No loads shall be applied to the epoxy grouted dowel bars until the epoxy resin has had sufficient time to cure as specified by the epoxy resin


Embed dowels 9 inches into existing concrete.


			December 16, 20
	S D D	PERMANENT 4'X 11', 5.5'X 11', AND 7'X 11'	PLATE NUMBE 670.92
Published Date: 1st Qtr. 2017	0 7	DROP INLET COVERS	Sheet I of 2













ARE CITY REGION YAR

R

Sheet Title: SDDOT STANDARD DETIALS