

210 ILAVAT - MOA.

OTTED FROM - TRAB

STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS
SOUTH DAKOTA	045-152	1	20
Plotting [	Date: 02/25/2020		

#### INDEX OF SHEETS

Sheet 1	Title Sheet & Layout Map
Sheet 2-3	Estimate of Quantities &
	Environmental Commitments
Sheet 4-5	Plan Notes
Sheet 6	Structure Details
Sheet 7-12	Shop Drawings & Original Construction Plans
Sheet 13-15	Traffic Control
Sheet 16-20	Standard Plates

PLO

## **ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS**

#### **Estimate of Quantities**

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E1693	Remove Erosion Control Wattle	150	Ft
110E7560	Remove Precast Concrete Box Culvert End Section for Reset	1	Each
120E0600	Contractor Furnished Borrow Excavation	150	CuYd
260E1010	Base Course	32.0	Ton
560E5111	Reset Precast Concrete Box Culvert End Section	1	Each
634E0010	Flagging	24.0	Hour
634E0110	Traffic Control Signs	121.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0275	Type 3 Barricade	3	Each
720E1015	Bank and Channel Protection Gabion	84.0	CuYd
734E0010	Erosion Control	Lump Sum	LS
734E0101	Type 1 Erosion Control Blanket	60	SqYd
734E0154	12" Diameter Erosion Control Wattle	150	Ft
831E0110	Type B Drainage Fabric	170	SqYd

#### SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

#### **ENVIRONMENTAL COMMITMENTS**

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

#### COMMITMENT B2: WHOOPING CRANE

The Whooping Crane is a spring and fall migratory bird in South Dakota that is about 5 feet tall and typically stops on wetlands, rivers, and agricultural lands along their migration route. An adult Whooping Crane is white with a red crown and a long, dark, pointed bill. Immature Whooping Cranes are cinnamon brown. While in flight, their long necks are kept straight and their long dark legs trail behind. Adult Whooping Cranes' black wing tips are visible during flight.

#### Action Taken/Required:

Harassment or other measures to cause the Whooping Crane to leave the site is a violation of the Endangered Species Act. If a Whooping Crane is sighted roosting in the vicinity of the project, borrow pits, or staging areas associated with the project, cease construction activities in the affected area until the Whooping Crane departs and immediately contact the Project Engineer. The Project Engineer will contact the Environmental Office so that the sighting can be reported to USFWS.

#### **COMMITMENT C: WATER SOURCE**

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species waters within South Dakota without prior approval from the SDDOT Environmental Office. Thoroughly wash all construction equipment to prevent and control the introduction and spread of invasive species into the project vicinity.

#### Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Environment and Natural Resources (DENR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of Aquatic Invasive Species in South Dakota can be accessed at: http://sdleastwanted.com/maps/default.aspx.

#### COMMITMENT D2: SURFACE WATER DISCHARGE

The DENR General Permit for Temporary Discharge is required for temporary dewatering and discharges to waters of the state. The effluent limit for total suspended solids will be 90 mg/L 30-day average. The effluent limit applies to discharges to all waters of the state except discharges to waters classified as cold water permanent fish life propagation waters according to the ARSD 74:51:01:45. For discharges to waters of the state classified as cold water permanent fish life propagation waters, the effluent limit for total suspended solids will be 53 mg/L daily maximum.

The permittee has the option of completing effluent testing or implementing a pollution prevention plan for compliance with this permit. If the permittee develops a pollution prevention plan instead of total suspended solids sampling, the plan must be developed and implemented prior to discontinuing total suspended solids sampling. Refer to section 3.0 of the permit. If any pollutants are suspected of being discharged, a sample must be taken for those parameters listed in section 2.2 of the permit.

#### Action Taken/Required:

Program, 605-773-3351.

The Contractor will provide a copy of the approved permit to the Project Engineer prior to proceeding with any dewatering activities. The approved permit must be kept on-site and as part of the project records.

Effluent monitoring, as a result of dewatering activities, will be summarized for each month and recorded on a separate Discharge Monitoring Report (DMR) and submitted to DENR monthly. Additional information can be found at http://denr.sd.gov/des/sw/WhatisaDMR.aspx

#### COMMITMENT E: STORM WATER

#### Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	045 -152	2	20

If construction dewatering is required, the Contractor will obtain the General Permit for Temporary Discharge Activities from the DENR Surface Water

http://denr.sd.gov/des/sw/swqformsandpermits.aspx

Construction activities constitute less than 1 acre of disturbance.

## **ESTIMATE OF QUANTITIES AND ENVIRONMENTAL COMMITMENTS**

#### COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

#### Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Environment and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench completely separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating "No Dumping Allowed".

2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period of time not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

#### **COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES**

State Historical Preservation Office (SHPO or THPO) concurrence has not been obtained for this project.

#### Action Taken/Required:

All earth disturbing activities require a cultural resource review prior to scheduling the pre-construction meeting. This work includes, but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view of which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office to determine an appropriate course of action.

The Contractor is responsible for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

#### COMMITMENT N: SECTION 404 PERMIT

The SDDOT has obtained a Section 404 Permit from the USACE for the permanent actions associated with this project.

#### Action Taken/Required:

The Contractor w Permit.

The Contractor will also be responsible for obtaining a Section 404 Permit for any dredge, excavation, or fill activities associated with material sources, storage areas, waste sites, and Contractor work sites outside the plan work limits that affect wetlands, floodplains, or waters of the United States.

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	045 -152	3	20

The Contractor will comply with all requirements contained in the Section 404

#### SCOPE OF WORK

Work involves removing and resetting three end sections of a Precast Concrete Box Culvert, PCBC, and installation of gabion baskets according to plan details and standard plates. Furnishing and placing Contractor furnished borrow or performing excavation will be done as necessary. Dewatering may be required depending on seasonal conditions.

The Contractor is encouraged to visit the sites prior to bidding to verify the extent of work needed.

#### **ORIGINAL CONSTRUCTION PLANS**

Construction plans and shop drawings included for reference are from Project P 0045(12)192 PCN 1282 Grading, Structures & Interim Surfacing for S.D. Highway No. 45 in McPherson County.

For additional information, contact the Aberdeen Area South Dakota Department of Transportation at (605)626-7885.

#### **SEQUENCE OF OPERATIONS**

- 1. Install traffic control devices.
- 2. Install erosion control measures.
- 3. Remove end sections for reset.
- 4. Excavate/Fill as needed.
- 5. Reset PCBC end sections.
- 6. Install and backfill Gabion Baskets.
- 7. Place Salvaged Topsoil.
- 8. Seed and mulch.
- 9. Install erosion control blanket.

Contractor requests to deviate from the sequence of operations will be submitted in writing to the Engineer for review. Approval of an alternate sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work. An alternate sequence will be submitted for review a minimum of one week prior to potential implementation.

#### **GENERAL TRAFFIC CONTROL**

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices including type II object markers will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for various items. Any delineators, object markers, and signs damaged or lost will be replaced by the Contractor at no cost to the State.

Standard Plate 632.01 and 632.04 have been included in the plans to indicate how Type II Object Markers shall be reset upon completion of work.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation.

All lane closer traffic control will be removed at night, and traffic control will be set up according to Standard Plate 634.03.

Type III barricades will be used on the inslope to the satisfaction of the Engineer.

All construction operations will be conducted in the general direction of traffic movement.

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Traffic Control Signs, as shown in the Estimate of Quantities, are estimates. Contractor's operation may require adjustments in quantities, either more or less. Payment will be for used signs ordered by the Engineer.

Fixed location signing placed more than 4 calendar days prior to the start of construction will be covered or laid down until the time of construction. The covers must be approved by the Engineer prior to installation. The cost of materials, labor, and equipment necessary to complete this work will be incidental to other contract items. No separate payment will be made.

All fixed location signs, sign posts, and breakaway bases will be removed within 7 calendar days following install of erosion control blanket.

All haul trucks will be equipped with an additional flashing amber light that is visible from the backside of the haul truck. The costs for the flashing amber lights will be incidental to the various related contract items.

At no time will a vertical drop-off of greater than 3 inches be left overnight adjacent to the traveled way. The Contractor will utilize embankment material to ensure a 3-inch vertical drop-off is not exceeded. The slope of the embankment material will not be steeper than a 4:1 within 30 feet of the traveled way.

Traffic will be maintained on the driving lanes. Use of the shoulder as a driving lane will not be permitted. Any damage to the shoulder due to rerouted traffic or Contractor's equipment will be repaired at no expense to the Department.

#### **FLAGGING**

Operations will be conducted so that the traveling public will not have to wait longer than 15 minutes at the flagger station.

It is required that the flaggers be able to communicate with one another. If an emergency vehicle needs to pass through the project, the Contractor will be required to expedite traffic movement. All costs associated with this will be incidental to the contract unit price per hour for "Flagging".

#### UTILITIES

Utilities are not planned to be affected on this project. If utilities are identified near the improvement area through the SD One Call Process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25, the Contractor will contact the Project Engineer to determine modifications that will be necessary to avoid utility impacts.

#### **GRADING OPERATIONS**

No separate payment will be made for "Water for Embankment" and all costs associated will be incidental to the contract unit price per cubic yard of "Contractor Furnished Borrow Excavation".

The Contractor will salvage and stockpile topsoil prior to culvert end section reset and gabion installation. Limits of this work, depth of salvage, and stockpile location will be to the satisfaction of the Engineer. Following completion of construction, topsoil will be spread evenly at a minimum 4" depth over the disturbed areas that are to be seeded.

Payment for this work will be incidental to the contract unit price per cubic yard for "Contractor Furnished Borrow Excavation".

#### PRECAST CONCRETE BOX CULVERT END SECTION RESET

There are three PCBC end sections to be removed and reset along with a cutoff wall. Payment for all three sections and the cutoff wall removal and install will be noted respectably as a quantity of one removal and one reset in the Estimate of Quantities for "Remove Precast Concrete Box Culvert End Section for Reset" and "Reset Precast Concrete Box Culvert End Section".

Any damage to box culvert sections caused by the Contractor will be repaired by the Contractor to the satisfaction of the Engineer.

After removal for reset, the installation area will be undercut to a minimum depth of 1 foot and backfilled with base course. The depth of undercut is an estimate and the actual depth necessary will be determined during construction. The Engineer will determine how much undercut will be done in accordance with Section 421.3 of the Specifications, but will not reduce the undercut to less than 1 foot in depth. Compaction of the undercut backfill will be in accordance with Section 421.3 A.

The remainder of the PCBC excavation will be backfilled with soils taken from the removal excavation or other suitable material designated as Contractor Furnished Borrow as approved by the Engineer.

PCBC base course for the undercut backfill will be paid for at the contract unit price per ton for "Base Course".

Flowline will match that of existing. If needed, sandbagging around wet areas will be done and the cost will be incidental to various contract items.

All reset precast PCBC end sections will be tied. New tie bolt assemblies will be provided by the Contractor and installed according to Standard Plate 560.01 at locations designated on Standard Plate 560.02. The PCBC end section connection to the cutoff wall is unknown with no Shop Plan from PCN 1282. Supplies needed for the cutoff wall will be provided by the Contractor. Cost of all ties and reset of the cutoff wall will be incidental to "Reset Precast Concrete Box Culvert End Section".

STATE OF	PROJECT	SHEET	TOTAL SHEETS
SOUTH DAKOTA	045 - 152	4	20

#### **INSTALLATION OF GABION BASKETS**

Gabions Baskets will be installed according to the Structure Details Sheet and Standard plate 720.01. Gabions installed on the inslopes near the box culvert inlet will be installed to match the existing inslopes. Gabions installed under the flow line will match the slope of the channel flow line. Gabion baskets will be backfilled to match the existing ground level.

Payment for excavation and back filling of the borrow material will be incidental to the contract unit price per cubic yard for "Contractor Furnished Borrow Excavation". Compaction of the Contractor Furnished Borrow will be to the satisfaction of the Engineer. The basis of payment will be plans quantity. There will be no additional payment for dewatering if it is needed.

Type B drainage fabric will be placed under the gabions and around the exterior sides (perimeter) of the gabions as approved by the Engineer. The type B drainage fabric shall be in conformance with Section 831 of the Specifications. Measurement and payment of the type B drainage fabric will be in conformance with Section 720 of the Specifications.

#### **INSLOPE TRANSITIONS**

The finished inslope will be in compliance with Standard Plate 120.05.

#### SHRINKAGE FACTOR:

Quantities were computed using a 40% shrinkage factor.

#### CONTRACTOR FURNISHED BORROW

Contractor will provide a suitable site for Contractor Furnished Borrow Excavation material. The Contractor is responsible for obtaining all required permits and clearances for the borrow site. The borrow material will be approved by the Engineer. The plans quantity for "Contractor Furnished Borrow Excavation" as shown in the Estimate of Quantities will be the basis of payment for this item.

Restoration of the Contractor Furnished Borrow Excavation Site will be the responsibility of the Contractor.

#### **EROSION CONTROL**

The estimated area requiring erosion control is 2,000 square feet. All costs for equipment, labor, seeding, and fiber mulching will be incidental to the contract lump sum price for "Erosion Control".

The limits of erosion control work will be determined by the Engineer during construction.

#### Mycorrhizal inoculum

Mycorrhizal inoculum will consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier will provide certification of the fungal species claimed and the live propagule count. The inoculum will include the following fungal species:

- 25% Glomus intraradices
- 25% Glomus aggregatum or deserticola
- 25% Glomus mosseae
- 25% Glomus etunicatum

All seed will be inoculated by the seed supplier with a minimum of 100,000 live propagules of mycorrhizal fungi per acre. All costs of inoculating the seed will be incidental to the contract Lump Sum price for "Erosion Control".

The mycorrhizal inoculum will be as shown below or an approved equal:

Product	Manufacturer
MycoApply	Mycorrhizal Applications, Inc. Grants Pass, OR Phone: 1-866-476-7800 www.mycorrhizae.com
Am 120 multi species blend	Reforestation technologies int. Gilroy, ca Phone: 1-800-784-4769 www.reforest.com

#### Fertilizing

Application of fertilizer will not be required on this project.

#### Permanent seeding

The areas to be seeded consist of all newly graded areas within the project limits.

Type C Permanent Seed Mixture will consist of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/Acre)
Western Wheatgrass	Arriba, Flintlock, Rodan, Rosana, Walsh	16
Canada Wildrye	Mandan	2
	Total:	18

#### Cover crop seeding

Cover crop seeding may be used on this project as a temporary erosion control measure. The actual limits and use of cover crop seeding will be determined by the Engineer during construction, and all costs will be incidental to the contract Lump Sum price for "Erosion Control".

#### Fiber mulching

seeding.

The Contractor will allow the fiber mulch to cure a minimum of 18 hours prior to watering or any storm event to ensure proper cohesion between the soil and fiber particles.

All costs for additional tackifier added to the fiber mulch including labor, equipment, and materials will be incidental to the contract Lump Sum price for "Erosion Control".

The fiber mulch provided will be from the approved product list. The approved product list for fiber mulch may be viewed at the following internet site:

http://apps.sd.gov/HC60ApprovedProducts/main.aspx

#### **EROSION CONTROL WATTLE**

Erosion control wattles for restraining the flow of runoff and sediment will be installed at locations determined by the Engineer during construction. Refer to Standard Plate 734.06 for details.

The Contractor will provide certification that the erosion control wattles do not contain noxious weed seeds.

Erosion control wattles will remain on the project to decompose.

internet site:

#### http://apps.sd.gov/HC60ApprovedProducts/main.aspx

#### **EROSION CONTROL BLANKET**

The erosion control blanket will be installed at locations of disturbed ground to be seeded and/or locations determined by the Engineer during construction. Shaping for the erosion control blanket is not needed. Standard Plate 734.01 will be referenced for all other requirements.

The erosion control blanket provided will be from the approved product list and may be viewed at the following internet site:


http://apps.sd.gov/HC60ApprovedProducts/main.aspx


	STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
		045 - 152	5	20


Fiber mulch will be applied in a separate operation following permanent

Fiber mulch will be applied at the rate of 2,000 pounds per acre.

The erosion control wattle provided will be from the approved product list. The approved product list for erosion control wattle may be viewed at the following







				1	000.0		SHEET	TOTAL
	ľ			STATE OF SOUTH DAKOTA	045-152		NO.	SHEETS
					ate: 01/22/2020	 0	8	20
TYPE - I SLOPED END SECTIONS	COMPACT NUMER	BC 305		ox Culvert				
TYPE - I SLOPE	none	B-26-93	. d70	ſ	at			
	SME	DUE	Name	Concrete	abr			
	1 0		-1	ouc	Ë			
	<u>ן</u> ז	ן ק	4-8	Ŭ	-			
5			7-8	<b>St</b>	Secti			
			<u>8-0</u>	Precast				
1	13	4	6-0	D C	pu			
	]]	9	20	ת	Ш			
	ļ	, n , n	6-0	Drigina				
: <u>9</u>	9 S	<u></u> រ	27					
081.12 X 8	DBL 12 X ID	DBL 12 X II	DBL 12 X 12	C				

LE - ... \MCPHI5UG\I5UG\_TITLE SHEET.DG

I DT NAMF - 1

#### SPECIFICATIONS-

Construction Specifications: South Dakota Standard Specifications for Roads and Bridges, 1990 Edition and Required Provisions, Supplemental Specifications and/or Special Provisions as Included In the Proposal,

#### DESIGN MIX OF CONCRETE

- I Mix shall be destaned to produce a concrete having a minimum compressive strength of 4500 p.s.l. at 28 days.
- 2 · Type ∏ Cement Is required.
- 3 Because of the presence of carrosive solls on the project, Class C Fly Ash will not be permitted in Box Culvert Concrete.

#### GENERAL NOTES-

Design shall be in accordance with Section 560 of the South Dakata Standard Specifications with the following criteria:


- I Design Live Load: HS 20-44 and Alternate Loading. No Construction Loading in excess of legal load shall be considered.
- 2 The design of the barrel sections shall be based on a minimum fill height of one (1) foot and include all subsequent fill heights up to and including the maximum fill height of 6 ft, over the box cuivert.
- 3 Minimum Inside corner fillet shall be 6 inches.
- 4 Minimum precast section length shall be 4 ft.
- 5 Ufiliples shall be plugged with an approved nonshrinkable grout.
- 6 The Fabricator shall imprint on the structure the date of construction as specified and detailed on Standard Plate No. 450.10 which is on Sheet No. 4 of 5.

#### SHOP PLANS-

The fabricator shall initially submit two (2) copies of the stop plans to the Office of Bridge Design for review. One reviewed copy will be sent back to the fabricator who will then make changes, if any, and then send the Office of Bridge Design seven (7) if nai approved copies for distribution. Include design and check design. If applicable, with initial submittal, N


#### UNDERCUT BACKFILL-

- I. Backfill material shall conform to the following: A tolerance of five percent in material retained on a one inch sleve will be permitted, provided all material passes a one and one - half inch sleve. A minimum of twenty - five percent shall be retained on a No. 4 sleve and not more than eighteen percent shall pass a No. 200 sleve.
- Backfill shall be compacted to ninety five percent of the maximum dry density.
- Bedding material shall be sand or selected sandy soli all of which passes a % inch sieve and not more than ten percent of which passes a No. 200 sieve.
- The extruded Insulation board (polystyrene) shall meet the requirments of ANSLITO MESO 70.
- 5. To avoid damage to the extruded insulation board (polystyrene), the equipment used to spread the 6 inch top layer shall not be operated on less than full depth of the layer.




(For Limits of Undercut)

## **Original Undercut Construction Plans**



(Bottom Dimensions)




### SITE A

#### OPTION III NOTES & UNDERCUT


FOR 2 - 9' X 8' BOX CULVERT (PRECAST) 0° SKEW OVER CREEK SEC. 29/28-TI25N-R67W STA. 589 + 00.00 P 0045(i2)I92 STR. NO. 45-380-230 HS 20-44 (& ALT.) MCPHERSON COUNTY S. D. DEPT. OF TRANSPORTATION SEPTEMBER 1994 (2) OF (5)

DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED 1 0 0 0
YL/HE	TP	"L/HE	John C. Colo
MCPHI282	1282PAI6		BRIDGE ENGINEER




# **Original Construction Plans Typical Grading Sections**


Sta. 548+90 TO Sta. 554+00




Sta. 556+00 TO Sta. 993+27




995+27 TO 1009+85




Detours



FED. HWY		PROJECT	SHEET NO,	TOTAL SHEETS
8	S.D.	P 0045(12)192	11	20





## **Original Construction Plans**



STATE OF	PROJECT	SHEET NO.	TOTAL SHEETS	
SOUTH DAKOTA	045-152	12	20	
Plotting Date: 01/22/2020				


ILE - ... \MCPHI5UG\I5UG\_TITLE SHEET.DGN






STATE OF SOUTH				SHEET NO.	TOTAL Sheets	
DAKOTA 045-152			13	20		
Plotting	Date:	02/14/2	2020			
				_		
Posted Spacing o Speed Advance War		Toper	Spacing o Channelizir			
Prior to Signs	Ĩ	_ength	Devices	' g		
Work (Feet) (M.P.H.) (A)		(Feet) (L)	(Feet) (G)			
0 - 30 200		180	25	-11		
35 - 40 350		320	25			
<u>45 500</u> 50 500		600 600	25 50			_
55 750		660	50			
60 - 65 1000		780	50	-1		
■Channelizing Devic	е					ž ⊢
END						
ROAD WORK						
The channelizing de 42" cones if †raffic						
overnight.						
For short duration or less) all channeli;						
eliminated if a vehi	icle \	with ar	n activate			
flashing or revolvin	ng ye	ellow li	ght is use	ed.		
Worker signs (W2I-I used instead of SH						
A SHOULDER WORK sig on the left side o						
roadway only if th				<sup></sup>		
affected.						N.
The SHOULDER WORK						
intersecting roadwo	oy is	not r tha <b>t</b> r	equired if	.		ATES
drivers emerging from that roadway will encounter another advance warning sign						ā
before they reach	a wa	ork ac	tivity are	a.		
						TANF
						ט. לי
1						
						-
						ц -
						II.
	15					
	4.					
ROAD						
< WORK						
	<b>N</b> 20 <sup>1</sup>					
τ_ / γ	H.					
			June 3, 20	216		
		F	LATE NUMBE	R		
R TRAFFIC CONTROL DEVICES 634.03						
ORK ON SHOULDERS			$\dashv$			

Posted Speed         Spacing of Advance Warning Signs         Spacing of Channelizing Devices           Prior to Work         Signs         Devices           Work         (Feet)         (Feet)           (M.P.H.)         (A)         (G)           0 - 30         200         25           35 - 40         350         25           45         500         25           50         500         50           60 - 65         1000         50	Warning sign sequence in opposite direction same as below.	
<ul> <li>Flagger</li> <li>Channelizing Device</li> <li>For low-volume traffic situations with short work zones on straight roadways where the flagger is visible to road users approaching from both directions, a single flagger may be used</li> <li>The ROAD WORK AHEAD and the END ROAD WORK signs may be omitted for short duration operations (I hour or less).</li> <li>For tack and/or flush seal operations, when flaggers are not being used, the FRESH OIL sign (W21-2) shall be displayed in advance of the liquid asphalt areas.</li> <li>Flashing warning lights and/or flags may be used to call attention to the advance warning signs.</li> <li>The channelizing devices shall be drums or 42" cones.</li> <li>Channelizing devices are not required along the centerline adjacent to work area when pilot cars are utilized for escorting traffic through the work area.</li> </ul>		
Channelizing devices and flaggers shall be used at intersecting roads to control intersecting road traffic as required. The buffer space should be extended so that the two-way traffic taper is placed before a horizontal or vertical curve to provide adequate sight distance for the flagger and queue of stopped vehicles. The length of A may be adjusted to fit field conditions.	GUIDES FOR TRAFFIC CONTROL DEVICES LANE CLOSURE WITH FLAGGER PROVIDED	



LOT SCALE - 1:200

>LOTTED FROM - TRAB1L017




#### ITEMIZED LIST FOR TRAFFIC CONTROL SIGNS


		CONVENTIONAL ROAD			
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0
W20-4	ONE LANE ROAD AHEAD	2	48" x 48"	16.0	32.0
W20-7	FLAGGER (symbol)	2	48" x 48"	16.0	32.0
W21-5	SHOULDER WORK	1	48" x 48"	16.0	16.0
G20-2	END ROAD WORK	2	36" x 18"	4.5	9.0
		CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT		121.0	

STATE OF South Dakota	PROJECT	SHEET NO.	TOTAL SHEETS	
	045-152	15 20		
Plotting Date: 02/14/2020				


.OT NAME - 3









STATE OF PROJECT SHEET TOTAL SOUTH NO. SHEETS	
DAKOTA 045-152 16 20	
TYPE 2 INSLOPE TRANSITION TYPE 2 INSLOPE at the pipe or RCBC is flatter than a 6:1 slope. TYPE 2 INSLOPE TRANSITION TYPE 2 INSLOPE TRANSITION TABLE 2 INSLE	FILENIGUG-STANDARD PLATES.DGN PLOT NAME - 4







PLOT SCALE - 1


PLOTTED FROM - TRAB1L017








Published D	ate: 1st Qtr. 20.	20	S D D O T	EROS
shaping the		II be inci		en installing th al to the contr
edges of the spots which	ne blanket t	o maintai ent unifo	n a	control blanke uniform slope and unrestricte
	control blar recommenda		l be	pinned to the
ditches and 6"wide by 6 blanket end	on slopes. deep There	The upsic shall be er begins	ope e at 1 5, wi <b>t</b>	lled in the dire and of the ero least a 6"overl h the upslope at.
GENERAL NOT Prior to plu seeded, and	acement of	the erosi	on c	control blanket,
TI	RENCH DET	AIL		
<u>MMM -</u>		10101010101		
.,,,,		or Staple		
	control 6" deep shall be	backfille	n a e. Th ed ar	erosion trench e trench nd compacted elevation.
SL0	PED DITCH	SECTI	ON	
be co	nstructed wi ling erosion	hen		* Us co
	∠Erosion C Blanket ditch section			۱ * Us er
1_20:1			(Win_)	<u>.</u> Т
Section	12' (Min.)		VOrio	DIE OF:1
-Sloped [	Vitob			
ST	ANDARD D	ITCH SE	ЕСТ	ION
2	Erosion Con	trol Blank	<et< td=""><td></td></et<>	
	20:1	20:1		
		1.01		





Published Date: 1st Qtr. 2020	S D D O T	EROSION CO
equipment, and materials sl "Remove Erosion Control Wo	hall be incid	
All costs for furnishing ar equipment, and materials sl for the corresponding er All costs for removing the		
Sediment removal, disposal, All costs for removing acc shaping shall be incidental Sediment".	cumulated se to the con	ediment, disposo tract unit pric
The Contractor and Engine week and within 24 hours Contractor shall remove, di necessary as determined b	after every ispose, or re	y rainfall event eshape the acc
Where installing running le wattle tightly against the	engths of wo first and	attles, the Con shall not overl
The stakes shall be 1"x2" or rebar may be used only if 6" from the ends of the w shall be 3' to 4'.	r 2"x2" wood approved l vattles and	stakes,howeve by the Enginee the spacing o <sup>.</sup>
The Contractor shall dig a that daylight can not be from the trench against	seen under the wattle	nch, install the the wattle, an on the uphill s

	STATE OF	PROJECT	SHEET	TOTAL	1
	SOUTH DAKOTA	045-152	20	SHEETS 20	
	Plotting	1 Date: 02/14/2020	20	20	
	<u> </u>		٦		
GENERAL NOTES:					ω
At cut or fill slope installations, wattles shall be installed a perpendicular to the water flow.	llong the	contour and			
At ditch installations, point A must be higher than point B the sourt the wattle and not around the ends.	to ensur	e that water			PLOT NAME
The Contractor shall dig a 3" to 5" trench, install the wattle that daylight can not be seen under the wattle, and then a from the trench against the wattle on the uphill side. See	compac <b>t</b>				PLO
The stakes shall be 1"x2" or 2"x2" wood stakes, however, other rebar may be used only if approved by the Engineer. The s 6" from the ends of the wattles and the spacing of the st shall be 3' to 4'.	takes sho	all be placed			
Where installing running lengths of wattles, the Contractor wattle tightly against the first and shall not overlap the e					
The Contractor and Engineer shall inspect the erosion cont week and within 24 hours after every rainfall event greate Contractor shall remove, dispose, or reshape the accumulate necessary as determined by the Engineer.	r than 🎙	2".The			
Sediment removal, disposal, or necessary shaping shall be as All costs for removing accumulated sediment, disposal of sed shaping shall be incidental to the contract unit price per c Sediment".	iment, an	d necessary			
All costs for furnishing and installing the erosion control wattles including labor, equipment, and materials shall be incidental to the contract unit price per foot for the corresponding erosion control wattle bid item.					TES. DGN
All costs for removing the erosion control wattle from the equipment, and materials shall be incidental to the contract "Remove Erosion Control Wattle".					UG-STANDARD PLATES.DGN
					- STAN
					15UG ·
					•••·15
					FILE -
					L L
S		December 23, 200	-		
		PLATE NUMBER 734.06			
Published Date: 1st Qtr. 2020	MIILE	Sheet 2 of 2	-		
			-		