

STATE OF SOUTH DAKOTA
DEPARTMENT OF TRANSPORTATION

PLANS FOR PROPOSED

PROJECT 034-451
SD HIGHWAY 34
MEADE COUNTY

DRAINAGE CHANNEL REPAIR
PCN i68p

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	1	17

Plotting Date: 02/12/2021

INDEX OF SHEETS



DESIGN DESIGNATION

AADT (2019)	6398
AADT (2039)	8025
DHV	901
D	50 %
DHV T%	2 %
AADT T%	4.5 %
V	45 mph

STORM WATER PERMIT
None Required

ESTIMATE OF QUANTITIES

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
100E0020	Clear and Grub Tree	1	Each
120E0010	Unclassified Excavation	83	CuYd
230E0100	Remove and Replace Topsoil	Lump Sum	LS
450E8900	Cleanout Pipe Culvert	1	Each
634E0110	Traffic Control Signs	73.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0420	Type C Advance Warning Arrow Board	1	Each
730E0210	Type F Permanent Seed Mixture	13	Lb
731E0100	Fertilizing	750	Lb
732E0250	Fiber Mulching	147	Lb
734E0102	Type 2 Erosion Control Blanket	285	SqYd
734E0510	Shaping for Erosion Control Blanket	160	Ft
734E0604	High Flow Silt Fence	30	Ft
734E0610	Mucking Silt Fence	1	CuYd

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: <https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf >

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT C: WATER SOURCE

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species waters within South Dakota without prior approval from the SDDOT Environmental Office. Thoroughly wash all construction equipment to prevent and control the introduction and spread of invasive species into the project vicinity.

Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Environment and Natural Resources (DENR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of Aquatic Invasive Species in South Dakota can be accessed at: http://sdleastwanted.com/maps/default.aspx.

COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Environment and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench completely separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating "No Dumping Allowed".

2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period of time not to exceed the duration of the project. Prior to project completion, the waste shall be removed from view of the ROW or buried and the waste disposal site reclaimed as noted above.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.

Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

COMMITMENT I: HISTORICAL PRESERVATION OFFICE CLEARANCES

State Historical Preservation Office (SHPO or THPO) concurrence has not been obtained for this project.

Action Taken/Required:

All earth disturbing activities require a cultural resource review prior to scheduling the pre-construction meeting. This work includes, but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view of which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office to determine an appropriate course of action.

The Contractor is responsible for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

UTILITIES

The Contractor will contact the involved utility companies through South Dakota One Call (1-800-781-7474) prior to starting work. It will be the responsibility of the Contractor to coordinate work with the utility owners to avoid damage to existing facilities.

If utilities are identified near the improvement area through the SD One Call Process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25, the Contractor will contact the Project Engineer to determine modifications that will be necessary to avoid utility impacts.

GRADING OPERATIONS

The estimated cubic yards of excavation and/or embankment required to construct outlet ditch is included in the earthwork balance notes on the profile sheets.

Generally, all shallow inlet and outlet ditches as noted on the plan sheets will be cut with an 8-foot wide bottom with 4:1 backslopes. However, the Engineer may direct the Contractor to adjust the ditch width for proper alignment with the drainage structure.

CLEANOUT PIPE

Cleanout the eastern pipe at Sta. 0+00 R

REMOVE AND REPLACE TOPSOIL

Topsoil will be salvaged and stockpiled prior to constructing the channel. Limits of this work, depth of salvage, and stockpile location will be directed by the Engineer. Following completion of construction, topsoil will be spread evenly over the disturbed areas.

All costs associated with removing and replacing the topsoil will be incidental to the contract lump sum price for “Remove and Replace Topsoil”.

MYCORRHIZAL INOCULUM

Mycorrhizal inoculum will consist of mycorrhizal fungi spores and mycorrhizal fungi-infected root fragments in a solid carrier. The carrier may include organic materials, calcinated clay, or other materials consistent with application and good plant growth. The supplier will provide certification of the fungal species claimed and the live propagule count. The inoculum will include the following fungal species:

25% *Glomus intraradices*
25% *Glomus aggregatum or deserticola*
25% *Glomus mosseae*
25% *Glomus etunicatum*

All seed will be inoculated by the seed supplier with a minimum of 100,000 live propagules of mycorrhizal fungi per acre. All costs of inoculating the seed will be incidental to the contract unit price per pound for the corresponding permanent seed mixture.

The mycorrhizal inoculum will be as shown below or an approved equal:

Product	Manufacturer
MycoApply	Mycorrhizal Applications, Inc. Grants Pass, OR Phone: 1-866-476-7800 www.mycorrhizae.com
AM 120 Multi Species Blend	Reforestation Technologies Int. Gilroy, CA Phone: 1-800-784-4769 www.reforest.com

PERMANENT SEEDING

The areas to be seeded consist of all newly graded areas within the project limits except for the top of roadways, temporary easements under cultivation, and areas designated to be sod.

Type F Permanent Seed Mixture will consist of the following:

Grass Species	Variety	Pure Live Seed (PLS) (Pounds/Acre)
Western Wheatgrass	Arriba, Flintlock, Rodan, Rosana, Walsh	7
Green Needlegrass	Lodorm, AC Mallard Ecovar	4
Sideoats Grama	Butte, Pierre	3
Blue Grama	Bad River	2
Oats or Spring Wheat: April through May; Winter Wheat: August through November		10
	Total:	26

FERTILIZING

The Contractor will apply an all-natural slow release fertilizer prior to seeding or placing sod. The all-natural fertilizer will have a minimum guaranteed analysis of 4-4-4 and be USDA Certified BioBased. It should provide a minimum of 4% (N) nitrogen with a minimum water insoluble nitrogen (WIN) fraction of 2.07%, a minimum of 4% (P_2O_5) available phosphate, a minimum of 4% (K_2O) soluble potash, and a maximum carbon to nitrogen ratio (C:N ratio) of 5:1. The all-natural fertilizer will be free of weed-seed and pathogens accomplished through thermophilic composting, and not mechanical or chemical sterilization, to assure presence of beneficial soil microbiology. The fertilizer will have a near neutral pH, a low salt index, a low biological oxygen demand, contain organic humic and fulvic acids, and have high aerobic organism counts. The fertilizer will also be stable, free of bad odors, and be unattractive as a food source for animals. It should also be in a granular form that is easily spread.

The fertilizer will be applied at a rate of 1,500 pounds per acre in accordance with the manufacturer’s recommended method of application.

The all-natural slow release fertilizer will be as shown below or an approved equal:

Product	Manufacturer
Sustane	Sustane Corporate Headquarters Cannon Falls, Minnesota Phone: 1-800-352-9245 www.sustane.com
Perfect Blend	Perfect Blend, LLC Bellevue, WA Phone: 1-866-456-8890 www.perfect-blend.com

FIBER MULCHING

Fiber mulch will be applied in a separate operation following permanent seeding.

An additional 2% by weight of tackifier will be added to the fiber mulch product selected from the approved product list. If the product selected has guar gum tackifier included, then the additional 2% of tackifier will be guar gum. If the product selected has synthetic tackifier included, then the additional 2% of tackifier will be synthetic.

The Contractor will allow the fiber mulch to cure a minimum of 18 hours prior to watering or any storm event to ensure proper cohesion between the soil and fiber particles.

All costs for the additional tackifier added to the fiber mulch including labor, equipment, and materials will be incidental to the contract unit price per pound for “Fiber Mulching”.

The fiber mulch provided will be from the approved product list. The approved product list for fiber mulch may be viewed at the following internet site:

http://apps.sd.gov/HC60ApprovedProducts/main.aspx

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	5	17

EROSION CONTROL BLANKET

Erosion control blanket will be installed 16 feet wide at the locations noted in the table and at locations determined by the Engineer during construction.

The erosion control blanket provided will be from the approved product list. The approved product list for erosion control blanket may be viewed at the following internet site:

http://apps.sd.gov/HC60ApprovedProducts/main.aspx

SHAPING FOR EROSION CONTROL BLANKET

The ditches will be shaped for the erosion control blanket as specified on Standard Plate 734.01.

HIGH FLOW SILT FENCE

The high flow silt fence fabric provided will be from the approved product list. The approved product list for high flow silt fence may be viewed at the following internet site:

http://apps.sd.gov/HC60ApprovedProducts/main.aspx

High flow silt fence will be placed at the locations noted in the table and at locations that will minimize siltation of adjacent streams, lakes, dams, or drainage areas as determined by the Engineer during construction. Refer to Standard Plate 734.05 for details.

DEWATERING AND SEDIMENT COLLECTING

The channel has a constant flow.

The Contactor has the option to treat sediment laden water trapped within the project limits or the Contractor may elect to transport sediment laden water off the project. Refer to the OPTIONS FOR DEWATERING AND SEDIMENT COLLECTING detail sheet for more information.

Water transported off the project limits will not be disposed of in an area where it can enter a waterway. The disposal site must be approved by the Engineer.

TABLE OF EROSION CONTROL

Seeding	Fertilizing	Fiber Mulch	Erosion Control Blanket	High Flow Silt Fence	Mucking Silt Fence
Lb	Lb	Lb	SqYd	Ft	CuYd
13	750	147	285	30	2

SEQUENCE OF OPERATIONS

1. Set up traffic control.
2. Install silt fence.
3. Remove topsoil.
4. Shape drainage channel.
5. Seed and install erosion control blanket.
6. Fiber mulch area not covered with erosion control blanket.
7. Remove traffic control.

Contractor requests to deviate from the sequence of operations will be submitted in writing to the Engineer for review. Approval of an alternate sequence of operations will only be allowed when the proposed changes meet with the Department's intent for traffic control and sequencing of the work. An alternate sequence will be submitted for review a minimum of one week prior to potential implementation.

GENERAL TRAFFIC CONTROL

Existing guide, route, informational logo, regulatory, and warning signs will be temporarily reset and maintained during construction. Removing, relocating, covering, salvaging, and resetting of existing traffic control devices, including delineation, will be the responsibility of the Contractor. Cost for this work will be incidental to the contract unit prices for the various items unless otherwise specified in the plans. Any delineators and signs damaged or lost will be replaced by the Contractor at no cost to the State.

All temporary traffic control sign locations will be set in the field by the Contractor and verified by the Engineer prior to installation.

Portable sign supports will not be located on sidewalks, bicycle facilities, or other areas designated for pedestrian or bicycle traffic.

All construction operations will be conducted in the general direction of traffic movement.

If there is a discrepancy between the traffic control plans, standard plates, and the MUTCD, whichever is more stringent will be used, as determined by the Engineer.

Unless otherwise stated in these plans, work will not be allowed during hours of darkness.

Traffic Control Signs, as shown in the Estimate of Quantities, are estimates. Contractor's operation may require adjustments in quantities, either more or less. Payment will be for those signs actually ordered by the Engineer and used.

Fixed location signing placed more than 4 calendar days prior to the start of construction will be covered or laid down until the time of construction. The covers must be approved by the Engineer prior to installation. The cost of materials, labor, and equipment necessary to complete this work will be incidental to other contract items. No separate payment will be made.

All fixed location signs, sign posts, and breakaway bases will be removed within 7 calendar days following completion of project.

TABLE OF TRAFFIC CONTROLS SIGNS

ITEMIZED LIST FOR TRAFFIC CONTROL SIGNS

		CONVENTIONAL ROAD			
SIGN CODE	SIGN DESCRIPTION	NUMBER	SIGN SIZE	SQFT PER SIGN	SQFT
W4-2	LEFT or RIGHT LANE ENDS (symbol)	1	48" x 48"	16.0	16.0
W20-1	ROAD WORK AHEAD	2	48" x 48"	16.0	32.0
W20-5	LEFT or RIGHT LANE CLOSED AHEAD	1	48" x 48"	16.0	16.0
G20-2	END ROAD WORK	2	36" x 18"	4.5	9.0
		CONVENTIONAL ROAD TRAFFIC CONTROL SIGNS SQFT			73.0

TYPICAL GRADING SECTION

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	7	17

Plotting Date: 02/11/2021

Channel 0+00 to 1+60



Plot Scale - 1:200

Plotted From - TRRC11610

File - ...\68p typ.dgn

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	8	17

HORIZONTAL ALIGNMENT DATA

MAINLINE

Type	Station			Northing	Easting
POB	0+00.00			231360.618	1055683.826
		TL= 138.56	S 77°55'06" E		
PC	1+38.56			231331.617	1055819.315
PI	1+50.35	R = 15.00	Delta = 76°21'54" L	231329.148	1055830.850
PT	1+58.55			231339.776	1055835.969
		TL= 0.97	N 25°42'59" E		
POE	1+59.52			231340.648	1055836.389

The coordinates shown on this sheet are based on the South Dakota State Plane Coordinate System. NorthZone (NAD 83/xx); epoch 20 xx.xx; Geoid xxx; SF = 0.xxxxxxxxx

LEGEND

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	9	17

Plotting Date: 02/11/2021

- Anchor
- Antenna
- Approach
- Assumed Corner
- Azimuth Marker
- BBQ Grill/ Fireplace
- Bearing Tree
- Bench Mark
- Box Culvert
- Bridge
- Brush/Hedge
- Buildings
- Bulk Tank
- Cattle Guard
- Cemetery
- Centerline
- Cistern
- Clothes Line
- Concrete Symbol
- Control Point
- Creek Edge
- Curb/Gutter
- Curb
- Dam Grade/Dike/Levee
- Deck Edge
- Ditch Block
- Doorway Threshold
- Drainage Profile
- Drop Inlet
- Edge Of Asphalt
- Edge Of Concrete
- Edge Of Gravel
- Edge Of Other
- Edge Of Shoulder
- Electric Transformer/Power Junction Box
- Fence Barbwire
- Fence Chainlink
- Fence Electric
- Fence Miscellaneous
- Fence Rock
- Fence Snow
- Fence Wood
- Fence Woven
- Fire Hydrant
- Flag Pole
- Flower Bed
- Gas Valve Or Meter
- Gas Pump Island
- Grain Bin
- Guardrail
- Gutter
- Guy Pole
- Haystack
- Highway ROW Marker
- Interstate Close Gate
- Iron Pin
- Irrigation Ditch
- Lake Edge
- Lawn Sprinkler
- Mailbox
- Manhole Electric
- Manhole Gas
- Manhole Miscellaneous
- Manhole Sanitary Sewer
- Manhole Storm Sewer
- Manhole Telephone
- Manhole Water
- Merry-Go-Round
- Microwave Radio Tower
- Miscellaneous Line
- Miscellaneous Property Corner
- Miscellaneous Post
- Overhang Or Encroachment
- Overhead Utility Line — OH —
- Parking Meter
- Pedestrian Push Button Pole
- Pipe With End Section
- Pipe With Headwall
- Pipe Without End Section
- Playground Slide
- Playground Swing
- Power And Light Pole
- Power And Telephone Pole
- Power Meter
- Power Pole
- Power Pole And Transformer
- Power Tower Structure
- Propane Tank
- Property Pipe
- Property Pipe With Cap
- Property Stone
- Public Telephone
- Railroad Crossing Signal
- Railroad Milepost Marker
- Railroad Profile
- Railroad ROW Marker
- Railroad Signs
- Railroad Switch
- Railroad Track
- Railroad Trestle
- Rebar
- Rebar With Cap
- Reference Mark
- Retaining Wall
- Riprap
- River Edge
- Rock And Wire Baskets
- Rockpiles
- Satellite Dish
- Septic Tank
- Shrub Tree
- Sidewalk
- Sign Face
- Sign Post
- Slough Or Marsh
- Spring
- Stream Gauge
- Street Marker
- Subsurface Utility Exploration Test Hole
- Telephone Fiber Optics — T/F —
- Telephone Junction Box
- Telephone Pole
- Television Cable Jct Box
- Television Tower
- Test Wells/Bore Holes
- Traffic Sign Double Face
- Traffic Sign One Post
- Traffic Sign Two Post
- Traffic Signal
- Trash Barrel
- Tree Belt
- Tree Coniferous
- Tree Deciduous
- Tree Stumps
- Triangulation Station
- Underground Electric Line — P —
- Underground Gas Line — G —
- Underground High Pressure Gas Line — HG —
- Underground Sanitary Sewer — S —
- Underground Storm Sewer — S —
- Underground Tank
- Underground Telephone Line — T —
- Underground Television Cable — TV —
- Underground Water Line — W —
- Water Fountain
- Water Hydrant
- Water Meter
- Water Tower
- Water Valve
- Water Well
- Weir Rock
- Windmill
- Wingwall
- Witness Corner
- State and National Line
- County Line
- Section Line
- Quarter Line
- Sixteenth Line
- Property Line
- Construction Line
- ROW Line
- New ROW Line
- Cut and Fill Limits
- Control of Access
- New Control of Access
- Proposed ROW (After Property Disposal)

- Drainage Arrow

- Remove Concrete Pavement
- Remove Concrete Driveway Pavement
- Remove Asphalt Concrete Pavement
- Remove Concrete Sidewalk
- Remove Concrete Median Pavement
- Remove Concrete Curb and/or Gutter

- Detectable Warning
- Pedestrian Push Button Pole and 30" x 48" Clear Space with 1.5% slope

Plot Scale - 1:200

Plotted From - TRRC11610

File - ...\legend.dgn

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	10	17

Plotting Date: 02/12/2021

0+00 R
Cleanout Pipe

1+07 L
Remove Tree

Regent Street

22 23 24 12 13 14 15 16 17 18 19

BLOCK 1

CITY LIMITS

FORT MEADE RESERVATION BOUNDARY

FORT MEADE MILITARY RESERVATION

TRACT 37

T/F

0+00

1+00

P

Present SD Hwy 34

150'

150'

Regent Street

Exc= 83
Total= 83

Emb= 26
30% 8 34
Waste= 49
Total= 83

PVI 0+00
Elev 3341.89

PVI 1+58
Elev 3341.47

-0.2633%

3340

3340

3330

3330

3341.89 3341.84 3341.78 3341.73 3341.68 3341.63 3341.57 3341.52

0+00

1+64

Plot Scale - 1:40

TRRC11610

Plotted From -

File - ...1001.dgn

EROSION AND SEDIMENT CONTROL PLAN

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	11	17

Plotting Date: 02/12/2021

Install Type 2 Erosion Control Blanket
in the highway ditch channel bottom
at the following locations:
0+00 L/R to 1+60 L/R 285 SqYd

Install High Flow Silt Fence at the following locations:
1+60 L/R Across ditch at inlet end of pipe 30 Ft



Type 2 Erosion Control Blanket

OPTIONS FOR DEWATERING AND SEDIMENT COLLECTING

OPTIONS ARE NOT LIMITED TO WHAT IS SHOWN ON THIS SHEET

Various systems, devices, and products are shown on this sheet to give the Contractor ideas of what may be used for water treatment. Other systems, devices, and products are available and can be used with approval from the Engineer. Minnesota DOT also has options and practices available at: ftp://ftp2.dot.state.mn.us/pub/outbound/erosion/CSM2017

The Contractor may elect to block a portion of storm sewer near the outfall with sand bags and pump the water out to be treated with a flocculent or allow the water to set in a lined dumpster until sediment to falls out of suspension before discharging the water. Drop inlet protection devices could also be used as part of a treatment train. The Contractor may pump dirty water into a hydroseeder and mix it with a flocculent, and spray the mixture back onto a sediment pond. No matter the system or method used, the Contractor must meet the terms of the Temporary Discharge Permit and the Stormwater Permit for Construction Activities.

PURPOSE

The purpose of a dewatering and sediment collection system is to collect turbid storm water on the project, treat it with flocculents as needed, and capture the sediment that falls out of suspension before the water is discharged into “Waters of the US” or “Waters of the State”. Refer to the Environmental Commitments for the specific requirements for each body of water on this project.

The Contractor will need to create a Pollution Prevention Plan (PPP) for dewatering and sediment collection if the Contractor choses to discharge the water into "Waters of the US" or "Waters of the State" instead of disposing of the water off-site, using it for irrigation, or using it for hydroseeding. The Contractor will also need to obtain a Temporary Discharge Permit from the South Dakota Department of Environment & Natural Resources (DENR) on all projects outside of Indian Reservation boundaries.

Suggestions for dewatering and sediment collection may be shown on the plan sheets. It is ultimately the Contractor's responsibility to dewater and collect sediment. The Contractor will have to intercept and treat the stormwater before storm sewer outfalls into "Waters of the US" or "Waters of the State". The Contractor may need more than one dewatering and sediment collection system to capture and treat stormwater at multiple outfalls and/or locations simultaneously during each phase of the project.

PAYMENT

No additional payment will be made for Dewatering and Sediment Collecting. Dewatering and Sediment Collecting shall be incidental to other items on the project.

DEWATERING BAGS AND SOCKS capture sediment and should be placed on pavement, vegetated areas, or gravel.

Dandy Dewatering Bag
Dandy Products, Inc.
Powell, OH
Phone: 1.800.591.2284
www.dandyproducts.com

Non-woven Sediment Filter Bags
Indian Valley Industries, Inc.
Johnson City, NY
Phone: 1.800.659.5111
www.iviindustries.com

Taurus Dewatering Bags/Socks
SolHuTec Group, Inc.
Sebastian, FL
Phone: 1.888.703.9889
www.solhutec.com

Ultra-Dewatering Bag
UltraTech International, Inc
Jacksonville, FL
Phone: 1.800.764.9563
www.spillcontainment.com

Heavy Duty Dirtbag 55
ACF Environmental
Richmond, VA
Phone: 1.800.223.9021
www.acfenvironmental.com

Pump-It Tube
Flo-Water, LLC
West Des Moines, IA
Phone: 1.515.577.6763
www.flo-water.net

FLOCCULENTS listed below are considered to be safe for the environment, if used as directed:

APS 700 Series Floc Logs
Applied Polymer Systems, Inc.
Woodstock, GA
Phone: 1.866.200.9868
http://www.siltstop.com

Floc, Floc Soc, Floc Bag
Innovative Turf Solutions Products
Cincinnati, OH
Phone: 1.513.317.8311
http://www.innovativeturfsolutions.com

Biostar CH
Hild & Associates, Inc.
Stillwater, MN
Phone: 1.715.426.5131
www.biostar-ch.com

Terra-Tubes
ACF Environmental
Buffalo Grove, IL
Phone: 1.800.366.1180
www.terratubes.com

FI-3500 Tablets
JRM Chemical, Inc.
Cleveland, OH
Phone: 1.216.475.8488
http://www.soilmoist.com

Tigerfloc
Floc Systems Inc.
Surrey, British Columbia
Phone: 1.604.343.2046
www.flocsystems.com

PORTABLE FLOCCULENT SYSTEMS

Eco Pond Rescue Water Wagon
Eco Pond Rescue LLC
Seminole, Florida
Phone: 1.727.412.4323
www.ecopondrescue.com

WTS2000 Portable Sediment Tank
Aqualete Industries, LLC
Ocean, New Jersey
Phone: 1.732.695.6336
http://aqualeteindustries.com

Dry Flocculent Mixing System
Innovative Equipment Solutions
Hot Springs, Arkansas
Phone: 1.501.525.8484
http://www.neptunewash.com

THE CASCADE SYSTEM

The cascade system is shown below and to the right for conceptual purposes only; however, the cascade system shall at a minimum incorporate the use of 2 flocculent housing units and 2 water and sediment storage units. Design and construction of the water and sediment storage units are project site specific and shall be the Contractor's responsibility. A water and sediment storage unit may consist of a storage bin lined with plastic, the bed of a dump truck lined with plastic, a sediment basin, or other Engineer approved unit. The treatment flocculent bag may be from the list or an approved equal.



VIEW A-A



ELEVATION VIEW
CASCADE SYSTEM



FLOCCULENT BAG
(Gallons each bag will treat varies by site)

FLOCCULENT HOUSING UNIT

FLOCCULENT HOUSING UNIT (estimated quantities for information only)			
NO.	DESCRIPTION	QUANTITY	UNIT
1	4" or 6" Dia. Sch. 40 Gate Valve	1	Each
2	4" X 6" or 6" X 8" Sch. 40 PVC Bushing	2	Each
3	6" or 8" Dia. Sch. 40 PVC "Y"	1	Each
4	6" or 8" Dia. Sch. 40 PVC Female Threaded Cap	1	Each
5	1" Dia. Sch. 80 PVC Drain Valve	1	Each
6	1/2" Eye Bolt with Wing Nut and Rubber Gromets	1	Each
7	6" or 8" Dia. Sch. 40 PVC Pipe	10	Ft.
8	6" or 8" Dia. Sch. 40 PVC Male Adapter	1	Each
9	4" or 6" Dia. Sch. 40 PVC Swing Check Valve	1	Each

FLOW RATE ESTIMATE	
Pump Type	Flow Rate (gpm)
2"	50-250
3" Gas	250-350
4" Diesel	500-750
6" Diesel	750-1000

Posted Speed Prior to Work (M.P.H.)	Spacing of Advance Warning Signs (Feet) (A)	Taper Length (Feet) (L)	Spacing of Channelizing Devices (Feet) (G)
0 - 30	200	180	25
35 - 40	350	320	25
45	500	600	25
50	500	600	50 *
55	750	660	50 *
60 - 65	1000	780	50 *

* Spacing is 40' for 42" cones.

◎ Reflectorized Drum

■ Channelizing Device

(4W) 4" White Temporary Pavement Marking

The channelizing devices shall be 42" cones or drums.

42" cones may be used in place of the drums shown in the taper if setup will not be used during night time hours.

Temporary pavement markings shall be used if traffic control must remain overnight.

The length of A and L may be adjusted to fit field conditions.



June 3, 2016

Published Date: 1st Qtr. 2021	SDDOT	GUIDES FOR TRAFFIC CONTROL DEVICES 4-LANE UNDIVIDED, RIGHT LANE CLOSED	PLATE NUMBER 634.47
			Sheet 1 of 1



RURAL DISTRICT



RURAL DISTRICT WITH SUPPLEMENTAL PLATE



URBAN DISTRICT

* If the bottom of supplemental plate is mounted lower than 7 feet above a pedestrian walkway, the supplemental plate should not project more than 4" into the pedestrian facility.



RURAL DISTRICT
3 DAY MAXIMUM
(Not applicable to regulatory signs)

September 22, 2014

Published Date: 1st Qtr. 2021	SDDOT	CRASHWORTHY SIGN SUPPORTS (Typical Construction Signing)	PLATE NUMBER 634.85
			Sheet 1 of 1



PLAN VIEW

(Examples of stub height clearance checks)



ELEVATION VIEW

GENERAL NOTES:

The top of anchor posts and slip bases SHALL NOT extend above a 60" chord line within a 120" diameter circle around the post with ends 4" above the ground.

At locations where there is curb and gutter adjacent to the breakaway sign support, the stub height shall be a maximum of 4" above the ground line at the localized area adjacent to the breakaway support stub.

The 4" stub height clearance is not necessary for U-channel lap splices where the support is designed to yield (bend) at the base.

July 1, 2005

Published Date: 1st Qtr. 2021	SDDOT	**BREAKAWAY SUPPORT STUB CLEARANCE**	PLATE NUMBER 634.99 Sheet 1 of 1



STANDARD DITCH SECTION



SLOPED DITCH SECTION



The median will be shaped to the limits shown in this detail where the erosion control blanket will be placed.

MEDIAN SECTION



* Use a 4" (Min.) overlap wherever two widths of erosion control blanket are applied side by side.

* Use a 6" (Min.) overlap wherever one roll of erosion control blanket ends and another begins.

OVERLAP DETAIL



TRENCH DETAIL



PIPE END DETAIL

GENERAL NOTES:

Prior to placement of the erosion control blanket, the areas will be properly prepared, shaped, seeded, and fertilized.

Erosion control blanket will be unrolled in the direction of the flow of water when placed in ditches and on slopes. The upslope end of the erosion control blanket will be buried in a trench 6" wide by 6" deep. There will be at least a 6" overlap wherever one roll of erosion control blanket ends and another begins, with the upslope erosion control blanket placed on top of the downslope erosion control blanket.

The erosion control blanket will be pinned to the ground according to the manufacturer's installation recommendations.

After the placement of the erosion control blanket, the Contractor will fine grade along all edges of the blanket to maintain a uniform slope adjacent to the blanket and level any low spots which might prevent uniform and unrestricted flow of side drainage directly onto the erosion control blanket.

All ditch sections will be shaped when installing the erosion control blanket. All costs for shaping the ditches will be incidental to the contract unit price per foot for "Shaping for Erosion Control Blanket".

February 14, 2020

Published Date: 1st Qtr. 2021	SDDOT	**EROSION CONTROL BLANKET**	PLATE NUMBER 734.01 Sheet 1 of 1

MANUAL HIGH FLOW SILT FENCE INSTALLATION



① EXCAVATE TRENCH



② DRIVE STEEL T FENCE POSTS



③ ATTACH SILT FENCE FABRIC

DETAIL B



④ BACKFILL TRENCH AND WHEEL COMPACT SOIL



SECTION A-A



February 14, 2020

Published Date: 1st Qtr. 2021	SDDOT	HIGH FLOW SILT FENCE	PLATE NUMBER 734.05
			Sheet 1 of 2

MACHINE SLICED HIGH FLOW SILT FENCE INSTALLATION



① INSTALL SILT FENCE FABRIC BY MACHINE SLICING METHOD.



WHEEL COMPACT SOIL — DRIVE STEEL T FENCE POSTS

② WHEEL COMPACT SOIL ABOVE SLICED IN PORTION OF FABRIC AND THEN DRIVE STEEL T FENCE POSTS.



③ ATTACH SILT FENCE FABRIC

DETAIL B



SECTION A-A



GENERAL NOTE:

If a trench can not be dug or the silt fence fabric can not be sliced in due to the type of earthen material (such as rock), then a row of 30 to 40 pound sandbags butted end to end will be provided on top of the extra length of silt fence fabric to prevent underflow.

February 14, 2020

Published Date: 1st Qtr. 2021	SDDOT	HIGH FLOW SILT FENCE	PLATE NUMBER 734.05
			Sheet 2 of 2



Plotting Date: 02/11/2021

STATE OF SOUTH DAKOTA	PROJECT	SHEET NO.	TOTAL SHEETS
	034-451	16	17









Plotting Date: 02/11/2021

STATE OF SOUTH DAKOTA	PROJECT	SHEET NO.	TOTAL SHEETS
	034-451	17	17