



Rapid City Region Design Office

2300 Eglin Street, PO Box 1970

Rapid City, SD 57709-1970

Phone: 605-394-2244 FAX: 605-394-1904

Website: <https://dot.sd.gov/> and <https://sd.511.org>

April 16, 2025

ADDENDUM NO. 1

RE: April 24, 2025 Rapid City Region Office Informal Letting
034-451, Meade County, PCN i7en
Pipe Replacement on Hwy 34 east of Sturgis

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made part of your proposal for the referenced project.

PROPOSAL:

- No change.

PLANS:

- Replace Sheet 2 with the attached. The bid item "Remove Asphalt Concrete Pavement" was added to the Estimate of Quantities. A revised DOT-123 will be sent to the prospective bidders for this change.

Sincerely,

John Rehorst
Region Design Engineer

ESTIMATE OF QUANTITIES

BID ITEM NUMBER	ITEM	QUANTITY	UNIT
009E0010	Mobilization	Lump Sum	LS
110E1010	Remove Asphalt Concrete Pavement	977.8	SqYd
110E1700	Remove Silt Fence	50	Ft
120E0600	Contractor Furnished Borrow	100	CuYd
230E0100	Remove and Replace Topsoil	Lump Sum	LS
250E0020	Incidental Work, Grading	Lump Sum	LS
260E1010	Base Course	616.0	Ton
260E6010	Granular Material	139.8	Ton
320E1200	Asphalt Concrete Composite	330.0	Ton
450E0162	30" RCP Class 2, Furnish	246	Ft
450E0170	30" RCP, Install	246	Ft
450E2024	30" RCP Flared End, Furnish	6	Each
450E2025	30" RCP Flared End, Install	6	Each
464E0100	Controlled Density Fill	29.6	CuYd
632E2510	Type 2 Object Marker Back to Back	4	Each
633E1220	High Build Waterborne Pavement Marking Paint, 4" White	550	Ft
633E1222	High Build Waterborne Pavement Marking Paint, 4" Yellow	70	Ft
634E0010	Flagging	100.0	Hour
634E0110	Traffic Control Signs	186.0	SqFt
634E0120	Traffic Control, Miscellaneous	Lump Sum	LS
634E0275	Type 3 Barricade	1	Each
634E0310	Temporary Flexible Vertical Markers (Tabs)	2,400	Ft
634E0600	4" Temporary Pavement Marking Tape Type I	144	Ft
730E0210	Type F Permanent Seed Mixture	6	Lb
731E0100	Fertilizing	345	Lb
732E0250	Fiber Mulching	460	Lb
734E0154	12" Diameter Erosion Control Wattle	190	Ft
734E0604	High Flow Silt Fence	200	Ft
734E0610	Mucking Silt Fence	4	CuYd
734E0620	Repair Silt Fence	50	Ft

SPECIFICATIONS

Standard Specifications for Roads and Bridges, 2015 Edition and Required Provisions, Supplemental Specifications, and Special Provisions as included in the Proposal.

ENVIRONMENTAL COMMITMENTS

The SDDOT is committed to protecting the environment and uses Environmental Commitments as a communication tool for the Engineer and Contractor to ensure that attention is given to avoid, minimize, and/or mitigate an environmental impact. Environmental commitments to various agencies and the public have been made to secure approval of this project. An agency with permitting authority can delay a project if identified environmental impacts have not been adequately addressed. Unless otherwise designated, the Contractor's primary contact regarding matters associated with these commitments will be the Project Engineer. During construction, the Project Engineer will verify that the Contractor has met Environmental Commitment requirements. These environmental commitments are not subject to change without prior written approval from the SDDOT Environmental Office.

Additional guidance on SDDOT's Environmental Commitments can be accessed through the Environmental Procedures Manual found at: <<https://dot.sd.gov/media/documents/EnvironmentalProceduresManual.pdf> >

For questions regarding change orders in the field that may have an effect on an Environmental Commitment, the Project Engineer will contact the Environmental Engineer at 605-773-3180 or 605-773-4336 to determine whether an environmental analysis and/or resource agency coordination is necessary.

Once construction is complete, the Project Engineer will review all environmental commitments for the project and document their completion.

COMMITMENT B: FEDERALLY THREATENED, ENDANGERED, AND PROTECTED SPECIES

COMMITMENT B2: WHOOPING CRANE

The Whooping Crane is a spring and fall migratory bird in South Dakota that is about 5 feet tall and typically stops on wetlands, rivers, and agricultural lands along their migration route. An adult Whooping Crane is white with a red crown and a long, dark, pointed bill. Immature Whooping Cranes are cinnamon brown. While in flight, their long necks are kept straight and their long dark legs trail behind. Adult Whooping Cranes' black wing tips are visible during flight.

Action Taken/Required:

Harassment or other measures to cause the Whooping Crane to leave the site is a violation of the Endangered Species Act. If a Whooping Crane is sighted roosting in the vicinity of the project, borrow pits, or staging areas associated with the project, cease construction activities in the affected area until the Whooping Crane departs and immediately contact the Project Engineer. The Project Engineer will contact the Environmental Office so that the sighting can be reported to USFWS.

STATE OF SOUTH DAKOTA	PROJECT	SHEET	TOTAL SHEETS
	034-451	Non	2/21

Revised 4/15/2025 NJT

COMMITMENT C: WATER SOURCE

The Contractor will not withdraw water with equipment previously used outside the State of South Dakota or previously used in aquatic invasive species (AIS) positive waters within South Dakota without prior approval from the SDDOT Environmental Office. To prevent and control the introduction and spread of invasive species into the project vicinity, all equipment will be power washed with hot water (≥140 °F) and completely dried for a minimum of 7 days prior to subsequent use. South Dakota administrative rule 41:10:04:02 forbids the possession and transport of AIS; therefore, all attached dirt, mud, debris and vegetation must be removed and all compartments and tanks capable of holding standing water must be drained. This includes, but is not limited to, all equipment, pumps, lines, hoses and holding tanks.

Action Taken/Required:

The Contractor will obtain the necessary permits from the regulatory agencies such as the South Dakota Department of Agriculture and Natural Resources (DANR) and the United States Army Corps of Engineers (USACE) prior to water extraction activities.

Additional information and mapping of water sources impacted by Aquatic Invasive Species in South Dakota can be accessed at: <https://sdleastwanted.sd.gov/maps/default.aspx>

[South Dakota Administrative Rule 41:10:04 Aquatic Invasive Species: https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04](https://sdlegislature.gov/rules/DisplayRule.aspx?Rule=41:10:04)

COMMITMENT E: STORM WATER

Construction activities constitute less than 1 acre of disturbance.

Action Taken/Required:

At a minimum and regardless of project size, appropriate erosion and sediment control measures must be installed to control the discharge of pollutants from the construction site.