



Division of Operations

Aberdeen Region Office
West Highway 12
PO Box 1767
Aberdeen, South Dakota 57402-1767
O: 605.626.2244 | F: 605.626.7875
dot.sd.gov

April 10, 2026

ADDENDUM NO. 1

Re: **0009-168, PCN i83N**
Watertown Area
Bridge Deck Sweeping

TO WHOM IT MAY CONCERN:

PROPOSAL: No Changes

PLANS: Please destroy Sheet 7 and replace with the enclosed Sheet 7, revised 04/10/2026.
Sweeper specifications for minimum broom width and hopper capacity were updated to allow a wider range of street sweeping equipment to be used.

Sincerely,

DEPARTMENT OF TRANSPORTATION

Mark Peterson
Region Engineer

cc: [M. Brey](#) C. Bennett File

JOINT CLEANING REQUIREMENTS

Transverse joint openings located on the bridge deck and approach slabs will be cleaned of debris with compressed air, or other methods approved by the Engineer. Joint cleaning will be accomplished at the same time as sweeping of the bridge deck and approach slabs. Debris will not be blown over the edge of the deck onto the underlying roadway or waterway channel. The entire length of the joint will be cleaned.

BRIDGE CLEANING EXCEPTIONS

The 2 bridges within the City of Watertown on US212 do not require cleaning. [The 2 bridges on SD127 1.0 and 2.7 miles north of Sisseton do not require cleaning as they will be replaced in 2026. The bridge on SD28 between Estelline and the Interstate will also not require cleaning do to the grading project in that area.](#)

BRIDGE CLEANING CONFLICTS

There are bridges that are scheduled for construction during the calendar year. This construction may conflict with the completion of 2 bridge cleanings. These potential conflicts are noted in The TABLE OF BRIDGES (Attachment 1) in the far-right column. It is anticipated that one cleaning can be accomplished on these bridges. Quantities for the project are based upon these conflict bridges being cleaned one time. The Contractor will work with the Engineer to determine what locations have conflicts at the time cleaning is planned.

DISPOSAL

All refuse materials and debris collected will become the property of the Contractor and will be properly disposed of.

NO "on road" storage or dumping will be permitted.

EQUIPMENT

All equipment will be adequately maintained both mechanically and visually, and will be fully operational during all sweeping operations.

All equipment will be properly registered and insured according to motor vehicles laws of the state of South Dakota.

All units will be clearly and prominently marked with Contractor's company name.

- AIR COMPRESSOR

Compressor will have a rated pressure of 100 psi with a minimum pressure level of 80 psi. Compressor will be capable of delivering a minimum of 180 CFM.

- SWEeper

Minimum width of main broom or pickup head will be 50 inches. Sweeper will utilize both left side and right side brooms for picking up debris. Sweeper will have an internal self-contained storage hopper. Storage hopper will be a minimum capacity of 3.4 Cubic Yards.