Rapid City Region Design Office
2300 Eglin Street, PO Box 1970
Rapid City, SD 57709-1970
Phone: 605-394-2244 FAX: 605-394-1904
Website: https://dot.sd.gov/ and https://sd.511.org

November 9, 2026

ADDENDUM NO. 1

RE: November 12, 2026 Rapid City Region Office Informal Letting
090E-452, Pennington County, PCN i89x
PCC Pavement Repair on I-90E near Piedmont

TO WHOM IT MAY CONCERN:

The following addenda to the plans shall be inserted and made part of your proposal for the referenced project.

PROPOSAL:

- No change.

PLANS:

- Replace Sheet 3 with the attached. The Asphalt Concrete Composite note was changed. The asphalt shoulder repair is incidental to Nonreinforced PCC Pavement Repair.

Sincerely,

_____
John Rehorst
Region Design Engineer

Revised 11/4/26 GDS

COMMITMENT H: WASTE DISPOSAL SITE

The Contractor will furnish a site(s) for the disposal of construction and/or demolition debris generated by this project.

Action Taken/Required:

Construction and/or demolition debris may not be disposed of within the Public ROW.

The waste disposal site(s) will be managed and reclaimed in accordance with the following from the General Permit for Construction/Demolition Debris Disposal Under the South Dakota Waste Management Program issued by the Department of Agriculture and Natural Resources.

The waste disposal site(s) will not be located in a wetland, within 200 feet of surface water, or in an area that adversely affects wildlife, recreation, aesthetic value of an area, or any threatened or endangered species, as approved by the Environmental Office and the Project Engineer.

If the waste disposal site(s) is located such that it is within view of any ROW, the following additional requirements will apply:

1. Construction and/or demolition debris consisting of concrete, asphalt concrete, or other similar materials will be buried in a trench separate from wood debris. The final cover over the construction and/or demolition debris will consist of a minimum of 1 foot of soil capable of supporting vegetation. Waste disposal sites provided outside of the Public ROW will be seeded in accordance with Natural Resources Conservation Service recommendations. The seeding recommendations may be obtained through the appropriate County NRCS Office. The Contractor will control the access to waste disposal sites not within the Public ROW with fences, gates, and placement of a sign or signs at the entrance to the site stating, “No Dumping Allowed”.

2. Concrete and asphalt concrete debris may be stockpiled within view of the ROW for a period not to exceed the duration of the project. Prior to project completion, the waste will be removed from view of the ROW or buried, and the waste disposal site reclaimed as noted above.

3.

The above requirements will not apply to waste disposal sites that are covered by an individual solid waste permit as specified in SDCL 34A-6-58, SDCL 34A-6-1.13, and ARSD 74:27:10:06.
Failure to comply with the requirements stated above may result in civil penalties in accordance with South Dakota Solid Waste Law, SDCL 34A-6-1.31.

All costs associated with furnishing waste disposal site(s), disposing of waste, maintaining control of access (fence, gates, and signs), and reclamation of the waste disposal site(s) will be incidental to the various contract items.

COMMITMENT I: HISTORIC PRESERVATION OFFICE CLEARANCES

State Historic Preservation Office (SHPO or THPO) concurrence has not been obtained for this project.

Action Taken/Required:

All earth disturbing activities not designated within the plans require a cultural resource review prior to scheduling the pre-construction meeting. This work includes but is not limited to: Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas.

The Contractor will arrange and pay for a record search and when necessary, a cultural resource survey. The Contractor has the option to contact the state Archaeological Research Center (ARC) at 605-394-1936 or another qualified archaeologist, to obtain either a records search or a cultural resources survey. A record search might be sufficient for review if the site was previously surveyed; however, a cultural resources survey may need to be conducted by a qualified archaeologist.

The Contractor will provide ARC with the following: a topographical map or aerial view in which the site is clearly outlined, site dimensions, project number, and PCN. If applicable, provide evidence that the site has been previously disturbed by farming, mining, or construction activities with a landowner statement that artifacts have not been found on the site.

The Contractor will submit the cultural resources survey report to SDDOT Environmental Office, 700 East Broadway Avenue, Pierre, SD 57501-2586. SDDOT will submit the information to the appropriate SHPO/THPO. Allow **30 Days** from the date this information is submitted to the Environmental Engineer for SHPO/THPO review.

In the event of an inadvertent discovery of human remains, funerary objects, or if evidence of cultural resources is identified during project construction activities, then such activities within 150 feet of the inadvertent discovery will immediately cease and the Project Engineer will be immediately notified. The Project Engineer will contact the SDDOT Environmental Office, who will contact the appropriate SHPO/THPO within 48 hours of the discovery to determine an appropriate course of action.

The Contractor is responsible for obtaining any additional permits and clearances for Contractor furnished material sources, material processing sites, stockpile sites, storage areas, plant sites, and waste areas that affect wetlands, threatened and endangered species, or waterways. The Contractor will not utilize a site known or suspected of having contaminated soil or water. The Contractor will provide the required permits and clearances to the Project Engineer at the preconstruction meeting.

COMMITMENT S: FIRE PREVENTION IN THE BLACK HILLS AREA

This project is located within the Black Hills Forest Fire Protection Boundary.

Action Taken/Required:

The Contractor will adhere to the “Special Provision for Fire Plan”.

UTILITIES

Utilities are not planned to be affected on this project. If utilities are identified near the improvement area through the SD One Call Process as required by South Dakota Codified Law 49-7A and Administrative Rule Article 20:25, the Contractor will contact the Engineer to determine modifications that will be necessary to avoid utility impacts.

EXISTING PCC PAVEMENT

I90 E MRM 48+0.430 – The existing 9" PCC Pavement is reinforced with welded wire fabric. The welded wire fabric weighs not less than 60 pounds per 100 square feet, the longitudinal wires are No. 1 gauge and are spaced 6" center to center and the transverse wires are No. 4 gauge and are spaced 12" center to center.

Existing contraction joints are spaced at approximately 60'. Longitudinal joints are reinforced with No. 5 x 24” deformed tie bars spaced 30” to 48” center to center. Transverse joints are reinforced with 1¼” x 18” plain round dowel bars and with No. 9/10 x 18” deformed tie bars spaced 12” to 18” center to center.

The aggregate in the existing PCC Pavement is limestone.

Asphalt concrete surfacing is placed on top of the PCCP. The depth varies from 0”, under the bridge to approx. 2” at the ends of the repair.

RESTORATION OF GRAVEL CUSHION

An inspection of the gravel cushion subgrade will be made after removing concrete from each pavement replacement area. Areas of excess moisture will be dried to the satisfaction of the Engineer. Loose and excess material will be removed. Each replacement area will be leveled and compacted to the satisfaction of the Engineer.

All costs associated with this work will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.

ASPHALT CONCRETE COMPOSITE

Asphalt Concrete Composite will be used for shoulder repair at full depth PCC replacement locations.

All other requirements in the Standard Specifications for Asphalt Concrete Composite will apply.

No MC-70 Asphalt for Prime will be required.

No flush seal will be required.

The asphalt used for the shoulder repair will be incidental to the contract unit price per square yard for Nonreinforced PCC Pavement Repair.